



Surgeon General's Office

LIBRARY

ANNEX

Section,


Shelf,

No.

Chemistry
133 036.

PRESENTED BY

Mrs. A. J. Augusta



A T Augusta

Trinity college

Toronto C W

Nov 21st 18 54

1870

1875

MORFIT'S CHEMICAL AND PHARMÆCEUTICAL MANIPULATIONS,

WITH

FOUR HUNDRED AND TWENTY-THREE ILLUSTRATIONS.

LINDSAY & BLAKISTON, PHILADELPHIA,

PUBLISHERS

A MANUAL OF THE MECHANICAL AND CHEMICO-MECHANICAL OPERATIONS OF THE LABORATORY;

CONTAINING A COMPLETE DESCRIPTION OF THE MOST APPROVED APPARATUS, WITH INSTRUCTIONS AS TO THEIR APPLICATION AND MANAGEMENT, BOTH IN THE MANUFACTURING PROCESS AND IN THE MORE EXACT DETAILS OF ANALYSIS
AND ACCURATE RESEARCH;

BY CAMPBELL MORFIT,

Practical and Analytical Chemist, author of "Applied Chemistry," &c. &c.,

ASSISTED BY ALEXANDER MUCKLE,

Chemical Assistant in Professor Booth's Laboratory.

IN ONE VOLUME, OCTAVO.

PUBLISHERS' ADVERTISEMENT.—This work, entirely new in its matter and arrangements, is designed for the thorough instruction of chemical and pharmaceutical students in every branch of their respective arts, from the veriest rudiments to the most delicate manipulations. The author gives, in a familiar but clear style, the details of all the manipulations of the laboratory, including the improvements of the present day, and illustrates his descriptions with numerous beautifully-executed and expressive wood-cuts, or drawings. No expense has been spared in endeavouring to make this book the substitute for all others on the same subject.

Extract of a Letter from Prof. J. C. Booth, Practical and Analytic Chemist.

"I regard it as a very valuable addition to a Chemical Library, whether to that of an experimental or manufacturing chemist, for while the business of the former is wholly experimental research, the latter is frequently forced to enter into the same field in order to improve his processes. Although I have been a witness of the author's untiring industry in preparing this work, yet, upon examining it in its present state, am surprised to find it so complete in all its parts. I know that there is a large amount of original matter contained in it, the result of the author's observation and experience; and that which has been derived from other sources, has been judiciously and harmoniously culled from a very extensive Chemical Library. I therefore think that every one connected with chemistry, in any of its numerous departments, should have a copy of this work in his library. I intend using it freely in my course of instruction in Experimental Chemistry, and shall recommend it to my students."

"Mr. Morfit's reputation as a scientific chemist has been established, here by his association with Professor Booth in the authorship of the 'Encyclopædia of Chemistry,'—and his practical ability was before well known from his work on 'Soap and Candles.' To such a work as the above, therefore, he brings those qualifications which alone can render it valuable. No man without both theoretical and practical knowledge, and especially the latter, can properly teach the economy of a laboratory. He must himself have encountered and overcome difficulties. This the author has done; and the student of chemistry, whether apothecary, manufacturer, or the amateur, will find his labours and comprehension very much assisted by such a manual. The characteristic of Mr. Morfit's public labours is practical common sense; and too much value can hardly be set on what so thoroughly obviates the mysteries and technicalities of chemical text-books."—*Saturday Evening Post.*

"We are always gratified by the issue of practical works from the press, as they tend to advance the arts of civilized life, and with them, the people who are engaged in them. It is, however, comparatively rare that we meet with an original work of this character issuing from the American press; and, therefore, we hail the appearance of the present one with peculiar pleasure. It is a book of nearly five hundred pages, illustrated with four hundred and twenty-three wood-cuts, and while its typography does credit to the publishers, we find that the manner in which the author has treated the subject is no less deserving of praise. It handles the subject of manipulations in experimental and manufacturing chemistry in a very elaborate and yet clear and perspicuous manner, giving a large amount of original matter, showing that the author must have had considerable practical experience in the subjects of which he treats. We feel confident that it will be extensively used as a guide by those who are entering upon chemical study or practice, and will be frequently resorted to by the more experienced practical chemist."

—*The Ledger.*

SPECIMEN OF THE ENGRAVINGS
IN
MORFIT'S CHEMICAL MANIPULATIONS.

Fig. 214.



Fig. 316.

Fig. 332.






Fig. 194.

Fig. 142.



CHEMICAL ANALYSIS,

QUALITATIVE AND QUANTITATIVE.

✓
BY

~~HENRY M. NOAD,~~

LECTURER ON CHEMISTRY AT ST. GEORGE'S HOSPITAL;
AUTHOR OF "LECTURES ON ELECTRICITY," "LECTURES ON CHEMISTRY," ETC. ETC.

WITH NUMEROUS ADDITIONS,

✓
BY

CAMPBELL MORFIT,

PRACTICAL AND ANALYTIC CHEMIST;
AUTHOR OF "CHEMICAL AND PHARMACEUTIC MANIPULATIONS," AND
CO-EDITOR OF THE "ENCYCLOPÆDIA OF CHEMISTRY."

WITH ILLUSTRATIONS.

~~~~~



PHILADELPHIA:  
LINDSAY AND BLAKISTON.

1849.

Entered according to the Act of Congress, in the year 1849, by  
LINDSAY AND BLAKISTON,  
in the Clerk's Office of the District Court for the Eastern District of  
Pennsylvania.

Annex  
QD  
75  
N 739c  
1849

## P R E F A C E.

---

THE present work was prepared by the Author as one of a series of Chemical treatises for the "*London Library of Useful Knowledge*." The care and fidelity with which he performed his laborious task, left little more to be done by the Editor than to make such additions as are called for by the latest investigations in Chemical Analysis. These have been supplied, and the work is now presented as a complete manual both of Qualitative and Quantitative Analysis, in organic and inorganic chemistry, in all their details.

In the original work there are some pages upon Chemical Manipulation, but as this subject, in order to be serviceable to the student, should have been more extensively elucidated, the Editor has taken the liberty of substituting other matter, and has preferred referring the reader, for such information, to "*Morfit's Chemical and Pharmaceutical Manipulations*."





# CONTENTS.

## INTRODUCTION,

|                                                                                                                                                                                                 | PAGE |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|
| EXPLANATORY OF THE IMPORTANT DOCTRINE OF EQUIVALENT PROPORTIONS; OF CHEMICAL NOTATION AND THE CONSTRUCTION AND USE OF FORMULÆ; AND OF THE GENERAL PRINCIPLES OF CHEMICAL NOMENCLATURE . . . . . | 17   |

## PART I.—QUALITATIVE.

### CHAPTER I.

|                                                |    |
|------------------------------------------------|----|
| GENERAL REMARKS ON CHEMICAL ANALYSIS . . . . . | 35 |
|------------------------------------------------|----|

### CHAPTER II.

|                       |    |
|-----------------------|----|
| ON REAGENTS . . . . . | 37 |
|-----------------------|----|

### CHAPTER III.

|                                                          |    |
|----------------------------------------------------------|----|
| ON THE COMPORTMENT OF SUBSTANCES WITH REAGENTS . . . . . | 56 |
|----------------------------------------------------------|----|

#### 1. METALLIC OXIDES.

|                                                                                                                               |    |
|-------------------------------------------------------------------------------------------------------------------------------|----|
| Group 1. Potassa, Soda, Lithia, Ammonia . . . . .                                                                             | 57 |
| — 2. Baryta, Strontia, Lime, Magnesia . . . . .                                                                               | 60 |
| — 3. Alumina, Yttria, Glucina, Thorina, Zirconia, Oxide of Chromium, Oxides of Cerium, Titanic Acid, Tantallic Acid . . . . . | 65 |
| — 4. Zinc, Nickel, Cobalt, Manganese, Iron, Uranium . . . . .                                                                 | 72 |
| — 5. Lead, Silver, Mercury, Bismuth, Cadmium, Copper, Palladium, Rhodium, Osmium . . . . .                                    | 82 |
| — 6. Antimony, Arsenic, Tin, Platinum, Iridium, Gold, Selenium, Tellurium, Tungsten, Vanadium, Molybdenum . . . . .           | 94 |

#### 2. ACIDS.—*Inorganic.*

|                      |          |
|----------------------|----------|
| Carbonic . . . . .   | 121      |
| Sulphur . . . . .    | 123, 143 |
| Selenic . . . . .    | 126      |
| Phosphorus . . . . . | 127      |
| Boracic . . . . .    | 128      |

|                                                                           | PAGE       |
|---------------------------------------------------------------------------|------------|
| <b>ACIDS.—Inorganic.</b>                                                  |            |
| Silicic . . . . .                                                         | 130        |
| Hydrofluoric . . . . .                                                    | 131        |
| Chromic . . . . .                                                         | 133        |
| Chlorine . . . . .                                                        | 134        |
| Bromine . . . . .                                                         | 135, 139   |
| Iodine . . . . .                                                          | 137, 139   |
| Cyanogen . . . . .                                                        | 140        |
| Nitrogen . . . . .                                                        | 144        |
| Chloric . . . . .                                                         | 147        |
| <b>Organic.</b>                                                           |            |
| Oxalic . . . . .                                                          | 148        |
| Tartaric . . . . .                                                        | 149        |
| Racemic . . . . .                                                         | 150        |
| Citric . . . . .                                                          | 150        |
| Malic . . . . .                                                           | 151        |
| Succinic . . . . .                                                        | 151        |
| Benzoic . . . . .                                                         | 152        |
| Tannic . . . . .                                                          | 152        |
| Gallie . . . . .                                                          | 153        |
| Acetic . . . . .                                                          | 153        |
| Formic . . . . .                                                          | 154        |
| Uric . . . . .                                                            | 155        |
| Meconic . . . . .                                                         | 155        |
| <b>CHAPTER IV.</b>                                                        |            |
| <b>ON SYSTEMATIC QUALITATIVE ANALYSIS . . . . .</b>                       | <b>155</b> |
| 1. Examination for Bases—Principles on which the method depends . . . . . | 162        |
| 2. Examination for Acids . . . . .                                        | 166        |
| Examples for Illustration . . . . .                                       | 172        |
| <b>QUALITATIVE ANALYSIS OF NATURAL SILICATES . . . . .</b>                | <b>188</b> |
| <b>MINERAL WATERS . . . . .</b>                                           | <b>191</b> |
| <b>QUALITATIVE DETECTION OF POISONS . . . . .</b>                         | <b>194</b> |
| <b>THE POISONOUS ACIDS . . . . .</b>                                      | <b>194</b> |
| 1. Sulphuric Acid . . . . .                                               | 194        |
| 2. Nitric Acid . . . . .                                                  | 196        |
| 3. Hydrochloric Acid . . . . .                                            | 198        |
| 4. Oxalic Acid . . . . .                                                  | 199        |
| 5. Hydrocyanic Acid . . . . .                                             | 201        |
| <b>THE POISONOUS METALS:</b>                                              |            |
| 6. Arsenic . . . . .                                                      | 204        |
| 7. Mercury . . . . .                                                      | 213        |
| 8. Copper . . . . .                                                       | 219        |
| 9. Lead . . . . .                                                         | 224        |
| 10. Antimony . . . . .                                                    | 229        |
| 11. Zinc . . . . .                                                        | 231        |



## TABLES.

PAGE

1. Course of Analysis for the Detection of Bases.
2. \_\_\_\_\_ of Bases—continued.
3. \_\_\_\_\_ of Inorganic Acids.
4. \_\_\_\_\_ of Organic Acids.

## PART II.—QUANTITATIVE.

## CHAPTER I.

|                                                                                                                     |     |
|---------------------------------------------------------------------------------------------------------------------|-----|
| ON THE QUANTITATIVE ESTIMATION OF SUBSTANCES, AND THEIR SEPARATION FROM EACH OTHER . . . . .                        | 233 |
| Group 1. Metals of the Alkalies proper . . . . .                                                                    | 235 |
| —— 2. _____ Alkaline Earths . . . . .                                                                               | 253 |
| —— 3. Aluminum, Glucinum, Yttrium, Thorium, Zirconium, Chromium . . . . .                                           | 259 |
| —— 4. Zinc, Nickel, Cobalt, Manganese, Iron, Uranium . . . . .                                                      | 267 |
| —— 5. Lead, Silver, Mercury, Bismuth, Cadmium, Copper, Palladium, Rhodium, Osmium, Ruthenium . . . . .              | 302 |
| —— 6. Antimony, Arsenic, Tin, Platinum, Iridium, Gold, Selenium, Tellurium, Tungsten, Vanadium, Molybdeum . . . . . | 342 |

## ACIDS:

|                             |     |
|-----------------------------|-----|
| Acids of Sulphur . . . . .  | 371 |
| —— Phosphorus . . . . .     | 380 |
| Boracic Acid . . . . .      | 388 |
| Silicic Acid . . . . .      | 390 |
| Carbonic Acid . . . . .     | 398 |
| Oxalic Acid . . . . .       | 407 |
| Hydrofluoric Acid . . . . . | 408 |
| Hydrochloric Acid . . . . . | 411 |
| Hydrobromic Acid . . . . .  | 421 |
| Hydriodic Acid . . . . .    | 423 |
| Hydrocyanic Acid . . . . .  | 425 |
| Nitric Acid . . . . .       | 427 |
| Chloric Acid . . . . .      | 437 |

## CHAPTER II.

|                                                        |     |
|--------------------------------------------------------|-----|
| ON THE ELEMENTARY ANALYSIS OF ORGANIC BODIES . . . . . | 438 |
|--------------------------------------------------------|-----|

## CHAPTER III.

|                                                          |     |
|----------------------------------------------------------|-----|
| ON THE QUANTITATIVE ANALYSIS OF MINERAL WATERS . . . . . | 475 |
|----------------------------------------------------------|-----|

## CHAPTER IV.

|                                    |     |
|------------------------------------|-----|
| ON THE ANALYSIS OF SOILS . . . . . | 490 |
|------------------------------------|-----|

## CHAPTER V.

|                                                                                                                                                                                |     |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| ON THE ANALYSIS OF COMPOUNDS CONTAINING THE OXIDES OF IRON<br>AND MANGANESE, ALUMINA AND ALKALINE EARTHS, IN COMBINA-<br>TION WITH PHOSPHORIC, ARSENIC AND SILICIC ACIDS . . . | 510 |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|

## CHAPTER VI.

|                                              |     |
|----------------------------------------------|-----|
| ON THE ANALYSIS OF ASHES OF PLANTS . . . . . | 519 |
|----------------------------------------------|-----|

## CHAPTER VII.

|                                                        |     |
|--------------------------------------------------------|-----|
| ON THE ANALYSIS OF URINE AND URINARY CALCULI . . . . . | 537 |
|--------------------------------------------------------|-----|

## TABLES.

|                                                                                                                                                               |     |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| 1. For the Conversion of Degrees on the Centigrade Thermo-<br>meter into Degrees of Fahrenheit's Scale . . . . .                                              | 553 |
| 2. Degrees of Tension of Aqueous Vapor for different Tem-<br>peratures . . . . .                                                                              | 554 |
| 3. Quantity of Oil of Vitriol of Specific Gravity 1.8485, and of<br>Anhydrous Acid, in 100 parts of dilute Sulphuric Acid of<br>different Densities . . . . . | 555 |
| 4. Quantity of Real or Anhydrous Nitric Acid in 100 parts of<br>Liquid Acid at different Densities . . . . .                                                  | 556 |
| 5. Quantity of absolute Alcohol in Spirits of different Specific<br>Gravities . . . . .                                                                       | 557 |
| 6. Quantity of absolute Alcohol by weight in Mixtures of Al-<br>cohol and Water of different Specific Gravities . . . . .                                     | 558 |
| 7. Tables for Calculations in Analysis . . . . .                                                                                                              | 561 |

## APPENDIX.

|                                                                               |     |
|-------------------------------------------------------------------------------|-----|
| NEW APPLICATIONS OF SULPHURETTED HYDROGEN IN CHEMICAL ANA-<br>LYSIS . . . . . | 569 |
|-------------------------------------------------------------------------------|-----|

# INTRODUCTION

## EXPLANATORY

OF THE IMPORTANT DOCTRINE OF EQUIVALENT PROPORTIONS;  
OF CHEMICAL NOTATION AND THE CONSTRUCTION AND USE OF  
FORMULÆ; AND  
OF THE GENERAL PRINCIPLES OF CHEMICAL NOMENCLATURE.

---

IN the course of this Work will be found a Table containing the names of all those substances which are at present regarded by Chemists as Elementary. There are sixty-three of these bodies, all of which have resisted every effort to resolve them into simpler forms of matter. Among them are found bodies of the most diverse characters, both physical and chemical; and out of them, as far as we yet know, everything solid, liquid, and gaseous, in and about the globe which we inhabit, is composed.

The names of these sixty-three substances have not been assigned to them in accordance with any prescribed rule, the discoverer of each particular body following his own fancy in this respect, and being generally guided in his selection either by some marked peculiarity in the new substance, or by some circumstance connected with its discovery. Thus *Mosander*, having found in *oxide of cerium* a large proportion of the oxide of a hitherto unnoticed metal, named the newly discovered body *Lantanium* or *Lanthanum*, from the Greek word *λανθάνω*, *I lurk*, it having lain concealed in the ores of cerium; and the name *osmium* was given to a peculiar metal found in the ores of platinum, from *ὀσμή*, *smell*, having reference to the disagreeable and pungent character of its vapor.

The names selected by their discoverers for some substances are indeed sufficiently eccentric; thus *Berzelius* derived the title of *Selenium*, which he conferred on a certain brittle opaque solid discovered by him in the sulphur of *Fahlun*, from Σελήνη, *the Moon*, in consequence of his having at first mistaken it for *Tellurium*, which derived its name from *tellus*, *the Earth*. But, whatever may be thought of the propriety of such names, they can lead neither to mistakes nor to confusion, and are in this respect far better than words more significantly chosen, and bearing reference to certain characteristic properties possessed, or supposed to be possessed by the substance. This method has rarely been successful: thus the name *oxygen*, proposed by *Lavoisier* for the *Dephlogisticated air* of *Priestley*, though at the time well chosen, has not stood the test of time. In *Lavoisier's* day this substance was supposed to be the sole cause of acidity, hence its name, from ὄξύς, acid, and γενναεῖν, to generate; we now know, however, that this property of generating acidity is not peculiar solely to oxygen. Again, the same celebrated French Chemist proposed the name *azote* for that gas first noticed by *Rutherford*, and which we now call *nitrogen*—the word “azote” is derived from α, privative, and ζῶν, life, and was suggested by the inability of the gas to support respiration; the term, however, was very unfortunate, there being several other gases in the same predicament, and equally fatal to animal life. The name *azote* is now abolished, that of *oxygen* is still retained, not because a better might not probably be found, but because it is inexpedient to make any change whatever in an old-established nomenclature, without cogent and well-considered reasons.

These sixty-three elementary substances have been differently classified by different chemists; some divide them into two great classes, viz: *Electro-positive*, including all those bodies which, by their union with oxygen, form compounds the electro-chemical relations of which are decidedly *positive*: and *Electro-negative*, including those bodies which, by their union with oxygen, form compounds, the electrical characters of which are either decidedly *not positive*, or which may be regarded either as positive or negative. Other chemists arrange the elements into certain small groups or natural families, the members of each group being connected together by certain analogies, and the several groups shading into each other through the medium of certain links, like the classes



created by the naturalist for the objects of the organic world: for a full exposition of this system of classification the reader may consult *Mr. Graham's "Elements of Chemistry."* Another division, sometimes adopted, is that into *combustibles* and *supporters of combustion*; but the most convenient is that founded on the physical properties of the elements in a free state—the division into *metalloids* and *metals*; the former comprising *oxygen, hydrogen, nitrogen, chlorine, bromine, iodine, fluorine, sulphur, selenium, tellurium, phosphorus, arsenic, carbon, boron, and silicon*, are, without exception, electro-negative; the metals, on the other hand, are nearly all electro-positive; those that are not so ought, according to *Berzelius*, to be ranked among the metalloids.

In the table above referred to there will be seen, opposite to each element, certain letters and figures; these constitute its *symbol* and its *chemical equivalent*: the former is a very convenient method of representing a substance, and the constitution of the compound into which it enters; it is formed from the first letter or letters of the Latin name of the body; thus the metal *Tin* is written *Sn*, an abbreviation of the Latin word *Stannum*; *Mercury*, *Hg*, from the Latin *Hydrargyrum*; *Antimony*, *Sb*, from *Stibium*. When there is only one elementary substance with the same initial letter, that letter usually serves as its symbol, thus *F* suffices for *Fluorine*, and *H* for *Hydrogen*; but where there are several elements, the name of each of which commences with the same letter, then other letters are added to the initial letter in order to keep each substance distinct; thus there are no less than eight substances commencing with the letter *C*, viz: Carbon, Cadmium, Chlorine, Cerium, Chromium, Cobalt, Copper, and Calcium, the respective symbols for which are C, Cd, Cl, Ce, Cr, Co, Cu (*Cuprum*), and Ca.

The meaning of the term "equivalent," as applied to the numbers in the third and fourth columns of the Table, may be illustrated by the following:—Common culinary salt, wherever or however procured, whether by evaporation from the waters of the ocean or excavated from the mines of *Salzburg*, or formed artificially in the laboratory by pouring hydrochloric acid on carbonate of soda, has always the same composition, viz: 35.5 parts of chlorine and 22.97 parts of the metal sodium; and a substance not having this precise composition, however similar it may be to common salt in other respects,


is not that substance, but some other. Now, if we pour not less than 49 parts of the strongest oil of vitriol over 58.47 parts of common salt, and heat the mixture till all action has ceased, we shall obtain as the result of the decomposition, 70.97 parts of sulphate of soda or Glauber salts, and 36.5 parts of hydrochloric acid; and, if we analyze this sulphate of soda and this hydrochloric acid, we shall find that the former is composed of 30.97 parts of soda and 40 parts of sulphuric acid, and the latter of 35.5 parts of chlorine and 1 of hydrogen; lastly, if we compare the composition of the sulphate of soda as thus obtained with that formed by pouring sulphuric acid on carbonate of soda, we shall find that they have both precisely the same composition; and, if we explode in a strong glass vessel a mixture of hydrogen and chlorine, we shall obtain a highly acid gas, the composition of which is 35.5 parts of chlorine and 1 of hydrogen, the same with that of the acid obtained by the decomposition of common salt by oil of vitriol.

If we look a little more closely at the facts of this decomposition, we shall get a clear idea of what is meant by the term "equivalent." We have seen that 58.47 parts of common salt, when treated with 49 parts of oil of vitriol, yield 70.97 parts of sulphate of soda, a *perfectly neutral substance*, containing 40 parts of sulphuric acid, but not a trace of chlorine; it is easy, therefore, to understand that in this reaction 40 parts of sulphuric acid must have removed 35.5 parts of chlorine, and the term *equivalents*, as applied to these two numbers, cannot be misunderstood: 40 parts of sulphuric acid are *equivalent* to 35.5 parts of chlorine, and whenever chlorine replaces sulphuric acid, or sulphuric acid chlorine, in a compound, it is always in proportions indicated by these numbers.

Again, the oil of vitriol which we have employed in effecting the above decomposition of common salt contained a certain quantity of *water*; none of this compound is, however, found in dry sulphate of soda. What, then, has become of it? The sulphate of soda, though it contains no water, contains an element which is not found in common salt, viz: *oxygen*; and the acid gas which is evolved during the decomposition contains also an element which is not found in common salt, viz: *hydrogen*; but these two substances, when chemically combined, constitute water, and the analysis of this fluid shows its composition to be 8 parts by weight of oxygen to 1 part by weight of hydrogen; but these are the *very proportions* in which the

former is found in the sulphate of soda combined with the 22.97 parts of *sodium*, and the latter in the hydrochloric acid gas combined with the 35.5 of chlorine. What do we deduce from these facts? Obviously this:—that, as 8 parts of oxygen are equally required by 22.97 parts of sodium, and by 1 part of hydrogen, 22.97 parts of *sodium* must be *equivalent* to 1 part of *hydrogen*; and, whenever sodium replaces hydrogen, or hydrogen sodium, the change must be effected in accordance with these proportions. Similarly as 22.97 parts of sodium and 1 part of hydrogen are equally saturated by 35.5 parts of chlorine, so 35.5 must be the proportion in which chlorine replaces 22.97 of sodium and 1 of hydrogen; in other words, 35.5 must be the “equivalent” of chlorine, and, on the same principles, 8 must be the “combining equivalent” of oxygen, that being the proportion in which it equally satisfies 22.97 of sodium and 1 of hydrogen; and whenever, in any compound, oxygen replaces hydrogen, it must do so in the proportion of 8 to 1: when chlorine, in the proportion of 8 to 35.5; and when sodium, in the proportion of 8 to 22.97.

This reaction between common salt and oil of vitriol may, perhaps, be more clearly shown by means of the following diagram.



The two compounds which react on each other are placed outside the two side brackets—their composition is shown inside the same; the products of the decomposition are placed at the top and bottom of the diagram, and the nature of the reaction is shown by the lines between the four brackets, connecting together the different constituents of the new compounds. On referring to the Table of Elements, the figures in the third column, opposite chlorine, sodium, hydrogen and

oxygen, will be found the same with those attached to these elements in the diagram: in this list, sulphuric acid, being a compound body, will not be found. The composition of this important acid has, however, been correctly ascertained; it is known to be composed of 16 parts, by weight, of sulphur, and 24 of oxygen; but opposite the element *sulphur* we find the number 16 as its equivalent, and from this we easily deduce the equivalent of sulphuric acid, thus:  $16 + 24 (8 \times 3) = 40$ .


But why these particular numbers in preference to any other? Why select 22.97 as the equivalent for sodium, and 35.5 as that for chlorine? It will be evident, on a little reflection, that any other set of numbers will do equally well, provided they bear to each other the same proportion as 22.97 does to 35.5. The real experimental import of the equivalent numbers is the expression of the *proportional* and *relative* weights of bodies, in which they produce analogous effects in chemical combinations, and the selection of these numbers is, therefore, a matter of indifference, provided they all bear to each other the true relations. The numbers selected in the above illustration are those which are now pretty generally adopted by chemists in all parts of Europe. The principle on which they are constructed assumes as its starting point the *composition of water*. This fluid is found on analysis to be composed of 8 parts, by weight, of oxygen, and 1 part, by weight, of hydrogen; hence 8 is employed to express the *equivalent* of oxygen, and 1 that of hydrogen.

The other system of numbers, forming the fourth column of the Table referred to, and which, till lately, seems to have had the preference at least in Germany and France, was constructed on the assumption of 100 as the equivalent of oxygen. The numbers in this series are obtained by multiplying those in the former by  $12\frac{1}{2}$ , which gives us 12.5 for hydrogen and 100 for oxygen, and the equivalent proportions of all the other substances represent the quantities of those substances which combine with 100 parts of oxygen to form a protoxide; thus 395.70 parts of copper, 350 parts of iron, 406.59 parts of zinc, and 735.29 parts of tin, each combine with 100 parts of oxygen to form the first stage of oxygenation of those metals: hence these numbers are taken as their respective equivalents, and dividing each by  $12\frac{1}{2}$  we obtain the numbers 31.66, 28, 32.52, and 58.52, which represent the equivalents of copper, iron, zinc, and tin, on that scale which assumes hydrogen as



unity. There can be no doubt as to which series of numbers deserves the preference on the ground of convenience, particularly since the progress of discovery is continually adding to the list of those elements, the equivalents of which, being exact multiples of that of hydrogen, may be expressed by whole numbers, and thus far more readily retained in the memory than numbers with the appendages of fractions, or than those longer ones found in the list on the oxygen scale.

Every elementary substance is thus provided with its *chemical equivalent*—with a number indicating the proportion in which it enters into combination with the equivalent of any other substance with which it is capable of combining, and in which it replaces the equivalent of every other substance in cases of decomposition. Do we wish to know, for example, how much *iron* is required to decompose thoroughly a certain quantity of *cinnabar* or *sulphuret of mercury*? We simply refer to the Table of Equivalents, where we find opposite the metals *mercury* and *iron* the numbers 100.07 and 28. Now cinnabar is known to be a compound of 100.07 of mercury and 16 of sulphur; it is known also that iron is capable of forming a definite compound with sulphur, and the law of equivalents teaches us, that as 28 and 100.07 are respectively the equivalents of *iron* and *mercury*, so the same quantity of sulphur that will satisfy 28 parts of the first will likewise satisfy 100.07 parts of the last, and that, therefore, to remove the whole of the sulphur from 116.07 (100.07 + 16) parts of cinnabar, we require at least 28 parts of iron, the reaction by which the decomposition is brought about being simply a substitution of 28 of iron for 100.07 of mercury: thus—



and this is not only true with regard to the compounds of these two metals with sulphur, for it has been fully proved that the

same quantity of any substance whatever, which combines with 100.07 of mercury, will also combine with exactly 28 of iron, provided this latter metal be capable of entering into chemical combination with that substance.

To give another example. If a rod of *zinc* be suspended in a clear solution of acetate of lead, the latter metal will be deposited on the zinc in a beautiful arborescent form. Now if this lead deposit be collected and weighed, and if, also, the loss sustained by the rod of zinc be carefully determined, it will be found that, for every 103.56 grains of metallic lead precipitated, there are 32.52 grains of zinc dissolved; these 32.52 grains of zinc may be obtained from the solution in the state of oxide, combined with 8 grains of oxygen; but it is known, also, that 103.56 grains of lead combine with 8 of oxygen to form litharge: hence it is clear, that as 32.52 grains of zinc and 103.56 grains of lead each combine with 8 grains of oxygen to form their respective oxides, these numbers must represent the equivalents of these metals, and the experiment itself proves that these are actually the proportions in which they replace each other in their union with acetic acid.

But some substances enter into combination with each other in more than one proportion, forming several distinct compounds—how are these proportions regulated? It is an important and well-established law, and one which of all others gives the most beautiful harmony to the science, “that when one body, A, unites with another body, B, in two or more proportions, the quantities of the latter united with the same quantity of the former bear to each other a very simple ratio.” For example, there are five compounds of nitrogen and oxygen known; the equivalent number of nitrogen, as lately deduced from the analyses of *sal-ammoniac*, *nitrate of silver*, and *nitrate of lead*, is 14. The simplest compound of nitrogen and oxygen known is *nitrous oxide*, or “laughing gas;” it is, therefore, considered as a *protoxide*, and to be composed of nitrogen 14, oxygen 8. The next compound, *nitric oxide*, is the gas obtained by the action of nitric acid on metallic copper, or mercury; and analysis shows that it contains just *twice as much* oxygen as nitrous oxide: it is, therefore, composed of nitrogen 14, oxygen 16 ( $8 \times 2$ ). The third compound, viz: *nitrous acid*, is formed by adding 50 measures of oxygen gas to 200 measures of nitric oxide; its composition is, nitrogen 14, oxygen 24 ( $8 \times 3$ ). The fourth compound, viz: *hyponi-*

*tric acid*, is formed by mixing together 4 volumes of nitric oxide and 2 volumes of oxygen, both perfectly dry; its composition is, nitrogen 14, oxygen 32 ( $8 \times 4$ ); and the fifth compound, viz: *nitric acid*, is composed of nitrogen 14, oxygen 40 ( $8 \times 5$ ). Here the most simple relation is observed between the quantities of oxygen in the different compounds; they are all simple multiples of the smallest quantity, while the proportion of nitrogen remains unchanged throughout. Occasionally, however, the proportions vary; for example, there are two compounds of *iron* and *oxygen* known—the first is composed of iron 28, oxygen 8; but the second is not iron 28, oxygen 16—but iron 28, oxygen 12 ( $8 + 4$ ). Here, though the relation of the two oxides is not so simple as in the former case, there is, nevertheless, no infraction of the great general law, “that bodies unite with each other in their combining proportions only, or in multiples of them, but in no *intermediate proportion*.” We have not 30 or 40, &c., of iron uniting with 15 or 20, &c., of oxygen, but a simple multiple of the equivalent of iron, 28, combines with once and a half of the equivalent number representing oxygen, viz: 12.

Compound bodies have likewise their “equivalent numbers,” and combine with each other according to the same laws with those which regulate the union of simple substances. The equivalent number of a compound body is always the sum of the equivalent numbers of its constituents; thus the combining equivalent of nitric acid is 54, being composed of nitrogen 14 and oxygen 40 ( $8 \times 5$ ); that of *baryta* is 76.64, being composed of barium 68.64, and oxygen 8; but nitric acid and baryta combine together, forming a neutral salt called nitrate of baryta, the equivalent of which is 130.64 (nitric acid 54 + baryta, 76.64). Again, the equivalent number of sulphuric acid is 40 (sulphur 16 + oxygen 24 ( $8 \times 3$ )), and that of soda is 30.97 (sodium, 22.97 + oxygen, 8); but sulphuric acid and soda combine together, forming likewise a neutral salt, sulphate of soda, the equivalent of which is 70.97, the sum of the combining numbers of its constituents. Now, on bringing a solution of nitrate of baryta into contact with a solution of sulphate of soda, mutual decomposition of the two salts takes place; the solution, however, remains neutral, there is no redundancy either of acid or of base. This fact, which appears to have been first noticed by the Saxon Chemist, *Wenzel*, as far back as 1777, is easily explained. The salts resulting


from the decomposition are each composed of a single equivalent of acid and of base, like the salts from which they are formed. Thus

|                             |                                                                                                      |  |                           |
|-----------------------------|------------------------------------------------------------------------------------------------------|--|---------------------------|
|                             | Nitrate of Soda<br>84.97                                                                             |  |                           |
| Nitrate of Baryta<br>130.64 | <div> <div>Nitric acid</div> <div>54</div> </div> <div> <div>Soda</div> <div>30.97</div> </div>      |  | Sulphate of Soda<br>70.77 |
|                             | <div> <div>Baryta</div> <div>76.64</div> </div> <div> <div>Sulphuric acid</div> <div>40</div> </div> |  |                           |
|                             | Sulphate of Baryta<br>116.64.                                                                        |  |                           |

Here it will be seen that the change which takes place is the substitution of *equivalent* quantities of the different bodies for each other; the two bases exchange acids, and the neutrality of the liquid is preserved, because each base meets with its precise equivalent of the new acid, with which it enters into combination. It also follows, as a consequence of the same law, that the neutrality of the liquid will still be preserved, whatever may be the proportions in which the salts may be mixed; the decomposition will go on to the extent of the equivalents present and no further, the excess of either salt remaining unaffected.

#### SYMBOLS AND FORMULÆ.

Having thus briefly explained the meaning and use of the figures in the third and fourth columns of the table, we may return to the consideration of the use of the letters in the second column, which constitute the symbols of the elements. These symbols afford a means of exhibiting, in a concise and comprehensible form, the composition of a compound; the mode in which its elements may be supposed to be arranged; and the changes which occur in its constitution by the substitution of one element for another. We will take the reaction between nitrate of baryta and sulphate of soda, which we have just been considering, by way of illustrating the application of these symbols, and the great advantages attending their use. This reaction would be written thus, in the form of an equation:





Here we have a most comprehensive view, not only of the whole reaction, but likewise of the composition of the different compounds therein concerned. The collocation of letters,  $\text{BaO}, \text{NO}_5$ , shows at once that nitrate of baryta is composed of nitric acid and baryta; it shows, further, that baryta is a compound of barium and oxygen, and nitric acid a compound of nitrogen and oxygen; that in baryta one *equivalent* of barium is combined with one *equivalent* of oxygen, and that in nitric acid one *equivalent* of nitrogen is combined with *five equivalents* of oxygen. But the formula has a still more significant meaning.  $\text{BaO}, \text{NO}_5$  expresses, not an indefinite quantity of nitrate of baryta, but 130.64 parts by weight of that salt. The equivalent number of a compound is, as we have stated above, the sum of the equivalent numbers of its constituents. On referring to the table, the equivalent number of barium will be found to be 68.64; that of oxygen, 8; and that of nitrogen, 14.  $\text{BaO}$  stands, then, for 76.64 parts by weight of baryta ( $68.64 + 8$ ), and  $\text{NO}_5$  stands for 54 parts by weight of nitric acid ( $14 + (8 \times 5)$ );  $\text{BaO}, \text{NO}_5$  consequently represents 130.64 parts by weight of nitrate of baryta. The same observations apply to the collocation of letters  $\text{NaO}, \text{SO}_3$ ; they express not only the construction of the salt sulphate of soda, and the composition of its constituents, but they signify 70.97 parts by weight of sulphate of soda. These are the salts which react on each other, and they are therefore placed on one side of the equation, with the sign + between them; on the other side of the equation we have the results of the decomposition, viz.  $(\text{BaO}, \text{SO}_3)$  (116.64 parts by weight of sulphate of baryta) and  $\text{NaO}, \text{NO}_5$  (84.97 parts by weight of nitrate of soda); but  $130.64 + 70.97 = 201.61$ ; and  $116.64 + 84.97 = 201.61$ ; both sides of the equation agree, and the decomposition is therefore complete.

In writing the formula for nitric acid, it will be observed that, in order to express the fact that it contains five equivalents of oxygen, a small 5 is placed underneath the O; now, whenever a figure is seen in this situation, it is always to be understood as affecting that element only at the foot of which it is placed. For example,  $\text{Fe}_2\text{O}_3$  means a compound of *two* equivalents of *iron* and *three* equivalents of oxygen;  $\text{S}_2\text{O}_2$  a compound of *two* equivalents of sulphur and *two* equivalents of oxygen. When, however, a large figure is placed *before* a collocation of letters, it affects the whole compound ex-

pressed by those letters; thus  $3\text{NO}_5$  means *three* equivalents of nitric acid;  $3\text{Fe}_2\text{O}_3$  represents *three* equivalents of sesquioxide of iron; and  $3\text{S}_2\text{O}_2$  *three* equivalents of hyposulphurous acid. When formulæ representing a reaction are thrown into the form of an equation, certain other signs are sometimes necessary. For example, when terchloride of gold and protosulphate of iron, both in solution, are brought into contact in certain proportions, the whole of the gold is precipitated in the metallic form. The reaction is concisely expressed thus:

$\text{AuCl}_3 + 6(\text{FeO}, \text{SO}_3) = 2(\text{Fe}_2\text{O}_3, 3\text{SO}_3) + \text{Fe}_2\text{Cl}_3 + \text{Au}$   
*one* equivalent of terchloride of gold and *six* equivalents of protosulphate of iron, give rise to *two* equivalents of persulphate of iron, *one* of sesquichloride of iron, and *one* of metallic gold. Now, here, as *six* equivalents of protosulphate of iron are required, the entire formula of that salt is placed within brackets, the figure 6 being prefixed; had the brackets been omitted, the formula would only have been affected by the 6 as far as the comma, and it would have read *six equivalents of protoxide of iron, and one equivalent of sulphuric acid*. Again, one of the products of this reaction is two equivalents of persulphate of iron; the whole formula of persulphate of iron is therefore placed within brackets, the figure 2 being prefixed: had this been omitted, it would have been interpreted *two* equivalents of sesquioxide of iron, and *three* of sulphuric acid, and thus the equation would no longer be intelligible.

Some chemists employ certain other abbreviations. Thus, in writing down the composition of certain minerals, instead of using the symbol for oxygen they express the number of equivalents of that element by dots or points placed over the symbol of the element with which it is associated; thus  $\ddot{\text{Fe}}$  signifies protoxide of iron, and  $2 \ddot{\text{Fe}}$  or  $\ddot{\text{Fe}}$  signifies two equivalents of the same oxide;  $\ddot{\text{S}}$  expresses sulphuric acid, and  $\ddot{\text{S}}_3$  or  $3\ddot{\text{S}}$ , *three* equivalents of that acid. When there are two equivalents of the *electro-positive* element, they are sometimes written by simply placing a dash underneath the symbol, thus  $\text{Fe}$  signifies sesquioxide of iron;  $\text{Al}$  means alumina; sometimes, however, the symbol itself is repeated instead thus,

$\text{Al}^{\text{Al}}\text{Al}$ ,  $\text{Fe}^{\text{Fe}}\text{Fe}$ . Compounds of sulphur are, in like manner occasionally expressed by placing commas over the element with which the sulphur is associated; thus  $\text{As}$ ,  $\text{As}$ ,  $\text{As}$  are sometimes written for the three sulphurets of arsenic, and  $\text{Sn}$ ,  $\text{Sn}$ , and  $\text{Sn}$ , for the three sulphurets of tin. The formulæ of certain organic acids are, likewise, often abbreviated; thus  $\text{A}$ ,  $\text{T}$ ,  $\text{C}$ , are written for acetic, tartaric, and citric acids, instead of the formulæ representing their composition as  $\text{C}_4\text{H}_3\text{O}_3$ ;  $\text{C}_3\text{H}_4\text{O}_{10}$ ;  $\text{C}_{12}\text{H}_5\text{O}_{11}$ ; which is sometimes annexed in parenthesis with the prefix of the equal sign, thus  $\text{A} = (\text{C}_4\text{H}_3\text{O}_3)$ .


The great advantages of this system of notation are particularly appreciated in the organic department of Chemistry; besides the immense assistance it offers to the memory, it enables Chemists to represent their theoretical views respecting the arrangement of the elements of certain compounds which would be wholly impossible from a mere statement of their per-centage composition as determined by analysis. We not unfrequently meet with two or more compounds which, though wholly unlike in their physical and chemical properties, yield nevertheless upon analysis the *same* elements in the *same* proportion; without the use of formulæ it would be quite impossible to give an intelligible representation of the constitution of such compounds, but with the aid of the symbolic language we can do so with the utmost perspicuity. The following may serve as an illustration.

By distilling benzoic acid with sulphuric acid and pyroxylic spirit, an oily, fragrant liquid is obtained, which yields on analysis a per-centage composition answering to the formula  $\text{C}_{16}\text{H}_8\text{O}_4$ . An oil of the same composition, but possessing totally different properties, is obtained by acting on oil of anise with dilute nitric acid. Lastly, by the action of dilute nitric acid on *cymol* (a hydrocarbon obtained from *oil of cummin*) a crystalline substance having acid properties is obtained, the composition of which is likewise  $\text{C}_{16}\text{H}_8\text{O}_4$ . In the language of chemistry these bodies are said to be *isomeric*; but it is evident that even the *empirical* formula,  $\text{C}_{16}\text{H}_8\text{O}_4$ , does not point out the true constitution of each substance. The symbolic language, nevertheless, enables the chemist to exhibit, at a glance, his theoretical ideas respecting them. Thus the first of these


oily compounds is considered to be a salt of the oxide of the hypothetical radical *methyle* ( $C_4H_3$ ) viz: the benzoate, and its composition is written thus:—



The second is regarded as the hydruret of another hypothetical radical *anisyle* ( $C_{16}H_7O_4$ ), and is thus expressed:—



The third, from the circumstances of its derivation, and from its great analogy to benzoic acid, may be considered as the hydrated oxide of another hypothetical radical ( $C_{16}H_7O_2$ ), corresponding to benzoyl, and be written thus:—



#### NOMENCLATURE.

We have already mentioned that the 63 elementary substances may be very conveniently arranged into two grand classes, viz: the *metalloids* and the *metals*. It has also been stated that, in giving names to these different bodies, no rule has, generally speaking, been observed, each particular discoverer following his own fancy in his selection. The names of compound bodies, however, are constructed in accordance with certain rules, and the system of nomenclature still followed is that of *Lavoisier*, which was constructed as far back as the year 1787, and which, though in some of its details it does not exactly accord with the views of the chemists of our day, is retained from the confusion and inconvenience which it has been felt would be introduced into the science, by making any alterations which might not meet the absolute approval of the chemical philosophers of all countries.

Of all the simple substances, the one which is the most plentifully diffused is *oxygen*; it is, moreover, the element, the combinations of which are, on the whole, the most important. The founders of the chemical nomenclature naturally, therefore, directed their especial attention to the compounds of oxygen, and made them the basis of their system.

Oxygen forms, with other simple bodies, three classes of compounds. I. Acids. II. Bases. III. Neutral or indifferent substances. The members of the two latter classes have received the name of *oxides*; *oxide* of potassium, *oxide* of iron, and *oxide* of lead furnish examples of *basic oxides*, and *oxide of carbon* may be quoted as an instance of an *indifferent oxide*. At the time the nomenclature was constructed, it was



supposed that there could not exist more than two compounds of oxygen and the same body possessing *acid* characters; hence names were only provided for two acids with the same radical.

To express the acid containing the smallest proportion of oxygen, the termination *ous* was given to the element forming the radical of the acid, and the termination *ic* was appended to signify the acid containing the largest proportion of oxygen. Thus two compounds of sulphur and oxygen were known, the first was called *sulphurous* and the latter *sulphuric* acid. But the progress of science has pointed out the existence of other acid compounds of sulphur and oxygen. One of these acids contains less oxygen than *sulphurous* acid; another contains more than *sulphurous*, but less than *sulphuric* acid. To give names to these new substances, without disturbing the general principles of the nomenclature, the term *hypo* (from the Greek ὑπό, under) was introduced. Thus *hyposulphurous* acid expresses very conveniently the acid containing less oxygen than *sulphurous* acid, and *hyposulphuric* acid, that containing less oxygen than *sulphuric*, but more than *sulphurous* acid. In other cases acids were discovered containing more oxygen than the *ic* compound, and to meet such cases the term *hyper* (from the Greek ὑπέρ, over) was introduced; thus an acid compound of chlorine and oxygen is known which contains more oxygen than *chloric* acid, the name *hyperchloric* acid was given to this substance; it is now, however, more generally called *perchloric* acid.

It frequently happens that the same body forms several compounds with oxygen which are either *basic* or *indifferent*. The Greek language is again resorted to for furnishing a means of distinguishing these different oxides. Thus there are three oxides of manganese and oxygen known; the first, written symbolically, is  $\text{MnO}$ , and is called the *protoxide*; the second is written  $\text{Mn}_2\text{O}_3$ ,\* and, as it contains once and a half as much oxygen as the protoxide, it is called the *sesquioxide*; these two oxides are *bases*, that is, they combine with oxygen acids forming definite salts; the formula of the third is  $\text{MnO}_2$ , and, as it contains *twice* as much oxygen as the protoxide, it

\* It is written  $\text{Mn}_2\text{O}_3$  instead of  $\text{MnO}1\frac{1}{2}$ , in order to avoid the inconvenience of introducing fractions, and to obviate the necessity of dividing the *atom* of oxygen, on the supposition that the equivalent numbers are actually expressive of the absolute weights of the individual atoms.

is called the *deutoxide*: this oxide is *indifferent*, that is, it does not form salts with oxygen acids; it is generally called *peroxide* of manganese, because it contains the largest proportion of oxygen with which the metal can combine to constitute an oxide: there are other compounds of manganese and oxygen, but these are distinct *acids*.

Salts are named according to a very simple rule, the names of acid and base being so combined that the name of the acid shall determine the *genus*, that of the base the *species*. When the name of the acid terminates in *ic*, the generic name of the salt terminates in *ate*, thus salts of sulphuric acid are sulphates. When the name of the acid terminates in *ous*, the generic name of the salt terminates in *ite*: thus salts of sulphurous acids are called sulphites. In the same manner we have *hyposulphates* and *hyposulphites*. The same acid sometimes combines with the same base in more than one proportion; thus we have two compounds of chromic acid and potassa, the symbols for which are  $\text{KO}, \text{CrO}_3$  and  $\text{KO}, 2\text{CrO}_3$ , and they are called respectively the *chromate* and the *bichromate* of potassa. Salts also exist, in which the quantity of acid is less than that which exists in the *neutral* salt; these compounds are designated *sub-salts*. And, lastly, we are furnished in common alum with an instance of what is called a double salt, where a new and characteristic compound is formed by the union of two distinct salts. The formula for dry alum is  $\text{KO}, \text{SO}_3 + \text{Al}_2\text{O}_3, 3\text{SO}_3$ , which shows it to be composed of sulphate of potash and sulphate of alumina.

The names given to the compounds formed by chlorine, iodine, and the other metalloids, either with the metals or with each other, are in strict accordance with the rule adopted for the oxygen compounds: thus we have *chlorides*, *bichlorides*, *sesquichlorides*, and *perchlorides*; *iodides*, *bromides*, *fluorides*, *sulphides* (sometimes called sulphurets), *carbides* (or carburets), *phosphides* (or phosphurets), *hydrides* (hydrurets), &c. Water is remarkable as acting sometimes the part of an acid and sometimes that of a base; when in the former capacity the compound is called a *hydrate*, as the *hydrate of potassa*; when in the latter, the compound ought, in strictness, to be named by adding the word *water* to that of the acid, though this rule is often infringed. Thus the strongest sulphuric acid of commerce is known to have the composition  $\text{SO}_3 + \text{H}_2\text{O}$ , it ought therefore to be called *sulphate of water*,

though it is generally termed *hydrated sulphuric acid*, or *hydrate of sulphuric acid*.

Certain of the metalloids form, amongst each other, energetic acids, as *chlorine* and *hydrogen*, *iodine* and *hydrogen*, *fluorine* and *hydrogen*, &c.; these are called hydrogen acids, and are named respectively *hydrochloric*, *hydriodic*, and *hydrofluoric* acids. It is here that the present nomenclature seems most defective, though it has not yet been thought advisable to make any important change, for the reasons already alluded to.

We have, lastly, to remark that, from the great analogy subsisting between certain compounds of sulphur with the metalloids and metals, and the corresponding compounds with oxygen, the terms *sulphur acids* and *sulphur bases* have been introduced to designate two classes of compounds, which act towards each other precisely as oxygen acids and oxygen bases, giving rise to a series of true salts called sulphur salts. Sulphur and carbon, for example, combine together and form a compound which corresponds in its properties so completely with carbonic acid, that it is called *sulphocarbonic acid*; it enters into combination with *monosulphuret of potassium*, forming a compound analogous to carbonate of potassa, and which has received the name of *sulphocarbonate of monosulphuret of potassium*.





# PART I.

## QUALITATIVE ANALYSIS.

---

### CHAPTER I.

#### GENERAL REMARKS ON CHEMICAL ANALYSIS.

CHEMISTRY is distinguished from most other sciences by being essentially experimental. Its object is the investigation of the material constituents of the globe, and the study of their different properties and relations; the student is, therefore, constantly engaged in observing the phenomena presented on submitting the different substances that come under his notice to the action of various agents, and in the accumulation of facts derived from experimental inquiry. It is, indeed, this circumstance which gives to Chemistry its principal charm. The tyro no sooner begins to read than he begins to experimentalize: and being thus enabled, to a certain extent, to verify for himself the facts brought before him, he acquires an interest in his pursuit which attaches him daily more and more to it.

In order to pursue analytical chemistry with any chance of success, the student must possess certain qualifications. These may be stated to be—habits of strict order and scrupulous neatness; a dexterity of manipulation which practice alone can give; a firm conviction that the laws of nature are unchangeable, and that variations in experimental results must consequently imply either a non-fulfillment of certain necessary conditions, or some error in manipulation; and a rigorous *honesty*, not only in recording results, but in experimenting, and in interpreting the phenomena which present themselves in the course of an investigation.

The determination of the constituent parts of a compound body is termed its *analysis*; and this may be either of two kinds, according to the object which the operator has in view. If he merely seek a knowledge of the general nature of the substance, he is satisfied when, by the application of certain tests, and by the performance of certain operations, he has obtained evidence of the presence of those elements of which the compound is made up, and the analysis he performs is called *qualitative*. But, if he desire to appeal to the balance, and to ascertain not only the *nature*, but the actual *amount* of the elements present, he must shape his analysis in such a manner as to separate the constituents of the compound completely from each other, and obtain them either pure or in some other well-known form of combination; he then performs a *quantitative* analysis. For example, if, on the addition of a few drops of solution of ferrocyanide of potassium to a neutral and clear liquid, a beautiful blue precipitate be obtained, the operator is at once satisfied of the presence of iron; and if he is working *qualitatively* only, this experiment is, with regard to that particular element, conclusive, it requires no additional confirmation; but if he desire to estimate the exact amount of iron present, he must conduct his analysis in such a manner as to separate every particle of the metal in the state of sesquioxide, in which state it is weighed, and the amount of metal deduced by calculation. Now, before the chemist can proceed to estimate the proportions of the constituents of a compound body, he must know exactly how many elements are present, and what those elements are. The qualitative analysis always, therefore, precedes the quantitative; and it will be necessary to separate the two courses of study, and to treat each individually. In either case, a certain amount of skill and manipulation is required; but, as this subject is one of sufficient extent for a separate treatise, we refer the reader to "*Morfit's Chemical and Pharmaceutic Manipulations*," which furnishes all the necessary instruction in detail.

## CHAPTER II.

## ON REAGENTS.

THOSE substances which are employed by the chemist to give him information as to the nature of the subject of his examination have received the general name of *Reagents*; though the manner in which they act, and the phenomena to which they give rise, are exceedingly varied. These bodies are of the highest importance to the analyst; indeed the judicious use of them, and the correct interpretation of the appearances presented by their action, constitute the skill of the analytical chemist. We shall here describe the preparation and uses of the most important of these substances, without, however, making any attempt to classify them.

The reagents to which we shall direct attention, are as follows:—

1. *Litmus Paper.*

This is an exceedingly delicate test of the presence of an acid; it is most conveniently prepared by dipping thin unsized paper into an infusion of the coloring principle in hot water until it acquires a full blue color. The paper is dried by exposure to the air, and kept carefully protected from the light, which injures and finally destroys the color. The blue color of this paper is instantly changed red by contact with a fluid having an acid reaction.

2. *Red Litmus Paper.*

This is a valuable test of the presence of an alkali. To prepare it, a few drops of hydrochloric acid are mixed with a large quantity of water, and the blue paper immersed in it until it becomes slightly reddened: it is then removed and dried for use. The blue color is restored by contact with an alkali.

3. *Turmeric Paper.*

This is prepared with an infusion of turmeric in the same

manner as litmus paper; it should have a fine yellow color; it indicates the presence of an alkali by changing to a red brown.

#### 4. *Georgina Paper.*

This, when properly prepared, is an excellent test of both acids and alkalies; by the former it is colored red, and by the latter green. It is prepared by dipping paper into the colored infusion of the petals of the *Georgina purpurea*, and should have a fine violet color.

#### 5. *Solution of Indigo.*

One part commercial indigo is digested in ten parts of concentrated sulphuric acid, and the solution diluted with water till it is just distinctly blue. It is an excellent test for free chlorine, and nitric acid, both of which, aided by heat, discharge the color.

#### 6. *Starch Paste.*

Common arrowroot starch is rubbed with cold water, and boiling water then added until a thin paste is formed. It is an invaluable test for free iodine; when brought into contact with which, an intense blue compound is formed. With free bromine it forms a yellow compound.

#### 7. *Lead Paper.*

Paper is saturated with a strong solution of basic acetate of lead, cut into strips and dried. It forms an extremely delicate test of the presence of sulphuretted hydrogen, which instantly communicates to it a deep brown black color.

#### 8. *Sulphuric Acid.* ( $\text{SO}_3$ .)

\* The commercial oil of vitriol always contains sulphate of lead, sometimes also nitric acid, arsenic, and tin. The first of these impurities is removed by diluting the acid with water; a turbidity indicates sulphate of lead, which is insoluble in the diluted acid. Nitric acid is indicated by the blue color of solution of indigo being discharged when boiled with the acid. Arsenic is indicated by passing a stream of sulphuretted hydrogen through the clear diluted acid; a yel-

\* A. A. Hayes (*Silliman's Journal*, July, 1848) gives an economical process for manufacturing pure acid.



low precipitate is formed: if the precipitate be brown, it indicates tin. From all these impurities it may be freed by distillation; the first portions being rejected, and not more than three-fourths of the acid in the retort drawn over; for almost every qualitative operation the commercial acid may be employed. Sulphuric acid is of the most extensive use to the chemist, from its strong affinity for bases.\* It liberates most other acids from their combinations, thus enabling their detection; and, from its powerful affinity for water, it effects remarkable changes in many substances in which the elements of that fluid exist. It is a powerful oxidizing agent, and in a diluted state it serves as a test for baryta, strontia, and lead, which it precipitates from their solutions.

#### 9. *Nitric Acid.* ( $\text{NO}_3$ .)

This acid, the aquafortis of commerce, is prepared by distilling equal weights of oil of vitriol and nitre. It almost always contains sulphuric and hydrochloric acids, from which it may be freed, by adding nitrate of silver as long as a precipitation takes place, and then re-distilling. This operation may, however, be avoided, if in the original preparation of the acid the first portions, about one-tenth or one-eighth of the whole, be collected in a separate receiver; these portions will contain all the impurities, and the remainder will be quite pure. Nitric acid is used as a solvent for metals, sulphurets, &c., and as a powerful oxidizing agent.

#### 10. *Hydrochloric Acid.* ( $\text{HCl}$ .)

The muriatic acid of commerce is not sufficiently pure for analytical purposes. It contains sulphuric acid and iron, sometimes also sulphurous acid, chlorine, and arsenic. Pure muriatic acid is conveniently obtained from the common muriatic acid of commerce; a quantity of the latter is introduced into a retort, to about one-third its capacity. Oil of vitriol is then poured into it gradually by a funnel tube which dips under the acid. The heat generated by the mixture drives over muriatic acid gas, which is sufficiently purified by passing through a good quality of the liquid acid contained in the receiver, the beak of the retort dipping under the surface. Two or more Woolfe's bottles half filled with water, being con-

\* Krameric acid, it is said, separates sulphuric acid from the sulphate of baryta.

nected with the receiver, the acid in the first will be found nearly or quite pure, that in the second perfectly pure. A gentle heat may be applied to the retort to extract nearly all the muriatic acid, and the sulphuric acid may be subsequently heated in a capsule to strengthen and partially purify it.

Hydrochloric acid is very extensively used as a solvent, and for the detection of silver, mercury, lead, and ammonia.

11. *Nitromuriatic Acid, or aqua regia.* ( $\text{NO}_4 + \text{Cl}$ ) HO.

This acid is prepared by adding nitric acid to twice or thrice its volume of strong hydrochloric acid; both acids undergo decomposition, hyponitric acid, chlorine, and water being formed. When the liquid is saturated with chlorine, this mutual decomposition ceases; but it recommences on the removal of the chlorine either by heat or by its combination with some other substance. Aqua regia is consequently the most powerful of solvents: its principal use in analytical chemistry is for dissolving gold and platinum, and for decomposing certain metallic sulphurets.

12. *Acetic Acid.* ( $\text{C}_4\text{H}_3\text{O}_3$ , or  $\bar{\text{A}}$ .)

The acetic acid of commerce frequently contains traces of sulphuric acid, but it may be obtained sufficiently pure for most analytical operations. If required quite free from all impurities, it is most conveniently prepared by distilling a mixture of ten parts of neutral acetate of lead with three of sulphate of soda, in a retort, with a cooled mixture of two and a half parts of sulphuric acid, and an equal weight of water: the distillation is continued to dryness. The acid thus obtained leaves no residue on evaporation. Acetic acid is employed as a solvent, and for acidifying liquids in the place of the mineral acids.

13. *Oxalic Acid.* ( $\text{C}_2\text{O}_3$ , or  $\bar{\text{O}}$ .) HO.

The commercial acid is purified by two or three recrystallizations. It should leave no residue on ignition. It is employed as a precipitant of certain substances, particularly lime, for the detection of which it is a very valuable reagent. All the oxalates are soluble in the stronger acids.

14. *Tartaric Acid.* ( $C_4H_4O_6 = \overline{T.}$ )

The commercial acid is sufficiently pure; well-defined crystals should be selected. It should be kept in powder, as its solution decomposes by keeping. It is employed to prevent the precipitation of certain metallic oxides by alkalies, and as a test for potassa.

15. *Potassa.* ( $KO.$ )

The best method of preparing this valuable reagent is to dissolve two parts of pure carbonate of potassa in twenty parts of boiling water in an iron pot, and to add in small portions at a time, to the boiling liquid, cream of lime, made by slaking one part of quicklime with boiling water; after boiling a few minutes the vessel is covered and allowed to stand for twenty-four hours; the clear liquid is then decanted. To obtain the potassa in the solid state, the liquid is evaporated to an oily consistence in a silver basin, poured out on a silver dish, and allowed to cool; it is then broken into fragments and preserved in well-stoppered bottles. Solutions of potassa, after being neutralized by nitric acid, should give no precipitate with chloride of barium, or nitrate of silver, nor should it effervesce on the addition of an acid. Silicic acid is a frequent impurity of potassa. It is detected by evaporating the alkali to perfect dryness, and adding water. Silicic acid, if present, remains undissolved.

The uses of potassa in analytical chemistry are very numerous; as a precipitant; as a solvent; as a means of separating certain oxides from others; and as a test for ammonia, which, aided by heat, it expels from all its salts. Of the bases which it precipitates, some are soluble in an excess—hence a means for their separation from those which are insoluble.

16. *Carbonate of Potassa.* ( $KO, CO_2.$ )

This salt is best prepared by calcining pure cream of tartar: the incinerated mass is boiled in distilled water, filtered, and the clear liquid evaporated to dryness in a clean iron vessel, with constant stirring towards the end of the process; the dried mass must be kept in a well-stoppered bottle, and one part dissolved in five or six of distilled water for use. The carbonate of potassa of commerce usually contains alkaline sulphates and chlorides, alumina and silica. Carbonate of

potassa is extensively employed as a precipitant, and for the decomposition of many insoluble salts, particularly organic, with metallic bases.

17. *Carbonate of Soda.* ( $\text{NaO}, \text{CO}_2$ .)

This salt is obtained pure by heating the best bicarbonate of soda of commerce for some time to low redness: its uses are the same as those of carbonate of potassa. It is an indispensable reagent in blowpipe operations; as a flux; as a solvent; and as a decomposing agent.

18. *Ammonia.* ( $\text{NH}_3$ .) HO.

Sal ammoniac is mixed with an equal weight of slaked lime, a little water added, and the mixture heated in a stoppered retort. The disengaged gas is first allowed to pass through a small quantity of water in a wash bottle, and from thence into another bottle nearly filled with distilled water immersed in a vessel containing ice-cold water; this bottle, for better security against sudden absorption, may be furnished with a safety tube. The water will absorb the gas, and become possessed of all its chemical properties in a very high degree. It should be kept in small well-stoppered bottles, and not in one large one, as every time it is exposed to the air it absorbs a certain quantity of carbonic acid, its freedom from which is proved by its not rendering lime-water turbid. Ammonia is in constant use for neutralizing acids, its peculiar fitness for which consists in its not introducing any fixed matter; for precipitating insoluble bases; and for separating them from each other. Some of the bases which it precipitates are redissolved by an excess.

19. *Carbonate of Ammonia.* ( $\text{NH}_4\text{O}, \text{CO}_2$ .)

The sesqui-carbonate of ammonia of commerce is dissolved in four parts of distilled water, and one of liquor of ammonia added. The solution when evaporated should leave no residue. This reagent is employed as a precipitant, and is very useful as a substitute for carbonate of potassa in cases where the introduction of a fixed base would be inconvenient. It is of special use in the separation of baryta, strontia, and lime, from magnesia, the latter of which earths is not precipitated in the presence of ammoniacal salts.



20. *Chloride of Ammonium.* ( $\text{NH}_4\text{Cl}$ .)

Sal-ammoniac of commerce is purified by two or three recrystallizations. Its solution in water should be neutral, and hydrosulphuret of ammonia should not discolor it: it should volatilize entirely when heated on platinum foil. The salt should be dissolved for use in eight parts of distilled water. It is of great use in analysis as a precipitant of various substances soluble in potassa, but insoluble in ammonia, and for keeping in solution certain oxides or salts when others are precipitated by ammonia or other reagents. [Its property of decomposing several oxides and sulphurets at a high temperature and forming very volatile chlorides with the metals, enabling their separation from the more fixed chlorides, renders it an important reagent in analysis. Rose uses it in his new method for estimating arsenic, antimony and tin.\*]

21. *Hydrosulphuret of Ammonia.* ( $\text{NH}_4\text{S}, \text{HS}$ .)

This reagent is prepared by transmitting sulphuretted hydrogen gas through solution of ammonia, till the liquid gives no precipitate with sulphate of magnesia. It must be kept in well-stopped bottles free from lead. When first prepared it contains excess of sulphuretted hydrogen, is nearly colorless, and does not give a precipitate of sulphur when mixed with an acid; but by exposure to the air it gradually absorbs oxygen, and assumes a yellow tint from the presence of excess of sulphur, of which element it now yields a precipitate on the addition of an acid. It is necessary to bear in mind these facts. Hydrosulphuret of ammonia is of great use for subdividing into two groups those metals which are precipitated as sulphurets by sulphuretted hydrogen, from their acid solutions; some of these sulphurets being soluble, others insoluble in hydrosulphuret of ammonia. It also subdivides into groups those metals that are not precipitated by sulphuretted hydrogen from their acid solutions; some of these metals being precipitated by hydrosulphuret of ammonia, while others remain in solution: it likewise precipitates certain oxides as hydrates by the action of its ammonia alone, and certain salts that are dissolved only in free acids; phosphate of lime, for instance,

\* *Chem. Gaz.*, vi. 166, 411.

from its solution in hydrochloric acid. Neutral solutions of magnesia-salts, though yielding a precipitate to caustic ammonia, give none with hydrosulphuret.

22. *Sulphuret of Potassium.* ( $\text{KOS}_2\text{O}_2 + 2\text{KS}_2$ .)

When sulphuret of copper is to be separated from sulphur combinations soluble in alkaline sulphurets, sulphuret of potassium prepared by boiling sulphur with solution of caustic potassa, is substituted for hydrosulphuret of ammonia, in which sulphuret of copper is partially soluble.

23. *Oxalate of Ammonia.* ( $\text{NH}_4\text{O},\text{O}$ .)

This reagent is prepared by slightly supersaturating a solution of pure oxalic acid with carbonate of ammonia, and crystallizing: one part of the salt is dissolved in twenty or twenty-four parts of water for use; it is employed for the detection and precipitation of lime, and is more convenient than oxalic acid, as its solution does not decompose by keeping, and moreover when mixed with a solution of lime previously neutral, liberates no free acid to retain oxalate in solution.

24. *Sulphuretted Hydrogen.* ( $\text{HS}$ .)

Fragments of protosulphuret of iron are covered with water in a gas evolution apparatus connected with a wash bottle; sulphuric or hydrochloric acid is poured into the bottle through a tube funnel, and the evolved gas received into a bottle containing cold distilled water as long as it continues to be absorbed. The solution must be preserved in well-stopped bottles. Sulphuretted hydrogen is a valuable reagent for separating metals into groups, and also as a means of reduction and of detection of individual metals.

25. *Ferrocyanide of Potassium.* ( $\text{K}_2\text{Cfy}$ .)

The commercial yellow prussiate of potassa is sufficiently pure for analytical purposes; one part is dissolved for use in ten or twelve parts of water. It is of especial use for the detection of sesquioxide of iron and oxide of copper.

26. *Ferriecyanide of Potassium.* ( $\text{K}_3\text{Cfy}_2$ .)

This reagent is prepared by transmitting a stream of chlo-

rine gas through a solution of the above salt until it ceases to produce a blue precipitate, with a solution of sesquichloride of iron. Its crystals have a magnificent red color; to procure them the solution is concentrated by evaporation, and rendered feebly alkaline by carbonate of potassa. This reagent serves to detect protoxide of iron by the formation of a characteristic blue precipitate.

27. *Chromate of Potassa.* ( $\text{KO}, \text{CrO}_3$ .)

Bichromate of potassa of commerce is dissolved in water, and carbonate of potassa added till the solution reacts slightly alkaline; from the concentrated liquid yellow crystals may be obtained. It is employed principally as a test for lead, with which it forms a pigment known as chrome yellow.

28. *Sulphate of Potassa.* ( $\text{KO}, \text{SO}_3$ .)

The salt of commerce is purified by two or three crystallizations, and dissolved for use in ten or twelve parts of water; it is used for the detection and separation of strontia and baryta, and is preferable to sulphuric acid, which disturbs the neutrality of solutions.

29. *Bisulphate of Potassa.* ( $\text{KO}, 2\text{SO}_3$ .)

This is the fusible salt remaining when nitrate of potassa is decomposed by two equivalents of oil of vitriol in the process for making nitric acid; it is extensively employed in blowpipe operations; in solution it indicates lithia, boracic acid, nitric acid, hydrofluoric acid, bromine, and iodine, and separates baryta and strontia from other earths and metallic oxides. Rose recommends it as a flux for highly aluminous minerals, and J. C. Booth, for chromic and other similar ores.

30. *Bitartrate of Potassa.* ( $\text{KO}, \text{HO}, \text{T}$ .)

The cream of tartar of commerce is sufficiently pure; it is useful in certain cases for separating metals from each other.

31. *Cyanide of Potassium.* ( $\text{KCy}$ .)

Eight parts of roasted ferrocyanide of potassium are fused at a bright red heat in a covered crucible with three parts of dry carbonate of potassa; the fused mass is poured carefully into a warm dish, and when cold broken into fragments, and

kept in a well-closed bottle: it must not be kept in solution, but dissolved as required in four or five parts of water. In analysis its most important application is as a means of separating cobalt from nickel. As a blowpipe reagent mixed with an equal weight of carbonate of soda, it is exceedingly valuable from its powerful reducing action; and from its easy fusibility it is of special application in the reduction of arsenic.

### 32. *Antimoniate of Potassa.* ( $\text{KO}, \text{SbO}_5$ )\*

A mixture of one part of crude antimony with four parts of powdered nitre is thrown a little at a time into a crucible at a dull red heat; the mass is kept in a pasty state, with occasional stirring, for about half an hour, after which it is cooled, well washed, and heated to bright redness for half an hour, with two-thirds of its weight of pure carbonate of potassa. The cooled mass is digested with about fifty parts of warm water, and filtered for use when cold. It should not contain excess of alkali. Its use is as a test for soda, with which it forms a very sparingly soluble crystalline precipitate. As compounds of antimonious acid with the alkaline earths, and most of the metallic oxides are also insoluble, this reagent is inapplicable in their presence.

### 33. *Caustic Baryta.* ( $\text{BaO}$ .)

Sulphuret of barium is boiled with excess of oxide of copper or oxide of lead, and filtered when the liquid gives a white precipitate, with acetate of lead: it is then diluted with water, and preserved in well-closed bottles. Its most important use is as a precipitant of magnesia, and for the detection of carbonic acid.

### 34. *Chloride of Barium.* ( $\text{BaCl}$ .)

To prepare this useful reagent, six parts of heavy spar (sulphate of baryta) are exposed to an intense red heat, with a mixture of one part of powdered charcoal and one and a half of flour or resin; the resulting sulphuret of barium is boiled with slight excess of hydrochloric acid filtered, and crystallized two or three times. The solution of these crystals must be neutral to test-papers, not affected by sulphuretted hydrogen, or hydrosulphuret of ammonia: it must, moreover, leave

\* Fremy's mode of preparation is given in *Chem. Gaz.*, vi. 396.



no residue when mixed with excess of sulphuric acid, filtered and evaporated. Its most important use is as a means of detecting and estimating sulphuric acid. From the property which baryta possesses of forming soluble salts with some acids, and insoluble salts with others, it is likewise a valuable reagent for distinguishing one group of acids from another.

### 35. *Nitrate of Baryta.* ( $\text{BaO}, \text{NO}_3$ .)

Native carbonate of baryta is digested with dilute nitric acid, the solution filtered and crystallized two or three times. Its uses and applications are the same as those of chloride of barium, and in cases where a chloride would be inadmissible.

### 36. *Phosphate of Soda.* ( $\text{HO}, 2 \text{NaO}, \text{PO}_5$ .)

The commercial salt is crystallized and dissolved for use in ten or twelve parts of water. It serves as a test for alkaline earths in general, but especially for the detection and estimation of magnesia, which it precipitates with the addition of ammonia as the basic phosphate of ammonia and magnesia.

### 37. *Phosphate of Soda and Ammonia.* ( $\text{NaO}, \text{NH}_4\text{O}, \text{PO}_5$ .) HO.

This salt (microcosmic salt) is prepared by boiling one hundred parts of crystallized phosphate of soda with sixteen of sal-ammoniac. Chloride of sodium separates, and the liquid, when filtered and evaporated, yields the double salt in fine crystals. When this salt is heated on charcoal or platinum wire, it loses water and ammonia, *meta-phosphate of soda* is formed, which, in consequence of its excess of acid, has the power of fusing almost every chemical compound. Hence its great use as a blowpipe reagent, in preference to borax, the beads or buttons formed by the fusion of which are less distinctly colored.

### 38. *Nitrate of Potassa.* ( $\text{KO}, \text{NO}_3$ .)

The nitre of commerce is purified by repeated crystallizations: its solution should give no precipitate with nitrate of silver, or chloride of barium: it is extensively employed as an oxidizing agent.

39. *Biborate of Soda.* ( $\text{NaO}, 2\text{BO}_3$ .)

The borax of commerce is purified by recrystallization. It should be exposed to a gentle heat in a platinum crucible till it no longer swells up; it is then powdered and kept for use. When heated on the ring of platinum wire, it should give a clear transparent glass. This glass possesses the property of dissolving most metallic oxides, the smallest portions of which communicate to it a color; hence its important use as a blow-pipe reagent.

40. *Nitrate of Silver.* ( $\text{AgO}, \text{NO}_3$ .)

Standard silver is dissolved in nitric acid, evaporated to dryness, and heated till all the copper present is converted into black oxide, which may be known by dissolving a portion of the fused salt in water and adding ammonia, which should not make the solution blue. The fused mass is dissolved in water, filtered and crystallized; the crystals are dissolved for use in fifteen or twenty parts of distilled water. It may be known to be pure by the filtrate from the precipitate, which it forms with excess of hydrochloric acid, leaving no residue when evaporated on a watch-glass. It is employed for arranging acids into groups, and is of special application in testing for, and estimating hydrochloric acid.

41. *Ammonia Nitrate of Silver.* ( $\text{AgONO}_2 + 2\text{NH}_3$ .)

Ammonia is dropped into solution of nitrate of silver till the precipitate which first forms is nearly redissolved. It is employed for the detection of arsenic.

42. *Sulphate of Copper.* ( $\text{CuO}, \text{SO}_3$ .)

Blue vitriol is purified by two or three crystallizations. A solution of one part of this salt mixed with two and one quarter parts of protosulphate of iron is employed for the precipitation of hydriodic acid, as protiodide of copper. Ammonia-sulphate of copper prepared in the same manner as the corresponding silver salt is also employed as a test for arsenic.

43. *Iodide of Potassium.* ( $\text{KI}$ .)

The commercial salt is tested for carbonate of potassa by treating it with hot alcohol, in which the latter salt is insoluble.

ble. It is a reagent for certain metals, particularly for lead and mercury, with which it forms characteristic precipitates.

44. *Neutral Acetate of Lead.* ( $\text{PbO}, \bar{\text{A}}.$ )

The best sugar of lead of commerce is dissolved in ten or twelve parts of distilled water: it is useful for arranging acids into groups, and for the special detection of chromic acid.

45. *Basic Acetate of Lead.* ( $3 \text{PbO}, \bar{\text{A}}.$ )

Seven parts of well-washed litharge and six of the best neutral acetate of lead are gently heated and agitated with thirty parts of water till the sediment has become perfectly white; the liquid is then decanted and preserved for use in a well-closed bottle. It has the same applications as the last described salt, but its chief use is as a test for sulphuretted hydrogen.

46. *Protosulphate of Iron.* ( $\text{FeO}, \text{SO}_3.$ )

Clean iron nails are digested with dilute sulphuric acid till hydrogen ceases to be evolved. The solution is filtered, and the crystals obtained washed with water slightly acidified with sulphuric acid and dried. This salt is a powerful deoxidizing agent, and is of especial application as a test for nitric acid. It also precipitates gold in the metallic state, and forms a blue compound with ferrieyanide of potassium.

47. *Lime Water.* ( $\text{CaO}.$ )  $\text{HO}.$

Fresh slaked lime is agitated with cold water, allowed to settle, and the clear fluid preserved in well-stopped bottles. It serves to detect carbonic acid, and as a means of distinguishing certain organic acids,—citric, tartaric, paratartaric; and also to liberate ammonia from its combinations.

48. *Sulphate of Lime.* ( $\text{CaO}, \text{SO}_3.$ )

The precipitate formed on adding chloride of calcium to dilute sulphuric acid is well washed, digested, and agitated with water, and the fluid filtered for use. It is employed to distinguish between lime, strontia, and barytes.

49. *Chloride of Calcium.* ( $\text{CaCl}.$ )

Pure carbonate of lime is dissolved in dilute hydrochloric

acid. The solution must be perfectly neutral. It is of great use for the classification of organic acids, as it precipitates some and forms soluble compounds with others.

50. *Protochloride of Tin.* ( $\text{SnCl}_2$ .)

Granulated tin is boiled with concentrated hydrochloric acid, the metal being in excess; it is then diluted with four or five times its quantity of water, slightly acidulated with hydrochloric acid and filtered. It must be kept in well-closed bottles containing fragments of metallic tin to prevent the protochloride from passing into the state of perchloride. It is a powerful reducing agent. It also serves to detect mercury, and, when mixed with nitric acid, it indicates the presence of gold.

51. *Bichloride of Platinum.* ( $\text{PtCl}_2$ .)

The solution of the metal in aqua regia is evaporated to dryness in the water bath, and redissolved in eight or ten parts of water. It is of great use in analytical chemistry for the detection and estimation of potassa and ammonia.

52. *Sesquichloride of Iron.* ( $\text{Fe}_2\text{Cl}_3$ .)

Clean iron nails are digested with diluted hydrochloric acid; the decanted acid liquid is then boiled with successive additions of nitric acid, in a capacious vessel, till all effervescence ceases, and till it no longer tinges solution of red prussiate of potassa blue; it is then precipitated with excess of ammonia, and the well-washed hydrated peroxide of iron is heated with hydrochloric acid, care being taken that it is not all dissolved, it being necessary that the test should not contain excess of acid; it is then filtered for use. It is employed as a means of classifying organic acids which are not precipitated by chloride of calcium, and is also of great use in the analysis of the phosphates of the alkaline earths.

53. *Sulphurous Acid.* ( $\text{SO}_2$ .)

This is prepared by transmitting the gases produced by the action of six parts of oil of vitriol on one part of charcoal (carbonic and sulphurous acid gases) through ice-cold water till no more is absorbed. It must be kept in well-closed bottles, and should always smell strongly of the acid. It is a



powerful means of reduction ; it precipitates mercury from its solution, converts chromic acid into oxide of chromium, arsenic acid into arsenious acid, &c.

54. *Hydrofluosilicic Acid.* ( $3 \text{ HF}, + 2 \text{ SiF}_3$ .)

Equal weights of powdered fluor spar and quartz are gently heated, together, in a retort, with six parts of oil of vitriol, and the gas evolved passed into water, the extremity of the delivering tube dipping into mercury placed at the bottom of the jar in order to prevent the tube from becoming choked up with the silicic acid which is precipitated the instant the gas comes into contact with water. The gelatinous mass is filtered through linen, and the filtrate preserved for use. Hydrofluosilicic acid forms an insoluble compound with potassa, which base it is sometimes employed to separate from chloric acid. It is also used to discriminate between baryta and strontia, with the former of which it forms a crystalline deposit.

55. *Chlorine Water.* ( $\text{Cl.}$ )  $\text{HO.}$

The gas evolved by heating finely powdered peroxide of manganese with five or six times its weight of hydrochloric acid is conducted into ice-cold water, until the fluid is saturated. It must be kept in a well-closed bottle and preserved from the light. It is employed to expel iodine and bromine from their combinations.

56. *Chloride of Mercury.* ( $\text{HgCl.}$ )

The corrosive sublimate of commerce is purified by crystallization, and dissolved for use in 12 or 14 parts of water. It forms characteristic colored precipitates with certain acids.

57. *Protonitrate of Mercury.* ( $\text{Hg}_2\text{O,NO}_5$ .)

Mercury is gently heated with an equal weight of nitric acid of 1.23, till the formation of red fumes ceases; it is then boiled with the undissolved metal till a few drops of the solution are so completely precipitated by common salt, that no precipitate occurs in the filtered liquid on the addition of protochloride of zinc. The solution is then agitated till it is cold, and the crystals formed, shaken with 20 parts of cold water, to which a small quantity of nitric acid has been added. The bottle in which this reagent is kept should contain a small

quantity of mercury. Its applications are the same as those of nitrate of silver. It is likewise employed to detect several substances of easy oxidation, formic acid, for instance, which it resolves into carbonic acid and water, a reduction of the metal at the same time taking place.

#### 58. *Protonitrate of Cobalt.* ( $\text{CoO}, \text{NO}_5$ .)

It is not easy to obtain this reagent quite pure, though for blowpipe experiments it is a matter of great consequence that it should be so. Fresenius gives the following directions for preparing it:—an intimate mixture of two parts of very finely powdered cobalt, four parts of saltpetre, one part of effloresced carbonate of soda, and one part of dry carbonate of potassa, is projected in small portions into a red-hot crucible, which is then exposed to the strongest possible heat till the mass is fusing; when cold, it is reduced to powder, boiled with water, and the well-washed mass dissolved in hydrochloric acid; the gelatinous mass is carefully evaporated to dryness; the residue boiled with water, filtered, and carbonate of ammonia (carbonate of potassa is better) added to the filtrate while kept at the boiling heat till all acid reaction ceases; the filtered solution is precipitated by carbonate of potassa, and the precipitate obtained washed and dissolved in nitric acid. The solution is evaporated to dryness at a gentle heat, and one part of the residue dissolved in ten parts of water for use. Solution of nitrate of cobalt is employed to distinguish certain metals in the oxidating flame of the blowpipe. Thus alumina acquires a beautiful pale blue color, magnesia a rose-red tint, and zinc a bright green. A few drops of the solution are placed on the substance to be operated upon by means of a platinum wire or dropping tube.

#### 59. *Distilled Water.* ( $\text{HO}$ .)

No other water should be employed in analysis. It should give no precipitate or even turbidity with chloride of barium, nitrate of silver, oxalate of ammonia or lime water, and should leave no residue on evaporation.

#### 60. *Alcohol.* ( $\text{C}_4\text{H}_6\text{O}_2$ .)

Rectified spirits of wine, sp. gr. about .840, are sufficiently strong for most purposes. What is termed absolute alcohol,

and which is sometimes required, is prepared by adding carbonate of potassa, that has recently been exposed to a red heat, to ordinary alcohol until it ceases to dissolve any more; the whole is allowed to digest for 24 hours; the liquid is then poured off, mixed with a sufficient quantity of quicklime to absorb the whole, and slowly distilled from a retort on a water bath at the temperature of about  $180^{\circ}$ ; it is then obtained of a sp. gr. of .7947. It must not redden litmus paper, and must volatilize without leaving any residue.

Alcohol is used as a solvent, and hence for the precipitation from solution, of substances insoluble in it. The characteristic tint imparted by certain substances to its flame serves for their detection.

#### 61. *Ether.* ( $C_4H_5O$ .)

Sulphuric ether of commerce when free from acid, is sufficiently strong and pure for all purposes. In inorganic analysis it is employed to detect and isolate bromine.

#### 62. *Acetate of Potassa.* ( $KO, \bar{A}$ .)

Prepared by dissolving pure carbonate of potassa in water and adding acetic acid until the solution is perfectly neutral. Is particularly useful for the detection of tartaric acid as the precipitated bi-salt is insoluble in the liberated acetic acid. It is also employed in analyses of the alkaline earthy phosphates.

#### 63. *Basic Silicate of Potassa.* ( $3KO, SiO_3$ .)

Employed in solution to detect phosphoric acid in phosphate of alumina. It is obtained by digesting gelatinous hydrate of silica in potassa water.

#### 64. *Succinate of Ammonia* (Neutral). ( $NH_4O, \bar{S} = (C_4H_2O_3)$ .)

Employed to distinguish baryta from strontia; and from lime, when hydrofluosilicic acid is not at hand. It is also used to separate protoxide of manganese from peroxide of iron.

#### 65. *Bicarb. Potassa.* ( $KO, 2CO_2$ .)

Is used in solution to distinguish magnesia from alumina and also baryta, strontia and lime from protoxide of manganese.

66. *Carbazotic Acid.* ( $C_{12}H_2N_3O_{13} + Aq.$ )

A very sensitive test for potassa, and may be prepared by adding cautiously and portionwise one part of finely powdered indigo to eleven parts of nitric acid (sp. gr. 1.43), and after the liquid is quiet, adding during boiling more acid until nitric oxide ceases to be given off. The solution on cooling drops the acid in crystals, which must be purified by solution in potash, precipitation by nitric acid and recrystallization from water.

67. *Nitrate of Nickel.* ( $NiO, NO_5.$ )

Used in solution to distinguish soda from potassa.

68. *Chloride of Gold.* ( $AuCl_3.$ )

Prepared by dissolving pure gold leaf with aid of heat in aqua regia, evaporating to dryness and redissolving in water. It is used for detecting protoxide of tin and also for converting protochlorides and protoxides into perchlorides and peroxides and chlorides.

69. *Sulphate of Alumina.* ( $Al_2O_3, 3SO_3.$ )

Prepared by dissolving pure alumina in sulphuric acid and crystallizing. Is employed to detect potassa and ammonia.

70. *Cyanide of Mercury.* ( $Hg, Cy.$ )

This reagent serves to detect palladium, and in some cases platinum.

71. *Chloride of Lead.* ( $Pb, Cl.$ )

Used in solution as a precipitate for silver when lead is present in large proportion. The ordinary precipitants of silver, hydrochloric acid and chloride of sodium, have no effect in dilute solutions, but solution of chloride of lead being very weak even when concentrated, throws down only the silver.

72. *Infusion of Galls.*

The aqueous infusion or tincture is used as a delicate test for peroxide of iron, in neutral solutions, with which it forms a black precipitate. It is also employed as a test for titanous



and tantalic acids, and in organic analysis for gelatin, which it precipitates from solutions in dirty white curdy flocculæ.

### 73. *Zinc.* (Zn.)

Zinc is employed for the reduction and precipitation of many metallic salts and oxides. Its principal use is for the precipitation of antimony and of tin and for separating silver from chloride of silver. The zinc must be previously purified by digestion in nitric acid which leaves the tin and antimony undissolved, converts the arsenic into arsenic acid, and dissolves the iron and cadmium. These latter two are precipitated by an excess of carbonate of ammonia; the filtered liquid is then evaporated to dryness, the residue ignited, dissolved in nitric acid and the solution precipitated with carbonate of potassa, which leaves the arsenic in the liquid. The precipitate is well washed, ignited and then reduced at a red heat with hydrogen. (*Smedt.*)

### 74. *Iron.* (Fe.)

Used in wire with polished surface for the detection of copper, which it precipitates in a metallic state.

### 75. *Copper.* (Cu.)

Employed in bright strips for the reduction and precipitation of mercury and in Reinsch's process for the detection of arsenic.

The student is recommended to prepare, as far as possible, his own reagents. He should at any rate assure himself by careful testing of their purity; by so doing he will not only save himself from much subsequent embarrassment, but he will be gaining much valuable experience in qualitative examinations.

## CHAPTER III.

## ON THE COMPORTMENT OF SUBSTANCES WITH REAGENTS.

## 1. METALLIC OXIDES.

By means of certain reagents this extensive class of compounds may be arranged into a series of groups; some of which, again, by other reagents may be subdivided into sections, the whole forming a very convenient classification.

*First Group.*—Metallic oxides not precipitated from their solutions by sulphuretted hydrogen, hydrosulphuret of ammonia, or alkaline carbonates.

The alkalis proper: *potassa, soda, lithia, ammonia.*

*Second Group.*—Metallic oxides not precipitated from their solutions by sulphuretted hydrogen, precipitated by hydrosulphuret of ammonia only under certain circumstances, as salts, and precipitated by alkaline carbonates.

The alkaline earths: *baryta, strontia, lime, magnesia.*

*Third Group.*—Metallic oxides not precipitated by sulphuretted hydrogen, but precipitated as oxides by hydrosulphuret of ammonia.

*Alumina, glucina, oxide of chromium, thorina, yttria, oxides of cerium, zirconia, titanio acid, tantalic acid.*

*Fourth Group.*—Metallic oxides not precipitated from their acid solutions by sulphuretted hydrogen, but completely precipitated by hydrosulphuret of ammonia as *sulphurets*.

*Oxide of zinc, oxide of nickel, oxide of cobalt, protoxide of manganese, protoxide and sesquioxide of iron, and sesquioxide of uranium.*

*Fifth Group.*—Metallic oxides completely precipitated from their solutions, whether acid, alkaline, or neutral, by sulphuretted hydrogen, their sulphurets being insoluble in alkaline hydrosulphurets. *Oxide of lead, oxide of silver, oxides of mercury, oxide of bismuth, oxide of cadmium, oxide of copper, oxide of palladium, sesquioxide of rhodium, oxide of osmium.*

*Sixth Group.*—Metallic oxides completely precipitated from their acid solutions by sulphuretted hydrogen, but not from

their alkaline solutions, their sulphurets being soluble in alkaline sulphurets.

*Oxide of antimony, oxide of arsenic, oxide of tin, oxide of platinum, oxide of iridium, oxide of gold, oxides of selenium, tellurium, tungsten, vanadium, and molybdenum.*

## GROUP 1.

*The Alkalies Proper, Potassa, Soda, Lithia, Ammonia.*

### POTASSA (KO).

*General Characters:* When pure it is quite white, dissolving in water with the disengagement of heat, and attracting both water and carbonic acid from the atmosphere. It is highly caustic, and eminently alkaline; nearly all its salts are soluble in water; it is capable of being precipitated by very few reagents. Its presence is, however, evinced by the following.

*Bichloride of platinum* produces a bright yellow crystalline precipitate of double chloride of platinum and potassium ( $KCl + PtCl_2$ ) very sparingly soluble in water, and the formation of which is promoted by the presence of free hydrochloric acid. It is quite insoluble in strong alcohol. Previous to applying this test, the operator must be certain of the absence of ammonia, and the solution should be concentrated.

*Tartaric acid* added in excess produces a granular crystalline precipitate ( $KO, HO, T$ ) soluble in strong acids and in carbonated and caustic alkalies, but insoluble in tartaric and acetic acids; the formation of the precipitate is facilitated by agitation and by the addition of alcohol.

*Carbazotic acid* dissolved in alcohol produces even in dilute solutions a bright yellow crystalline precipitate.

*Perchloric acid* produces a sparingly soluble white crystalline precipitate.

*Hydrofluosilicic acid*, poured in excess into concentrated solutions of potassa gives a gelatinous translucent precipitate, insoluble in muriatic acid but losing transparency in its presence.

*Concentrated sulphate of alumina* forms crystals of alum when poured into strong solutions of potassa previously saturated with an acid (hydrochloric).

*Before the blowpipe*, potassa salts, if free from soda, heated on a platinum wire in the inner flame, tinge the outer flame

*violet*; if soda salts be present, potassa may be detected by fusing a clear bead of borax with a small quantity of *oxide of nickel*, and then adding the mixture, the brown color of the bead is changed to blue.\*

#### SODA (NaO).

*General Characters:* They are very similar to those of potassa; its dilute solution or that of any of its salts affords no precipitates with any of the above reagents for potassa; but

*Antimoniate of potassa*, if properly prepared, produces in neutral and even in very diluted solution, if well agitated, and provided no other oxide but potassa be present, a crystalline precipitate ( $\text{NaO}, \text{SbO}_3$ ). *Hydrofluosilicic acid* produces in *concentrated* soda solutions a gelatinous precipitate of silicofluoride of sodium.

*Before the blowpipe*, soda salts are distinguished by the strong yellow colour which they communicate to the outer flame, which reaction is not prevented by a very considerable excess of potassa. According to *Kobell*, one part of chloride of sodium may hereby be detected in 25 or 30 parts of chloride of potassium.—See note below.

\* Potassa as well as soda may be detected in the presence of magnesia by Chapman's method, as follows:

"1st. A small quantity of boracic acid (perfectly pure) is to be fused before the blowpipe in a loop of platinum wire; 2d, a portion of the compound under examination, with a particle of oxide of copper, is then to be added to it; and, 3d, the whole subjected to an oxidating flame. If magnesia alone be present, the greater portion of it will remain undissolved, together with the oxide of copper, in the flux, the bead continuing colorless; if, on the contrary, potash or soda be mixed with the magnesia, these bodies will be immediately dissolved by the boracic acid, forming borate of potash or soda, in which the oxide of copper dissolves, communicating to the compound its peculiar colors, the bead becoming green whilst hot and blue when cold.

"If the alkaline salt be in excess, the magnesia will be also dissolved. If the contrary be the case, the coloration from the dissolved oxide of copper will still be effected; but the magnesia will be perceived in the centre of the globule as a white or light-colored insoluble mass.

"It must be observed that salts of baryta or strontia fuse likewise with boracic acid, giving rise to borate of baryta or strontia, in which, as in the alkaline borates, oxide of copper dissolves, producing a green or blue coloration. If present, therefore, in the magnesia compound, these bodies must be removed by sulphuric acid before attempting to ascertain the presence of the alkalis by the above method. We can finally examine a fresh portion of the assay matter for potash by chloride of platinum, and for soda by the production of its well-known yellow flame."



LITHIA ( $\text{LiO}$ ).

*General Characters:* When pure, this oxide is white; it is not so soluble in water as potassa or soda; its solution rapidly absorbs carbonic acid, when exposed to the air. Carbonate of lithia is very sparingly soluble in water. When a solution of a lithia salt is boiled with phosphate of soda no precipitate occurs, but if ammonia be added, a very sparingly soluble double phosphate of soda and lithia is deposited.

*Tartaric and oxalic acids* give no precipitate in salts of lithia.

*Before the blowpipe*, salts of lithia are detected by the fine crimson tinge which they communicate to the outer flame, when heated in the inner flame on platina wire. Potassa salts do not interfere with this reaction; but soda salts destroy it, substituting for the crimson their own peculiar yellow color. Lithia may be distinguished from strontia by fusing the suspected substance with chloride of barium, the presence of which, according to Plattner and Chapman, prevents chloride of strontium from imparting a crimson flame, whilst it does not impair the fine red color characteristic of lithia.

AMMONIA ( $\text{NH}_4\text{O}$ ).

*General Characters:* The solution of pure ammonia in water is when concentrated highly caustic and alkaline; it has a powerful and penetrating smell, by which its presence can generally be detected. It attracts carbonic acid from the atmosphere. Most of its salts are soluble in water; and nearly all of them are totally volatilizable by heat. When present in an uncombined state in a quantity too small to be detected by the smell, its presence may be evinced by the production of white clouds, when a feather dipped in strong hydrochloric, or acetic acid (the former is preferable), is held over the liquid.

*Behavior of Ammonia and Ammoniacal Salts with Reagents.*

*Bichloride of platinum* produces a yellow crystalline precipitate ( $\text{NH}_4\text{Cl} + \text{PtCl}_2$ ) having a great resemblance to the corresponding double salt of potassium.

*Tartaric acid* produces, in concentrated solutions, only a crystalline bitartrate of ammonia much more soluble than the corresponding potassa salt.

*Carbazotic acid* produces no precipitate except in very concentrated solutions.

When mixed and triturated with hydrate of lime, or caustic potassa, ammoniacal salts part with their ammonia, which may then be detected either by its smell or by strong acetic acid, or by reddened litmus paper. This reaction is facilitated by the application of slight warmth.

## GROUP 2.

*The Alkaline Earths, Baryta, Strontia, Lime, Magnesia.*

### BARYTA ( $\text{BaO}$ ).

*General Characters:* When pure it is of a grayish white color; it combines with water with the evolution of great heat, and is completely dissolved. Its concentrated aqueous solution deposits crystals of hydrate. It is powerfully caustic and alkaline; it combines greedily with carbonic acid, forming a white insoluble compound, which is poisonous.

#### *Behavior of Soluble Barytic Salts with Reagents.*

*Alkaline carbonates* produce a white precipitate ( $\text{BaO}, \text{CO}_2$ ) soluble with effervescence in free acids.

*Ammonia and caustic alkalis* do not produce any permanent precipitate, provided atmospheric air be excluded.

*Sulphuric acid*, or solution of any *soluble sulphate*, (sulphate of lime preferable,) produces, even in the most dilute solutions, a white precipitate ( $\text{BaO}, \text{SO}_3$ ) wholly insoluble in all acids and alkalis.

*Hydrofluosilicic acid* produces after awhile a colorless crystalline precipitate ( $3\text{BaFl} + 2\text{SiFl}_3$ ) silico fluoride of barium, almost completely insoluble in free nitric or muriatic acids.

*Neutral phosphate of soda* produces a white precipitate ( $2\text{BaO}, \text{HO}, \text{PO}_3$ ) soluble in free acids.

*Oxalic acid*, or *binoxalate of potassa*, produces in concentrated solutions only, a white precipitate ( $\text{BaO}, \bar{\text{O}} + \text{aq.}$ ) soluble in free acids; the formation of this precipitate is favored by ammonia. The absence of strontia and lime must be ascertained previous to the use of this test.

*Chromate of potassa* produces a yellow precipitate ( $\text{BaO}$ ,  $\text{CrO}_3$ ) soluble in nitric acid and in caustic alkalies.

*Hydrosulphuret of ammonia* gives no precipitate in barytic solutions.

*Ferrocyanuret of potassium* produces in strong solutions, after some time, a yellowish white precipitate of ferrocyanuret of potassium and barium.

*Before the blowpipe*, baryta cannot positively be detected; most of its salts impart a yellow color to the flame of alcohol, but it is not characteristic.

#### STRONTIA ( $\text{StrO}$ ).

*General Characters:* It greatly resembles baryta, but it is not so heavy, neither is its hydrate so soluble in water; its aqueous solution is consequently less caustic.

#### *Behavior of Soluble Strontia Salts with Reagents.*

*Alkaline carbonates, the caustic alkalies and phosphate of soda*, behave towards solutions of strontia salts precisely as towards solutions of baryta salts.

*Sulphuric acid* produces a white precipitate ( $\text{StrO}, \text{SO}_3$ ) insoluble in free acids, but not altogether insoluble in water: in very dilute solutions, therefore, sulphate of lime and other soluble sulphates do not occasion an immediate precipitate.

*Hydrofluosilicic acid* occasions no precipitate even in concentrated solutions, and this acid affords a means of separating strontia from baryta, for the latter is precipitated by it, while the former unites with it, forming a salt readily soluble in a slight excess of acid.

*Chromate of potassa* in cold and dilute solutions produces no precipitate; but, by boiling, a copious yellow precipitate ( $\text{StrO}, \text{CrO}_3$ ) is determined.

*Oxalic acid* produces a white precipitate ( $\text{StrO}, \bar{\text{O}} + \text{aq.}$ ) even in dilute neutral solutions: in very dilute solutions the precipitate is immediately determined by the addition of ammonia.

*Ferrocyanuret of potassium* gives no precipitate.

*Hydrosulphuret of ammonia* does not produce any precipitate.

*Before the blowpipe* sulphate of strontia fuses to an opalescent mass, and colors the outer flame carmine red. Chloride

of strontium, heated on the ring of platinum wire at the apex of the blue flame, tinges the whole flame immediately deep crimson; but as the assay fuses the color disappears, by which it is distinguished from chloride of lithium. The presence of chloride of barium prevents the production of the colored flame. Soluble salts of strontia, digested with alcohol, and inflamed, give rise to an intense and characteristic carmine red color.

#### LIME (CaO).

*General Characters:* When pure, it is white and infusible. It has an acrid, caustic, alkaline taste. It has a powerful affinity for water, in combining with which it emits great heat, and falls into a bulky powder. The hydrate of lime is far less soluble in water than the hydrates of the two preceding oxides, one part requiring for a perfect solution from 450 to 500 parts of water. The solution is slightly caustic, and gradually absorbs carbonic acid from the atmosphere, until the whole of the lime is converted into carbonate.

#### *Behavior of Solutions of Salts of Lime with Reagents.*

The *caustic and carbonated alkalies*, and *phosphate of soda*, behave with calcareous solutions precisely as with solutions of baryta and strontia.

*Sulphuric acid* and the *soluble sulphates* occasion no precipitate in very dilute solutions; but, on the addition of alcohol, a precipitate ( $\text{CaO}, \text{SO}_3$ ) immediately takes place: in concentrated solutions a bulky precipitate is produced, soluble, though not remarkably so, in nitric and hydrochloric acids.

*Hydrofluosilicic and perchloric acids* do not produce any precipitate in solutions of calcareous salts.

*Oxalic acid* and the *soluble oxalates* occasion an immediate precipitate ( $\text{CaO}, \bar{\text{O}} + 2\text{aq.}$ ) in neutral solutions, soluble in the mineral acids, but nearly insoluble in acetic acid. The formation of this precipitate is increased and quickened by the addition of ammonia.

*Hydrosulphuret of ammonia* does not produce any precipitate.

*Ferrocyanuret of potassium* gives a white precipitate only



in very strong solutions. The precipitate is soluble in hydrochloric acid.

*Before the blowpipe*, chloride of calcium, unless it has been fused, heated on the ring of the platinum wire tinges the outer flame red, but the color is more feeble than with chloride of strontium. Pure lime and the carbonate emit a very strong light. Soluble lime salts impart a yellowish red tinge to the flame of alcohol.

Plattner detects lime in barytic and strontia salts by fusing them with salt of soda upon a platinum foil:—if the salts are pure the flux remains clear,—if they contain lime it remains undissolved.

#### MAGNESIA ( $\text{MgO}$ ).

*General Characters*: It is a white infusible powder, possessed of a feeble but distinct alkaline reaction. Like lime, it is more soluble in cold than in hot water: 36,000 parts of boiling water, and 5,142 parts at  $32^\circ$ , being required to dissolve one part of the earth. Caustic magnesia does not emit any heat on being moistened with water.

#### *Behavior of Magnesian Salts with Reagents.*

*Ammonia*, in neutral solutions, occasions a white bulky precipitate ( $\text{MgO}, \text{HIO}$ ). If the solution be acid, or if ammoniacal salts be present, no precipitate takes place, in consequence of the property possessed by magnesia of forming double salts with ammonia.

*Caustic potassa* produces a voluminous flocculent precipitate, which disappears on the addition of muriate of ammonia; but, on boiling with excess of potassa, the precipitate reappears, in consequence of the decomposition of the ammoniacal salt.

*Carbonate of potassa* produces in neutral solutions, and in the absence of ammoniacal salts, a white voluminous precipitate  $2 (\text{HIO}, \text{MgO}) + 3 (\text{MgO}, \text{CO}_2)$ , which is increased by boiling, in consequence of the expulsion of the carbonic acid which in the cold keeps a portion of magnesia in solution in the form of bicarbonate.

*Carbonate of ammonia*, by boiling, and in the absence of ammoniacal salts, occasions a slight precipitate of subcarbonate.

*Sulphuric acid* produces no precipitate ( $\text{MgO}, \text{SO}_3$ ), being very soluble in water.

*Phosphate of soda* alone does not produce any precipitate in very dilute cold solutions; but, if ammonia be added, a crystalline precipitate of basic phosphate of magnesia and ammonia ( $2\text{MgO}, \text{NH}_4\text{O}, \text{PO}_5 + 2\text{H}_2\text{O} + 10\text{H}_2\text{O}$ ) is formed in highly diluted solutions. This precipitate is insoluble in ammoniacal salts, but soluble in free acids.

*Oxalate of ammonia*, in the absence of ammoniacal salts, forms a white precipitate ( $\text{MgO}, \bar{\text{O}} + 2 \text{aq}$ ), but oxalic acid gives none in neutral solutions.

*Hydrosulphuret of ammonia* gives no precipitate in neutral solutions, unless they are very concentrated, or contain free ammonia.

*Before the blowpipe*, in the absence of other metallic oxides, salts of magnesia, when ignited on charcoal, then moistened with solution of protonitrate of cobalt, and again strongly ignited, acquire a feeble red tint, visible only on cooling of the button.

#### *General Remarks on the Oxides of the Second Group.*

From the property of magnesia to form soluble double salts with ammonia, this earth may be kept in solution by the addition of sal-ammoniac and ammonia, while baryta, strontia, and lime are precipitated by carbonate of ammonia. The magnesia is detected in the filtered liquid by phosphate of soda. The immediate formation of a precipitate, on the addition of hydrofluosilicic acid, is characteristic of baryta. Strontia, in combination with baryta, is detected by converting both earths into chlorides, and digesting with absolute alcohol, in which chloride of barium is almost insoluble. Chloride of strontium is detected in the alcoholic solution by the carmine red flame it communicates to the alcohol when ignited; and lime is detected by oxalate of ammonia. To discover the alkalies in the presence of the oxides of the second group, the baryta, strontia, and lime are first removed by boiling with carbonate of ammonia and caustic ammonia, and from the filtered liquid the magnesia is precipitated by water of baryta; the excess of baryta is removed by adding sulphuric acid in slight excess, and boiling; the whole is then filtered, and the clear filtrate evaporated to dryness in a platinum dish, and ignited;

the residue is redissolved in water, and the solution tested for potassa, soda, and lithia, by dividing it into three portions, and proceeding with each in the manner above directed for the discovery of the alkalies. A portion of the original solution is tested for ammonia by heating with caustic potassa, and applying a feather moistened with strong acetic acid to the mouth of the tube.

### GROUP 3.

*Metallic Oxides* not precipitated by sulphuretted hydrogen, but precipitated as oxides by hydrosulphuret of ammonia, *Alumina, Yttria, Glucina, Thorina, Zirconia, Oxide of Chromium, Oxides of Cerium, Titanic Acid, Tantallic Acid.*

#### ALUMINA ( $\text{Al}_2\text{O}_3$ ).

*General Characters:* When pure it is white, and in the state of powder it is light, and not at all compact. It has neither taste nor smell, but it adheres to the tongue, thereby occasioning a slight sense of astringency. By the heat produced by a stream of oxygen gas directed against the flame of a spirit-lamp, it slowly melts, and gives a limpid and colorless globule, which, on cooling, becomes crystalline. It is quite insoluble in water, although it possesses a powerful affinity for that fluid, from which it can only be deprived by heating to redness. It condenses moisture from the atmosphere in a remarkable manner. The hydrate of alumina has a strong affinity for vegetable coloring principles.

#### *Behavior of Aluminous Solutions with Reagents.*

*Potassa* produces in neutral solutions a bulky precipitate ( $\text{Al}_2\text{O}_3 \cdot \text{H}_2\text{O}$ ), entirely soluble in excess of the precipitant, but reprecipitated by solution of salammoniac, which destroys the solvent,  $\text{NH}_4\text{Cl} + \text{KO}$  becoming  $\text{KCl} + \text{NH}_4\text{O}$ .

*Ammonia* occasions a bulky precipitate, not soluble in excess of the precipitant, and insoluble also in solution of salammoniac.

The *alkaline carbonates* precipitate  $\text{Al}_2\text{O}_3 \cdot \text{H}_2\text{O}$ , with the evolution of carbonic acid.

*Phosphate of soda* produces, in neutral solutions, a precipitate soluble in free acids, and in potassa.

*Silicate of potassa* (soluble glass) produces a precipitate of alumina in solutions of alumina in potassa.

*Before the blowpipe*, alumina, and many of its compounds, may be detected by heating the assay on charcoal, then moistening it with solution of protonitrate of cobalt; and again heating it strongly in the oxidating flame, a fine blue color is produced.

#### GLUCINA (GIO).

*Oxide of Beryllium.* — *General Characters:* This earth, when pure, has neither smell nor taste. It is insoluble in water, and infusible; but it does not harden in the fire like alumina, neither is the paste which it forms with water plastic. After ignition it is less soluble in acids.

#### *Behavior of Solutions of Glucina with Reagents.*

*Potassa* precipitates and redissolves it; but, by continuous boiling in a dilute alkaline liquor, the earth is again completely precipitated. Solution of sal-ammoniac likewise precipitates it from its solution in potassa.

*Ammonia* produces a voluminous precipitate, insoluble in excess of precipitant; the presence of chloride of ammonium does not prevent the formation of this precipitate.

The *carbonated alkalis* occasion a bulky precipitate, which is soluble in great excess of the precipitants, but more easily in carbonate of ammonia than in carbonate of potassa.

*Phosphate of soda* produces a voluminous precipitate.

Free acids produce no precipitate in glucina solutions.

*Before the Blowpipe*, glucina and its salts cannot well be detected; they do not become blue when strongly heated with protonitrate of cobalt, like alumina, but take a gray or black shade.

#### YTTRIA (YO).

*General Characters:* This earth is of a pale yellow color. Its specific gravity is 4.842; hence it is heavier than baryta, the specific gravity of which is 4.00. It is soluble in acids after ignition. It gradually absorbs carbonic acid from the



atmosphere. Many of its salts have a faint amethyst red color and a sweet taste.

*Behavior of Salts of Yttria with Reagents.*

*Potassa* produces a white voluminous precipitate, insoluble in excess of the precipitant even by heat.

*Ammonia* behaves in the same manner.

The *carbonated alkalis* produce precipitates soluble in excess of the precipitants, particularly in carbonate of ammonia. From the latter solution, crystals of double carbonate of ammonia and yttria may be obtained. When yttria contains peroxide of iron, or of cerium, it is very sparingly soluble in a solution of carbonate of ammonia.

*Sulphate of potassa* produces, after a time, a precipitate which is completely redissolved by the addition of water, even if the water contain sulphate of potassa in solution.

*Phosphate of soda* produces a precipitate soluble in hydrochloric acid, from which it is again thrown down by boiling.

*Ferrocyanide of potassium* occasions a white precipitate.

*Oxalic acid* gives, in faintly acid solutions, a white precipitate, soluble in hydrochloric acid.

*Before the blowpipe*, yttria cannot with certainty be detected. According to Plattner, phosphate of yttria may be recognized by its giving a regulus of phosphuret of iron with boracic acid and iron, and from the difficulty with which it is dissolved by microcosmic salt.

THORINA (ThO).

*General Characters:* This rare earth is, when quite free from manganese, *white*. It is the heaviest of all the earths, its sp. gr. being 9.402. Its solutions have an astringent taste; it absorbs carbonic acid from the air. When moist, the hydrate dissolves readily in acids; but after having been dried it is acted on with difficulty. The calcined earth is only attacked by hot sulphuric acid. Sulphate of thorina is, according to Berzelius, distinguished from all other oxidized bodies known, by its property of being precipitated by boiling, and slowly redissolving on cooling.

*Behavior of Solutions of Thorina with Reagents.*

*Potassa* and *ammonia* produce a quickly subsiding precipitate insoluble in an excess of the precipitants.

*The carbonated alkalis* produce a precipitate dissolving readily in an excess of the precipitants.

*Sulphate of potassa* produces a double salt, insoluble in water containing sulphate of potassa.

*Ferrocyanide of potassium* occasions a heavy white precipitate soluble in acids.

*Before the blowpipe*, the reactions of thorina have not been studied.

#### ZIRCONIA ( $Zr_2O_3$ ).

*General Characters:* When pure and calcined, zirconia is a white infusible powder; when ignited, it becomes brilliantly incandescent; it is sufficiently hard to scratch glass. Its sp. gr. is 4.3. After having been ignited, it is soluble only in concentrated sulphuric acid. Its soluble salts have a purely astringent taste without any sweetness.

#### *Behavior of Solutions of Zirconia with Reagents.*

*Potassa and ammonia* produce precipitates insoluble in an excess of the precipitants.

*The carbonated alkalis* produce precipitates slightly soluble in an excess of the precipitants; the hydrate of zirconia is soluble in carbonate of ammonia, but very sparingly so in the carbonates of the fixed alkalis.

*Ferrocyanide of potassium* occasions a white precipitate.

*Sulphate of potash* produces, after a time, in hot solutions, a white double salt almost insoluble in pure water.

*Before the blowpipe*, zirconia cannot be recognized except by the brilliant light it affords when ignited.

#### OXIDE OF CHROMIUM ( $Cr_2O_3$ )

*General Characters:* After ignition it is of a fine green color, and is only soluble in hot sulphuric acid: the hydrate is of a grayish green color, and is readily soluble in acids, forming green solutions under reflected, and red by transmitted light; but if the hydrate has been strongly dried, but not ignited, it dissolves in acids with difficulty.

#### *Behavior of Solutions of Oxide of Chromium with Reagents.*

*Potassa* produces a bluish green precipitate ( $Cr_2O_3 \cdot HO$ ),

readily soluble in an excess of the precipitant forming a green solution, from which the green anhydrous oxide is reprecipitated by boiling either alone or with chloride of ammonium.

*Ammonia and carbonate of ammonia* produce a bluish green precipitate, partially soluble in the precipitant, to which it imparts a red color; but the precipitation is complete by boiling the ammoniacal solution.

*Carbonate of potassa* produces a bluish green precipitate, soluble completely in considerable excess of the precipitant, and not reprecipitated by boiling.

*Phosphate of soda* produces a light green precipitate.

Any compound of oxide of chromium when fused with nitre gives rise to the formation of chromate of potassa ( $\text{KO}$ ,  $\text{CrO}_3$ ), which is soluble in water, and to which it communicates a yellow color.

*Before the blowpipe*, the presence of oxide of chromium is easily detected by the beautiful green bead obtained when it is heated with borax or microcosmic salt, both in the inner and outer flame: oxide of copper gives also a green bead, but only in the outer flame.

#### OXIDES OF CERIUM ( $\text{CeO}$ , $\text{Ce}_2\text{O}_3$ ).

*General Characters:* The hydrated protoxide of cerium, when first precipitated, is white, but it gets rapidly yellow by exposure to the air by absorbing oxygen; it has never been obtained in a pure anhydrous state. Peroxide of cerium is a powder of a brick red color; it is easily dissolved by acids; when heated with hydrochloric acid, chlorine is evolved.

#### *Behavior of Solutions of Oxide of Cerium with Reagents.*

*Potassa and Ammonia* produce bulky precipitates, insoluble in excess of the precipitants; the precipitate is first yellowish white, but by exposure to the air it becomes deep yellow.

The *alkaline carbonates* produce a precipitate soluble in a slight degree in an excess of the precipitants, which thereby acquire a yellow color.

*Ferrocyanide of potassium* occasions a white precipitate in neutral solutions.

*Sulphate of potassa* forms after a time, a crystalline double salt very sparingly soluble in water, and not at all soluble in solution of sulphate of potassa.

*Before the blowpipe*, pure salts of cerium may be detected by fluxes. Red or dark yellow beads are obtained with borax or microcosmic salt in the oxidating flame, according to the quantity dissolved; these beads on cooling, or when subjected to the reducing flame, become quite colorless.

#### TITANIC ACID ( $\text{TiO}$ ).

*General Characters:* It is a white, insipid, infusible powder: when heated, it assumes a fine yellow color, but again becomes colorless on cooling. It reddens infusion of turnsole even after having been exposed to a red heat, though the calcination renders it insoluble in acids, except boiling sulphuric.

#### *Behavior of Solutions of Titanic Acid with Reagents.*

*Ammonia* precipitates a white gelatinous hydrate ( $\text{TiO}, \text{HO}$ ), soluble with great readiness in acids, and soluble also in small quantities in the carbonated alkalis: it is precipitated from its solution in carbonate of ammonia by long boiling: its solution in carbonate of potassa or soda is precipitated by boiling with sal-ammoniac.

Titanic acid is precipitated as a heavy white powder from its acid solutions by continued boiling: this precipitate cannot, however, be washed on a filter with pure water (Rose): according to Berzelius it can be completely precipitated from its solution in sulphuric acid by long-continued boiling.

The *caustic alkalies and hydrosulphuret of ammonia* do not precipitate titanic acid in the presence of a sufficient quantity of tartaric acid.

*Ferrocyanide of potassium* produces a red brown precipitate. A bar of *metallic zinc or iron* placed in a solution of an alkaline titanate in hydrochloric acid, effects a reduction of the acid by the nascent hydrogen: and a blue or violet colored oxide of titanium gradually subsides slowly, becoming white. Titanic acid precipitated by boiling is likewise reduced by zinc or iron in an acid liquid.

*Sulphite of ammonia* ( $\text{NH}_4\text{O}, \text{SO}_2$ ), aided by a gentle heat, completely precipitates titanic acid.

*Before the blowpipe*, pure titanic gives with microcosmic salt a violet bead; the reaction is observed better on adding metallic tin; in the presence of peroxide of iron the glass appears, when strongly heated in the reducing flame, yellow, and



on cooling, red; with borax no alteration is produced by the presence of iron, the bead being colorless in the outer flame, but turning milky when heated again. In the inner flame it is slightly yellow.

#### TANTALIC ACID ( $\text{TaO}_3$ ).

*General Characters:* The hydrated acid is a powder of a milky white color, insipid and inodorous. It reddens moistened turnsole paper. It dissolves wholly in hydrofluosilicic and partially in sulphuric acid, but is precipitated from the latter by water, a circumstance which may be regarded as characteristic of tantalic acid. The solution of tantalic acid dissolved in binoxalate of potassa, is precipitated of an orange yellow color, by infusion of galls. It is not precipitated by sulphuretted hydrogen; but alkaline hydrosulphurets throw it down unaltered, with the disengagement of sulphuretted hydrogen.

#### *Behavior of Solution of Tantallic Acid with Reagents.*

*Ferrocyanide of potassium* occasions a yellow precipitate.

The *hydrate of tantalic acid* is easily soluble in *caustic alkalies*, and at a boiling temperature, it is soluble also in alkaline carbonates with the evolution of carbonic acid; it is soluble also in *hydrofluoric acid*, and in *binoxalate of potassa*.

At a certain temperature hydrated tantalic acid loses water and becomes anhydrous. When hot it is yellow, but in cooling it regains its white appearance; in this state it is soluble only with great difficulty in acids and alkalies. When a solution of tantalic acid is precipitated by sulphuric acid, and brought into contact with zinc and hydrochloric acid, it dissolves, forming a fine blue liquid, which subsequently turns brown.

*Before the blowpipe* it gives a limpid bead, with microcosmic salt. The borax bead is clear when hot, but becomes milky on cooling.

#### *General Remarks on the Oxides of the Third Group.*

*Alumina and glucina* are both dissolved readily by caustic potassa; but the two earths are distinguished from each other by the latter being precipitated from its alkaline solution by boiling, and by its hydrate being soluble in carbonate of ammonia. *Ytria, thorina, and zirconia* are not soluble in caus-

tic potassa: *yttria* is distinguished from the other two earths by the double salt which it forms with sulphate of potassa being soluble in solution of sulphate of potassa; whereas the double salts formed by *thorina* and *zirconia* are not soluble in sulphate of potassa. These two latter earths are not very easily distinguished from each other; but the precipitate produced by carbonated alkalies in solutions of *thorina* is much more soluble in carbonate of potassa than the corresponding precipitate in solution of *zirconia*. *Thorina* is, moreover, more than double the density of *zirconia*, which is distinguished again by the glaring white light which it produces when strongly ignited. The color of the salts of *oxide of chromium*, and their behavior before the blowpipe, is quite sufficient to distinguish this oxide from all the other members of the group. *Oxide of cerium* is characterized by the deep yellow color which it acquires by exposure to the air. *Titanic* and *tantalic* acids are distinguished by the blue color produced on bringing a rod of zinc or iron into contact with their acid solutions; and *tantalic* acid is distinguished from *titanic* acid by the ready solubility of its hydrate in caustic potassa, and by its precipitation from its hydrochloric solution by sulphuric acid.

This group may be conveniently subdivided into two sections by the comportment of its members with caustic potassa: thus *alumina*, *glucina*, *oxide of chromium*, and *hydrated tantalic acid* are soluble in caustic potassa: the other members are insoluble.

#### GROUP 4.

*Metallic Oxides* not precipitated from their acid solutions by sulphuretted hydrogen, but completely precipitated by hydrosulphuret of ammonia as sulphurets—*Oxides of Zinc, Nickel, Cobalt, Protoxide of Manganese, Protoxide and Sesquioxide of Iron, Sesquioxide of Uranium.*

##### OXIDE OF ZINC ( $\text{ZnO}$ ).

*General Characters:*—When pure it is white; it becomes yellow when heated, but on cooling its whiteness usually returns, though sometimes it retains its yellow tinge. It is

sometimes obtained crystalline, and is then always yellow. When the metal is burned in the air, the oxide is obtained of snowy whiteness, and in light flocks. In this state it is known as "philosophical wool." It has a remarkable affinity for alumina; a combination of the two oxides in atomic proportions is met with in the mineral kingdom crystalized in regular octohedrons, and is known under the name of *Gahnite*.

*Behavior of Solutions of Oxide of Zinc with Reagents.*

*Potassa and ammonia* produce in neutral solutions a white gelatinous precipitate ( $\text{ZnO}$ ,  $\text{HO}$ ), readily soluble in an excess of the precipitants.

*Sulphuretted hydrogen* produces in *neutral* solutions a white precipitate ( $\text{ZnS}$ ): in *acid* solutions no precipitate is formed.

*Hydrosulphuret\* of ammonia* completely precipitates salts of oxide of zinc, as ( $\text{ZnS}$ ), insoluble in an excess of the precipitant, as well as in *potassa* and *ammonia*, but soluble in  $\text{HCl}$  and dilute  $\text{SO}_3$  acids.

*The carbonates of the fixed alkalis* precipitate basic carbonate of zinc ( $3 \text{HO}$ ,  $\text{ZnO} + 2 \text{ZnO}$ ,  $\text{CO}_2$ ), quite insoluble in an excess of the precipitants, but soluble in *potassa* and in *ammonia*. The presence of any salt of the latter prevents the formation of this basic salt, a soluble double salt of zinc and ammonia being formed.

*Carbonate of ammonia* produces a white precipitate, soluble in an excess of the precipitant.

*Phosphate of soda* produces a precipitate soluble in acids, and in *potassa* and in *ammonia*.

*Oxalic acid and binoxalate of potassa* occasion precipitates which are soluble in acids and in fixed alkalis, but the formation of which is not prevented by sal-ammoniac.

*Ferrocyanide of potassium* produces a white gelatinous precipitate, insoluble in free hydrochloric acid.

*Ferricyanide of potassium* produces a yellowish red precipitate, soluble in hydrochloric acid.

*Before the blowpipe*, zinc salts are easily detected. Heated with carbonate of soda on charcoal in the reducing flame me-

\* Otto proposes to separate zinc from manganese when they exist in solutions containing a large proportion of muriate of ammonia, by adding ammonia which produces no precipitate, and then passing a stream of sulphuretted hydrogen. If any manganese is present in the precipitate it may be dissolved out by acetic acid in which sulphuret of zinc is insoluble.

tallic zinc is produced, which volatilizes, and on coming into contact with the air is again oxidized, and the charcoal becomes covered with a sublimate, which when hot is yellow, and on cooling white, and gives when heated in the oxidating flame, with a few drops of protonitrate of cobalt, a beautiful and characteristic green color.

#### OXIDE OF NICKEL ( $\text{NiO}$ ).

*General Characters:*—The pure oxide is of a deep ash gray color; it is not magnetic; it dissolves readily in acids; its hydrate is of an apple-green color.

##### *Behavior of Solutions of Oxide of Nickel with Reagents.*

*Potassa* produces a bright green precipitate, insoluble in an excess of the precipitant, but soluble in carbonate of ammonia.

*Ammonia* precipitates the same green hydrate, but an excess redissolves it, forming a clear blue solution, from which *potassa* again precipitates the hydrate. If free acid or ammoniacal salt is present no precipitate is produced.

*Sulphuretted hydrogen* does not precipitate acid solutions of nickel. In neutral solutions, after a time, an inconsiderable black precipitate is formed; but in the presence of an alkaline acetate, aided by a gentle heat, sulphuretted hydrogen effects a complete precipitation.

*Hydrosulphuret of ammonia* produces a black precipitate, partially soluble in an excess of the precipitant and wholly soluble in nitro-muriatic acid; hence after the subsidence of the precipitate the fluid remains black.

*Alkaline carbonates* produce a pale green precipitate, soluble in carbonate of ammonia.

*Phosphate of soda* occasions a very pale yellow precipitate.

*Ferrocyanide of potassium* produces a pale yellowish green precipitate, insoluble in  $\text{HCl}$  acid.

*Cyanide of potassium* throws down a greenish white precipitate ( $\text{NiCy}$ ), which an excess redissolves into a brownish yellow liquid ( $\text{NiCy}, \text{KCy}$ ); on the addition of a mineral acid, cyanide of nickel is again precipitated, and hydrocyanic acid set free.

*Before the blowpipe*, salts of nickel, heated in the outer flame with borax or microcosmic salt, give a reddish colored



bead. The addition of nitre changes the color to dark purple or blue: heated in the inner flame on charcoal with carbonate of soda, reduction takes place, and renders the bead gray.

#### OXIDE OF COBALT ( $\text{CoO}$ ).

*General Characters*.—As obtained by the calcination of the carbonate, it is of an ash gray color; as obtained by the combustion of the metal, it is blue or grayish blue; as precipitated from its solutions by caustic *potassa*, it has a fine blue color. When this precipitate is boiled for some time, it assumes by degrees a violet, and finally a dirty red tinge, which according to Proust, is the hydrate: the blue precipitate is considered by some chemists to be a basic salt. It dissolves by fusion with vitreous fluxes, communicating to them a magnificent blue color, or, if in excess, black.

#### *Behavior of Solutions of Oxide of Cobalt with Reagents.*

*Potassa* produces a blue precipitate, insoluble in an excess of the precipitant, but soluble in carbonate of ammonia; the precipitate becomes green by exposure to the air, and dingy red when boiled.

*Ammonia*\* produces a blue precipitate, which an excess redissolves, forming a solution which is at first green, but which by exposure to the air becomes brown; if sal-ammoniac be present in sufficient quantity, neither *potassa* nor *ammonia* produce any precipitate, though, if air have access, the solution gradually becomes brown.

*The alkaline carbonates* produce a red precipitate, which upon being boiled becomes blue.

*Phosphate of soda* occasions a blue precipitate in neutral solutions.

*Ferrocyanide of potassium* gives a green precipitate, which gradually turns gray.

*Ferricyanide of potassium* gives a dark reddish brown precipitate.

*Sulphuretted hydrogen* in acid solutions occasions no precipitate: in neutral solutions, after a time, a slight black precipitate, the solution acquiring a dark color.

\* If the cobalt is pure the solution of its protoxide in carbonate and caustic ammonia has a fine red color, but if nickel is present, the shade is dirty purple or even brownish black. Caustic potassa does not precipitate from such a solution.

*Cyanide of potassium* precipitates cyanide of cobalt as a brownish white precipitate from acid solutions, soluble in excess of the precipitant, and not again precipitated by acids.

*Hydrosulphuret of ammonia* produces a black precipitate, quite insoluble in excess.

*Before the blowpipe*, salts of cobalt are distinguished by the beautiful blue color they communicate to borax and microcosmic salt, in both oxidating and reducing flames. Heated with carbonate of soda in the reducing flame, a gray powder, metallic cobalt, is produced.

#### OXIDE OF MANGANESE ( $MnO$ ).\*

*General Characters*:—It is of a grayish green color. When prepared by igniting the carbonate or oxalate in an atmosphere of hydrogen, it absorbs oxygen from the air, gradually becoming brown. The oxide, prepared by fusing the chloride with anhydrous carbonate of soda, undergoes no alteration by exposure to the air. The hydrate when first precipitated is white, but on exposure to the air it gradually becomes brown. This oxide possesses, in common with magnesia and oxide of iron, the property of only being partially precipitated by ammonia, and of carrying with it a portion of silicic acid when precipitated from a liquid holding this acid in solution. The salts of oxide of manganese are sometimes colorless, and sometimes of a pale rose color.

#### *Behavior of Solutions of Oxide of Manganese with Reagents.*

*Potassa and ammonia* produce precipitates which at first are white, but soon become colored; first yellow, then brown, and finally nearly black: if ammoniacal salts be present, *ammonia* occasions no precipitate, and *potassa* only a partial one, which slowly becomes brown by exposure to the air. A clear ammoniacal solution containing oxide of manganese gradually gets turbid by exposure to the air, brown hydrated sesquioxide of manganese being deposited.

The *carbonated alkalis* produce a white precipitate of carbonate of manganese, which assumes an amethyst shade after long exposure, and is sparingly soluble in sal-ammoniac.

\* The protoxide forms the base of nearly all the salts of manganese, for the salts of the peroxide easily resolve themselves into salts of protoxide with disengagement of oxygen.

*Phosphate of soda* produces a white precipitate persistent in the air.

*Ferrocyanide of potassium* produces a pale red precipitate, soluble in free acids.

*Ferricyanide of potassium* gives a brown precipitate, insoluble in free acids.

*Sulphuretted hydrogen* does not precipitate either acid or neutral solutions.

*Hydrosulphuret of ammonia* produces a flesh-red precipitate insoluble in excess, but soluble in mineral acids and even in strong acetic acid; by exposure to the air it becomes oxidized, finally assuming a brownish black color.

By fusing any salt of manganese on platinum foil with a mixture of nitre and carbonate of soda, *manganate of soda* of a fine green color is produced; the smallest portion of manganese may in this manner be detected.

*Before the blowpipe*, fused in the oxidating flame with borax or microcosmic salt, salts of manganese give an amethyst colored bead, the color of which disappears in the reducing flame, but may again be produced in the oxidating flame.

#### PROTOXIDE OF IRON ( $\text{FeO}$ ).

*General Characters:* This oxide, which is only obtained pure with extreme difficulty, is black, and has frequently a metallic lustre: it is brittle, fuses at a high temperature, and on cooling is converted into a brittle, brilliant, but not vitreous mass. It is dissolved in acids with great difficulty, after having been exposed to a red heat; but the salts formed are identical with those obtained by dissolving the metal itself in the respective acids. It is very feebly magnetic, by which it is distinguished from the ferrosoferric oxide, which is strongly magnetic. It combines with water, forming a hydrate which, when pure, is white; but by contact with the atmosphere it speedily becomes colored; first gray, then green, then bluish-black, and finally yellow. When boiled in an hermetically closed vessel, it parts with its water, and becomes black. It is the basis of all the protosalts of iron.

*Behavior of Solutions of Protoxide of Iron with Reagents.*



*Potassa and ammonia* produce a flocculent precipitate of

hydrated protoxide of iron, which at first is nearly white, but which readily becomes colored by exposure to the air. The presence of ammoniacal salts prevents the precipitation of oxide of iron by *ammonia*, and in some degree by *potassa*.

*Alkaline carbonates* produce a white carbonate, gradually becoming colored, though not so readily as the oxide. It is soluble in sal-ammoniac, but a colored precipitate makes its appearance by exposure to the air.

*Phosphate of soda* produces a white precipitate, which after a time becomes green.


*Ferrocyanide of potassium* produces a precipitate, which, if air be entirely excluded, is white ( $K, Fe_3Cfy_2$ ); but, if air or a small quantity of sesquioxide of iron be present, it has a blue tinge; by exposure to the air, or by contact with nitric acid or chlorine, it absorbs oxygen, and gives rise to the formation of Prussian blue. The transformation will be understood from the following equations:



(a.) Three equivalents of protochloride of iron and two equivalents of ferrocyanide of potassium react in such a manner as to form three equivalents of chloride of potassium and one of the white compound.

(b.) Three equivalents of the white compound combine with four equivalents of oxygen to form two equivalents of Prussian blue, three equivalents of potassa, and one of oxide of iron. Prussian blue is insoluble in hydrochloric acid; its color is discharged by the fixed caustic alkalies.

*Ferricyanide of potassium* produces a beautiful blue precipitate, insoluble in acids, but easily decomposable by alkalies. The composition of this substance is  $Cfy_2F_3$ , and it is thus formed:—



Three equivalents of protochloride of iron, and one equivalent of ferricyanide of potassium, produce three equivalents of chloride of potassium, and one of Turnbull's blue.

*Sulphuretted hydrogen* does not precipitate acid solutions of oxide of iron; and neutral compounds very incompletely.

*Hydrosulphuret of ammonia* produces a black precipitate, speedily becoming brown by exposure to the air. It is insoluble



in alkalies and alkaline sulphurets, but easily soluble in mineral acids.

*Before the blowpipe*,\* protosalts of iron heated on charcoal with borax or microcosmic salt in the oxidating flame give dark red beads, becoming lighter on cooling; in the inner flame the color produced is green, which disappears on cooling, if the metal be not present in too large quantity. When fused with soda on charcoal in the reducing flame, a metallic magnetic powder is obtained.

#### SESQUIOXIDE OF IRON ( $\text{Fe}_2\text{O}_3$ ).

*General Characters:* Its color and physical appearance differ according to its mode of preparation. It is met with in nature of a gray color, and crystalline; as prepared by the calcination of the subsulphate of the sesquioxide, it has a fine red color; from the sulphate its color is deeper, and when made from the nitrate it is brownish black; and it is sometimes met with quite black. By the action of a high heat it is converted into ferroso-ferric oxide ( $\text{FeO}, \text{Fe}_2\text{O}_3$ ) with the disengagement of oxygen gas. It does not dissolve very readily save in concentrated acids, after having been strongly heated, though much more easily than the protoxide. It is not easily precipitated from its solutions by means of an alkali or an earth. If too little alkali be added, a subsalt is thrown down; if too much, a portion is precipitated with the oxide. When iron is oxidized by degrees in contact with a large quantity of water, a hydrate of the sesquioxide of a clear orange color is formed.

#### *Behavior of Solutions of Sesquioxide of Iron with Reagents.*

*Potassa and ammonia* produce a voluminous reddish brown hydrate, insoluble in excess. The precipitation is prevented by the presence of organic acids, sugar, &c.


The *carbonated alkalis*† throw down precipitates of rather a lighter color, carbonic acid being at the same time disengaged.

\* Chapman gives the details of his mode of separating the protoxide from the peroxide of iron in *Chem. Gaz.*, 6, 107.

† Recently precipitated hydrated peroxide of iron is entirely soluble in an excess of carbonate of ammonia, but the peroxide may again be thrown down entirely by diluting the liquid largely with water.

*Phosphate of soda* produces a white precipitate ( $2 \text{Fe}_2\text{O}_3$ ,  $3 \text{PO}_5 + 13 \text{aq.}$ ) which becomes brown, and finally dissolves on the addition of ammonia.


*Ferrocyanide of potassium* produces a beautiful precipitate ( $\text{Fe}_4\text{Cfy}_3$ ) by the following reaction:—



Two equivalents of sesquichloride of iron and three of ferrocyanide of potassium give rise to one equivalent of Prussian blue, and six equivalents of chloride of potassium.

*Sulpho-cyanide of potassium* changes the color of neutral or acid solutions to a deep blood red color, owing to the formation of a soluble sulphocyanide of iron. This is the most unerring test, as it will detect the slightest trace of iron even in the most dilute solution.

*Sulphuretted hydrogen* produces in neutral and acid solutions a white deposit of sulphur, the sesquioxide being reduced to protoxide thus:—



*Hydrosulphuret of ammonia* produces in neutral solutions a black precipitate, insoluble in excess, and becoming brown by exposure to the air. This precipitation is preceded by the reduction of the sesquioxide into protoxide.

*Before the blowpipe*, salts of sesquioxide of iron behave in the same manner as those of the protoxide.

#### SESQUIOXIDE OF URANIUM ( $\text{Ur}_2\text{O}_3$ ).\*

*General Characters:* The hydrate is a beautiful yellow powder, soluble in acids, forming fine yellow solutions; heated to about  $300^\circ$ , it loses its water and becomes anhydrous; it then has a dark green color. Heated above that temperature, it loses oxygen and becomes converted into *uranoso-uranic oxide* ( $\text{UrO}, \text{Ur}_2\text{O}_3$ ) of a deep gray color. Sesquioxide of uranium reddens moistened turnsole paper, though it blues paper stained red with infusion of logwood. It produces, therefore, the reaction of acid and base. According to Berzelius, this substance should more properly be called *uranic acid*; its properties being rather those of an electro-negative than of an electro-positive oxide. It forms definite compounds

\* As the indications of peroxide are more characteristic than those of the protoxide, the latter should be converted into the former by heating with nitric acid.

with bases, all of which are insoluble in water; and, when precipitated from its solution in an acid by means of an alkali, the latter is divided into two portions, and the precipitate obtained is a *uranate*.

*Behavior of Solutions of Sesquioxide of Uranium with Reagents.*

*Caustic alkalis* precipitate *uranates* of the bases of a pale yellow color.

*Alkaline carbonates* produce pale yellow precipitates, soluble in an excess, but again precipitated by boiling.

*Sulphite of ammonia* produces at a boiling temperature a yellow precipitate.

*Ferrocyanide of potassium* gives a red brown precipitate.

*Sulphuretted hydrogen* reduces salts of sesquioxide with the deposition of sulphur; but sesquioxide is again produced by exposure to the atmosphere, or by the action of oxidizing agents.

*Hydrosulphuret of ammonia* produces a black precipitate.

*Before the blowpipe*, heated alone on charcoal, sesquioxide of uranium is converted into protoxide; heated with microcosmic salt on platinum wire in the oxidating flame, it dissolves, producing a clear yellow glass, which on cooling becomes green.


*General Remarks on the Oxides of the Fourth Group.*

Of the seven oxides constituting this group, *oxide of zinc* alone is soluble in *caustic potassa*. It is thus readily separated from the other six, and it is distinguished from *alumina*, *oxide of chromium*, &c., members of the third group, by its being again precipitated from its alkaline solution by sulphuretted hydrogen. *Oxides of zinc, cobalt, iron, and manganese*, form with *ammonia* soluble double salts not precipitable by alkalies. *Oxide of iron* is easily eliminated from the other three oxides by converting it into *sesquioxide*, by boiling with nitric acid. It is then completely precipitated by *ammonia*, provided no non-volatile organic matter be present. The same is the case with *sesquioxide of uranium*. *Hydrate of oxide of nickel* is dissolved by *ammonia*, but again precipitated by *potassa*. *Hydrated oxide of nickel*, and *hydrated oxide of cobalt* are both soluble in *carbonate of ammonia*, which is not the case with *hydrated protoxide of manganese*, which may thus, therefore, be

separated from them. The perfect separation of *oxide of nickel* from *oxide of cobalt*, is attended with great difficulties. The presence of *nickel* may be recognized by the behavior of the solution of its cyanide in cyanide of potassium with hydrochloric acid, which precipitates it, the same not being the case with cyanide of cobalt. In the former case a double cyanide of nickel and potassium ( $\text{NiCy}, \text{KCy}$ ) is formed; but in the latter, with the presence of free hydrocyanic acid, a *cobaltocyanide of potassium* is formed. Thus:—



Two equivalents of cyanide of cobalt, three equivalents of cyanide of potassium, and one equivalent of hydrocyanic acid, give rise to one equivalent of *cobaltocyanide of potassium*, and one of hydrogen. Now, though the solution of cyanide of cobalt in cyanide of potassium is not precipitated by an acid, it may be so in the presence of nickel, and if that metal be present in the proportion of three equivalents to two equivalents of cobalt, the whole of the latter will be precipitated—the three equivalents of nickel replacing the three equivalents of potassium in the cobaltocyanide of potassium, and giving rise to cobaltocyanide of nickel ( $\text{N}_3\text{Co}_2\text{Cy}_6$ ). Thus:



Three equivalents of the double cyanide of nickel and potassium, and one equivalent of the cobaltocyanide of potassium, giving rise to one equivalent of cobaltocyanide of nickel, and six equivalents of cyanide of potassium.

The blowpipe is, moreover, an infallible test of the presence of *oxide of cobalt*.

## GROUP 5.

*Metallic Oxides* completely precipitated from their solutions, whether acid or alkaline, or neutral, by sulphuretted hydrogen, their sulphurets being insoluble in alkaline sulphurets—*Oxides of Lead, Silver, Mercury, Bismuth, Cadmium, Copper, Palladium, Rhodium, and Osmium.*

### OXIDE OF LEAD ( $\text{PbO}$ ).

*General Characters:* When pure, this oxide is yellow, but its powder has a reddish tint. When certain lead salts, as the subnitrate and oxalate, are decomposed by heat without



fusion, they furnish an oxide of a pure sulphur yellow color, which by trituration becomes red: in this state it is sometimes called *massicot*. By allowing a solution of oxide of lead, in caustic soda, to remain for some months exposed to the air, white, semi-transparent, dodecahedron crystals of anhydrous oxide may be obtained. The same crystals, according to Payen, are formed on mixing a dilute solution of acetate of lead, with great excess of caustic ammonia, and exposing to the rays of the sun. Oxide of lead becomes of a deep red color when heated, regaining its primitive color on cooling: at a red heat it fuses and cools in semi-transparent, deep brick-red, crystalline scales; at a still higher temperature it undergoes partial decomposition, the metal being reduced. It absorbs carbonic acid slowly from the air; hence an effervescence generally attends its solution in an acid. Pure water is capable of retaining in solution from  $\frac{1}{7000}$  to  $\frac{1}{12000}$  of oxide of lead; but water containing the smallest traces of saline matter does not dissolve it. The hydrate is white, and absorbs carbonic acid rapidly from the air. It loses its water at about  $300^{\circ}$ . Oxide of lead combines with alkalies and earths; its combinations with potassa and soda are crystallizable. It enters into fusion with, and dissolves, the earths with great facility. Its best solvent is nitric or acetic acids.

*Behavior of Solution of Oxide of Lead with Reagents.*

*Potassa and ammonia* produce white precipitates, which are basic salts, soluble in a great excess of *potassa*,\* but insoluble in ammonia.

The *carbonated alkalies* produce white precipitates, soluble in *potassa*.

*Phosphate of soda* occasions a white precipitate, soluble in *potassa*.

*Oxalic acid* produces, in neutral solutions, a white precipitate.

*Ferrocyanide of potassium* produces a white precipitate, soluble in *potassa*.

*Iodide of potassium* produces a yellow precipitate, soluble in great excess by heat, and separating on cooling, in magnificent yellow spangles.

\* One part of protoxide of lead requires eleven parts of potassa or 13 of soda for its solution.

*Chromate of potassa* produces a fine yellow precipitate soluble in potassa, but insoluble in dilute nitric acid.

*Hydrochloric acid and soluble chlorides* produce a heavy white precipitate, soluble in boiling water, out of which it separates on cooling, in brilliant crystals. This precipitate is soluble in *potassa*.

*Sulphuretted hydrogen* produces a black precipitate, both in acid and neutral solutions.

*Hydrosulphuret of ammonia* produces a black precipitate, insoluble in excess.

*Sulphuric acid and soluble sulphates* produce a white precipitate ( $\text{PbO}, \text{SO}_3$ )\* sparingly soluble in dilute acids, but soluble in solution of potassa, and assuming a black color when moistened with hydrosulphuret of ammonia.

*Before the blowpipe*, on charcoal, mixed with carbonate of soda, salts of lead are immediately reduced, furnishing a metallic globule, which gradually sublimes, leaving a yellow residue. The metallic globule can easily be flattened under the hammer.

#### OXIDE OF SILVER ( $\text{AgO}$ ).

*General Characters:* As obtained by dropping solution of nitrate of silver into *caustic potassa*, it is a grayish brown powder; but, if the solutions are concentrated and boiling, the oxide precipitates as a heavy black powder. Exposed to the rays of the sun, it disengages a certain quantity of oxygen, and turns black. It is entirely reduced by ignition. It is slightly soluble in pure water, and in water of barytes. It reacts alkaline to test paper, and displaces from their combinations with the alkalies a portion of the acids, with which it forms insoluble compounds. It combines with caustic ammonia, giving rise to a dangerous substance (fulminating silver). It readily dissolves in nitric and other acids.

#### *Behavior of Solutions of Oxide of Silver with Reagents.*

*Potassa and ammonia* produce a light brown precipitate, readily soluble in ammonia. The presence of ammoniacal salts wholly or in part prevents precipitation by potassa.

The *carbonated alkalies* produce a white precipitate, soluble in carbonate of ammonia.

\* Sulphate of lead is soluble in 47 parts of acetate of ammonia of sp. gr. 1.036. (*Bischof*.)

*Phosphate of soda* produces, in neutral solutions, a yellow precipitate, soluble in ammonia. Solution of ignited phosphate of soda ( $2\text{NaO}, \text{PO}_5 + 10\text{HIO}$ ) gives a white precipitate.

*Ferrocyanide of potassium* gives a white precipitate.

*Ferricyanide of potassium* produces a reddish brown precipitate.

*Chromate of potassa* produces a rich brown precipitate.

*Protosulphate of iron* produces a white precipitate, consisting of metallic silver.

*Hydrochloric acid* and the *soluble chlorides* produce a white curdy precipitate even in exceedingly dilute solutions. This precipitate becomes violet, and finally black, without, however, suffering decomposition by exposure to light. It is insoluble in diluted acids, but readily soluble in ammonia. When heated it fuses, without decomposition, into a horny mass. If the solution of silver be exceedingly dilute, hydrochloric acid produces an opalescent appearance.

*A bar of metallic zinc* precipitates silver from its solution in the metallic state.

*Sulphuretted hydrogen* produces a black precipitate, both in acid and in neutral solutions.

*Hydrosulphuret of ammonia* gives a black precipitate, insoluble in excess.

*Before the blowpipe*, mixed with carbonate of soda, and heated on charcoal, salts of silver are readily reduced while no incrustation takes place.

#### SUBOXIDE OF MERCURY ( $\text{Hg}_2\text{O}$ ).

*General Characters:* It is a black powder, which a very gentle heat converts into metallic mercury and oxide of mercury, and a stronger heat into mercury and oxygen gas. The black powder obtained by the long-continued agitation of the metal, and which was supposed to consist of this oxide, is probably only the metal in a state of very fine division. The soluble salts of this oxide redden litmus paper, and are decomposed, when mixed with much water, into soluble acid and insoluble basic salts.

*Behavior of Salts of Suboxide of Mercury with Reagents.*

*Potassa and ammonia* produce a black precipitate insoluble in excess.

*Alkaline carbonates* produce a dirty yellow precipitate which turns black by boiling.

*Phosphate of soda* produces a white precipitate.

*Ferrocyanide of potassium* produces a white gelatinous precipitate.

*Ferricyanide of potassium* gives a reddish brown precipitate, which gradually becomes white.

*Iodide of potassium* produces a greenish yellow precipitate, rendered black by a larger quantity, and soluble in an excess.

*Chromate of potassa* produces a red precipitate.

*Sulphuretted hydrogen* produces a black precipitate, both in acid and neutral solutions.

*Hydrosulphuret of ammonia* produces a black precipitate, insoluble in excess, but decomposed by *potassa* into *sulphuret of mercury* and *metallic mercury*. It is not decomposed or dissolved by boiling nitric acid, but easily by aqua regia.

A bar of *metallic zinc* throws down an amalgam of zinc and mercury.

*Hydrochloric acid and soluble chlorides* produce a white precipitate, nearly insoluble in acids, but rendered black by *potassa* and *ammonia*, the suboxide being formed.

*Protochloride of tin* produces a gray precipitate, which, boiling, resolves into globules of *metallic mercury*. A drop of solution of a salt of suboxide of mercury, rubbed with a rag on a piece of bright copper, leaves a silvery stain, which disappears when it is heated to redness.

*Before the blowpipe*, mixed with carbonate of soda, and heated in a glass tube, *metallic mercury* sublimes in the form of a gray powder, which, on being rubbed with a glass rod, is resolved into globules.


#### OXIDE OF MERCURY ( $\text{HgO}$ ).

*General Characters:* It is a brick-red crystalline powder; but when finely pulverized has a yellow tinge. At a slightly elevated temperature it turns black, but it regains its red color on cooling. At a red heat it is resolved into oxygen gas and *metallic mercury*, and is entirely volatilized. In this manner the presence of impurities, red lead, or brick-dust, may be detected. It dissolves readily in acids, but is not acted on by *ammonia*, and is not entirely insoluble in water.



*Behavior of Solutions of Oxide of Mercury with Reagents.*

*Potassa* produces a yellow precipitate ( $\text{HgO}, \text{HO}$ ) insoluble in excess. If an insufficient quantity of the alkali be added, the precipitate is reddish brown. The presence of ammoniacal salts causes the formation of a white precipitate, which is a compound of *amidide of mercury* with undecomposed mercury salts. Thus,



*Fixed carbonated alkalies* produce a reddish brown precipitate, insoluble in excess, but converted, in the presence of ammoniacal salts, into white ( $\text{HgCl}_2\text{N}_2\text{H}_3\text{Cl}_2$ ) + ( $\text{Hg}_2\text{Cl}_2 + \text{HgO}$ .) (*Duflos*.)

*Carbonate of ammonia* produces a white precipitate.

*Phosphate of soda* produces a white precipitate.

*Ferrocyanide of potassium* produces a white precipitate, which eventually becomes blue, owing to the formation of Prussian blue.

*Ferricyanide of potassium* produces, in solutions of the nitrate and sulphate, a yellow precipitate; in solutions of the chloride, none.

*Sulphuretted hydrogen and hydrosulphuret of ammonia* give rise to different colored precipitates according to the quantity of the reagent added. If it be added in small quantity, and the solution agitated, the precipitate is white, being a compound of sulphuret of mercury and undecomposed salt; the addition of larger quantities causes the precipitate to assume, successively, a yellow, orange, brown, red, and black color. The sulphuret of mercury is soluble in solution of potassa, but not in boiling nitric acid, though it dissolves readily in aqua regia.

*Iodide of potassium* produces a cinnabar red precipitate, soluble in excess. It crystalizes out of a hot solution in magnificent crimson spangles.

*Protochloride of tin*, when added in excess, separates the metal in the form of a gray powder, which may be united into globules by boiling with hydrochloric acid. All the salts of mercury are decomposed when heated in a glass tube with a slightly moistened alkaline carbonate, the metal subliming in small globules: the metal is likewise reduced when the solution is brought into contact with clean metallic copper, and rubbed.

OXIDE OF BISMUTH ( $\text{BiO}$ ).

When pure it is of a straw yellow color, and melts at a strong red heat to an opaque glass, which, while hot, is dark brown or black, but on cooling becomes yellow; when melted with silica, alumina, or metallic oxides, it dissolves them readily. The oxide precipitated by water retains nitric acid, from which it may be freed by caustic potassa or soda, which convert it into a hydrate. It is easily reduced by ignition with organic substances or charcoal powder. It dissolves readily in water, forming colorless salts.

*Behavior of Solutions of Oxide of Bismuth with Reagents.*

*Potassa and ammonia* produce a white precipitate, insoluble in excess.

*Alkaline carbonates and phosphate of soda* produce white precipitates.

*Ferrocyanide of potassium* occasions a white precipitate, insoluble in hydrochloric acid.

*Ferriocyanide of potassium* produces a light yellow precipitate soluble in hydrochloric acid.

*Iodide of potassium* produces a brown precipitate, readily soluble in excess.

*Chromate of potassa* produces a yellow precipitate, soluble in dilute nitric acid, and insoluble in potassa.

*Sulphuretted hydrogen and hydrosulphuret of ammonia* produce a black precipitate, both in acid and neutral solutions, insoluble in excess, and in dilute nitric acid, but soluble in boiling nitric acid.

The neutral salts of bismuth are distinguished by their property of being decomposed by water into a soluble acid, and an insoluble basic salt. The chloride\* of bismuth exhibits this property in the most marked manner. The insoluble basic bismuth salt is distinguished from the basic salt of antimony, formed under similar circumstances, by its being insoluble in tartaric acid.

*Before the blowpipe*, heated on charcoal in the reducing flame, salts of bismuth are easily reduced to brittle globules, which spring to pieces under the hammer; the charcoal, at the same time, becomes covered with a yellow incrustation.

\* Alcohol dissolves chloride of bismuth without decomposing it.

OXIDE OF CADMIUM ( $\text{CdO}$ ).

*General Characters:* The color of this oxide varies according to its state of aggregation. It is sometimes of a deep red brown, sometimes clear brown, and occasionally black. It is infusible, and does not volatilize at exceedingly high temperatures; but, when mixed with powdered charcoal, it is reduced by heat, and the metal burns and volatilizes. By long-continued gentle ebullition of the metal, the oxide may be obtained, according to *Herapath*, in long purple needles, opaque, and grouped in rays. Its hydrate is white; it loses its water by heat, and absorbs carbonic acid from the air. It is not soluble in the fixed alkalies, but it dissolves in caustic ammonia. It dissolves easily in acids, forming colorless solutions.

*Behavior of Solutions of Oxide of Cadmium with Reagents.*

*Potassa and ammonia* produce a white precipitate ( $\text{HO}$ ,  $\text{CdO}$ ), insoluble in potassa, but easily soluble in ammonia.

The *carbonated alkalies* produce a white precipitate ( $\text{CdO}$ ,  $\text{CO}_2$ ), insoluble in excess. Ammoniacal salts do not prevent the formation of this precipitate.

*Phosphate of soda* produces a white precipitate in neutral solutions.

*Oxalic acid* produces a precipitate soluble in ammonia.

*Ferrocyanide of potassium* produces a slightly yellow precipitate, soluble in hydrochloric acid.

*Ferricyanide of potassium* produces a yellow precipitate, also soluble in hydrochloric acid.

*Sulphuretted hydrogen and hydrosulphuret of ammonia* produce a rich yellow precipitate, insoluble in excess, and in dilute acids and alkalies, unalterable in the air, but decomposed by boiling with concentrated nitric acid.

A *bar of metallic zinc* precipitates the metal from its solutions in the form of small glancing, gray-colored spangles.

*Before the blowpipe*, heated with carbonate of soda on charcoal, the metal is reduced and volatilizes, leaving a dark yellow red incrustation.

OXIDE OF COPPER ( $\text{CuO}$ ).

*General Characters:* It is pulverulent, and of a black

color; at a high temperature it fuses, and on cooling exhibits a crystalline fracture. By particular management, Becquerel obtained it in the form of fine tetrahedral crystals, having a high metallic lustre. Heated with charcoal, or in contact with organic matter, it is reduced either to metallic copper or to the suboxide. It dissolves easily in acids with the disengagement of heat, and its solutions have mostly a blue or a green color. Its hydrate is blue; but at the temperature of boiling water it becomes black, a property which interferes with its employment as a pigment. It does not unite in the humid way with the caustic alkalies; but at a red heat it combines with both alkalies and earths, forming blue or green compounds. Caustic alkalies containing organic matters dissolve it, forming blue or purple compounds.

*Behavior of Solutions of Oxide of Copper with Reagents.*

*Potassa* produces a voluminous blue precipitate ( $\text{HO}, \text{CuO}$ ), which by boiling loses water and becomes black.

*Ammonia* added in small quantities produces a green basic salt, which dissolves in excess, forming a fine blue solution. In this solution potassa produces in the cold, after a time, a blue precipitate, which by boiling becomes black.

*Carbonate of potassa* produces a greenish blue precipitate of basic carbonate of copper, which by boiling is converted into black oxide.

*Carbonate of ammonia* behaves precisely as ammonia.

*Phosphate of soda* produces a greenish white precipitate, soluble in ammonia, forming a blue solution.

*Ferrocyanide of potassium* produces, even in very dilute solutions, a chocolate brown precipitate, insoluble in dilute acids, but decomposed by potassa. This is a very delicate test.

*Ferricyanide of potassium* produces a yellowish green precipitate, insoluble in dilute acids.

*Cyanide of potassium* produces a yellowish green cyanide, soluble in excess of cyanide of potassium.

*Chromate of potassa* produces a reddish brown precipitate, soluble in ammonia, forming an emerald green solution, soluble also in dilute nitric acid.

*Sulphuretted hydrogen and hydrosulphuret of ammonia* produce a black precipitate, slightly soluble in excess of hydrosulphuret of ammonia, but insoluble in caustic alkalies, and



in sulphuret of potassium, and in dilute acids. It is readily decomposed by boiling nitric acid, and is completely soluble in cyanide of potassium.

*Metallic iron*, when introduced into solutions of oxide of copper, becomes covered with a deposit of reduced copper.

*Before the blowpipe*, salts of copper heated with borax or microcosmic salt in the oxidating flame, give a grass green bead, becoming blue on cooling; in the reducing flame the glass is red and opaque, mixed with carbonate of soda; and heated on charcoal in the inner flame the metal is reduced, and gives a bead of metallic copper.

#### OXIDE OF PALLADIUM ( $\text{PdO}$ ).

*General Characters*: It is a black powder, acted on with great difficulty by acids. The hydrate is of a deep brown color, and parts with its water only at a high temperature. Its solution in nitric and nitro-hydrochloric acid has a red brown color.

#### *Behavior of Solutions of Oxide of Palladium with Reagents.*

*Potassa* precipitates a yellowish brown basic salt, soluble in excess.

*Ammonia* precipitates from solution of chloride of palladium a pink compound of chloride of palladium and ammonia ( $\text{Pd Cl, NH}_3$ ), soluble in excess of ammonia. In the nitrate of palladium, ammonia gives no precipitate.\*

*Carbonated alkalis* precipitate a yellowish brown basic salt, soluble in excess of the precipitants.

*Cyanide of potassium and cyanide of mercury* produce a yellowish white precipitate of cyanide of palladium, soluble in great excess of hydrochloric acid.

*Sulphuretted hydrogen and hydrosulphuret of ammonia* produce a black precipitate, insoluble in hydrosulphuret of ammonia.

*Palladium salts* are reduced by *sulphurous acid*, and by being heated with a salt of *oxide of iron*, or with a *formiate*.

\* The neutral solutions of *proto-nitrate* of palladium give yellow precipitates with the neutral phosphates, arseniates, oxalates, tartrates and citrates.

SESQUIOXIDE OF RHODIUM ( $R_2O_3$ ).

*General Characters:* The metal, as well as the anhydrous sesquioxide, is insoluble even in boiling *aqua regia*. Both, however, are dissolved on fusion with *bisulphate of potassa*, or on heating a mixture of both with chloride of sodium to redness, and passing over it a stream of chlorine. The color of the hydrated oxide is greenish gray. The haloid salts of this metal are red: the oxysalts yellow, red, or brown.

*Behavior of Salts of Sesquioxide of Rhodium with Reagents.*

*Potassa* does not occasion any immediate precipitate; but after protracted digestion a precipitate of a brownish yellow color makes its appearance.

*Ammonia and carbonate of ammonia* produce, after a time, a yellow precipitate, composed of sesquioxide of rhodium and ammonia, which is soluble in hydrochloric acid.

*Hydrosulphuret of ammonia and sulphuretted hydrogen* produce, after a time, a dark brown precipitate, insoluble in an excess of the former.

All the salts of rhodium are decomposed, and the metal is reduced by exposure to a gentle heat, in contact with dry hydrogen gas.

OXIDES OF OSMIUM ( $OsO$ ;  $Os_2O_3$ ;  $OsO_2$ ;  $OsO_4$ ).

The presence of osmium is discovered in the salts by mixing them with a little carbonate of soda, and heating on platina foil, the metal is converted into osmic acid, which possesses an extremely acrid and penetrating odor like chloride of sulphur, attacking powerfully the olfactory and respiratory organs, and producing, even in minute quantities, a burning sensation in the eyes. It communicates also a considerable brilliancy to flame. The metal itself is whitish, like platinum, but less brilliant. It is easily pulverized. It dissolves in nitric acid and in *aqua regia*, osmic acid, passing over with the water of the acid. Osmic acid is easily reduced by many metals and organic compounds. Solutions of salts of oxide of osmium are precipitated by *hydrosulphuret of ammonia* and *sulphuretted hydrogen*, as a brownish black sulphuret insoluble in *hydrosulphuret of ammonia*.

*General Remarks on the Oxides of the Fifth Group.*

The metallic oxides constituting this group admit of a division into two sections by their comportment with hydrochloric acid. Three of them, viz: *oxide of lead*, *oxide of silver*, and *oxide of mercury* are precipitated by that reagent; the others are not. Of the chlorides thus formed, *chloride of silver* is easily separated from the other two by ammonia, in which it is perfectly soluble, and from which it is again precipitated by nitric acid. The same alkali decomposes *subchloride of mercury*, converting the metal into black protoxide, from which *chloride of lead* may be removed by boiling water, and the metal tested for in the clear solution by any of the reagents mentioned under its head. The insolubility of sulphuret of mercury in nitric acid serves to separate this metal from all the others in the group. The precipitates caused by *potassa* and *ammonia* in solutions of *oxide of cadmium* and *oxide of copper*, are soluble in *ammonia*; those of the others are not; but the *hydrated oxide of copper* is soluble also in *carbonate of ammonia*. *Hydrated oxide of cadmium* has no such property; moreover, the blue color of the ammoniacal solution of *oxide of copper* is perfectly characteristic of that metal. *Cadmium*, again, is distinguished by the color of its sulphuret, which, being insoluble in *hydrosulphuret of ammonia*, distinguishes it from the yellow sulphurets of some of the metals in the next group, all of which are soluble in hydrosulphuret of ammonia. *Oxide of bismuth* is readily detected by the decomposition of its salt by water. *Salts of palladium* are recognized by their behavior with *cyanide of mercury* and *cyanide of potassium*. The insolubility of *oxide of rhodium* in acids, and the color of its salts, serve to distinguish this metal; and the presence of *osmium compounds* is recognized by the penetrating odor of *osmic acid*.

## GROUP 6.

*Metallic Oxides* completely precipitated from their acid solutions by sulphuretted hydrogen; but not from their alkaline solutions, their sulphurets being soluble in alkaline sulphurets—Oxides of *Antimony*, *Arsenic*, *Tin*, *Platinum*,

*Iridium, Gold, Selenium, Tellurium, Tungsten, Vanadium, and Molybdenum.*

#### ANTIMONIC ACID ( $\text{SbO}$ ).

*General Characters:* It is a white powder, soluble in small quantities in boiling water. This oxide is insoluble in nitric acid; but it dissolves in hydrochloric acid, and the solution is decomposed by water, a basic salt being separated.

#### *Behavior of Solutions of Antimonic Acid with Reagents.*

*Potassa and ammonia* produce a white precipitate partially soluble in excess of the reagent.

*Alkaline carbonates and phosphate of soda* behave in a similar manner.

*Metallic zinc* throws down metallic antimony as a black powder; if nitric acid be present, the sesquioxide is precipitated at the same time.

*Sulphuretted hydrogen* throws down from acid solutions an orange yellow precipitate, readily soluble in excess and in *potassa*; but very sparingly soluble in *ammonia*, and entirely insoluble in *carbonate of ammonia*. It is insoluble in dilute acids, but is decomposed by concentrated and boiling hydrochloric acid; the precipitate is very incompletely formed in neutral solutions.

*Hydrosulphuret of ammonia* produces an orange yellow precipitate, completely soluble in excess.

The solution of double tartrate of antimony and potassa (tartar emetic) is only precipitated after a time by alkalies and their carbonates.

*Antimony* possesses the property of forming a gaseous combination with hydrogen; the union of these two bodies may be brought about by adding zinc and sulphuric acid to a solution containing the oxide, which becomes deoxidized by the zinc; a portion of the metal unites with the hydrogen of the water, which is at the same time decomposed. *Antimoniuretted hydrogen* is inflammable, burning with a bluish green flame, and emitting copious fumes of sesquioxide; if the flame be allowed to impinge on a cold surface, such as a porcelain plate, a dark spot of reduced antimony will be produced. If the gas, as it proceeds from an evolution flask, be allowed to pass along a horizontal tube of hard German glass, and the



tube be heated to redness at a certain point, decomposition of the gas will take place at that spot; on both sides of which a brilliant mirror of metallic antimony will be deposited: if now a stream of *dry* sulphuretted hydrogen be allowed to pass through the tube, the bright mirror will vanish, and a deposit of a more or less intense yellow color will take its place, the antimony being converted into sulphuret. If now the flask in which sulphuretted hydrogen is generating be removed, and its place supplied by one containing the materials for generating hydrochloric acid gas, and if a gentle stream of this gas be sent through the tube, the yellow deposit will vanish, the sulphuret being converted into chloride, which being volatile may be conveyed with the gas into a vessel of water, in which the presence of antimony may then be proved by acidulating it with hydrochloric acid, and transmitting through it a stream of sulphuretted hydrogen gas.

*Before the blowpipe*, mixed with carbonate of soda on charcoal, oxide of antimony is easily reduced, and brilliant metallic globules obtained: the metal fumes and volatilizes, covering the charcoal with a white incrustation, amongst which needle-shaped crystals frequently appear.

#### ARSENIOUS ACID ( $\text{As}_2\text{O}_3$ ).


*General Characters:* As met with in commerce, this acid is almost completely pure; it is without smell and almost without taste; if kept for some time in contact with the tongue, it induces a slightly bitter taste, which, however, leaves one of sweetness. It sublimes before entering into fusion; but with certain precautions it may be fused in close vessels, and obtained on cooling in the form of a colorless transparent glass. When sublimed in a current of air, it forms fine octahedral crystals. Its vapor is without color or taste; the odor which accompanies it is due either to the reduction of the metal or to the formation of a lower oxide. This acid has two isomeric modifications, one of which is represented by the *vitreous* and the other by the *milky* variety. The latter was supposed to be merely the result of an admixture of water; but it has been ascertained that the two varieties differ both in their specific gravity and in their chemical properties. The milky variety is much more soluble in water than the other, 100 parts of water at the ordinary temperature dissolving 1.25 of the for-

mer and 0.96 of the latter, and at the boiling temperature 11.47 of the former and 9.63 of the latter; while at  $32^{\circ}$  water retains in solution 2.9 parts of the milky and 1.78 of the vitreous acid. The aqueous solution of the vitreous variety reddens paper tinged with infusion of turnsole; that of the milky appears, on the other hand, to have rather an alkaline reaction. Rose has observed that a saturated solution of the vitreous acid in hydrochloric acid deposits on cooling octahedral crystals, during the formation of which flashes of light may be observed in the dark: neither of these phenomena occur with the milky variety. The great diversity of statements made with regard to the solubility of arsenious acid in water, have arisen not only from the difference of the two varieties in this respect, but also probably from the different manner in which the experiments have been made. Arsenious acid dissolves much more readily in acids than in water, and is deposited unaltered on cooling from hot solutions. It forms a class of salts called *arsenites*, all of which are poisonous, though not so eminently so as the acid itself. The best antidote to this poison is *hydrated sesquioxide of iron*, perfectly free from alkali, and which has not been dried, but preserved in a gelatinous state saturated with water: arsenious acid forms with this oxide a basic insoluble salt. Perhaps the best method of administering this antidote is in the form of a completely saturated solution of the hydrated sesquioxide in *acetic acid*.

*Behavior of Solutions of Arsenious Acid with Reagents.*

*Sulphuretted hydrogen* produces in aqueous solutions of arsenious acid a very slow and incomplete precipitation; but in the presence of free hydrochloric acid an immediate precipitate of *sulpharsenious acid* ( $\text{AsS}_3$ ) of a bright yellow color is produced. This precipitate is easily soluble in *alkalies*, alkaline carbonates, and alkaline sulphurets; it is also decomposed by boiling nitric acid, though it is nearly insoluble in hydrochloric acid. When fused with a carbonated alkali and nitre, it is decomposed, the products being arseniated and sulphated alkali. When an alkaline solution of sulpharsenious acid is boiled with oxide of copper, sulphuret of copper and arseniated alkali are formed. When a mixture of sulpharsenious acid and carbonate of soda is heated in a current of dry hydrogen gas, as shown in Fig. 1, a reduction of a portion of

the arsenic compound takes place, and a metallic mirror is formed within the tube, thus:—



Two equivalents of sulpharsenious acid, and four equivalents of carbonate of soda, producing one equivalent of arsenite of soda, and three equivalents of *sulpharsenico-sulphuret of sodium* + four of carbonic acid.


When the vapors of sulpharsenious acid are passed over ignited lime, sulphuret of arsenic and calcium and arseniate of lime are formed, with the separation of arsenic.

When sulpharsenious acid is fused with cyanide of potassium, *sulphocyanide* of potassium is formed, and arsenic set free, thus:—



This experiment is best made by introducing a mixture of one part of sulpharsenious acid with ten or twelve parts of a mixture of two parts of dry carbonate of soda and one part of cyanide of potassium, into a glass tube drawn out as shown in Fig. 1, and heated to redness; while a current of dry carbonic acid gas is passed over it, the arsenic is deposited on

Fig. 1.



the cold surface of the narrow part of the tube in the form of a black mirror.

A is the flask containing lumps of solid marble, provided with a funnel tube, through which hydrochloric acid is poured for the generation of carbonic acid. B is a smaller flask containing oil of vitriol, in passing through which the carbonic acid becomes dried. C, the mixture of sulpharsenious acid with carbonate of soda and cyanide of potassium heated by a spirit lamp; d, the metallic mirror.

Sulpharsenious acid is also reduced by heating it with a mixture of equal parts of carbonate of soda and cyanide of

potassium in a small tube of hard German glass closed at one end, and drawn out into a long and open point at the other.

*Hydrosulphuret of ammonia* produces in acid solutions of arsenious acid a yellow precipitate of sulpharsenious acid; in neutral or alkaline solutions no precipitate occurs.

*Nitrate of silver* produces in neutral solutions a yellow precipitate of *arsenite of silver* ( $2\text{AgO}, \text{AsO}_3$ ), soluble in dilute nitric acid and ammonia.

*Ammonio-nitrate of silver* produces the same precipitate in acid solutions.

*Sulphate of copper* (neutral) produces a yellowish green precipitate of arsenite of copper in neutral solutions, but none in the free acid.


*Ammonio-sulphate of copper* produces the same precipitate in acid solutions.

*Neutral chromate of potassa* produces a green color, but no precipitate in a solution of arsenious acid. If the liquids are added in reversed order, the green colored solution congeals in a few moments to a jelly.—(*Schweitzer*.)

*Arsenic*, like *antimony*, forms a gaseous compound with hydrogen; the combination of the two elements may be effected by bringing together *arsenious acid* or an *arsenite* with *zinc*,\* *water*, and *sulphuric* or *hydrochloric acid* (chemically pure); this property is taken advantage of as a test for the metal, and forms a valuable means of isolating it. The materials for gener-

ating the hydrogen are introduced into the evolution flask, A, Fig. 2, and the gas being filtered by passing through a tube filled with dry cotton wool, B, is inflamed at the point of the bent tube, C, (sufficient time being allowed to expel the atmospheric air from the apparatus,) and a porcelain plate depressed on the flame. If, after burning for some time, no incrustation or blacken-

Fig. 2.



\* It is indispensable that the zinc be previously purified, and freed of arsenic and antimony.




ing appears on the plate, it is a sign that the materials in the evolution flask are free from arsenic; additional assurance is, however, obtained by heating a portion of the horizontal tube to redness at *b*, by means of a spirit lamp; no incrustation must be observed in the tubes. The liquid to be tested for arsenic is now introduced into the evolution flask through the funnel tube; and if it contains any traces of the poison, the flame of the hydrogen will acquire a bluish white color, owing to the reduction and separation of the arsenic, and fumes of arsenious acid will make their appearance. On now depressing the porcelain plate upon the flame, brown arsenic spots will be obtained: these incrustations have a shining metallic appearance, those of antimony being black and possessing scarcely any metallic lustre. On applying the flame of the spirit lamp to the horizontal part of the tube, a beautiful incrustation of metallic arsenic will be formed on the cold part of the tube, which is darker and less silvery than that formed by antimony under similar circumstances; and on cutting off the tube near the deposit, and applying heat, the arsenic is converted into arsenious acid, which is recognized by its garlic odour, and which may be dissolved in hot water, and tested by nitrate of silver and sulphate of copper.

The following modification of Marsh's apparatus by the Academy of Sciences of Berlin, is described by Dr. Ure in his *Supplement to his Dictionary of Arts, Manufactures and Mines*:—

A is a narrow glass cylinder open at top, about ten inches high, and one and a quarter, or one and a half inch in diameter inside. B is a glass tube about one inch in diameter outside, drawn to a point at bottom, and shut with a cork at top. Through the centre of this cork a small tube C passes down air-tight, and is furnished at top with a stop-cock, into which the small bent glass tube (without lead) E is cemented. The bent tube E is joined to the end of F by a perforated cork.

Fig. 3.



This apparatus is used as follows:—Introduce a few oblong slips of zinc free from arsenic into B, and then insert its air-tight cork with the attached tubes. Having opened the stop-cock, pour into the tube A as much of the suspected liquid, acidulated with dilute pure sulphuric acid, as will rise to the top of the cork after B is full, and immediately shut the stop-cock. The generated hydrogen will force down the liquid out of the lower orifice of B into A, and raise the level of it above the cork. The extremity of the tube F being dipped beneath the surface of a weak solution of nitrate of silver, and a spirit flame being placed a little to the left of the letter E, the stop-cock is then to be slightly opened, so that the gas which now fills the tube B may escape so slowly as to pass off in separate small bubbles through the silver solution. By this means the whole of the arsenic contained in the arseniuretted hydrogen will be deposited either in the metallic state upon the inside of the tube E, or with the silver into the characteristic black powder. The first charge of gas in B being expended, the stop-cock is to be shut, till the liquid be again expelled from it by a fresh disengagement of hydrogen. The ring of metallic arsenic deposited beyond E may be chased onwards by placing a second flame under it, and thereby formed into an oblong, brilliant, steel-like mirror. It is evident that, by the patient use of this apparatus, the whole arsenic in any poisonous liquid may be collected, weighed, and subjected to every kind of chemical verification. By means of the perforated cork, the tube F may readily be turned about, and its taper point raised into such a position as, when the hydrogen issuing from it is kindled, the flame may be made to play upon a surface of glass or porcelain, in order to form the arsenical mirror.

The most satisfactory method, however, of distinguishing between the metallic mirrors\* formed by antimony and arsenic

\* MacLagan proposes to discriminate between an arsenical and antimonial stain by the difference of temperature at which they undergo sublimation. The results of a series of experiments give confidence in this mode as the readiest and most satisfactory. The degree of heat employed ranges from  $335^{\circ}$  to  $565^{\circ}$ , at which temperature arsenic is volatilized whilst antimony remains permanent. The heat is applied by means of a "bath of olive oil, which may be urged even to its boiling-point without at all affecting an antimonial stain, whilst the heat so employed will entirely sublime an arsenical crust into a crystalline sublimate of arsenious acid. It will always be best, if it is possible, to have a thermometer in the oil bath, that the extreme temperature employed may be stated in evidence if asked for. But this is not indispensable; olive oil does not begin to boil till the heat rises above  $600^{\circ}$ ; and this heat, however long applied, does not cause

under similar circumstances, is founded on the decomposition of sulphuret of antimony by hydrochloric acid gas, and the volatility of the chloride of antimony thus formed. We can thus not only distinguish an arsenical from an antimoniacal deposit, but when both metals are present we can separate them perfectly. We proceed thus:—The mirror having been obtained, a feeble stream of dry sulphuretted hydrogen is sent through the tube, a gentle heat being at the same time applied: if the metal be arsenic alone, sulphuret of that metal of a light yellow color will be formed; if it be antimony alone, the sulphuret is either orange red or nearly black; if both

antimony to volatilize. Stains which are so faint as not to appear distinctly metallic till the tube is held over a sheet of white paper, may be distinguished in this way. The pure arsenical metallic stain entirely disappears from the spot where it was deposited, the pure antimonial remains unchanged; whilst the mixed arsenical and antimonial becomes visibly less, a portion has undergone sublimation, whilst the residue, however long the heat may be prolonged, remains fixed. If, in addition to the disappearance of the stain from the portion of the tube immersed in the oil, we can observe the formation of a crystalline sublimate in the upper portion of the tube, the proof may be said to be absolute. Very small quantities of arsenic may be rendered distinctly visible in this form. I have operated upon stains produced from a Marsh's apparatus, which contained less than a thousandth of a grain of arsenic, and have yet been able to see distinctly the crystalline character of the sublimate. The gentle and gradual way in which the heat is applied in the oil bath causes the sublimate to deposit itself in fewer but much larger crystals, and thus makes it much more appreciable by the eye or lens than could be supposed by those who have been in the habit of subliming small stains of arsenic by a spirit-lamp flame. In the case of some poisoned swine which I examined, and where, from one of the articles, I could obtain in the tube a mere shade of brown, and when, by the spirit-lamp, this was sublimed into a mere white cloud, I was able, by again heating in the oil-bath, to obtain a sublimate distinctly of crystalline appearance to the naked eye. In order, therefore, to determine whether a stain be arsenical or antimonial, all that is required is to operate with Marsh's apparatus and the narrow glass tube; if a stain is procured, to seal up the point, immerse it in the oil-bath, and heat this steadily. The heating does not require to be prolonged. Ten minutes after the temperature has risen to about  $500^{\circ}$ , will have affected the stain if it is arsenical. It is well remarked by Taylor, that, in such investigations, we have to determine the presence of arsenic in antimony, not of antimony in arsenic; and therefore, if any sublimation in the oil-bath can be observed at all, the question as to the presence of arsenic is settled. To enable us to observe this more readily, it is a good plan to make a small scratch on the tube at each limit of the stained portion before heating it; and thus, by its diminution, we may pronounce upon its nature, although no sublimate should be distinctly visible. Should any peculiar case occur, in which it might be of importance to determine that antimony was present, as well as arsenic, the heat must be continued for a longer period. I have found that a large pure arsenical stain, weighing on a delicate balance 0.036 gr., required an hour and a half of heating at  $500^{\circ}$  in a narrow tube to sublime it entirely. But long before one-third had been sublimed, the tube was lined with splendid crystals of arsenious acid. The heat, to sublime the whole arsenic, need never be raised beyond  $520^{\circ}$ ; but, even if the oil boils, it does not affect the correctness of the experiment."

metals be together, then both are converted into sulphurets; but the sulphuret of arsenic being more volatile than the sulphuret of antimony, it will be deposited in a more advanced part of the tube. A current of dry hydrochloric acid gas is now passed through the tube; *chloride of antimony* is formed *without the application of heat*, and is entirely removed in the current of gas. The sulphuret of arsenic remains unaltered, and may be distinguished from sulphur by its solubility in ammonia.

It was the late Mr. Marsh, of Woolwich, who first took advantage of the property of arsenic to form a gaseous compound with hydrogen, and employed it as a test for the metal. The apparatus he employed is shown in an improved form in Fig. 4. The stop-cock being removed from the tube, a few fragments of pure zinc are introduced into the bend of the tube, and pure dilute sulphuric acid poured upon them; the gas evolved having been proved to be free from arsenic, the suspected liquid is introduced, and the gas burned against a porcelain plate as above described.



*Oxygen compounds* of arsenious acid may be reduced by heating them in one of the small tubes figured above, over a spirit lamp, with a mixture of carbonate of soda and charcoal; the metal volatilizes and condenses in the cool part of the tube, forming a mirror of great lustre. Arsenious acid is reduced by merely heating it to redness in contact with a splinter of charcoal.

*Metallic copper*, when boiled with an acidified mixture containing arsenious acid, becomes covered with a steel-gray crust of metallic arsenic. This is an exceedingly delicate test, and will, according to its discoverer, *Reinsch*,\* detect arsenic when present in no more than a *millionth part* of the liquid; but as various other metals, *silver, gold, platinum, bismuth, and antimony*, are likewise precipitated under similar circumstances, it is necessary to submit the crust to a careful examination.† When arsenious acid is heated with a dry *acetate*

\* MacLagan has shown (*Chem. Gaz.*, vi. 450,) that Reinsch's test is less delicate than that of Marsh.

† Abren has recently announced the following method of "determining the nature of one or several metals mixed up with organic matter." It will comprise the compounds of the following metals:—

|           |          |         |
|-----------|----------|---------|
| Arsenic.  | Mercury. | Tin.    |
|           | Copper.  | Zinc.   |
| Antimony. | Lead.    | Silver. |




and *hydrate of potassa*, *oxide of kakodyl* is produced, the insupportable odor of which serves to detect very minute traces of

The following is the plan of operation:—The experimenter should begin by examining attentively with a lens the substances vomited and evacuated, those found in the digestive canal, and the mucous surface of this canal. This will frequently furnish valuable indications; and in some cases it is possible to find in the digestive canal, especially in its mucous folds, solid particles of the poisonous substance. In this latter case the particles of poison should be carefully removed with a small forceps, and their nature ascertained if possible by the ordinary methods; but supposing no definite result to follow from this physical examination, we proceed as follows:—The suspected matter to be examined is cut into small pieces with a pair of very small scissors; and a known weight of it, which should never exceed 200 grms., conveyed into a flask capable of holding two quarts, with half its weight of pure fuming muriatic acid. A cork with two perforations is adapted to the neck of this flask, into one of which is fitted a tube from 55 to 60 centimetres in length, and one centimetre internal diameter. It dips a few millimetres into the muriatic acid. The second perforation is destined for a tube curved at right angles, the second vertical branch of which passes through a cork into some distilled water contained in a test-tube; this cork has also a second perforation, into which is fitted a straight tube not dipping into the water. When this arrangement is made, the flask is placed on a sand-bath, and the test-tube immersed in cold water, which is changed from time to time. The sand is kept at a temperature near the boiling-point of the liquid, and the flask is agitated from time to time for at least four hours. The organic matter is gradually disintegrated, and finally forms a dense homogeneous liquid of a more or less dark color. The flask is then removed from the sand-bath, and boiled over an Argand lamp for two or three minutes, upon which some crystals of chlorate of potash are gradually introduced through the large tube, taking care to agitate the flask constantly until from sixteen to eighteen grms. have been used for every 100 grms. of suspected substance employed. A violent reaction takes place, with an abundant disengagement of chlorinated gases; the liquid gradually clears, and at last becomes perfectly transparent and of a yellow color, the intensity of which appears to depend especially on the large excess of chlorine remaining in solution. Both the liquid in the flask and the water in the test-tube present the peculiar odor of chlorine in the highest degree. Some small fragments of charcoal and of a resinous substance float upon the liquid in the flask; their quantity is very small in investigations of blood, but very considerable in examinations of the tissues of the liver and other parenchymatous organs.

The apparatus is allowed to cool, the liquid in the flask filtered through Swedish paper, and mixed with the water in the test-tube and with the wash-waters. A current of well-washed sulphuretted hydrogen is passed through the united liquids for a considerable time, and the whole is then left till the morning in a corked flask. In all cases there will be a more or less abundant precipitate, which should be examined for all the metals comprised in our table except silver and zinc. This precipitate may nevertheless contain only sulphur and a little organic substance, which should be got rid of by the following plan:—

The precipitate is thrown upon a filter without folds, washed with distilled water, and boiled in a small flask with its weight of pure and fuming muriatic acid, to which a few fragments of chlorate of potash are added. When the reaction is complete, a little distilled water is added, and the whole heated with great care, in order to expel the whole of the free chlorine. It is again filtered through Swedish paper, and a very transparent liquid is thus obtained with but a faint tint of yellow. The arsenic, antimony, mercury, copper, lead and

arsenic. The following is the reaction which gives rise to the formation of this poisonous compound:



Two equivalents of acetate of potassa, two of potassa, and one of arsenious acid, producing one equivalent of oxide of kakodyl, and four of carbonate of potassa.

To prepare an organic mixture suspected to contain arsenic for the reception of sulphuretted hydrogen, Fresenius digests it in a water-bath, with an equal weight of concentrated *pure* hydrochloric acid, and as much water as will give the whole a thin consistence. *Chlorate of potassa* is then added, in portions of about half a drachm, at intervals of about five minutes, and until the contents of the basin have assumed a bright yellow, perfectly homogeneous, and a thin liquid appearance. When this point is attained, about two drachms more of chlorate of potassa are added to the mixture, and the basin is removed from the water-bath. When cool, it is filtered, and the residue washed, until all acid reaction ceases. The filtrate is concentrated to about a pint, and excess of *sulphurous acid* added, to reduce the *arsenic acid* to *arsenious acid*, the former being far less readily precipitated by sulphuretted hydrogen than the latter. The excess of sulphurous acid is then expelled by heat, and the fluid exposed to a slow stream of sulphuretted hydrogen gas for about twelve hours. The sulphuret of arsenic thus obtained is washed and dried over a water-bath, and treated with fuming nitric acid, evaporated to dryness, moistened with pure sulphuric acid, and gently heated, first on the water-bath, and afterwards at a higher temperature (not, however, above  $300^\circ$ ), until the mass begins to crumble. The residue is treated with boiling-water, filtered; and the limpid fluid, after being acidified with hydrochloric acid, is again precipitated by sulphuretted hydrogen. The pure sulphuret of arsenic thus obtained is mixed with carbonate of soda and cyanide of potassium, and reduced in an atmosphere of carbonic acid, as above described.

*M.M. Duflos* and *Hirsh* proceed as follows.—The suspected mass (the stomach, for instance, with its contents) is digested in a tubulated retort, with an equal weight of pure hydro-

tin, if the suspected matter contained any, will have to be sought for in this liquid. As zinc is not precipitated by sulphuretted hydrogen from an acid solution, it must be sought for in the liquid obtained by filtration after the action of the sulphuretted hydrogen. The silver will be found in the residue from the first filtration.

chloric acid; the retort is connected with a receiver in which a little water is placed, the object of which is to collect any chloride of arsenic that might volatilize during the process. The retort is heated by a bath of chloride of calcium until the mass acquires the consistence of paste, when it is allowed to cool. It is then mixed with twice its weight of strong alcohol, and after some time the undissolved portion is collected on a filter, and washed with alcohol. The alcoholic liquid and the washings are lastly introduced into a retort, and the alcohol distilled off. The residue in the retort is mixed with the acid liquor which passed into the receiver during the first distillation, and the mixture is exposed to sulphuretted hydrogen.

*Danger* and *Flandin* heat the organic substance with one-sixth of its weight of concentrated sulphuric acid; the substance is carbonized without foaming; it is continually stirred till the charcoal is dry; a small quantity of nitric acid, or aqua regia, is then added, and the whole extracted with water. They observe, however, that the carbonizing process must only be had recourse to, when all attempts to obtain evidence of the poison without it have failed.

*Dr. Letheby* proposes the following method of treating organic substances, by which he states that it is not difficult to discover  $\frac{1}{200}$  of a grain of arsenic in many ounces of organic matter. The substance of solid, such as the liver, intestine, or muscle, is cut into small pieces, and heated to dryness with aqua regia; the charred mass is boiled with two or three successive portions of water, slightly acidulated with nitric acid, and then boiled for about half an hour with pure granulated zinc; which is best prepared by exposing to a red heat, in a Hessian crucible, alternate layers of granulated zinc, and one-fourth of its weight of nitre, taking care to begin by a layer of saltpetre, and to finish by one of zinc; deflagration takes place, and when it is over, the scorïæ are removed, and the pure metal runs into an ingot; the arsenic will be deposited on the zinc, giving it a grayish black appearance. The arseniated zinc is introduced into a Marsh's apparatus of peculiar construction, and the evolved gas conveyed into a jar containing solution of *nitrate of silver*. According to *Lassaigne's* method, a black precipitate is produced; and by taking the precaution of not allowing the gas to come over too quickly, the whole of it is certain to be decomposed. To this black, turbid solution, hydrochloric acid is added, till all the

silver is precipitated, and a little acid remains in excess. It is then boiled for a few minutes, filtered, and evaporated to dryness; the residue, if there is any, is boiled with distilled water, and carefully precipitated by *ammonia-nitrate of silver*. If any arsenic had been present, it would by this process have been converted into arsenic acid, which would give a red precipitate, with ammonio-nitrate of silver.

#### ARSENIC ACID ( $\text{AsO}_5$ ).

This acid, which is even more poisonous than arsenious acid, is remarkable for its analogy with common or tribasic phosphoric acid. Like the latter, it only partially dissolves in water,\* leaving a powder, which is only dissolved with great difficulty. At a red heat it is partially decomposed, and at a high temperature it is resolved into *arsenious acid* and *oxygen*. It is deliquescent, and strongly acid. The salts which it forms are called *arseniates*; they are mostly insoluble in water, but dissolve in hydrochloric acid; the alkaline arseniates are soluble in water. *Sulphurous acid*, aided by heat, reduces it into arsenious acid.

#### *Behavior of Solutions of Arsenic Acid and the Arseniates, with Reagents.*

*Sulphuretted hydrogen* and *hydrosulphuret of ammonia*, produce no precipitate in neutral or alkaline solutions; but, in acid solutions, a yellow precipitate ( $\text{AsS}_3$ ) is very slowly formed. Hence, previous to precipitating arsenic, when in the form of arsenic acid, by means of the first reagent, it is reduced to arsenious acid by treatment with sulphurous acid.

*Nitrate of silver* produces a red brown precipitate of arseniate of silver ( $3\text{AgO}, \text{AsO}_5$ ), soluble in dilute nitric acid, and in ammonia.

*Ammonio-nitrate of silver* behaves in a similar manner.

*Sulphate* and *ammonio-sulphate of copper* produce a greenish blue precipitate ( $2\text{CuO}, \text{AsO}_5$ ).

*Before the blowpipe*, heated on charcoal in the inner flame arseniates are reduced, disengaging the peculiar garlic odor of suboxide of arsenic, by which minute traces may be recognized.

\* One part of arsenic acid dissolves in two of boiling, or six parts of cold water.



OXIDE OF TIN ( $\text{SnO}$ ).

*General Characters:* When pure, it is black, but by trituration it acquires a gray, green, or brown tinge. It is not altered in dry air, but when brought into contact with bodies in a state of ignition it takes fire, burning with considerable intensity, emitting a white smoke, and is converted into white peroxide. The hydrated oxide, which is obtained by precipitating a solution of the metal in hydrochloric acid by carbonate of potassa, is a white powder, which also takes fire on being brought into contact with a burning body, and glows like tinder. It is more easily soluble in water than the anhydrous oxide. When boiled in water, it is decomposed, and a black powder is formed, which slowly absorbs oxygen, and acquires a lighter color. Oxide of tin is dissolved by the fixed caustic alkalies, but the solution gradually decomposes, depositing metallic tin, the solution then containing a combination of *peroxide* and alkali. *Chloride* of tin is decomposed when brought into contact with water, an insoluble compound of oxide and chloride being formed. This decomposition is prevented by the addition of free hydrochloric acid.

*Behavior of Solutions of Oxide of Tin, with Reagents.*

*Potassa, ammonia,* and their carbonates produce a white precipitate ( $\text{SnO}, \text{HO}$ ), soluble in potassa, but not in ammonia; by repose, and more rapidly when boiled, the solution is decomposed, *metallic tin, peroxide of tin,* and *potassa* being formed thus:—



*Phosphate of soda* produces a white precipitate.

*Ferrocyanide of potassium* gives a white gelatinous precipitate.

*Ferriocyanide of potassium* occasions a white precipitate, soluble in hydrochloric acid.

*Sulphuretted hydrogen* and *hydrosulphuret of ammonia* produce a dark brown precipitate, soluble in potassa, and in alkaline sulphurets, particularly such as contain excess of sulphur, soluble also in hydrochloric acid; but nitric acid converts it by boiling into peroxide of tin; the solution of *sulphuret of tin* in *sulphuret of lime* is precipitated as a yellow *bisulphuret of tin* by hydrochloric acid.

A bar of metallic zinc precipitates tin in small grayish white metallic spangles.

*Chloride of gold* produces a purple precipitate, a mixture probably of peroxide of tin and metallic gold (purple of Cassius), insoluble in hydrochloric acid.

*Chloride of mercury* produces a white precipitate of *subchloride of mercury* ( $\text{Hg}_2\text{Cl}$ ).

The salts of this oxide, from their tendency to absorb oxygen, are powerful reducing agents; they are all decomposed by exposure to the air, passing into salts of the *peroxide*.

*Before the blowpipe*, heated in the inner flame on charcoal with a mixture of *carbonate of soda* and *cyanide of potassium*, protosalts of tin yield ductile grains of metallic tin without any incrustation taking place.

#### PEROXIDE OF TIN ( $\text{SnO}_2$ ).

*General Characters:* This oxide differs according to its mode of formation, not only in its physical but also in its chemical properties: it is found native and crystallized; the crystals are sometimes yellowish brown, and transparent, and sometimes nearly black; when prepared by the action of nitric acid on the metal, it is a white powder, and quite insoluble in acids, but by fusion with carbonate of potassa it is rendered soluble; the oxide\* produced by precipitating the perchloride by ammonia is easily soluble in acids; but after it has been ignited it is insoluble, but it is again rendered soluble by fusion with carbonate of potassa.

#### *Behavior of Solutions of Peroxide of Tin with Reagents.*

*Potassa* and *ammonia* produce a white precipitate, soluble in *potassa*, and, in great excess of *ammonia*, if the salt contains the soluble modification.

*Carbonate of potassa* and *ammonia* produce a white precipitate, soluble in *carbonate of potassa*, but insoluble in *carbonate of ammonia*.

*Phosphate of soda* produces a white precipitate.

\* This hydrated peroxide, after being boiled in hydrochloric acid, subsides without dissolving, but if then freed of the supernatant liquor and treated with water, is wholly taken up. This aqueous solution, when heated, precipitates the dissolved salt on cooling.

*Sulphuretted hydrogen* and *hydrosulphuret of ammonia* throw down from acid and neutral, but not from alkaline solutions, a yellow precipitate of bisulphuret of tin soluble in alkalis, alkaline carbonates, and sulphurets, and in concentrated boiling hydrochloric acid; *nitric acid* converts it into peroxide, and by fusion with nitre it gives rise to the formation of *sulphate* and *stannate of potassa*.

A bar of metallic zinc throws down a white gelatinous precipitate, hydrogen gas being disengaged, or if there is no free acid present gray colored scales of metallic tin.

*Before the blowpipe*, heated with carbonate of soda on charcoal in the inner flame, persalts of tin are reduced to the metallic state.

#### PEROXIDE OF PLATINUM ( $\text{PtO}_2$ ).

*General Characters:* The hydrate is obtained as a reddish brown voluminous precipitate, closely resembling *hydrated sesquioxide of iron*, by precipitating a solution of the nitrate by caustic soda; it contracts considerably on drying; heated in a retort, it loses its water and becomes black; at a higher temperature it parts with oxygen, leaving the metal. Platinum is insoluble in nitric and hydrochloric acids, but it dissolves in *aqua regia*, forming a red brown solution containing perchloride of platinum ( $\text{PtCl}_2$ ).

#### *Behavior of Solutions of Platinum with Reagents.*

*Potassa* produces a yellow crystalline precipitate, consisting of the double chloride of platinum and potassium; the addition of hydrochloric acid favors its formation; it is insoluble in acids, but dissolves with the aid of heat in *potassa*; it is very slightly soluble in water, and insoluble in strong alcohol.

*Ammonia* produces a similar yellow crystalline precipitate, the *double chloride of platinum* and *ammonium* having the same characters as the former, and soluble in excess of ammonia aided by heat; when exposed to red heat it is completely decomposed, leaving the metal in a spongy form.

*Subnitrate of mercury* produces a yellowish red precipitate.

*Chloride of tin*, in presence of free  $\text{HCl}$  acid, communicates to solutions of *bichloride of platinum* a deep red brown color without producing any precipitate.

*Sulphuretted hydrogen* and *hydrosulphuret of ammonia*

produce in acid and neutral solutions a brownish black precipitate ( $\text{PtS}_2$ ), soluble in excess of alkalies and alkaline sulphurets, insoluble in nitric and hydrochloric acids, but soluble in aqua regia. When the solution is heated the action of sulphuretted hydrogen is immediate.

*Before the blowpipe* compounds of platinum are easily reduced, but impart no color to the flux.

#### PEROXIDE OF IRIUM ( $\text{IrO}_2$ ).

*General Characters:* This oxide has not yet been isolated; the metal itself is very slowly acted on by aqua regia, in which it forms a dark red brown solution containing  $\text{IrCl}_2$ , which is not precipitated by alkalies: *sulphuretted hydrogen* produces a brown precipitate,  $\text{IrS}_2$ , which is soluble in *hydro-sulphuret of ammonia*. *Iodide of potassium, cyanide of potassium, protosulphate of iron, and oxalic acid*, all discolor solutions of iridium, without, however, producing any precipitate.

#### PEROXIDE OF GOLD ( $\text{AuO}_3$ ).

*General Characters:* The hydrate of this oxide, which from its tendency to combine with bases, and from the little disposition which it has to combine with acids, ought perhaps more correctly to be called *auric acid*, is of a yellowish red color; the anhydrous oxide is black or deep brown. The hydrate, dried without the aid of heat, is of a chestnut brown color, and has a vitreous fracture. At  $212^\circ$  it loses its water, and becomes partially reduced; even in the dark it undergoes partial decomposition, and at a red heat it is resolved into metallic gold and oxygen. The metal is insoluble in nitric and hydrochloric acid, but it dissolves in aqua regia, forming a fine yellow solution, containing terchloride of gold ( $\text{AuCl}_3$ ).

#### *Behavior of Solution of Terchloride of Gold with Reagents.*

*Potassa*\* after a time produces an inconsiderable reddish brown precipitate, consisting of *teroxide of gold* mixed with *terchloride of gold* and *potassa*.

\* Neither ammonia nor potassa produce precipitates in *cold acid* solutions of peroxide of gold. The solution must also be heated, in order to obtain a precipitate, if it contains ammoniacal salts.




*Ammonia* produces a yellow precipitate (aurate of ammonia, or fulminating gold).

*Ferrocyanide of potassium* communicates to solution of gold an emerald green color.

*Protosulphate of iron* produces in concentrated solutions an immediate dark brown precipitate of metallic gold. In dilute solutions a blue coloring is first perceived, followed by a brown colored precipitate.

*Protonitrate of mercury* occasions a black precipitate.

*Oxalic acid* produces a precipitate of metallic gold, thus:—



*Protochloride of tin*, to which a drop of nitric acid has been added, communicates a reddish purple color to very dilute solutions; in concentrated solutions a red purple precipitate (purple of Cassius) is formed.

A bar of metallic zinc precipitates metallic gold in the form of a brown coating.

*Sulphuretted hydrogen* and *hydrosulphuret of ammonia* precipitate from neutral and acid solutions of gold, the tersulphuret ( $\text{AuS}_3$ ), partially soluble in potassa, soluble in great excess of hydrosulphuret of ammonia, and in aqua regia, but insoluble in all other acids and alkalies.

#### SELENIOUS ACID ( $\text{SeO}_2$ ).

*General Characters:* On evaporating a solution of selenium in aqua regia, this acid remains in the form of a white saline mass, which at the temperature of about  $600^\circ$  assumes the form of a deep yellow gas, much resembling chlorine: on cooling, the acid condenses in long needles, and by allowing it to cool slowly it is deposited in the form of a semi-transparent crust. When first prepared it has a brilliant appearance, but by exposure to the air it becomes dull, from the absorption of moisture. Its taste is distinctly acid, but it leaves a burning taste in the mouth; it is very soluble in alcohol and boiling water; the solution deposits the hydrated acid on cooling in the form of striated prisms. The hydrated acid is also deposited from a hot solution in nitric acid in long prisms resembling nitre. It is easily reduced. On introducing a slip of zinc or polished iron into a solution of selenious acid mixed with hydrochloric acid, it immediately becomes covered with a copper-colored deposit, and selenium precipitates by degrees

in the form of red, brown, or grayish black flocks, according to the temperature. A mixture of *sulphuric* and *selenious* acids is slowly acted on, and the precipitate contains a little sulphur. Selenious acid is also decomposed by *silver*. *Selenium* is best precipitated from *selenious acid*, and the *selenites* by *sulphite of ammonia*. The liquor, which is at first clear, becomes yellow, then turbid, then cinnabar red, and after a few hours it deposits red flocks of *selenium*. If nitric acid be present, a perfect reduction cannot be effected.

*Sulphuretted hydrogen* produces in an acid solution a yellow precipitate (becoming red when dried) of *sulphuret of selenium*, which is soluble in *hydrosulphuret of ammonia*.

*Solid selenites*, heated in a tube with *chloride of ammonium*, afford a sublimate of selenium, which is recognized by its peculiar odor.

*Before the blowpipe*, the minutest trace of selenium may be recognized by ignition on charcoal in the oxidating flame; a strong disagreeable smell similar to *decaying horseradish* is given off. If much selenium be present, a reddish vapor is evolved, and a steel-gray sublimate is deposited on the charcoal, which on the exterior edges sometimes passes into violet, and in their layers blue.

#### TELLUROUS ACID ( $\text{TeO}_2$ ).

This acid is obtained in crystalline grains, by acting on *tellurium* with *nitric acid*, and, as a white flocculent hydrate, by precipitating the solution in nitric acid with water. The yellow color which the acid frequently exhibits arises from impurities. When first laid on the tongue, it produces little taste; but after a time a very disagreeable metallic taste, similar to that of salts of silver, is experienced. It reddens litmus paper, though not immediately; it is very sparingly soluble in water. On being heated, it acquires a fine citron yellow color; but on cooling it again becomes colorless; at a red heat it melts into a transparent deep yellow liquid, solidifying on cooling into a colorless crystalline mass; heated in the open air it fumes, and slowly sublimes; heated in open vessels with carbon, it is reduced with detonation, the greater part of the tellurium volatilizing; in close vessels the reduction takes place easily, but the metal is obtained with difficulty in a compact mass. It is also reduced, though not very

readily, by hydrogen gas. It is very sparingly soluble in acids, in ammonia, and in the carbonated alkalis. The caustic fixed alkalis, on the other hand, dissolve it immediately. When tellurous acid is fused with an equal weight of carbonate of potassa, and the tellurite of potassa thus obtained dissolved in water, and mixed with a slight excess of nitric acid, a white voluminous hydrate is produced, which has an acrid metallic taste, instantly reddens litmus paper, and is soluble in water, and very soluble in nitric and other acids, and also in caustic ammonia and the carbonated alkalis.

*Behavior of Solution of Tellurous Acid with Reagents.*

The caustic alkalis and their carbonates produce a white precipitate, soluble readily in potassa, and soluble also in alkaline carbonates.

Sulphuretted hydrogen produces in an acid solution a dark brown precipitate, very soluble in hydrosulphuret of ammonia.

Sulphurous acid, alkaline sulphites, and metallic zinc, produce a black precipitate of metallic tellurium.

Protochloride of tin and protosulphate of iron produce a black powder, which, on being rubbed, assumes a metallic lustre.

Before the blowpipe, heated on charcoal, or in a glass tube open at both ends, a white sublimate with a reddish border is obtained in either flame, and which disappears with a beautiful bluish green tinge; when the reducing flame is directed on it in large quantities, the flame also becomes blue; if the peculiar smell of horseradish is perceptible, selenium is present. If the substance under examination contains other metals, as lead or bismuth, it should be mixed with boracic acid, which will dissolve those metals and prevent them from volatilizing.

OXIDE OF TUNGSTEN ( $\text{WO}_2$ ).

*General Characters:* This oxide, when prepared by reducing tungstic acid by hydrogen gas, is brown; it may be obtained crystalline and of a metallic lustre by employing crystallized tungstic acid, such as is obtained by decomposing tungstate of ammonia in close vessels. The oxide in this state has, when pressed together, a deep copper color. By

pouring dilute hydrochloric acid on tungstic acid, and placing in the liquor a strip of *zinc*, it is gradually decomposed, and oxide of tungsten is obtained in the form of brilliant copper-colored spangles, but it cannot be preserved or even dried in this state. It may also be obtained in the form of a beautiful violet brown precipitate by mixing *chloride of tungsten* with water, but it is very unstable: the oxide obtained in the dry way may be preserved without alteration. When heated below redness, it burns like tinder, and is converted into tungstic acid. It does not appear to form salts with acids, but it dissolves in concentrated *caustic potassa* with the disengagement of heat, and the formation of *tungstate of potassa*. This oxide is remarkable for a beautiful compound which it forms with *soda*; it is prepared by saturating fused *tungstate of soda* with tungstic acid, and reducing the mass by heat in a current of hydrogen gas: after having dissolved out the neutral undecomposed tungstate, the new compound remains in the form of regular cubes and scales of a golden yellow color, possessing metallic lustre, and having all the appearance of *gold*. It is not acted upon by any acid but the *hydrofluoric*; *aqua regia* has no action on it, but it is decomposed by *oxygen gas*, *sulphur*, and *chlorine*, at a high temperature. No such compound can be formed with *potassa* or with the alkaline earths.

#### TUNGSTIC ACID ( $\text{WO}_3$ ).

*General Characters:* This acid is generally prepared by fusing a mixture of finely powdered *wolfram* with an equal weight of carbonate of potassa, and half its weight of nitre.

The alkaline tungstate thus formed is dissolved in water exactly neutralized by nitric acid, precipitated by nitrate of mercury, and the precipitate calcined in a platina crucible. It is of a fine yellow color, becoming dark green when strongly heated; it also assumes a green tint by mere exposure to the rays of the sun; it is insoluble in water, but readily soluble in caustic alkalies. Hydrated tungstic acid is formed slowly as a gelatinous mass, by heating a diluted solution of an alkaline tungstate with dilute nitric acid; when washed and dried it is a powder of a brilliant opaque yellow gray color. *Tungstic acid* like *molybdic acid*, unites with other acids, acting the part of a base.



*Zinc* produces in acid (except nitric) solutions of tungstic acid a beautiful blue color, owing to the formation of *oxide of tungsten*.

*Sulphuret of tungsten* is precipitated when a tungstate is decomposed by acids in the presence of *hydrosulphuret of ammonia*.

*Before the blowpipe* tungstic acid is thus detected: Mix a small portion of the mineral with five times its volume of *soda*, and heat strongly in a platinum spoon; dissolve in water, and precipitate the filtered solution with hydrochloric acid; the precipitate assumes, when heated, a beautiful yellow color. The oxides of tungsten, when perfectly pure, liquefy with microcosmic salt in the oxidating flame; in the reducing flame they become green, and when cold beautiful blue. The glass, when treated with tin on charcoal in the reducing flame, assumes a darker color, which, on cooling, is *green*.

#### OXIDES OF VANADIUM ( $\text{VO}_2$ , $\text{VO}$ , $\text{VO}_3$ ).

*General Characters:* *Suboxide of vanadium*, obtained by reducing *vanadic acid* at a red heat by a current of hydrogen gas, is a black crystalline powder. It is remarkable as being an excellent conductor of electricity, and as excelling, as a negative electromotive element, copper, and even gold or platina. It has not hitherto been made to combine with either acids or bases. It oxidizes gradually in the air, and under water it acquires a fine green color. Heated in the air, it takes fire and burns, leaving a black mass; by chlorine it is converted into *chloride* and *vanadic acid*.

#### OXIDE OF VANADIUM, OR VANADIOUS ACID ( $\text{VO}_2$ ).

The anhydrous oxide is a black powder which has no action on test paper. It is insoluble in water, but when left for some time in contact with that fluid it oxidizes, becoming, by degrees, green. The hydrate which, when first formed, is grayish white, oxidizes rapidly in the air, becoming first brown, then green, and finally black. The calcined oxide is slowly but completely dissolved in acids; the solution is blue; though acting the part of a base, it nevertheless combines with bases, giving rise to a class of salts called *vanadites*. It is dissolved by alkaline carbonates; the solution, which is

of a deep brown color, contains a *vanadite* and a *bicarbonate*. The bicarbonates also dissolve it, forming blue solutions, probably neutral double carbonates of the oxide and alkali.

#### VANADIC ACID ( $\text{VO}_3$ ).

Prepared by decomposing *vanadite of ammonia* by heat. It is a rusty red brown powder, without taste or smell. It supports a high temperature without losing oxygen; but at a red heat it enters into fusion. In contact with organic matter at a red heat, it loses oxygen. It strongly reddens litmus paper. The fused acid crystalizes, on cooling, in the form of interlaced needles of a yellowish red color; but if a small quantity of oxide be present, it has a violet tint. It does not conduct electricity. It dissolves sparingly in water, forming a clear yellow solution. It cannot be obtained crystalline in the humid way, nor can it be obtained pure out of solution, as it combines with acids as well as with bases. It is easily reduced to the state of oxide under the influence of an acid, such as fuming *nitric acid*, *sulphurous*, *oxalic*, or *tartaric acids*; *alcohol* and *sugar* likewise effect its reduction, blue oxide of vanadium being formed. Hydrochloric acid dissolves it, forming a green solution; but, after a while, *chlorine* is disengaged, and the liquid acquires the property of dissolving gold and platinum.

#### *Behavior of Solution of Oxide of Vanadium with Reagents.*

*Potassa* produces a grayish white hydrate, soluble in excess of *potassa*, but insoluble in *ammonia*: a larger amount of alkali gives a brown precipitate of vanadite, soluble in *pure* water, imparting a brown color.

*Sulphuretted hydrogen* occasions no precipitate; but *hydrosulphuret of ammonia* produces a brownish black precipitate, soluble in excess, the solution having a purple color.

#### *Behavior of Solution of Vanadic Acid with Reagents.*

*Nitrate of silver* produces a yellow precipitate, becoming white by exposure to the air, and soluble in *nitric acid* and in *ammonia*.

*Chloride of barium* produces a bulky orange yellow precipitate, slightly soluble in water.

*Hydrosulphuret of ammonia* gives a brown color ( $\text{VaS}_3$ ),

also, (if the solution is acid,) a precipitate soluble in excess, forming a brown liquid.

*Ferrocyanide of potassium* produces a fine green precipitate.

*Chloride of ammonium* produces a white flocculent precipitate of *vanadate of ammonia*, quite insoluble in hydrochloric acid.

*Before the blowpipe, oxides of vanadium*, heated in the outer flame with borax or microcosmic salt, give a yellow bead; in the inner flame a fine green one, which again becomes yellow in the outer flame. *Vanadic acid*, heated on charcoal, leaves a compact mass the color of plumbago (suboxide of vanadium); with borax and microcosmic salt it gives a beautiful green glass, which while hot is brown. It is not colored blue by the addition of tin. *Chromic acid* gives with borax and microcosmic salt a green bead; but *vanadic acid* is distinguished from *chromic acid* by the circumstance that the green bead in the former can be changed in the oxidating flame to yellow, which is not the case with the latter.

#### OXIDES OF MOLYBDENUM ( $\text{MoO}$ . $\text{MoO}_2$ . $\text{MoO}_3$ ).

*General Characters:* When to a solution of a *molybdate* in water hydrochloric acid is added, and the mixture digested with *distilled zinc*, the latter becomes oxidized at the expense of the molybdic acid; and the liquid becomes first blue, then red, brown, and finally black. From this solution *potassa* precipitates *hydrated oxide of molybdenum* in the form of a black flocculent mass. This hydrate is dissolved with difficulty in acids; the solutions are opaque and almost black, unless greatly diluted; the taste astringent, but not metallic. When heated to redness in vacuo, it takes fire, burning with vivid scintillations, and a hydrous oxide remains of a pitchy blackness, and insoluble in acids. Heated in the air, it burns and is converted into *molybdic oxide* ( $\text{MoO}_2$ ). *Oxide of molybdenum* is not soluble either in *caustic potassa* or in solutions of the *fixed alkaline carbonates*. It dissolves, however, in *carbonate of ammonia*.

#### MOLYBDIC OXIDE ( $\text{MoO}_2$ ).

When pure, it is a powder of a deep brown color; by the

light of the sun it is *brilliant purple*. It is insoluble in alkalis and in acids, but it dissolves in small quantities in a mixture of *concentrated sulphuric acid* and *tartrate of potassa*. Nitric acid converts it into *molybdic acid*. Hydrated molybdic oxide is similar in appearance to *hydrated sesquioxide of iron*. It is, to a certain extent, soluble in water, the solution having a deep red color, and it appears to form with some acids subsalts, which are soluble. If dried by exposure to the air, it acquires a blue color on the surface from the absorption of oxygen; the solution in water reddens litmus paper; it has an astringent and somewhat metallic taste. It is completely precipitated by sal-ammoniac, and when once dried cannot again be dissolved in water. Heated in vacuo, it loses its water, and brown anhydrous oxide remains. Though it reddens litmus paper, it has none of the other properties of an acid. Caustic alkalies do not dissolve it, though it is soluble in alkaline carbonates. The solution in *carbonate of ammonia* is entirely precipitated by boiling, and that in *carbonate of potassa* is by degrees converted into *molybdate of potassa*.

#### MOLYBDIC ACID ( $\text{MO}_3$ ).

When pure, it is a light, porous, white mass; and when diffused through water it assumes the appearance of extremely small, silky, brilliant, crystalline scales. Heated to redness, it melts into a deep yellow liquid, which, on cooling, becomes pale straw yellow and crystalline, and on breaking divides into crystalline spangles. In close vessels it supports a strong red heat without volatilizing; but in open vessels it sublimes at its fusing point, its surface becoming covered with crystalline spangles. Water dissolves it in small quantities (about  $\frac{1}{50}$ th of its weight). The solution has a feeble metallic taste, and reddens litmus paper. Before calcination it is soluble in acids, forming compounds in which it acts the part of a base. It dissolves also in a saturated solution of *tartrate of potassa*, and in solutions of *caustic* and *carbonated alkalies*.

#### *Behavior of Solutions of Oxide of Molybdenum, with Reagents.*

*Potassa* and *ammonia* produce a brownish black precipitate, insoluble in excess of the precipitants.



*Carbonate of potassa* and *carbonate of ammonia* produce a similar precipitate, slightly soluble in *carbonate of potassa*, more soluble in *carbonate of ammonia*.

*Hydrosulphuret of ammonia* gives a yellowish brown precipitate, soluble in excess of the precipitant.

*Molybdic oxide* is distinguished from *oxide of molybdenum* by its greater solubility in *carbonate of potassa*.

#### *Behavior of Molybdic Acid with Reagents.*

*Nitrate of silver* produces a white precipitate, soluble in much water and in *nitric acid* and in *ammonia*.

*Chloride of barium* produces a similar precipitate, soluble in *nitric acid*, and in a large quantity of water.

*Sulphuretted hydrogen*, added in excess to an acid solution, produces, after a time, a brown precipitate, subsiding slowly; the supernatant fluid being blue or green.

*Metallic zinc* or *tin* produces in solutions containing free hydrochloric acid a blue color, which becomes green and finally black.

*Before the blowpipe*, the oxides of molybdenum give to microcosmic salt in the inner flame a fine green color, becoming more perceptible on cooling; with borax they produce in the inner flame a brownish red bead.

#### *General Remarks on the Oxides of the Sixth Group.*

Of the metallic oxides comprehended in this group, it will be only necessary to make a few remarks on the method of detecting *tin*, *antimony* and *arsenic*, when these metals exist together in a compound. The three metals are obtained together in the form of *sulphurets* ( $\text{SnS}_2, \text{SbS}_3, \text{AsS}_3$ ), by precipitating their solution in hydrosulphuret of ammonia by an acid. The dry sulphurets are fused with a mixture of *nitre* and *carbonate of soda*, by which operation the sulphur becomes converted into sulphuric acid, which combines with the potassa of the nitre; and the nitric acid furnishes oxygen, whereby the sulphurets are converted into oxides ( $\text{SnO}_2, \text{SbO}_3, \text{AsO}_3$ ). These oxides act the part of acids, and combine with the *potassa*, giving rise to *stannate*, *antimoniate* and *arseniate*, of the alkali. The dry mass is treated with water, which dissolves out the *arseniate of potassa*, and also a small quantity of *stannate* and *antimoniate* of potassa. The two latter are

removed from the filtered solution by the addition of a few drops of nitric acid, the solution is again filtered and exactly neutralized by ammonia, and arsenic acid detected by *nitrate of silver*. The white mass insoluble in water is fused in a porcelain crucible with *cyanide of potassium*; the globule of reduced metal is heated with nitric acid, and the oxides thus produced, after being well washed, are boiled with *tartaric acid*, in which *oxide of antimony* is soluble, and may be detected by *sulphuretted hydrogen*. A portion of the mixed oxides may likewise be tested before the blowpipe by fusing in the reducing flame on charcoal with a mixture of carbonate of soda and cyanide of potassium; the antimony is dispersed, leaving a characteristic white oxidation crust, and a ductile globule of metallic tin remains.

## 2. ACIDS.

Although acids cannot be classified with the same degree of perspicuity with which we are enabled to arrange the bases, there are certain reagents by which we can divide them into groups; the subdivision of which is afterwards effected by other reagents, which are called *special*.

The reagents for grouping the *inorganic* acids are *chloride of barium* and *nitrate of silver*; those for grouping the *organic* acids are *chloride of calcium*, and *sesquichloride of iron*.

### *Inorganic Acids.*

I. Acids precipitated from their neutral solutions by *chloride of barium*.

|                      |                       |
|----------------------|-----------------------|
| Carbonic acid.       | Hypophosphorous acid. |
| Sulphurous acid.     | Boracic acid.         |
| Hyposulphurous acid. | Silicic acid.         |
| Hyposulphuric acid.  | Hydrofluoric acid.    |
| Sulphuric acid.      | Chromic acid.         |
| Selenic acid.        | Arsenic acid.         |
| Phosphoric acid.     | Arsenious acid.       |
| Phosphorous acid.    | Other metallic acids. |

II. Acids precipitated from their neutral solutions by *nitrate of silver*.

Hydrochloric acid.

Iodic acid.

Hydrobromic acid.

Periodic acid.

Bromic acid.

Hydrocyanic acid.

Hydriodic acid.

Hydrosulphuric acid.

III. Acids precipitated by neither *chloride of barium* nor *nitrate of silver*.

Nitric acid.

Chloric acid.

Nitrous acid.

Chlorous acid.

Perchloric acid.

### *Organic Acids.*

I. Acids precipitated by *chloride of calcium*.

Oxalic acid.

Citric acid.

Tartaric acid.

Malic acid.

Pyrotartaric acid.

II. Acids precipitated by *sesquichloride of iron*.

Succinic acid.

Tannic acid.

Benzoic acid.

Gallic acid.

III. Acids precipitated by neither *chloride of calcium* nor *sesquichloride of iron*.

Acetic acid.

Uric acid.

Formic acid.

Meconic acid.

### INORGANIC ACIDS.

1. Those precipitated from their neutral solutions by *chloride of barium*.

### CARBONIC ACID ( $\text{CO}_2$ ).

*General Characters:* At common temperatures and pressures, this acid is a colorless transparent, irrespirable, and incombustible gas. It is heavier than atmospheric air in the proportion of 1.5 to 1, and totally unfit for supporting combustion. It has a sour and somewhat astringent taste. It reddens litmus paper, but as the gas volatilizes the blue color returns. It may be poured from one vessel to another, and a small animal exposed to its influence instantly dies in strong convulsions. It is decomposed at a red heat in contact with

carbon and other combustibles, carbonic oxide, an inflammable gas, being produced. A succession of electric sparks likewise decomposes it into carbonic oxide and oxygen. Water at ordinary temperatures and pressures absorbs rather more than its own volume of carbonic acid gas, and considerably more at a low temperature and under pressure. The solution has an agreeable, piquant, and feebly acid taste. At a temperature of  $0^{\circ}$ , and under a pressure of 36 atmospheres, it is condensed into a colorless liquid, and by peculiar management it may even be obtained in the solid state, having the appearance of a mass of snow. All the neutral carbonates, with the exception of those of the alkalis, are *insoluble* in water; they are, however, decomposed by nearly all acids that are soluble in water, the carbonic acid gas escaping with effervescence; but, to expel the whole, excess of acid must be added, in consequence of the formation of *bicarbonates*. Most of the carbonates lose their acid by ignition.

*Behavior of the Soluble Carbonates with Reagents.*

*Lime water* and *water of barytes* produce white precipitates, insoluble in water, but soluble with effervescence in hydrochloric acid.

*Chloride of barium* and *chloride of calcium* produce white precipitates in solutions of neutral alkaline carbonates; but in solutions of *bicarbonates* no precipitate is formed until the second atom of carbonic acid is expelled by boiling, because both *bicarbonate of baryta* and *bicarbonate of lime* are soluble in water.

SULPHUROUS ACID ( $\text{SO}_2$ ).

*General Characters:* At common temperatures and pressures it is a permanent gas, of a suffocating odor and a very disagreeable taste, not inflammable nor possessing the power of supporting combustion. It is very fatal to animal life. It is absorbed in large quantities by water, and still more copiously by alcohol. It destroys the color of vegetable substances. Its acid properties are very weak. All acids but *carbonic* and *hydrocyanic acids* displace it from its combinations. The class of salts which it forms are called *sulphites*; they are all insoluble in water but those of the alkalis. All




the acid salts of sulphurous acid are soluble. At a low temperature and under pressure it is reduced to a liquid.

*Behavior of Solutions of Sulphites with Reagents.*

*Chloride of barium* and *chloride of calcium* produce a white precipitate, soluble in hydrochloric acid; if, however, the solution of the sulphite has been for some time exposed to the air, this precipitate is no longer completely soluble in hydrochloric acid.

*Protonitrate of lead* produces a white precipitate, soluble in cold nitric acid, but decomposing when boiled, *sulphate of lead* being precipitated, and nitrous fumes evolved.

*Nitrate of silver* produces a white precipitate ( $\text{AgO}, \text{SO}_2$ ), becoming black by the application of heat, the metal being reduced, and sulphuric acid formed. Thus:—



*Protochloride of tin*, acidified with hydrochloric acid, produces a yellowish brown precipitate ( $\text{SnS}_2$ ).

*Chloride of barium*, when boiled with a solution of a sulphite, together with a nitric acid, produces a white precipitate ( $\text{BaOSO}_3$ ).

*Chlorine, nitric acid* and *fused nitre* convert *sulphites* into *sulphates*.

Solid sulphites, when moistened with an acid, evolve sulphurous acid, which may be recognized by its odor; when ignited in a glass tube, they are decomposed into *sulphurets* and *sulphates*, and on treating the fused mass with a diluted acid, *sulphuretted hydrogen* gas is disengaged, provided the metallic sulphuret belongs to that class which decomposes water with the assistance of an acid.

*Liquid sulphuretted hydrogen* produces in solutions containing sulphurous acid a white precipitate of *sulphur*.


### HYPOSULPHUROUS ACID ( $\text{S}_2\text{O}_2$ ).

The aqueous solution of this acid decomposes spontaneously into *sulphurous acid* and *sulphur*; the compounds which it forms with alkalies and alkaline earths are, with the exception of hyposulphite of baryta, soluble in water.


*Behavior of Solutions of Hyposulphites with Reagents.*

*Chloride of barium* in concentrated solutions occasions a white precipitate.

*Nitrate of silver* produces a precipitate which at first is white, but it rapidly becomes yellow, and finally black, *sulphuret of silver* being formed and nitric acid set free, thus:—




*Hydrochloric acid* produces a yellow precipitate of sulphur, sulphurous acid being set free, thus:—



Solutions of soluble hyposulphites possess the property of dissolving recently precipitated *chloride of silver*; the solution has an intensely sweet taste, leaving one of that nauseous bitterness peculiar to salts of silver.

#### HYPOSULPHURIC ACID ( $\text{S}_2\text{O}_5$ ).

The aqueous solution of this acid, when heated, is resolved into *sulphuric* and *sulphurous acids*; its salts undergo the same decomposition by hydrochloric acid, aided by heat, thus:—



The hyposulphates are generally soluble in water.

#### SULPHURIC ACID ( $\text{SO}_3$ ).

*General Characters:* In its pure anhydrous state it forms a tenacious crystalline mass resembling *asbestos*; exposed to the air it gives off thick opaque fumes; its affinity for water is so powerful, that it hisses like a red hot iron when brought into contact with it; *monohydrate* of sulphuric acid ( $\text{HO}, \text{SO}_3$ ) is sometimes fuming, but as manufactured in England, it does not fume, but has an oily consistence; hence its commercial name *oil of vitriol*. When pure it is colorless, the dark tinge that the acid sometimes has arising from the separation of carbon from organic substances, which it rapidly decomposes. It has a powerful affinity for water, abstracting it from the atmosphere with great rapidity; during its combination with water great heat is evolved; the monohydrated acid freezes at  $31^\circ$ , and boils at  $617^\circ$ ; it distils without alteration; its acid properties are exceedingly powerful; it displaces all other acids from bases at temperatures below its boiling point; but at a higher temperature it is itself displaced by certain weaker acids which are not volatile; the greater number of its compounds with bases are soluble in water; the sulphates of *baryta*, *strontia*, and *lead* are, however, nearly insoluble, the first entirely so.

*Behavior of Solutions of Sulphates with Reagents.*

*Chloride of barium* produces an immediate white precipitate ( $\text{BaO}, \text{SO}_3$ ),\* even in highly dilute solutions, insoluble in water and in acids. The solution to be precipitated should not contain too much *nitric* or hydrochloric acid, as baryta salts which are very *soluble* in water are very sparingly so in acids; and a white precipitate might be formed which could be mistaken for *sulphate of baryta*. Such a precipitate would, however, be readily soluble in water.

*Acetate of lead* produces a white precipitate, soluble to a slight extent in dilute nitric acid, and in *boiling and concentrated* hydrochloric acid.

The sulphates of the alkaline earths and alkalies are not decomposed by heat alone; when heated in contact with charcoal they are reduced to sulphurets; the reduction is facilitated by mixture with carbonate of soda. On treating the reduced mass with an acid, *sulphuretted hydrogen* is evolved, which may be detected by the odor, by lead paper, or by making the experiment on a bright silver surface. All the other sulphates, with the exception of that of *oxide of lead*, are decomposed at a high temperature, *sulphuric acid*, or a mixture of *sulphurous acid* and *oxygen*, being set free, and pure oxides, or the metals themselves, left. Insoluble sulphates are converted into carbonates by fusion with carbonate of soda, alkaline sulphates being formed.

*Before the blowpipe*, colorless sulphates may be detected by fusing them with *silicate of soda* in the reducing flame; a sulphuret is thereby formed, and the glass assumes a red or dark yellow color, according to the quantity of acid present. *Colored* sulphates are detected by fusing them with two parts of soda and one of borax, in the reducing flame, on charcoal, and placing the fused mass on a plate of silver, and moistening it water. A tarnishing of the metal indicates *sulphur*.

\* Salts of baryta give, also, a white precipitate with selenic acid, but it is soluble in HCl acid. The hydrofluosilicate of baryta is also white and insoluble in both nitric and hydrochloric acids: to distinguish therefore from the sulphate it is necessary to test the original solution with a lead or strontia salt, which yields no precipitate with hydrofluosilicic acid.

SELENIC ACID ( $\text{HO,SeO}_3$ )

Produces a precipitate with *chloride of barium*, which is insoluble in nitric acid. *Seleniate of baryta* is, however, decomposed by boiling hydrochloric acid, chlorine being evolved. This is not the case with *sulphate of baryta*.


TRIBASIC PHOSPHORIC ACID ( $3\text{HO,PO}_5$ ).

*General Characters:* When anhydrous, it has the form of white flakes, which rapidly absorb moisture from the atmosphere. The hydrate is a vitreous mass, and is known as *glacial phosphoric acid*. It deliquesces in the air to a syrupy liquid; it has a free acid, but not caustic taste; if pure, it volatilizes without residue when strongly heated in an open platinum vessel; it attacks vessels of glass or porcelain when fused therein. The alkaline phosphates are soluble in water, but the neutral compounds of phosphoric acid with the earths and metallic oxides are insoluble in water, though they dissolve in excess of phosphoric acid and in nitric acid. By ignition they are not completely decomposed, but may thereby be converted into *pyrophosphates* or *metaphosphates*.

*Behavior of Solution of Phosphates with Reagents.*

*Chloride of barium* and *chloride of calcium* produce, in solutions of neutral or basic phosphates, a white precipitate, soluble in *nitric*, *hydrochloric*, and *acetic* acids. *Phosphate of lime* ( $2\text{CaO,PO}_5$ ) is slightly soluble in solution of sal-ammoniac.


*Nitrate of silver*\* produces, in solutions of neutral and basic phosphates, a lemon yellow precipitate ( $3\text{AgO,PO}_5$ ), soluble in nitric acid and in ammonia, and sparingly soluble in acetic acid. Common phosphate of soda, after having been ignited, produces, with nitrate of silver, a curdy white precipitate, ( $2\text{AgO,PO}_5$ ). The fluid in which the yellow precipitate is suspended has an acid reaction in consequence of the presence of free nitric acid, thus:—



\* This is a very characteristic test, but as nitrate of silver gives a similar precipitate in alkaline silicates, the absence of silicic acid must be determined before the employment of this reagent.



The fluid in which the white precipitate is suspended is neutral, there being no excess of nitric acid, thus:—



*Acetate of lead* produces a white precipitate, very sparingly soluble in acetic acid, but readily so in nitric acid. This precipitate, when fused on charcoal in the outer blowpipe flame, forms a bead, which crystalizes on cooling.

*Sesquichloride of iron* produces, in solutions of alkaline phosphates, a yellowish white gelatinous precipitate, insoluble in acetic acid. If to the solution\* of a phosphate of an alkaline earth in hydrochloric acid sesquichloride of iron be added in excess, and then ammonia in slight excess, a brown precipitate is produced, consisting of a mixture of *phosphate of sesquioxide* and *hydrated sesquioxide of iron*. The latter may be dissolved in acetic acid; and the former, after being well washed, is decomposed by digestion with hydrosulphuret of ammonia into *sulphuret of iron* and *phosphate of ammonia*. The whole of the phosphoric acid is thus brought into the form of a soluble salt.

*Sulphate of magnesia* and *soluble magnesian salts* produce a crystalline precipitate, which makes its appearance only gradually; but in the presence of ammonia a crystalline precipitate of basic phosphate of magnesia and ammonia ( $2\text{MgO}, \text{NH}_4\text{O}, \text{PO}_5$ ) immediately subsides, and is favored by agitation. This precipitate is insoluble in ammonia and in ammoniacal salts, but is soluble in free acids.

*Before the blowpipe*, phosphoric acid is detected by the following method of Berzelius:—Dissolve the subject of examination in boracic acid, upon charcoal, in the oxidating flame; introduce into the melted bead a piece of fine iron wire, and expose the whole to a strong reducing flame. The iron oxidizes at the expense of the phosphoric acid, and *borate* and *phosphate of iron* are produced. The latter fuses in a strong red heat. When cold, the glass is removed from the charcoal, and broken into pieces on an anvil, between folds of paper. A globular metallic button of *magnetic phosphuret of iron* is thus pro-

\* To detect phosphoric acid in phosphate of alumina, the latter is to be dissolved in hydrochloric acid and then tested with potassa solution sufficient to completely redissolve the phosphate of alumina at first precipitated: afterwards a solution of bisilicate of potassa is added to throw down alumina (with silicate of potassa). Into the filtered liquid pour chloride of calcium, which precipitates phosphate of lime.

duced. This operation requires address on the part of the operator. To detect phosphoric acid in an aluminous compound, Berzelius gives the following method: The substance, pulverized in an agate mortar, is rubbed with a mixture of six parts of soda and one and a half of silica, and the mass fused on charcoal in the oxidating flame. The fused residuum is boiled with water, in which phosphate and the excess of carbonate of soda dissolves, leaving the alumina in combination with silicic acid. The phosphoric acid is detected in aqueous solution as above directed.

#### PHOSPHOROUS ACID ( $\text{PO}_3$ ).\*

*General Characters:* In its anhydrous state it is a white, but not crystalline powder. Its hydrate may be obtained in the form of deliquescent crystals, by evaporating the aqueous solution obtained by acting on *sesquichloride of phosphorus* by water. It slowly absorbs oxygen from the air, becoming converted into phosphoric acid. At an elevated temperature it is decomposed, phosphuretted hydrogen being formed, which inflames on the approach of a burning body, fumes of phosphoric acid making their appearance. The alkaline *phosphites* are soluble in water, and are powerful deoxidizing agents. They reduce solutions of *gold* and *silver*, and salts of *copper* and *mercury*, passing into *phosphates*. Heat also converts them into *phosphates*, hydrogen gas being evolved, which burns with a blue flame without producing any fumes of phosphoric acid. *Hypophosphites* are distinguished from *phosphites* from their giving rise to a spontaneously inflammable phosphuretted hydrogen when strongly heated, fumes of phosphoric acid being formed. All the *hypophosphites* are soluble in water.

#### BORACIC ACID ( $\text{BO}_3$ ).

*General Characters:* This acid crystalizes, out of its aqueous solution, in brilliant scales, which are greasy to the touch. It has no smell, and a very faint acid taste. It is soluble in hot

\* Wohler determines the presence of phosphorous acid in phosphoric acid by adding to the mixture an aqueous solution of sulphurous acid and applying moderate heat. If phosphorous acid is present sulphur will be separated;—and if arsenious or arsenic acid, also a yellow precipitate of sulphuretted arsenic is formed.

water. In the presence of aqueous vapors it sublimes easily, but alone it is perfectly fixed at a red heat, at which, however, it fuses into a colorless, transparent, brittle glass. It dissolves in alcohol, to the flame of which it communicates a green tinge, a property which is characteristic of this acid. It volatilizes with the vapor of alcohol as with that of water. The alkaline borates are soluble in water, but the borates of the earths and the metallic oxides are almost insoluble, though they dissolve readily in acids and ammoniacal salts. They are all very fusible, and promote the fusion of other bodies when mixed with them; hence their uses as fluxes. Free boracic acid browns turmeric paper like an alkali.

*Behavior of Solutions of Borates with Reagents.*

*Chloride of barium* produces a white precipitate ( $\text{BaO}, \text{BO}_3$ ), soluble in acids and in ammoniacal salts, and in a large quantity of water.

*Nitrate of silver*, in concentrated solutions, produces a white precipitate, soluble in ammonia, and in dilute nitric acid.

*Chloride of calcium* produces a white precipitate, soluble in acids and in ammonia, and in a large quantity of water.

*Acetate of lead* produces a white precipitate, soluble in acids.

*Nitrate of suboxide of mercury* produces an olive-brown precipitate, soluble in nitric acid and in ammonia.

*Hydrochloric and sulphuric acids* separate *borycic* acid from solutions of borates, at a boiling temperature, in the form of crystalline scales.

If a pulverized borate be moistened in a porcelain capsule with a few drops of sulphuric acid, and covered with alcohol, warmed and inflamed, the flame will have a green tinge, most perceptible at its borders. The presence of *chlorides* interferes with this test, in some measure, in consequence of the formation of hydrochloric ether; the flame, however, in this case, has a decided *blue* tinge.

*Borate of soda* precipitates solution of sesquichloride of iron. The precipitate dissolves on heating to a dark red liquid, which might be mistaken for the reaction produced between *acetic acid* and the same reagent if the solutions are not very concentrated, only a darker color is observable, and no precipitate.

*Before the blowpipe*, the following method of detecting

boracic acid in salts and minerals has been recommended by *Turner*: Knead into a paste, with a few drops of water, a mixture of the finely divided substance, with  $4\frac{1}{2}$  parts of *bisulphate of potassa*, and 1 of powdered *fluor spar*, and fuse the mass on the ring of the platinum wire. At the apex of the blue flame *fluoboric acid* gas is liberated, which communicates to the outer flame a pure green color.

#### SILICIC ACID ( $\text{SiO}_2$ ).

*General Characters:* Of this acid there are two isomeric modifications; one is insoluble in water, and resists the action of all acids but *hydrofluoric*. It is a white, tasteless powder, gritty between the teeth, and infusible at the strongest heat of a furnace, but fusing before the blowpipe flame urged with oxygen, into a limpid, colorless liquid. This form of silicic acid exists nearly in a state of purity in *rock crystal* and in *white quartz*. By fusion with a mixture of carbonate of potassa, or a mixture of carbonate of potassa and carbonate of soda, all silicious minerals are decomposed, basic alkaline silicates being formed, which are soluble in water, and from which acids separate silicic acid in its soluble modification; but, by drying, it again returns to the insoluble state. The soluble variety of silicic acid is obtained in the form of a gelatinous mass, by passing the gas obtained by heating together a mixture of powdered fluor spar and quartz, with sulphuric acid, into water. In this state water dissolves a small quantity, without, however, acquiring any taste, or the property of reddening litmus paper. By evaporation, the acid is obtained as a white, earthy, but not crystalline mass, which may again be dissolved in water; but, if a strong mineral acid be added to the water during its evaporation, the dry silicic acid is no longer soluble in water. Gelatinous silicic acid is soluble, to a considerable extent, in acids. No precipitation is therefore observed on adding hydrochloric acid to a dilute solution of an alkaline silicate, until the liquid has been concentrated by evaporation. In most silicious minerals, silicic acid exists in its insoluble form. There are, however, a number of native, hydrated silicates, denominated *zeolites*, which contain silicic acid in its soluble form, and which are, therefore, decomposed by concentrated hydrochloric acid even in the cold, forming a gelatinous mass soluble in water. There are other minerals which are only dissolved



in hydrochloric acid by prolonged digestion, the silicic acid separating as a flaky powder, and not as a jelly. At ordinary temperatures, silicic acid is the weakest of the acids, dissolving in a boiling solution of the fixed alkaline carbonates, without expelling their carbonic acid, but at high temperatures it is capable of expelling all the volatile acids, not even excepting the sulphuric acid, from their combinations.

Diluted solutions of alkaline silicates, when nearly neutralized by nitric acid, are precipitated by most heavy oxides, and by the salts of the alkaline earths, and by ammonia. The first step, therefore, in analyzing a mineral containing silicic acid, is to convert the silicic acid from its soluble to its insoluble condition, which is done by evaporating the hydrochloric solution to perfect dryness, and then dissolving out with acid the basic metallic oxides.

*Before the blowpipe*, silicic acid is recognized by means of microcosmic salt and soda; the examination is generally performed on a platinum wire. The microcosmic salt is first fused into a bead, the silicate added, and the whole treated in the oxidating flame; the glass bead, while hot, is clear, and the separated silicic acid floats through it in a collected state; the bases combine with the free acid in the flux. Silicic acid with soda, on charcoal, gives a clear bead, carbonic acid escaping with effervescence; even when a small quantity of an earth is present, it still fuses to a clear glass. This is the case with *felspar*: but if the silicate contain a large proportion of a non-alkaline base, the compound becomes infusible.

#### HYDROFLUORIC ACID (HF).

This acid is very volatile and corrosive, giving off dense fumes in the air; it is distinguished from all other acids by its property of dissolving the insoluble form of silicic acid; it cannot, therefore, be preserved in glass vessels. It combines with water with the same energy as sulphuric acid. It decomposes metallic oxides, giving rise to water and *metallic fluorides*. Towards metals it behaves in general in the same manner as the oxyacids, and it dissolves copper and silver gradually with the disengagement of hydrogen; in its concentrated state it acts on many substances with great energy, dissolving some bodies which are not acted on even by boiling aqua regia, such as *silicic, titanic, molybdic, and tungstic*.

*acids.* The concentrated acid acts with extreme violence on the skin, causing painful ulcers very difficult to heal. The alkaline fluorides are soluble in water, as are also the fluorides of *aluminum, tin, iron, and mercury.* The fluorides of the metals of the alkaline earths are almost insoluble, as are also the fluorides of *copper, lead, and zinc,* though they dissolve more or less readily in hydrofluoric acid. The greater number of the fluorides bear ignition without being decomposed; the insoluble fluorides are decomposed by fusion with alkaline carbonates.

*Behavior of Solutions of Fluorides with Reagents.*


*Chloride of barium* produces a white precipitate soluble in hydrochloric acid.

*Chloride of calcium* produces a gelatinous and very transparent precipitate, almost insoluble in free acids, even in hydrofluoric acid: and in alkalies, in the cold, the addition of ammonia causes the complete subsidence of the precipitate ( $\text{CaFl}$ ).


*Acetate of lead* occasions a white precipitate soluble in hydrochloric acid.

*Sulphuric acid* at the boiling temperature decomposes all fluorides with disengagement of hydrofluoric acid. The experiment is made by tracing lines on a plate of glass covered with bees' wax, with a wooden point, so as to expose the glass; and laying the plate on a platinum crucible containing the pulverized fluoride and concentrated sulphuric acid, a moderate heat, insufficient to melt the wax, is applied to the crucible for about a quarter of an hour. The exposed lines are found etched, on the removal of the wax, which is effected by spirits of turpentine.

When a fluoride is mixed with a substance containing silicic acid, such as pounded glass, and heated together with concentrated sulphuric acid, fluosilicic acid is formed thus:



This acid is disengaged as a gas which fumes strongly in a moist atmosphere, and when brought into contact with water is decomposed, with the separation of silicic acid in its gelatinous form, and the formation of *hydrofluosilicic acid*, thus:



One equivalent of every three equivalents of the fluosilicic acid (or fluoride of silicon) combines with three equivalents of

water, giving rise to one equivalent of silicic acid, which is precipitated, and three equivalents of hydrofluoric acid, which combines with the two remaining equivalents of fluosilicic acid to form hydrofluosilicic acid. This interesting reaction is observed by heating the materials in a test tube, and conveying the gas, by a bent tube, into another test tube containing water.

By cautiously fusing in a test tube equal parts of a finely pulverized fluoride, and bisulphate of potassa, hydrofluoric acid is rendered evident by the roughening and loss of transparency of the upper part of the tube.

#### CHROMIC ACID ( $\text{CrO}_3$ ).

This acid is obtained by the decomposition of bichromate of potassa by sulphuric acid, in the form of brilliant crimson needles, which absorb moisture from the air, and pass into a deep brown viscous fluid; evaporated to dryness it is, while hot, black, but on cooling it becomes deep red; it has no smell; its taste is strongly acid, but not metallic; it tinges the skin yellow. It is soluble in alcohol; but the solution decomposes by the action of heat and light, an ether being formed, and hydrated oxide of chromium precipitated. When alcohol is dropped on the concentrated acid, it takes fire, and the acid becomes incandescent; an aqueous solution of chromic acid is gradually decomposed by the light of the sun, oxygen gas being liberated. All its salts are colored yellow or red; the alkaline chromates and bichromates are soluble in water; most of the other salts of chromic acid are insoluble in water, though they are all soluble in nitric acid.

#### *Behavior of Solutions of Chromates with Reagents.*

*Chloride of barium* produces a pale yellow precipitate soluble in nitric and hydrochloric acids.

*Acetate of lead* produces a yellow precipitate soluble in potassa, and sparingly soluble in nitric acid.

*Nitrate of silver* produces a dark purple precipitate, soluble in nitric acid and in ammonia.

*Subnitrate of mercury* produces a brick-red precipitate.

*Sulphuretted hydrogen* in neutral solutions reduces the chromic acid with the precipitation of sulphur and oxide of chromium; *sulphuric acid* and *water* are, at the same time,

formed, and the fluid becomes green; in the presence of a free acid the oxide of chromium is dissolved, at least in part, and sulphur precipitated.

*Sulphurous acid* likewise reduces chromic acid, *sulphuric* and *hyposulphuric* acids being formed.

*Oxalic*, *tartaric*, and *citric acids* reduce the acid to sesquioxide of chromium, carbonic acid being evolved.

*Hydrochloric acid* and *alcohol*, or *zinc*, on being boiled with solution of a chromate, reduce the acid, the fluid becoming green.

Insoluble chromates are decomposed by fusion with alkaline carbonates, alkaline chromates being formed.

## II.—*Acids precipitated from their Neutral Solutions by Nitrate of Silver.*

### HYDROCHLORIC ACID (HCl).

This acid is a transparent colorless gas, fuming strongly in a moist atmosphere: it has a pungent suffocating smell, and a strongly acid taste. At a low temperature, and under a pressure of about eighteen atmospheres, it becomes liquid: it is decomposed by those metals which decompose water, and by substances which combine with chlorine: it is also decomposed by metallic oxides. It is absorbed with the greatest avidity by water, the saturated solution forming what is called concentrated hydrochloric acid. This solution is colorless and strongly acid; the yellow tinge which the acid frequently has arises from impurities. The greater number of the chlorides are soluble in water; the principal exceptions are those of *lead* and *silver*, and *protochloride of mercury*: some chlorides volatilize without decomposition, as the chlorides of *tin*, *antimony*, and *arsenic*: some are fixed, and others undergo decomposition by heat.

### *Behavior of Solutions of Chlorides with Reagents.*


*Nitrate of silver* produces a white curdy precipitate even in highly dilute solutions, becoming violet-colored, and finally black, when exposed to the light: it is quite insoluble in nitric acid, but readily soluble in ammonia: it fuses without decomposition, forming, when cold, a tough horny mass, and is reduced by hydrogen, and by fusion with carbonate of soda, or with resin.




*Nitrate of suboxide of mercury* produces a white precipitate (calomel  $\text{Hg}_2\text{Cl}$ ), becoming black when brought into contact with caustic alkalis.

*Acetate of lead* produces a white precipitate soluble in boiling water, less so in *nitric* and *hydrochloric* acids, and not altered by ammonia.

By heating a soluble chloride with peroxide of manganese and sulphuric acid, chlorine gas is evolved thus:—



On heating a chloride with *chromate of potassa* and sulphuric acid, a brownish red gas is disengaged, which condenses into a blood red liquid, *chromate of chloride of chromium* ( $\text{CrCl}_3$ ,  $2 \text{CrO}_3$ ), thus:—



On the addition of ammonia a yellow liquid (chromate of ammonia) is formed, which becomes red on the addition of an acid, bichromate of ammonia being formed.

*Before the blowpipe* chlorides are thus detected: Dissolve oxide of copper in microcosmic salt on platinum wire, until a diaphanous bead is obtained in the oxidizing flame: the substance under examination is now added and heated; if chlorine be present, the assay will be surrounded by a beautiful blue-colored flame inclining to purple, which after some time disappears, but can be reproduced by adding a fresh supply of the sample.

For the detection of chlorine in a compound soluble in water, the following method is also given by *Berzelius*:—A small quantity of sulphate of copper or iron is dissolved; a few drops of the solution placed upon a bright piece of silver, and the chlorine compound added, the silver will be blackened.

#### HYDROBROMIC ACID ( $\text{HBr}$ ).

*General Characters*: It very much resembles hydrochloric acid gas; like it, it fumes strongly when allowed to escape into a moist atmosphere, and it acts in a similar manner with metals and metallic oxides: it dissolves freely in water, and the concentrated solution, which is denser than that of hydrochloric acid gas, is fuming: chlorine expels from it bromine, hydrochloric acid being formed. The aqueous solution dissolves a large quantity of bromine, and acquires a deep, red

color: there is also a strong analogy between the bromides and chlorides.

*Behavior of Solutions of Bromides with Reagents.*


*Nitrate of silver* produces a yellowish white precipitate, insoluble in nitric acid and soluble with difficulty in ammonia.

*Nitrate of suboxide of mercury* produces a yellowish white precipitate.


*Acetate of lead* produces a white precipitate insoluble in water, by which it is distinguished from *chloride of lead*.

*Nitric acid*, when heated with solution of a bromide, decomposes it, evolving bromine, which colors the solution yellowish red; when heated with a solid bromide, yellowish red vapors are produced, having an odor resembling that of chlorine; these vapors condense into red drops in the upper part of the test tube.

*Concentrated sulphuric acid* also decomposes bromides, with the separation of *bromine* and *sulphurous acid*, thus:—



*Dilute sulphuric acid* decomposes bromides with the disengagement of hydrobromic acid, thus:—



If a stream of chlorine be passed through a solution of a bromide, and the solution agitated with *ether*, the latter will dissolve all the evolved bromine, and assume a yellow color: if the ethereal solution be removed with a pipette, and agitated with solution of potassa, the yellow tint will vanish, the bromine having passed into *bromide of potassium* and *bromate of potassa*, thus:—



If this solution be evaporated to dryness, and ignited, the bromate is decomposed with evolution of oxygen, and bromide of potassium remains: in order to detect bromine in this residue, it is heated in a small retort, with peroxide of manganese and sulphuric acid, and the vapors received in a small receiver containing *starch paste*, which becomes tinged orange-yellow, the color vanishing by exposure to the air.

On heating a bromide with *chromate of potassa* and *sulphuric acid*, a brownish red gas is produced, as in the case of a chloride: this gas, however, is *bromine*, and the color vanishes on the addition of ammonia; this reaction serves, there-

fore, to distinguish between bromides and chlorides, and for detecting the presence of the latter in the former.

#### HYDRIODIC ACID (IH).

This acid gas, likewise, resembles in its properties hydrochloric acid: it is absorbed rapidly, and in large quantities, by water, the solution being colorless and fuming: there is also a strong analogy between the compounds of *iodine* and those of *bromine* and *chlorine*.

#### *Behavior of Solution of Iodides\* with Reagents.*

*Nitrate of Silver* produces a yellowish white precipitate, which blackens by exposure to the light, is insoluble in dilute nitric acid, and very sparingly soluble in ammonia.

\* Dr. Cantu detects the presence of iodine and bromine in mineral waters by the following method: "The water under examination is evaporated in a porcelain capsule to about half its bulk; carbonate of potash, of absolute purity, is then added (I say absolute purity, as the ordinary carbonate of potash contains sensible traces of iodine and bromine\*) in slight excess, and boiled for some time in order to decompose the earthy salts contained in it; the liquid is allowed to become cool, and is then filtered; it is now evaporated to dryness, taking care, however, not to heat the saline matter too highly in the desiccation; the residue, if in small quantity, is powdered in the same capsule, and is treated with alcohol of 40°, in order to separate the salts soluble in this menstruum, among which will be found the bromides and iodides if they existed in the water. The liquid is evaporated to dryness at a gentle heat; and if it contain organic matter, as is generally the case, this is destroyed by ignition at a low red heat; a few drops of dilute acetic acid are next added in such proportion as to be in slight excess, taking care that the small quantity of carbonate of potash taken up by the alcohol is dissolved and neutralized. It is now again evaporated to dryness, to expel the excess of carbonic acid, avoiding a degree of heat that would decompose the acetate of potash, as this would communicate a brown tinge to the liquid and obscure the action of the test. At this point the residuary matter is dissolved in the smallest possible quantity of pure water, with two or three drops of a weak solution of starch recently prepared. This being done, a small quantity of the test-liquor (consisting of a mixture of 10 parts of sulphuric acid of 66° with 1 part of nitric acid of 25°) is placed in a glass with a narrow base; then the solution of the saline residue is poured very gently down the side of the glass

\* To obtain carbonate of potash free from chlorides, bromides and iodides, it is necessary to proceed in the following manner:—Bitartrate of potash, colorless and crystallized, is calcined to whiteness, the residue treated with distilled water, and the solution evaporated to the consistence of syrup; alcohol of 40° (Beaume?) is then added, agitating thoroughly the mixture, and allowing it to react for some time, the alcoholic liquor being afterwards decanted; the saline residue is brought on a filter, and washed with alcohol until a portion of the latter, being evaporated to dryness and examined with the proper tests, no longer gives any indication of the presence of iodides, bromides or chlorides.

*Nitrate of suboxide of mercury* produces a yellowish green precipitate.

*Chloride of mercury* produces a beautiful scarlet precipitate.

*Acetate of lead* produces an orange yellow precipitate, soluble in hot water, and in nitric acid, and crystalizing out of its solution in brilliant golden-colored scales.

*Protochloride of palladium* produces a black precipitate in solutions of alkaline iodides: no precipitate is afforded by this reagent in solutions of bromides.

An aqueous solution of one part of crystalized sulphate of copper, and two and a half of protosulphate of iron, produces a dingy white precipitate ( $\text{Cu}_2\text{I}$ ): this mixture has no effect in solutions of *chlorides* and *bromides*.

*Chlorine, nitric acid, concentrated sulphuric acid* and *peroxide of manganese* eliminate iodine from solutions of iodides, the solutions becoming colored; and, if the solution is concentrated, *iodine* separates as a black precipitate: on applying heat, the characteristic violet vapors of iodine make their appearance: with excess of chlorine, a colorless *chloride* of iodine is formed.

With *starch paste* free iodine forms a blue compound, and this reagent serves to detect minute traces of iodine in insoluble as well as in soluble compounds of that element. The substance under examination is mixed in a retort with concentrated *nitric acid*, and a strip of *white cotton cloth*, moistened with solution of starch, suspended from the stopper; in a few hours the cloth will become colored blue if the most minute trace of iodine be present: nitric acid is better as an oxidizing agent than chlorine, because of the formation of the colorless *chloride of iodine*, above referred to. The blue color of the iodide of starch disappears by heat, and by the action of certain deoxidizing agents.

If a solid iodide be heated with concentrated sulphuric acid and peroxide of manganese, violet vapors of iodine will make their appearance.

*Before the blowpipe*, metallic iodides, when treated with

so as to rest on the test-liquor without mixing with it. By operating in this manner, if iodides or bromides existed in the water, and the coexistence of these substances is almost constant, there will quickly appear two zones in the saline solution, one of a clear topaz-yellow, sometimes inclining to green, and the other of a blue color, floating on it."



cupriferous microcosmic salt, impart a beautiful and deep green color to the flame.

#### BROMIC ACID ( $\text{HO,BrO}_3$ ).

When concentrated, it is very sour but not caustic: it has very little odor: it first reddens, and then discolors blue litmus paper; *sulphurous phosphorous* acids, and all the hydracids decompose it, liberating bromine: most of the bromates are soluble in water, and are converted by ignition into bromides, with evolution of oxygen: they are decomposed with violent deflagration when heated with combustible substances, such as *carbon, sulphur, and phosphorus*. These mixtures likewise detonate violently when moistened with a drop of concentrated sulphuric acid. Bromates, when treated with concentrated sulphuric and other oxygen acids in the cold, evolve oxygen and red vapors of bromine; they are likewise reduced by sulphuretted hydrogen with separation of sulphur.

#### *Behavior of Solutions of Bromates with Reagents.*

*Nitrate of suboxide of mercury* produces a light yellow precipitate, soluble in nitric acid.

*Acetate of lead* produces a white precipitate, soluble in much water.

*Nitrate of silver* produces a white precipitate, soluble in ammonia, but soluble with difficulty in dilute nitric acid.

*Sulphuretted hydrogen* reduces bromates to bromides; *sulphuric acid* being formed and sulphur separated.

*Sulphurous acid* reduces bromates to bromides, sulphuric acid being formed.

#### IODIC ACID ( $\text{HO,IO}_3$ ).

The aqueous solution of this acid is, when concentrated, very sour: it first reddens, and then destroys the color of litmus paper: it oxidizes all metals but *gold* and *platina*, and detonates violently when heated with combustible substances: with sulphuric, nitric, and phosphoric acid, it forms crystalline compounds, and when mixed with vegetable acids a decomposition of both takes place; *carbonic acid* being liberated, and *iodine* precipitated. The iodates are mostly insoluble in water; the neutral alkaline iodates are soluble.

*Behavior of Solutions of Iodates with Reagents.*


*Nitrate of silver* produces a white precipitate, soluble in ammonia and difficultly in nitric acid.

*Chloride of barium, chloride of calcium, and acetate of lead,* give white precipitates, soluble in nitric acid. Iodates, when heated alone, are decomposed into iodides and oxygen; they deflagrate when heated with combustibles: they are decomposed by *protochloride of tin, sulphurous acid, binoxide of tin, sulphuric acid,* and *iodine* being separated; the latter may be made evident by adding starch paste.

*Sulphuretted hydrogen* reduces iodates to iodides, *sulphuric acid* and *water* being formed, and *iodine* separated.

## HYDROCYANIC ACID (HCy).

In its pure, anhydrous state, this acid possesses the following properties: it is colorless, inflammable, very volatile, and possessing a strong odor analogous to that of bitter almonds: its taste is at first cool, then burning and disagreeable. Its specific gravity is 0.6957 at 66°, it boils at 80°, it volatilizes rapidly in the air, producing a degree of cold sufficient (if it be not perfectly anhydrous) to cause it to assume a solid form: it is feebly acid to test paper: it is the most energetic poison known, one drop being sufficient to destroy an animal of considerable size. It is rapidly decomposed, even in close vessels, becoming darker and darker in color, and eventually quite black: a trace of sulphuric acid prevents this decomposition from taking place; strong acids cause its elements so to arrange themselves with the elements of water as to produce *formic acid* and *ammonia*; thus




by distillation the formic acid may be separated, the ammonia remaining in combination with the acid which occasioned the decomposition.

The alkalis are reduced by hydrocyanic acid, their metallic radicals combining with cyanogen, and water being formed, thus:—



the metallic cyanides thus formed have an alkaline reaction;

they are decomposed gradually when dissolved in water, rapidly when boiled, and instantly in contact with an acid, the result of the decomposition being *formiate* of the oxide of the metallic base and ammonia. *Cyanide of potassium* and *cyanide of sodium* may, however, be heated to redness out of contact of air, without suffering decomposition; but in contact with oxides of *tin*, *lead*, *copper*, and many other metals, they are converted into cyanates, the metals being reduced thus:—



The greater number of the metallic cyanides are insoluble in water: they comport themselves differently under the influence of heat, some being resolved into the metal and cyanogen, as is the case with *cyanide of mercury*, and others into carburets and nitrogen: the compounds of cyanogen with gold, silver, and other heavy metals, are not decomposed by dilute, and with difficulty with concentrated nitric acid; hydrochloric acid and sulphuretted hydrogen, however, decompose them easily and completely. The cyanides of *iron*, *cobalt*, *manganese*, and *chromium*, when brought into contact with alkaline cyanides, unite with their cyanogen, forming peculiar salt radicals, in which the presence of the heavy metal cannot be detected by the usual tests.

#### *Behavior of Solutions of Cyanides with Reagents.*

*Nitrate of silver* produces a white curdy precipitate ( $\text{AgCy}$ ) insoluble in dilute nitric acid, and sparingly soluble in ammonia, easily soluble in cyanide of potassium, and leaving pure silver when ignited; when moistened with hydrochloric acid, hydrocyanic acid is disengaged.

*Acetate of lead* produces a white precipitate ( $\text{PbCy}$ ).

*Subnitrate of mercury* produces, in hydrocyanic acid, a gray precipitate of metallic mercury, cyanide of mercury remaining in solution, thus:—



*Oxide of mercury* dissolves freely in hydrocyanic acid, and alkalies occasion no precipitate in the solution; in no other alkaline fluid can oxide of mercury be held in solution; this reaction serves therefore as a test of the presence of hydrocyanic acid. In the presence of hydrochloric acid, *ammonia* produces a precipitate.

A solution of *protosulphate of iron*, which has been partially oxidized by exposure to the air (magnetic oxide of iron),


occasions the formation of *Prussian blue* in solution of an alkaline hydrocyanate containing free hydrochloric acid; this reaction forms an excellent test for hydrocyanic acid, but it is essential that an alkali should be present, as also hydrochloric acid, to dissolve any oxide and sesquioxide of iron that may have been precipitated by the alkali together with the blue compound.

*Protosulphate of iron* produces, in solutions of alkaline *ferrocyanides*, a pale blue precipitate.


*Sulphate of copper* produces a chocolate brown precipitate.

*Sesquichloride of iron* produces, in solutions of alkaline *ferricyanides*, a deep blue precipitate.

Insoluble *ferro-* and *ferricyanides* are decomposed by fusion with alkaline carbonates, soluble alkaline *ferro-* and *ferricyanides* being formed. By distilling a ferrocyanide with dilute sulphuric acid, hydrocyanic acid is produced, and by heating it with a great excess of concentrated sulphuric acid, carbonic oxide is formed by the following reaction:—



One equivalent of ferrocyanide of potassium and nine equivalents of water from the oil of vitriol and the water of crystallization of the ferrocyanide, give rise to six equivalents of carbonic oxide, two equivalents of potassa, one of protoxide of iron, and three of ammonia; the sulphuric acid, iron, potassa, and ammonia arrange themselves into a crystalline anhydrous iron alum, having the following composition (Fownes):—



The most delicate and valuable test of the presence of hydrocyanic acid that has hitherto been proposed, is that of *Professor Liebig*, and is dependent on the fact that the higher sulphurets of ammonium are instantly deprived, by cyanide of ammonium, of the excess of sulphur they contain above the *monosulphuret sulphocyanide of ammonium* ( $\text{NH}_4\text{CyS}_2$ ) being formed, which produces, with persalts of iron, a very deep blood-red color. Mr. Alfred Taylor recommends the following method of applying this test:—Place the diluted hydrocyanic acid in a watch-glass, and invert over it another watch-glass, holding in its centre one drop of hydrosulphuret of ammonia containing sulphur in excess; there is no apparent change in the hydrosulphuret, but if the watch-glass be removed after the lapse of from half a minute to ten minutes,



according to the quantity of hydrocyanic acid present, sulphocyanide of ammonium will be obtained on gently heating the drop of hydrosulphuret and evaporating it to dryness. The addition of a drop of a solution of a persalt of iron to the dried residue brings out the blood-red color instantly, which is intense in proportion to the quantity of sulphocyanide present; the warmth of the hand may be employed to expedite the evolution of the vapor. This test is even more delicate and expeditious than the nitrate of silver test, in which the vapors are received in a solution of that salt, and will, according to Taylor, detect in five minutes hydrocyanic acid not exceeding  $\frac{1}{4\frac{1}{3}}$  of a grain in ten drops of a liquid.

#### HYDROSULPHURIC ACID OR SULPHURETTED HYDROGEN (HS).

This acid is a colorless gas, which under a strong pressure becomes liquid; it has a highly offensive odor resembling that of putrid eggs; its taste is acid, astringent, and bitter; it is inflammable, burning with a blue flame, and disengaging sulphurous acid; it explodes violently when mixed with oxygen or atmospheric air and ignited; when mixed with chlorine, sulphur is deposited and hydrochloric acid formed; it is highly deleterious when inspired, even when mixed with a large quantity of air; it is absorbed by water, which acquires its peculiar smell and a nauseous sweet taste; the solution reddens litmus paper, and decomposes by exposure to the air, sulphur being deposited; most metallic oxides are decomposed by sulphuretted hydrogen, *sulphuret of the metals* and *water* being formed. The *alkalies* and *alkaline earths*, and the oxides of *chromium*, *tantalum*, and *titanium*, do not exchange their oxygen for sulphur in the moist way. The sulphurets of the metals of the alkalies, and the alkaline earths, are soluble in water; they are decomposed by dilute mineral acids with the evolution of sulphuretted hydrogen, which is readily recognized by its odor and by its action on paper moistened with solution of lead. The sulphurets of the metals of the fourth group are insoluble in water, but are likewise decomposed by dilute mineral acids; all the other metallic sulphurets but *sulphuret of mercury* are decomposed by strong nitric acid, sulphuric acid being formed and sulphur generally separated; aqua regia effects their decomposition more easily, it also dissolves sulphuret of mercury. As some metallic oxides,

when dissolved in acids, are precipitated by sulphuretted hydrogen, while others are not, and as the precipitated sulphurets differ in color and in other properties, sulphuretted hydrogen becomes a valuable reagent for detecting and separating metallic compounds. Most metallic sulphurets are decomposed by heat with access of air, evolving sulphurous acid; the alkaline sulphurets thus treated are converted into sulphates.

When sulphuretted hydrogen, or a solution of an alkaline or earthy sulphuret, is brought into contact with *nitrate of silver* or *acetate of lead*, black precipitates are formed; either of these salts is, therefore, a certain test of the presence of this acid in the gaseous state; a strip of paper moistened with solution of subacetate of lead is generally employed.

### III.—Acids not precipitated by either *Chloride of Barium* or *Nitrate of Silver*.

#### NITRIC ACID ( $\text{NO}_3$ ).

*General Characters:* This acid, which has never been obtained in an anhydrous state, forms with water, when pure, a colorless solution, which when concentrated fumes in the air; it is very easily decomposed, mere exposure to the light of the sun causing it to become yellow and disengage oxygen gas; it is one of the strongest of the acids, and constitutes a reagent of the greatest value, from the facility with which it parts with a portion of its oxygen. The yellow fuming acid, containing nitrous acid, possesses generally the greatest oxidating power; the most highly concentrated acid is in many cases without action on bodies on which a diluted acid acts with violence; thus the concentrated nitric acid does not attack *lead* or *tin*, while the addition of a small quantity of water causes an energetic action to take place. Organic substances are for the most part resolved by the concentrated acid into carbonic acid and water, the action in many cases being sufficiently energetic to cause them to take fire; the diluted acid generally converts them into oxalic, malic, and carbonic acids. Nearly all metallic oxides are dissolved by nitric acid, the exceptions are oxides of *tin* and *antimony*, *tellurous* and *tungstic acids*. All the neutral salts of nitric acid are soluble in water, and all are decomposed at a strong red heat, the nature of the products depending on the nature of the base; thus the alkaline nitrates yield oxygen and nitrogen, while

other metallic nitrates give oxygen and an inferior oxide of nitrogen. When nitrates are ignited in the presence of other substances susceptible of oxidation, they take the liberated oxygen, and in some cases the combination is attended by deflagration; thus a nitrate thrown on red-hot charcoal causes the latter to throw off brilliant scintillations, a mixture of a nitrate with cyanide of potassium deflagrates vividly when heated on a platinum plate, and phosphorus and sulphur brought into contact with a heated nitrate occasion a violent detonation.


*Methods of Detecting Nitric Acid in Solutions of the Nitrates.*

*Hydrochloric acid*, added in excess to solution of a nitrate, gives it the property of dissolving gold leaf, in consequence of the following reaction:—



One equivalent of nitrate of potassa, and two of hydrochloric acid, give rise to one equivalent of hyponitric acid, one of chloride of potassium, two of water, and free chlorine: the solubility of gold leaf\* in a liquid which has been heated with hydrochloric acid, is a certain proof, therefore, of the presence of nitric acid.

When a solution containing a nitrate is mixed with half its volume of concentrated sulphuric acid, allowed to cool, and a crystal of *protosulphate of iron* added, the liquid round the crystal assumes a reddish brown color in consequence of the following reaction:—



Ten equivalents of protosulphate of iron, four equivalents of sulphuric acid, and one of nitre, give rise to three equivalents of persulphate of iron, one of sulphate of potassa, and four of protosulphate of iron in a peculiar state of combination with nitric oxide: as the latter is very unstable, and is decomposed by heat, nitric oxide being set free, it is necessary that the liquid should be allowed to cool before making the experiment.

When a nitrate is heated in a test tube, with copper filings and concentrated sulphuric acid, nitric oxide gas is set free,

\* Chlorates, perchlorates, chromates, bromates, &c., mixed with HCl acid also dissolve gold leaf.

which, combining with the oxygen of the air in the tube, forms ruddy fumes of nitrous acid.

When a solution of a nitrate is mixed with sulphuric acid, and a sufficient quantity of a solution of indigo in sulphuric acid added, to give it a blue color, and the mixture heated, the color is either discharged or turned yellow in consequence of the oxidation of the indigo at the expense of the nitric acid set free from the nitrate. This test is not, however, decisive, as other substances, especially free chlorine, cause the same discoloration.

The following test was proposed by *Runge*. Metallic zinc is dissolved in mercury in such a proportion that the fluidity of the mercury is only slightly diminished. A portion of this amalgam is placed in a little porcelain capsule, and barely covered with a neutral solution of protochloride of iron: a small piece of the nitrate is then laid upon the mercury in the solution, and after some time a black stain is produced upon the mercury, just at the spot where the nitrate had been placed.\*

#### NITROUS ACID ( $\text{NO}_3$ ).

The properties of this acid in a state of purity are not well known. It is a very volatile liquid, which, at a low temperature, is colorless, but at ordinary temperatures it is a gas of a dark yellowish red color; when brought into contact with water, it is decomposed, being resolved into nitric acid and nitric oxide, thus:—



Almost all its salts are soluble in water: they very much resemble the nitrates in their properties, from which they may thus be distinguished:—

When submitted to gentle distillation, *nitrites* expel nitric oxide gas, (the salt in solution being converted into a nitrate,) and by boiling they are rapidly converted into solutions of nitrates.

When heated with concentrated sulphuric acid, they evolve nitric oxide gas, nitric acid remaining in solution; nitrites

\* Berthémot proposes to detect nitric acid even to the  $\frac{1}{100000}$  by adding a few drops of the suspected liquor to a drachm or so of pure sulphuric acid and stirring the mixture with a glass rod moistened at the end with a little *brucine*. If any nitric acid is present the liquid becomes red and afterwards yellow.



reduce *chloride of gold* and *nitrate of mercury* to the metallic state.

When treated with hydrochloric acid, solutions of *nitrites* do not acquire the property of dissolving gold leaf.

#### CHLORIC ACID ( $\text{HO}, \text{ClO}_3$ ).

When concentrated, it is a yellowish oily-looking liquid, very sour, reddening, and finally bleaching, litmus paper; it is very unstable, being resolved by heat into *perchloric acid*, *oxygen*, and *chlorine*: it converts sulphurous into sulphuric acid, and is at the same time itself reduced to chlorine: it also converts sulphuretted hydrogen into sulphuric acid, sulphur, and water: and all its compounds, with bases, are soluble in water: they do not possess bleaching properties, but when mixed with sulphuric acid they are decomposed; perchloric acid, chlorine, hypochloric acid and oxygen being formed, the solution becoming yellow, and it then possesses the power of destroying the color of blue vegetable infusions, and by the application of heat decolorizes solution of indigo. The alkaline *chlorates*, when ignited, disengage oxygen, and become converted into *chlorides*: most other chlorates are resolved by heat into metallic oxides, and a mixture of oxygen and chlorine. When triturated with sulphur or phosphorus, chlorates detonate with dangerous violence: a mixture of a chlorate with sugar bursts into a flame on being touched with a drop of concentrated sulphuric acid.

The compounds of *perchloric acid* ( $\text{HO}, \text{ClO}_7$ ), with bases, are distinguished from chlorates by their greater stability, not being decomposed by acids or reducing agents; their solutions do not therefore become yellow on being mixed with sulphuric acid. The *perchlorate of potassa* is remarkable for its difficult solubility in water.

The compounds of *hypochloric acid* ( $\text{ClO}_4$ ) with bases have bleaching properties, and are decomposed on the addition of an acid with the evolution of chlorine only; they are powerful oxidizing agents, and are decomposed by heat or even by exposure to light: they decompose *manganese* and *lead salts*, precipitating from the former hydrated peroxide of manganese, and from the latter, first chloride, and then brown peroxide of lead.

## ORGANIC ACIDS.

I.—Acids precipitated by *Chloride of Calcium*;—*Oxalic, Tartaric, Paratartaric, Citric, and Malic Acids.*

OXALIC ACID ( $\text{HO}, \text{C}_2\text{O}_3$ , or  $\bar{\text{O}}$ ).

*General Characters:* It crystalizes in four-sided prisms, which are colorless, very soluble in water, very acid, and eminently poisonous. These crystals contain three equivalents of water of crystalization, which when sharply heated they lose, the dry acid subliming: at a high temperature oxalic acid is decomposed into *water, carbonic, and formic acids*, without blackening, by which it is distinguished from most other organic acids. The alkaline oxalates are soluble in water, as are also some other oxalates with a metallic base: they are all decomposed at a red heat; alkaline and earthy oxalates being thereby converted into carbonates.

*Behavior of Solutions of Oxalic Acid and Oxalates with Reagents.*

*Chloride of calcium*, and all soluble lime salts, produce a white precipitate even in highly dilute solutions ( $\text{CaO}, \bar{\text{O}} + 2 \text{ aq.}$ ), insoluble in water as well as in oxalic and acetic acids, but readily soluble in hydrochloric and in nitric acids; the presence of ammonia promotes the precipitation of oxalic acid by salts of lime.

*Chloride of barium* produces a white precipitate ( $\text{BaO}, \bar{\text{O}} + \text{aq.}$ ) almost insoluble in water, but soluble in nitric and in hydrochloric acids.


*Nitrate of silver* gives a white precipitate, soluble in nitric acid and in ammonia.

*Acetate of lead* produces a white precipitate.

When heated with concentrated sulphuric acid, oxalic acid and dry oxalates are decomposed, and the oxalic acid resolved into carbonic acid and carbonic oxide gases, which escape with effervescence. The latter gas may, if present in sufficient quantity, be kindled; it burns with a full flame: if the mixture becomes black, it is a proof that it contains some other organic substance.

TARTARIC ACID ( $C_8H_4O_{10} + 2HO$ ; or  $\bar{T}$ ).

This acid crystallizes in large rhombic prisms, which are soluble in water and have a pleasant acid taste; the solution decomposes by keeping, becoming covered with a mouldiness; when heated, the crystallized acid loses water, and gives rise to the formation of a series of new compounds; and when treated at a high temperature with a strong solution of *hydrate of potassa*, it is converted into *acetate* and *oxalate* of potassa, thus:—



The alkaline tartrates are soluble in water; all the salts of tartaric acid that are insoluble in water are easily soluble in hydrochloric acid.

*Behavior of Tartaric Acid and Solutions of Tartrates with Reagents.*

*Chloride of calcium* produces a white precipitate almost insoluble in water, but soluble in ammoniacal salts, the presence of which, therefore, prevents its formation; it is soluble also in cold potassa, but excess must be avoided, or hydrate of lime will be precipitated; if the potassa solution be boiled, *tartrate of lime* separates as a gelatinous mass, which redissolves as the solution cools.

*Lime water* produces in solutions of neutral tartrates a white precipitate dissolving in tartaric acid, and also in ammoniacal salts.

*Chloride of barium* produces a white precipitate soluble in dilute acids.

*Acetate of lead* occasions a white precipitate of tartrate of lead, which when ignited out of access of air is decomposed, metallic lead in a fine state of division being formed, which burns when projected into the air.

*Nitrate of silver* produces a white precipitate of tartrate of silver, which by boiling is reduced to a shining mirror, adhering to the glass by agitation; the reduced metal separates in thin laminæ.

Where a salt of *potassa* (the acetate answers best) is added to free tartaric acid, and the mixture agitated, a sparingly soluble crystalline *bitartrate of potassa* separates; the addition

of alcohol further diminishes the solubility of this salt, which is freely dissolved in alkalies and in mineral acids.

*Tartaric acid* possesses the property of preventing the precipitation of several metallic oxides by alkalies, in consequence of the formation of soluble tartrates not decomposed by alkalies; among the metallic oxides which it thus affects are *alumina*, *peroxide of iron*, and *protoxide of manganese*.


*Tartrates*, when heated, carbonize, emitting a peculiar odor; the tartrates of the alkalies and alkaline earths are thus converted into carbonates.

PARATARTARIC ACID or RACEMIC ACID ( $C_4H_2O_5.HO$  or  $\bar{R}.HO$ ).

This acid is isomeric with tartaric acid, from which it is distinguished by the insolubility of its *lime salt* in excess of acid, in ammoniacal salts, in an excess of racemic and tartaric acids, and by the formation after a time of a precipitate with solution of *gypsum*.

CITRIC ACID ( $C_6H_8O_7.3HO$  or  $\bar{C}_i.3HO$ ).

This acid forms large transparent crystals, very soluble in water, and of a strong but pleasant acid taste; its solution, like that of tartaric acid, decomposes by keeping. The acid itself carbonizes when heated to redness, emitting a pungent acid vapor; when heated with sulphuric acid in excess, it is decomposed into *carbonic acid*, *carbonic oxide*, *acetic acid*, and water, thus:—



The alkaline citrates are soluble in water; the insoluble salts of citric, and in fact of all organic acids are decomposed by boiling with carbonate of soda, soluble alkaline salts being thus obtained.

#### *Behavior of Citric Acid and Solutions of Soluble Citrates with Reagents.*

*Chloride of calcium* produces in solutions of citrates, but not in citric acid, a white precipitate of neutral citrate of lime, insoluble in potassa, but readily soluble in sal-ammoniac, (and free acids,) from which, however, a basic citrate of lime ( $\bar{C}_i.3CaO + CaO + aq.$ ) is precipitated by boiling.

*Lime water* produces no precipitate in the cold; but, by



boiling, basic citrate of lime is deposited, which is redissolved as the solution cools: this reaction serves to distinguish *citric acid* from most other organic acids.

*Acetate of lead* produces a white precipitate, sparingly soluble in ammoniacal salts and in ammonia, but readily soluble in citrate of ammonia.

*Citric acid*, like *tartaric acid*, prevents the precipitation of certain metallic oxides by alkalies.

#### MALIC ACID ( $C_4H_4O_6 \cdot 2HO$ , or $\overline{M}_2HO$ ).

This acid, which occurs in several acid fruits, crystalizes with some difficulty, and deliquesces rapidly when exposed to the air: at the temperature of  $230^\circ$  it gradually decomposes into *fumaric acid*, ( $C_4H_2O_4 \cdot HO$ ), crystalizing in micaceous scales; at a higher temperature it is, in a great measure, converted into *maleic acid* ( $C_4H_2O_4 \cdot 2HO$ ), which rises as a crystalline sublimate, *fumaric acid* remaining in the retort. The salts which this acid forms with bases are mostly soluble in water.

#### *Behavior of Malic Acid and Solutions of Malates with Reagents.*

*Chloride of calcium* does not produce any precipitate till alcohol is added, when white *malate of lime* is deposited.

*Lime water* produces no precipitate either in hot or cold solutions of malates, by which this acid is distinguished from *tartaric*, *racemic*, *citric*, and *oxalic* acids.

*Acetate of lead* produces a white precipitate, which, by repose, crystalizes in needles, and which fuses under the boiling point of water. The best test of malic acid is, probably, its comportment under heat. The precipitate is insoluble in an excess of malic acid.

#### II.—Acids precipitated by *Sesquichloride of Iron*; *Succinic*, *Benzoic*, *Tannic*, and *Gallic* Acids.

##### SUCCINIC ACID ( $C_4H_4O_3 \cdot HO$ or $\overline{S}_1HO$ ).

This acid is crystalline and volatile; its vapor is exceedingly acrid and penetrating; by distillation with sulphuric acid, it yields a new acid, the nature of which has not yet

been exactly determined. The salts which it forms with bases are mostly soluble in water.

*Behavior of Succinic Acid and Solutions of Succinates with Reagents.*

*Sesquichloride of iron* produces a brownish red voluminous precipitate, soluble in acids, and decomposed by ammonia, hydrated sesquioxide of iron being formed.

*Acetate of lead* produces a white precipitate of succinate of lead, soluble in excess, and in *tartaric*, *nitric*, and *acetic acids*.

As the alkaline and earthy succinates are insoluble in alcohol, the acid, after the addition of alcohol and ammonia, is precipitated by *chloride of barium*.

BENZOIC ACID ( $C_{14}H_5O_3HO$ , or  $Bz,HO$ ).

This acid is obtained by sublimation, in the form of light flexible pearly scales, or by precipitation as a crystalline powder. When pure it has no smell. It is fusible and volatile, its vapor being, like that of succinic acid, very irritating. It is not very soluble in cold water, more so in hot, and readily soluble in alcohol. Most of its salts are soluble in water.

*Behavior of Benzoic Acid and Solutions of Benzoates with Reagents.*

On the addition of hydrochloric acid to the solution of a benzoate in water, benzoic acid separates as a white crystalline powder.

*Sesquichloride of iron* produces a pale yellow precipitate, decomposed by ammonia, and by strong acids, which combine with sesquioxide of iron, benzoic acid being precipitated.

*Acetate of lead* does not immediately precipitate free benzoic acid; but it produces a white flaky precipitate in solutions of fixed alkaline benzoates.

TANNIC ACID ( $C_{18}H_5O_9,3HO$ , or  $\overline{Q},3HO$ ).

When pure, this acid is nearly white, but not all crystalline. It is very soluble in water; the solution absorbs oxygen from the air, and is converted into *gallic* and *ellagic* acids. It has a most astringent but not bitter taste. It is almost insoluble

in ether. On the addition of a mineral acid, a precipitate composed of tannic acid and the acid employed is determined. Solution of *gelatine* produces an insoluble curdy precipitate. The whole of the tannic acid in a solution may be removed by a piece of animal membrane.

*Solution of starch*, and most of the vegetable bases also produce precipitates.

*Sesquichloride of iron* gives a dark blue black precipitate.

#### GALLIC ACID ( $C_7H_5O_6, 2HO$ , or $G, 2HO$ ).


This acid forms beautiful prisms of a silky lustre, and a slightly yellow color. It is not very soluble in cold, but dissolves in three parts of boiling water. Its alkaline solution, when exposed to the air, becomes first yellow, then green, red, brown, and finally nearly black, by the absorption of oxygen. It is *not* precipitated by *gelatine*; its solution in hot sulphuric acid is precipitated by water as a reddish brown, crystalline powder, possessing coloring properties, and which, when heated, yields fine red prisms. By the action of heat it is converted into pyrogallic and metagallic acids.

Solutions of *gallic acid* give with salts of *sesquioxide of iron* a dark blue precipitate; with salts of *oxide of iron* the precipitate is black.

### III.—Acids not precipitated by *Chloride of Calcium* or by *Sesquichloride of Iron*: *Acetic, Formic, Uric, and Meconic Acids*.

#### ACETIC ACID ( $C_4H_3O_3, HO$ , or $AcO_3, HO$ , or $\bar{A}, HO$ ).


The hydrated acid at temperatures below  $60^\circ$  is a crystalline solid. It melts at  $62^\circ$  or  $63^\circ$ , forming a liquid of a pungent, peculiar, and agreeable smell, and a burning acid taste. It has a powerful action on the skin, on which it raises a blister, producing a painful sore. It boils at  $248^\circ$ , and its vapor is inflammable. It is decomposed by anhydrous sulphuric acid, and also by chlorine, two new acids, *sulphacetic* and *chloroacetic acids* being formed. It is also decomposed when passed in a state of vapor through a red hot tube, the products being *carbonic acid* and *acetone*. Thus:



Acetates, when heated, are decomposed with the same transformation. The greater number of the acetates are soluble in water. *Acetate of silver* and acetate of *protoxide of mercury* are crystalline, and only sparingly soluble. When heated with dilute sulphuric acid, acetates are decomposed with the liberation of acetic acid; when heated with concentrated sulphuric acid and alcohol *acetic ether* is disengaged, which may be known by its peculiar odor; when an acetate is heated with *potassa* and *arsenious acid*, *oxide of kakodyl* is disengaged. With excess of oxide of lead, acetic acid forms a solution which has an alkaline reaction. Sesquichloride of iron exhibits no reaction with acetic acid; but in solutions of neutral acetates peracetate of iron is formed, which imparts to the solution a blood-red color.


#### FORMIC ACID ( $C_2H_3O_3, HO$ ; or $FeO_3, HO$ ).

This acid, in its most concentrated state, fumes in the air, and has a very pungent acid smell. At a low temperature it crystalizes in brilliant scales. It is highly corrosive, acting powerfully on the skin, and producing painful sores. It boils at  $212^\circ$ , and its vapor is inflammable; all its salts are soluble in water. They have a general resemblance to the acetates, but are, nevertheless, quite distinct. When heated to redness, they give off carbonic acid and carbonic oxide, leaving the metal reduced, or carbonic oxide, leaving a metallic oxide. By the property which this acid and its salts possess of reducing the oxides of the precious metals, it is distinguished from acetic acid. When *nitrate of silver*, or *protonitrate of mercury*, are added to concentrated solutions of alkaline formiates, sparingly soluble precipitates are formed, and on the application of heat a reduction instantly takes place, carbonic acid and water being formed, thus:



By gently heating chloride of mercury with an alkaline formiate, it is reduced first to subchloride, and then to metallic mercury.

When formic acid is heated with concentrated sulphuric acid, it is decomposed into water and carbonic oxide, thus:



The sulphuric acid withdraws from the formic acid the elements of water, and a transposition of its atoms takes place.



The same decomposition occurs on heating a formiate with sulphuric acid.

URIC ACID ( $C_{10}H_4N_4O_5, HO$ , or  $\bar{U}, HO$ ).

This acid is separated from its compounds by mineral acids as a white crystalline powder. It is very sparingly soluble in water, the solution reddens litmus; all its salts are likewise very sparingly soluble. When uric acid is dissolved in *nitric* acid, the solution evaporated to dryness, and *ammonia* added, a beautiful *purple* red color is obtained. By fusion with alkalies, uric acid disengages ammonia.

MECONIC ACID ( $C_{14}HO_{11}, 3HO$ , or  $Me, 3HO$ ).

This acid, which is found only in opium, crystallizes, when pure, in the form of beautiful white silvery scales. It is soluble in water and in alcohol. The solution is decomposed by boiling; it is also decomposed by hydrochloric acid; and entirely so when heated with excess of *potassa*; *oxalic acid*, *carbonic acid*, and a coloring matter being the products. Its distinguishing character is that of causing a *deep blood red color* in solutions of *persalts of iron*, without, however, any precipitation taking place.

---

## CHAPTER IV.

### ON SYSTEMATIC QUALITATIVE ANALYSIS.

IN the last chapter the chemical comportment of a great number of substances with reagents has been described. Amongst the bases there have been omitted only a few metallic oxides of very rare occurrence, the history of which, and their relation to different reagents, have not been as yet made out; and amongst the acids, nearly all in the inorganic, and a great number of those in the organic kingdom that are of any thing like frequent occurrence, have been included. Now, when the student has made himself *experimentally* acquainted

with the relations of these substances to reagents, and when he has become familiar with all the reactions that have been described, he is in a position certainly to pronounce a correct opinion as to the nature of almost any *simple compound*, by which is meant any arrangement of *single base* with a *single acid*, that may be presented to his notice; but if he be called upon to decide the nature of a compound, consisting perhaps of a mixture of several substances, it is clear that a mere knowledge of the action of reagents *alone* will not serve him, but that he must possess the knowledge of a method of separating the various substances from each other, and of determining the *absence*, as well as the *presence*, of certain bases and acids: in short, he must know how to proceed on a *systematic method* of examination, without which chemical analysis would be little better than mere guess-work, and its *correctness* or incorrectness quite a matter of chance. Even in the examination of a compound which is known to be simple, the greatest advantage is derived from the systematic method, a great saving of time and labor is effected, and the result is arrived at in a far more satisfactory manner than it could be by the indiscriminate application of test after test, following no rule or order, but merely throwing out baits, as it were, with the hope of eventually meeting with appearances, and observing phenomena, that may enable us to recognize the presence of some particular substance. In this chapter our object will be to point out the manner in which this systematic method of qualitative analysis is to be conducted, illustrating the course of proceeding by examples; and our attention will be confined to those substances and combinations only which are of general occurrence. The subject will be thus rendered far more inviting, and less embarrassing, to the beginner; and, after the student has made himself thoroughly acquainted with the principles on which general examinations are conducted, and has acquired a dexterity in conducting the manipulatory processes, he will afterwards find no difficulty in encountering the analysis of compounds in which the rarer substances occur, to the existence of which a careful preliminary examination will, generally speaking, arouse his attention.

*Preliminary examination.*—Before submitting a compound to analysis, there are certain operations to be performed upon it, which should never be neglected, as they frequently fur-

nish valuable hints for the subsequent examination, and always give some insight into the nature of the substance. In the first place, if the body be a solid, its physical characters, such as its *form, density, color, hardness, &c.* should be noted; it should next be reduced to powder, and subjected to the action of heat, both alone, and also together with certain fluxes. The experiments are conducted in the following manner:—

1st. A small quantity of the substance is heated on a strip of platinum foil, and it is observed whether it undergoes any alteration. If it be wholly or partly volatile, its odor will frequently enable us at once to decide on the presence of some particular substances, such as *ammonia, sulphur, arsenic, benzoic acid, &c.* If fumes are evolved, a portion of the substance may be heated in a test tube, and notice taken of the appearance of a sublimate in the cool parts of the tube. It should be examined carefully with a pocket lens, and its physical characters minutely ascertained; sulphur, certain sulphurets, as those of mercury and arsenic, mercury, arsenic, cadmium, tellurium, selenium, and certain metallic seleniurets, oxide of antimony, arsenious acid, ammoniacal salts, and salts of mercury, may thus be detected. *Chlorine, nitrous acid, sulphurous acid, hydrocyanic acid, &c.,* are thus also frequently discovered. If the substance under examination contains water, it will be condensed in drops on the upper part of the tube. These drops should be examined by test papers, and it should be noted whether they have an acid, alkaline, or neutral, reaction. If the substance changes color without entering into fusion, certain metallic oxides, such as those of *tin, lead, bismuth, or zinc,* may be looked for; and, if it blackens, the presence of organic matter is nearly certain. It is advisable also to heat a little of the substance in a tube, with bisulphate of potassa; *nitrates* are thus decomposed, deep red fumes of nitrous acid being produced. Compounds of *iodine, bromine, and fluorine* are likewise decomposed, the former yielding violet fumes of iodine, the second, bromine in a gaseous state, and the last hydrofluoric acid, the presence of which is recognized by its action on the glass. The presence of a *sulphate* is proved by heating a portion of the thoroughly dried substance in a glass tube, with powdered charcoal: the sulphuric acid becomes thereby deoxidized, and fumes of sulphurous acid are evolved. *Metallic sulphurets* likewise disengage sulphurous acid when heated in a tube open at both ends,

being thus exposed to a current of air. Under similar treatment *metallic arseniurets* furnish a crystalline sublimate of arsenious acid, sometimes mixed with the reduced metal; the sulphurets of arsenic yield arsenious acid and realgar; and compounds of antimony give a white sublimate of oxide of antimony, which is recognized by the readiness with which it is volatilized by a gentle heat. A similar sublimate is formed on heating *metallic tellurets* in an open glass tube; but it is distinguished from oxide of antimony by fusing into colorless drops when heated, a character which belongs also to volatilized chloride of lead. It is not easy, by means of the blowpipe, to distinguish *lead* from *bismuth*, as the oxides of both metals fuse into a dark yellow mass, which becomes lighter on cooling. The color of oxide of lead is certainly lighter than that of oxide of bismuth, but the distinction is by no means definite.

2d. The substance is heated on charcoal *alone*, before the blowpipe. If it fuses, and is absorbed, wholly or partly, by the charcoal, *alkaline salts* are probably present; if it deflagrates, *nitrates*, *chlorates*, *bromates*, and *iodates* must be particularly looked for. If, when strongly heated, it leaves a white residue, the *alkaline earths* may be expected to be met with.

3d. The substance is mixed with carbonate of soda, and heated on charcoal in the reducing flame. By this treatment most metallic oxides are reduced, some with the production of metallic beads without any incrustation taking place on the charcoal, as *gold*, *silver*, *tin* and *copper*; others are reduced with an incrustation, and with or without the production of metallic beads, as *bismuth*, *lead* *cadmium*, *antimony*, and *zinc*; and others are reduced without giving either beads or incrustations, as *iron*, *cobalt* *platinum*, *nickel*. *Manganese*, if present, is converted, in the outer flame, to *manganic acid*, which forms, with soda, manganate of soda of a green color. *Chromium*, under similar circumstances, gives rise to chromate of soda of a yellow color. When, however, the substances under examination contain several metallic bases, the student must not expect to meet with well-defined reactions; he will have to draw his conclusions from a comparison of the phenomena he will observe by submitting the subject of experiment to a variety of treatments. The formation of a glass is characteristic of the presence of silicic acid; the bead is, however,



transparent only when there is a great excess of silicic acid. Quartz, felspar, with some other minerals and refractory clays, give limpid beads; but the glasses produced by most minerals containing silicic acid are colored by the metallic oxides present. Silicic acid is remarkable as being almost the only substance insoluble by fusion in microcosmic salt.

4th. The substance is heated in a test tube with concentrated sulphuric acid; if any volatile acid be present, it will almost certainly be detected by this operation; thus, hydrosulphuric acid gas (sulphuretted hydrogen) is evolved from sulphurets, and is immediately recognized by its odor; sulphurous acid gas is liberated from the lower oxides of sulphur; a yellow gas (a mixture of chlorine and hydrochloric acid) is set free from chlorates; a mixture of bromine and oxygen from bromates; hydrochloric acid gas from chlorides; hydrofluoric acid gas from fluorides; bromine and iodine from bromides and iodides: by heating with sulphuric acid also, nearly all organic substances are decomposed; sulphurous and carbonic acid gases, and sometimes carbonic oxide, being evolved. If a cyanide be heated with dilute sulphuric acid, hydrocyanic acid is set free.

If the substance to be analyzed be a liquid, the first step is to evaporate a portion of it to dryness on platinum foil, in order to see whether it really contains anything in solution, and then to ascertain, by means of test papers, whether it has an acid, or alkaline, or neutral reaction; if the first, it does not necessarily follow that the solution contains free acid, for it must be borne in mind that saline solutions of most of the heavy metallic oxides redden litmus paper: it is not difficult, however, to decide whether the acid reaction is occasioned by a metallic salt or by a free acid; the addition of a drop or two of solution of carbonate of potassa generally, in the first case, renders the liquid turbid, while, in the latter case, it remains clear. If the solution be alkaline, it can contain no metallic oxides that are soluble in alkaline liquids; and if it be perfectly neutral it probably consists only of salt of the alkalies, or alkaline earths.

These preliminary experiments having been made, and some insight into the general nature of the substance under examination having thereby been obtained, its relation to solvents is next to be examined. It is reduced to a fine state of division by trituration in an agate mortar, and a portion digested for

some time in a test tube with distilled water; if it be entirely dissolved, the quantitative analysis of the aqueous solution may at once be proceeded with, taking about twenty-five or thirty grains of the substance. If a complete solution do not take place, a drop or two of the clear liquid is to be evaporated to dryness on platinum foil, in order to see whether water has dissolved anything. If the evaporated liquid leave a residue, then the substance must a second and a third time be digested with fresh portions of distilled water, filtered, and the filtrate set aside for subsequent examination. The undissolved residue is next gradually heated to the boiling point, with dilute hydrochloric acid, and if complete solutions be not effected, the fluid is decanted and the residue digested with concentrated hydrochloric acid, particular attention being paid to the nature of the gases evolved. If an effervescence take place, carbonic acid, sulphuretted hydrogen, and hydrogen gases, may be looked for; the first betrays the presence of carbonates, the second that of sulphurets, the third that of certain metals: the evolution of chlorine indicates peroxides or chromates, and hydrocyanic acid points out the existence of certain cyanides. If complete solution of the substance be not effected by concentrated hydrochloric acid, a fresh portion is to be digested with nitric acid; a few of the metals only escape solution by this acid (*gold, platinum, palladium, &c.*), *tin* and *antimony* are oxidized by it, but the oxides are not dissolved: it moreover decomposes all sulphurets, with the single exception of sulphuret of mercury, setting free sulphur, which is easily recognized by its color and levity, and its being completely evaporated when heated on a strip of platinum foil: if nitric acid fail to dissolve the substance completely, aqua regia may be tried, and, if this leave a residue, recourse must be had to fusion with an alkali or an alkaline carbonate, the following preliminary experiments being first performed upon it:—

1st. A small portion is heated on a slip of platinum foil, the odor of sulphurous acid is conclusive as to the presence of sulphur, and, if no other substance be present, the whole will be dissipated by a very moderate heat; in this case, a prolonged digestion of the residue in aqua regia will, generally speaking, give a clear solution, the whole of the sulphur becoming oxidized into sulphuric acid.

2d. A small quantity is moistened with hydrosulphuret of

ammonia; if it immediately becomes black, an insoluble *silver*, *mercury*, or *lead*, salt is present.

3d. A small portion is mixed with carbonate of soda, and heated in the inner blowpipe flame; a metallic reduction, accompanied by a yellow incrustation, indicates *lead*.

4th. A small quantity is digested with carbonate of potassa; if it become black, *protochloride of mercury* is present, which is farther confirmed by mixing a portion of the residue with slightly moistened carbonate of soda, and heating it in a glass tube, small globules of mercury are easily recognized with the aid of a lens.

5th. Another small quantity may be digested with ammonia, and the clear ammoniacal liquid supersaturated with nitric acid; the formation of a white precipitate, insoluble in the nitric acid, indicates *silver*.

Besides insoluble compounds of *silver*, *lead*, and *mercury*, the residue, insoluble in aqua regia, may contain *sulphates of the alkaline earths*, *silicates*, *fluorides*, *certain phosphates and arseniates*, and the *insoluble modifications of oxides of tin*, *antimony* and *chromium*. *Sesquioxide of iron* also is dissolved only with great difficulty, after having been strongly ignited. All these compounds may, however, be brought into a soluble state by fusion with carbonate of soda, or with a mixture of carbonate of soda and cyanide of potassium; or they may have their constituents transposed in such a manner as to admit of their easy detection by a proper subsequent treatment. For example, if the original substance undissolved by nitric acid or by aqua regia contain sulphates of the alkaline earths, the result of a fusion with carbonate of soda is to bring them to the state of carbonates, which, though insoluble in water, are readily dissolved by dilute hydrochloric acid, and the bases are then easily detected in the hydrochloric solution: the sulphuric acid with which these bases were previously combined is found in the *aqueous* solution of the fused mass, in the form of *sulphate of soda*. Again, if the insoluble residue contain *chloride*, *iodide*, or *bromide of silver* or *lead*, the result of the fusion with an alkaline carbonate, which in this case must be performed in a porcelain and not in a platinum crucible, is to transfer the *chlorine*, *bromine*, or *iodine* to the metal of the alkaline base, forming compounds easily soluble in water, and therefore easy of detection in the aqueous solution of the fused mass; while the *metal* or *metals* with which the chlorine, iodine,

or bromine was originally combined, being of course, insoluble in water, may be dissolved in nitric acid, and detected by the appropriate tests. If *baryta*, *strontia*, and *lime* be present, besides the oxides of *silver* and *lead*, the two latter metals are precipitated from the nitric solution by sulphuretted hydrogen: the liquor filtered from the precipitate is mixed with hydrofluosilicic acid, by which the *baryta*, after a time, is precipitated. To the liquor filtered from this precipitate, solution of sulphate of potassa is added, which precipitates the *strontia*, in company, perhaps, with a little of the *lime*, and on filtering off the precipitated sulphate of strontia, adding to the filtrate ammonia, and then oxalate of ammonia, a white precipitate, indicating the presence of *lime*, is determined. *Silicic acid*, if present, passes into the state of silicate of soda, and is discovered by adding excess of hydrochloric acid to the aqueous solution of the fused mass, evaporating to perfect dryness, and treating the residue with water; by this treatment the silicic acid is brought to its insoluble condition, and remains undissolved.

It thus appears that when we have before us a complex substance, which is partly soluble in water, and not wholly dissolved by either hydrochloric acid, nitric acid, or aqua regia, three distinct analytical operations may be performed on it, viz:—1. Examination of the aqueous solution. 2. Examination of the acid solution. 3. Examination of the insoluble residue. If the operator be desirous of obtaining a precise knowledge of the mode of arrangement of the different acids and bases in such a complex mixture, he must make these three distinct analyses; but, if his object be only to ascertain what acids and bases are present, he may generally omit a distinct analysis of the aqueous solution, and after a careful preliminary examination he may confine his attention to the acid solution (the substance not having been previously exhausted by water), and to the mass obtained by fusion of the residue with an alkali.

### 1.—*Examination for Bases: Principles on which the method Depends.*

In the last chapter it was shown that by means of certain *general* reagents metals may be arranged into groups; some of which by other reagents may again be subdivided into minor groups, each of the individuals composing which may be recognized by their comportment with certain other reagents,



which may be called *special*. The general reagents are *sulphuretted hydrogen*, *hydrosulphuret of ammonia*, *carbonate of ammonia*, *caustic ammonia*, and *potassa*, and they are of the greatest use and importance to the analytical chemist in conducting a systematic qualitative analysis. Thus, if on the addition of sulphuretted hydrogen to an acid liquid, no precipitate should occur, the operator is assured that none of the metals composing the fifth or sixth groups can be present; and if, after having neutralized the liquid with ammonia, no precipitate or decided change of color should occur on the addition of hydrosulphuret of ammonia even on the application of heat, a proof is obtained that the solution can contain no bases, but some one or more of those included in the first or second groups; and, lastly, the addition of carbonate of ammonia will show at once whether any of the alkaline earths are present. If this reagent should give no precipitate, then the solution in question can contain no metallic oxides but magnesia and those contained in the first group; and if phosphate of soda and ammonia should occasion no precipitate, it must be a solution of some salt or salts of some one or more of the alkalis proper. Supposing, however, that sulphuretted hydrogen *has* occasioned a precipitate in the acid liquid, this precipitate must be a sulphuret of some one or more of the metals of the fifth or sixth groups; and it may contain the whole of the metals of both groups. By digesting it with hydrosulphuret of ammonia, we easily separate these two groups; the metals of the sixth being soluble in that reagent, while those of the fifth are insoluble. The two groups being thus separated, the individual metals are sought for by the application of special tests.

Again suppose that the filtrate from the precipitate occasioned by sulphuretted hydrogen should furnish a precipitate with hydrosulphuret of ammonia, this precipitate may contain any or all of the metals of the *third* and *fourth* groups, and it may also contain *phosphates*, *oxalates*, *borates*, and *hydrofluates* of the *alkaline earths*; but it can contain no metal belonging to the fifth or sixth groups; neither can it contain either of the alkalis proper. The color of this precipitate furnishes some guide to the substances present: if it be white, it can contain neither *iron*, *cobalt*, or *nickel*; it may, however, contain small quantities of *manganese* and *chromium*: if it be black, then *iron*, *cobalt*, and *nickel*, either or all must be pre-

sent. *Potassa* and *ammonia* are the general reagents employed for the further examination of the precipitate, which is treated in the following manner:—It is washed and digested with dilute hydrochloric acid; if complete solution take place, neither *cobalt* nor *nickel* is present, as the sulphurets of these metals are decomposed only by a protracted digestion with concentrated hydrochloric acid; if complete solution do not take place, then regard must be had to these metals in the subsequent examination by special tests: *nitric acid* is added to the hydrochloric solution, and the mixture is boiled: complete solution of everything takes place, with the exception, perhaps, of the separated sulphur, which is removed by filtration. To a portion of the clear solution sal ammoniac is added, and then *ammonia* in excess. If a precipitate be produced, the whole of the solution is treated in the same manner. The precipitate produced by ammonia may contain the oxides of the second group in the form of certain salts (phosphates, oxalates, borates, hydrofluates); the oxides of the third group, *as oxides*, and of the metals of the fourth group, *iron*, in the state of sesquioxide. The filtrate from the precipitate produced by ammonia may contain all the other metals of the fourth group (*nickel, cobalt, zinc, and manganese*). *Potassa* now becomes an important reagent in the further analysis both of the precipitate and the filtrate, as will be seen presently, when we minutely describe and illustrate the whole analytical process.

But, again, suppose after having acidified with hydrochloric acid the filtrate from the precipitate occasioned by hydrosulphuret of ammonia, and well boiled it till it has lost all odor of sulphuretted hydrogen, it should give a white precipitate when digested with *carbonate of ammonia*, the presence of some one or more of the members of the *second group* (the alkaline earths) may with certainty be inferred: as this precipitate can contain no metallic oxide of either of the other groups, special testing is at once had recourse to for the detection of *baryta, strontia, and lime*. The filtrate from the precipitate occasioned by carbonate of ammonia can contain only *magnesia* and the *alkalies proper*. It is first examined as to its perfect freedom from *baryta, strontia, and lime*, by testing a small portion with sulphate of potassa for the two former earths, and a small portion with oxalate of ammonia for the latter. The absence of these earths being proved, another portion is specially tested for


*magnesia* by phosphate of soda, and, its presence having been proved, the whole of the remainder of the filtrate is evaporated to dryness, and the ammoniacal salts expelled by ignition; the residue is dissolved in water, and *baryta water* added as long as any precipitate of *magnesia* is formed; the solution is then boiled and filtered, and dilute sulphuric acid added to the filtrate till it becomes acid; the fluid is then filtered off from the precipitated sulphate of *baryta*, and the filtrate specially tested for the alkalies.

By the above course of treatment, no base can escape detection but *ammonia*, which is specially tested for in the original solution by heating it with an excess of a concentrated solution of potassa; the ammonia if present is thus discharged in its gaseous form, and its presence is indicated by its odor, or by the white fumes produced on bringing near the mouth of the test tube a feather moistened with strong acetic acid. In following out the foregoing operations, there are certain precautions to be observed, in order to ensure accuracy and to lead to just conclusions. In the first place, it must be borne in mind that, if we employ hydrochloric acid to acidify our solution previous to subjecting it to sulphuretted hydrogen, certain metals (silver, mercury, lead) are precipitated as chlorides. The two former may be completely removed from the solution by adding a sufficient quantity of hydrochloric acid, and of course, therefore, need not be sought for in the subsequent analysis. *Lead*, however, will not be completely separated in this manner, and must, therefore, be had regard to. The operator must take especial care that the precipitates of the several groups be most completely removed, by washing, from the solution containing the members of the following groups. The greatest confusion and perplexity will arise from neglecting this precaution. He must also be careful that the precipitation by the general reagents be complete, which object is attained by adding the reagent by degrees as long as any precipitation takes place; and in the case of the sulphuretted hydrogen, by continuing to pass the gas through the solution till it smells strongly of it after agitation, and which sometimes requires two or three hours; the deposition of the newly formed sulphuret is much facilitated by gently heating. Should the preliminary examination have indicated *arsenic* in the form of *arsenic acid*, the metal must be brought into the state of *arsenious acid* by boiling the solution with *sulphurous*

*acid*, before subjecting it to the action of sulphuretted hydrogen.

Fig. 5 represents the arrangement of the apparatus for passing a current of sulphuretted hydrogen through a solution; A is a wide-mouthed bottle containing water and fragments of proto-sulphuret of iron. It is closed with a good

Fig. 5.



sound cork, through which are inserted, perfectly air tight, two tubes, one surmounted by a funnel, the other bent at right angles and joined, by a connector of caoutchouc, with a third tube also bent at right angles, and which passes to the bottom of the bottle B containing water. Into the cork with which this second bottle is closed is cemented the wide tube C, bent twice at right angles; the delivering tube D, at one end, is connected with the bottle B by means of a good sound cork. When this apparatus is about to be used for transmitting a stream of sulphuretted hydrogen gas through a liquid, the solution to be operated on is placed in a beaker, or in a Phillip's precipitating jar, and the tube D immersed in it. Sulphuric acid is now poured into A through the funnel, the gas is immediately evolved, and in traversing the water in B, which should be quite cold, it becomes washed, and thus passes in a state of purity into the solution. Sometimes, when the evolution of gas is too rapid, portions of protosulphuret of iron and of sulphuric acid are carried forward with it; both are, however, retained in the wash bottle B. When the solution has become thoroughly saturated with the gas, the delivering tube is removed, and after being rinsed out, or, if required, cleaned with a small feather, it is fit for another operation.

## II.—Examination for *Acids*.

The following is the systematic course for the detection of acids, inorganic and organic, pursued in the Royal College of Chemistry. The author is indebted for it to Mr. Bloxam, one of the assistants in the laboratory of that institution.



*General Rules.*

1st. All the bases, except alkalies and alkaline earths, should be removed before testing for acids.

2d. *Chromic acid*, if present, should be reduced by sulphuretted hydrogen, and the oxide separated by ammonia.

3d. *Silicic acid* should be separated by evaporating to dryness, with excess of hydrochloric acid, redissolving the residue in dilute hydrochloric acid, and neutralizing by ammonia.

NOTE.—In this case the volatile acids—viz: *hydrocyanic*, *hydrobromic*, *hydriodic*, *acetic*, *formic*, *succinic*, and *benzoic* acids—cannot be found in the solution. *Acetic* acid may be tested for specially with sulphuric acid and alcohol. The presence of *silicic acid* does not interfere with the testing for *succinic* and *benzoic acids* by *sesquichloride of iron*, nor with that of *hydrocyanic acid*, *hydrobromic acid* and *hydriodic acid* by *nitrate of silver*.

4th. If the substance be insoluble in water, but soluble in acids, and has been found by the preliminary examination to contain an organic acid, or *hydrocyanic*, *hydrobromic*, or *hydriodic acid*, it should be boiled with *carbonate of soda*; the base remains in the residue either free or combined with carbonic acid, and the acid is dissolved in combination with soda. The solution should be exactly neutralized by nitric acid previous to testing for acids.

5th. If the solution to be tested for acids contain ammoniacal salts, *boracic*, *tartaric*, and *citric acids* cannot be recognized by the usual reagents. In such a case the *boracic acid* may be tested for specially; or the ammoniacal salts may be removed by long-continued boiling with potassa, and the solution afterwards neutralized by nitric acid.

6th. If the substance be insoluble in water, but soluble in acids, and *not* a compound of an organic acid, or of *hydrocyanic*, *hydrobromic*, or *hydriodic* acids, a part may be dissolved in hydrochloric acid, and tested for all acids but hydrochloric, and another part in nitric acid, and tested for hydrochloric acid by nitrate of silver.

7th. *Carbonic*, *hydrosulphuric* and *sulphurous* acids should be separated, if present, by a strong acid, and the solution neutralized, one part with *potassa*, in order to test for *boracic*, *tartaric*, and *citric* acids, the other part with ammonia, to test for the other acids. *Carbonic acid* may be recognized by the

precipitate caused by transmitting the gas through baryta water. *Hydrosulphuric* acid is recognized by its odor and by its reaction with a salt of lead, and sulphurous acid is also recognized by its odor and by the white precipitate occasioned by passing the gas through a solution of sulphuretted hydrogen.

### I.—*Absence of Organic Acids.*

1. To the neutral solution *chloride of barium* is added; if a precipitate be produced, it may be *sulphate, borate, oxalate, phosphate of baryta*, and *fluoride of barium*, all or any. It is digested with hydrochloric acid, which dissolves everything but *sulphate of baryta*; a white residue indicates, therefore, *sulphuric acid*.

2. The solution filtered from the sulphate of baryta is exactly neutralized with ammonia, and *chloride of calcium* added. If a precipitate be produced, it may consist of *borate, oxalate*, and *phosphate of baryta*; and *fluoride of barium*, all or any. It is digested with *acetic acid*. If complete solution be not effected, the residue may be *oxalate of lime* and *fluoride of calcium*, both or either, and the solution may contain *phosphate and borate of lime*.

*a. Examination of the precipitate.*—It is digested with hydrochloric acid. If complete solution do not take place, the residue is *fluoride of calcium*; and the presence of *fluoride* is confirmed by heating the original substance in a tube with concentrated sulphuric acid. The hydrochloric solution is heated with excess of ammonia; if a white precipitate be produced, it is *oxalate of lime*. The presence of *oxalic acid* is confirmed by heating the original solution with concentrated sulphuric acid in a test tube; *carbonic oxide* is evolved, which burns with a blue flame.

*b. Examination of the filtrate.*—Ammonia is added; if this fail to produce a precipitate, *no phosphoric acid* can be present; but, in the presence of ammoniacal salts, *borate of lime* may be held in solution. The original solution is, therefore, specially tested for *boracic acid* by sulphuric acid and alcohol. If a precipitate be produced by ammonia, *phosphoric acid* is specially tested for in the original solution by ammonia, chloride of ammonium, and sulphate of magnesia.

3. To another portion of the original solution, *nitrate of silver* is added. If a precipitate occur, it may be *phosphate*,

*borate, oxalate, chloride, bromide, iodide, and cyanide of silver*, any or all. It is digested with nitric acid. *Phosphate, oxalate, and borate of silver*, if present, are dissolved; but, as these acids have already been detected in the precipitate by chloride of calcium, no further attention need be bestowed on the solution.

*Examination of the residue insoluble in nitric acid.*—It may consist of *chloride, iodide, bromide, cyanide, and sulphocyanide of silver*, either or all.

It is gently heated with excess of ammonia, by which *chloride, bromide, and cyanide of silver* are dissolved, *iodide and sulphocyanide of silver* remaining.

*a. Examination of the solution.*—Nitric acid is added. *Chloride, bromide, and cyanide of silver*, if present, are precipitated. If *bromine* has not been found in the preliminary examination, the precipitate is washed, dried, and ignited; it is then boiled with nitric acid. By the ignition the cyanide of silver is decomposed, the metal being reduced, which is dissolved by the nitric acid; and, if any residue remain insoluble in the nitric acid, it is chloride of silver, and indicates *hydrochloric acid* in the substances under examination. To the nitric acid solution hydrochloric acid is added. If a precipitate be produced, it indicates that silver had been dissolved, and consequently that *hydrocyanic acid* existed in the original solution. The confirmatory tests for hydrocyanic acid are—1st, the Prussian blue test; 2d, a few drops of the original solution are heated for some time with hydrosulphuret of ammonia, a film of sulphur appears on the watch glass, and the addition of a drop of *sesquichloride of iron* produces a deep red color, owing to the formation of *sulphocyanide of iron*.

If *bromine* has been found in the preliminary examination, a portion of the original solution is first tested for hydrocyanic acid; from another portion the *iodine*, if it contain any, is separated by a mixture of *sulphate of copper* and *protosulphate of iron*; and the excess of the oxides of copper and iron having been removed by potassa, the filtered solution is concentrated by evaporation, and a stream of chlorine passed through; it is then agitated with ether, the brown color communicated to which indicates *bromine*. The ethereal solution is agitated with *potassa*, evaporated to dryness, and the residue treated with sulphuric acid and peroxide of manganese; red brown vapors of bromine are evolved.

*b. Examination of the residue.*—It consists of iodide and sulphocyanide of silver, either or both. The original solution is tested for iodine by chloride of mercury and by starch paste, after the addition of chlorine. Another portion of the original solution is specially tested for sulphocyanic acid by sesquichloride of iron.

4. A portion of the original solution is mixed with sulphuric acid, and a crystal of protosulphate of iron added. The formation of a brown halo indicates nitric acid, which is confirmed by boiling with sulphuric acid and metallic copper.

5. A portion of the original substance, in a solid form, is heated with dilute hydrochloric acid. The production of a deep, pungent, yellow gas, which explodes on the contact of flame, disengaging chlorine, indicates chloric acid.

6. A portion of the original solid is treated with acetic acid in the cold. The evolution of chlorine indicates hypochlorous acid.

7. If the original substance evolve oxygen when ignited, and if it give off red fumes when gently heated with sulphuric acid, and if the solution cause a precipitate of metallic mercury in a solution of the nitrate, the presence of nitrous acid may be inferred.

## II.—*Presence of Organic Acids.*

1. To a neutral solution of the substance, chloride of barium is added. If a precipitate be produced, it may be sulphate, phosphate, borate, oxalate, tartrate, and citrate of baryta, and fluoride of barium, either or all. The precipitate is digested with hydrochloric acid, which dissolves everything but sulphate of baryta. A white residue indicates, therefore, sulphuric acid.

2. To the hydrochloric solution, neutralized exactly by ammonia, chloride of calcium is added. The precipitate may contain phosphate, oxalate, borate, and tartrate of lime, and fluoride of calcium, either or all. The solution may contain citrate of lime.

*a. Examination of the precipitate.*—It is divided into two parts. To one part acetic acid is added, which dissolves borate and phosphate of lime if they be present. The further treatment of this solution has been described above. Oxalate of lime and fluoride of calcium remain undissolved; hydrochloric



acid is added, which dissolves the *oxalate of lime*, while the *fluoride of calcium* remains. On the addition of ammonia to the hydrochloric solution, *oxalate of lime* is again precipitated. The other portion of the precipitate is digested with *potassa*. *Tartrate of lime*, if present, is dissolved, but by boiling is again precipitated. *Borate*, *phosphate*, and *oxalate of lime*, and *fluoride of calcium* remain undissolved by the *potassa*. The object of this operation is the detection of *tartaric acid*.

*b. Examination of the solution.*—It is boiled for some time. If any precipitate take place, it is *citrate of lime*, indicating *citric acid*.

3. To another portion of the original neutral solution *nitrate of silver* is added. The object here being the detection of *bromine*, *iodine*, *hydrocyanic*, and *sulphocyanic acids*, without reference to any of the organic acids, the method of treatment is precisely as has been already described.

4. To another portion of the original neutral solution, *sesquichloride of iron* is added. If a light brown precipitate be produced, *benzoic* and *succinic acids*, either or both, are present. If the precipitate be black, it contains *tannic* or *gallic acids*, or both. If no precipitate be determined, or if, after the subsidence of the precipitate, the solution have a deep red color, *sulphocyanic* or *acetic acids*, or both, are present.

*a. Treatment of the precipitate.*—It is digested with *ammonia*, by which it is decomposed, all the acids present combining with the alkali and sesquioxide of iron, being separated from which, the solution must be filtered off.

The solution is divided into three parts:—

To one portion, *alcohol* and *chloride of barium* are added; the formation of a white precipitate indicates *succinic acid*.

Another portion is concentrated by evaporation, and hydrochloric acid added; a white crystalline precipitate indicates *benzoic acid*.

The third portion is exposed to the air; if it assume a red color, *gallic acid* is present, and if on the addition of sulphuric acid a thick precipitate take place, the presence of *tannic acid* is to be inferred, which is confirmed by the curdy precipitate produced on the addition of solution of gelatine.

*Acetic acid* is specially tested for by heating the original solution with sulphuric acid and alcohol, acetic ether, of a peculiar and unmistakeable odor, being evolved.

*Nitric, nitrous, chloric, and hypochlorous acids*, are tested for as above described.

*Uric acid* is specially tested for by mixing a portion of the original solution with nitric acid, evaporating nearly to dryness, and then adding ammonia; a fine purple color indicates *uric acid*.

*Sulphocyanic acid* is specially tested for in the original solution, by boiling with sulphuric acid; the liquor becomes of a red brown color, and by continued boiling deposits a lemon yellow powder.

## EXAMPLES FOR ILLUSTRATION.

### EXAMPLE 1.

*Examination of an Aqueous Solution containing one Acid and one Base, regard being had to the latter only.*

It is neutral to test paper: evaporated to dryness on a slip of platinum foil, it leaves a white residue; boiled with caustic potassa, it emits no smell of ammonia.

I. To a portion in a test tube, a few drops of hydrochloric acid are added: no precipitate; absence of *silver, protoxide of mercury*, and probably also of *lead*.

II. To another portion, acidified with hydrochloric acid, solution of sulphuretted hydrogen is added: no precipitate or discoloration; absence of all the metals of the fifth and sixth groups.

III. To another portion, ammonia and hydrosulphuret of ammonia are added: no precipitate, even after boiling; absence of all the metals of the third and fourth groups.

IV. To another portion, carbonate of ammonia containing a little caustic ammonia, is added: no precipitate, even after long boiling; absence of *baryta, strontia*, and *lime*: phosphate of soda is then added; no precipitate after agitation and subsequent repose; absence of *magnesia*; absence of all the metals of the second group.

V. The remainder of the solution is divided into three parts: to one portion *tartaric acid* is added, in slight excess and well shaken; a crystalline precipitate subsides: to another portion, concentrated by evaporation, *chloride of platinum* is added, which occasions a yellow crystalline precipitate: the

remaining portion of the solution is evaporated nearly to dryness, alcohol added and ignited; the flame is tinged *violet*. These three tests concur in proving that the base sought after is *potassa*.

### EXAMPLE 2.

A fluid slightly acid to test paper evaporated to dryness on platinum foil; it leaves a black residue, which does not *disappear* on ignition.

I. Hydrochloric acid occasions no precipitate; absence of *silver* and *protoxide of mercury*, probably also of *lead*.

II. Sulphuretted hydrogen gives a black precipitate: present some metal of the fifth or sixth group. The solution is heated, to facilitate the subsidence of the precipitate, which is then digested with hydrosulphuret of ammonia, by which it is dissolved; present, therefore, some metal of the sixth group; from the color of the precipitate, it must be either *platinum* or *gold*.

III. To a portion of the original solution, concentrated by evaporation, a few drops of protosulphate of iron are added: no brown precipitate or discoloration; absence of *gold*.

IV. To another portion, concentrated by evaporation, *chloride of potassium* is added; this immediately occasions a fine yellow crystalline precipitate, indicating *platinum*.

### EXAMPLE 3.

*Examination of a solid Substance, consisting of one Acid and one Base: detection of both Acid and Base.*

*Preliminary.*—It is a yellow powder: heated alone on a platinum foil, its color becomes deeper, but it regains its original color on cooling. It suffers no further change by heat, either on platinum foil or on charcoal. Heated with microcosmic salt, it gives in both flames of the blowpipe a yellowish green glass, becoming emerald green on cooling. Heated in a test tube with concentrated sulphuric acid, it becomes white, and, on the addition of water, a yellowish green solution is obtained. It is insoluble in water. Digested with hydrochloric acid, a green solution is obtained, and chlorine is evolved, but complete solution does not take place. Digested with nitric acid, a red solution is obtained, but the substance is not completely dissolved, even by aqua regia. These experiments

render it certain that the subject of the analysis is *chromic acid* in combination with some metallic oxide.

### *Examination for Base.*

I. It is fused with about three times its weight of a mixture of carbonate of potassa and carbonate of soda, in a platinum crucible; the fused mass is digested with distilled water, and the residue, after being well washed, is dissolved in hydrochloric acid and filtered.

II. Sulphuretted hydrogen occasions no precipitate; absence of all the metals of the fifth and sixth groups.

III. Hydrosulphuret of ammonia produces no precipitate; absence of all the metals of the third and fourth groups.

IV. Carbonate of ammonia gives an immediate precipitate; present, *baryta*, *strontia*, or *lime*.

V. To a portion of the hydrochloric solution, solution of gypsum is added: an immediate precipitate is formed, indicating *baryta*, which is confirmed by adding to another portion a *hydrofluosilicic acid*; a colorless crystalline precipitate is formed.

*Examination for acid.*—Although the preliminary experiments indicated *chromic acid* with sufficient distinctness, it is advisable to perform some confirmative experiments on the filtrate from the fused mass.

I. To a portion of the clear fluid *nitrate of silver* is added; a dark purple precipitate, soluble in nitric acid and in ammonia, is produced.

II. To another portion *acetate of lead* is added; a yellow precipitate is formed, which changes to red on the addition of ammonia.

III. To another portion *sulphurous acid* is added; the color of the solution changes from yellow to green.

The substance examined is, therefore, *chromate of baryta*.

### EXAMPLE 4.

*A Solid Crystalline Compound, consisting of one Acid and one Base.*

*Preliminary Examination.*—It is a white crystalline heavy substance, having a nauseous metallic taste. Heated on platinum foil, it fuses, leaving a residue which, while hot, is deep red, but on cooling becomes yellow: on increasing the heat, it gradually disappears, leaving no residue. Heated alone, in a



test tube, it fuses, and gives off red nitrous vapors; and, on continuing to apply heat to the red residue, it is decomposed, the upper part of the tube becoming lined with a metallic film. Heated in a test tube with concentrated sulphuric acid, nitrous fumes are evolved, and a white crystalline mass remains. Heated with carbonate of soda in a glass tube, a gray metallic crust is formed, from which metallic globules are obtained by rubbing with a glass rod.

These experiments are quite conclusive as to the nature of the compound; *nitrate of protoxide of mercury*.

The following are the confirmatory experiments.

I. A portion is boiled with distilled water, a yellow insoluble residue remains (basic nitrate).

II. To a portion of the solution a drop of hydrochloric acid is added, a copious white precipitate is formed (protochloride of mercury).

III. To another portion *potassa* is added, a black precipitate is formed (protoxide of mercury).

IV. A drop of the solution is rubbed on a plate of polished copper; a bright silvery white color appears, which vanishes on the application of heat (metallic mercury).

V. To another portion of the solution *protochloride of tin* is added, a gray precipitate is determined, which by boiling with hydrochloric acid unites into globules metallic mercury.

#### EXAMPLE 5.

##### *A Powder containing one Acid and one Base.*

*Preliminary examination.*—It is a white amorphous tasteless powder; heated on a strip of platinum foil, it first blackens, and then ignites, and on removing the source of heat continues to glow, and metallic globules make their appearance. Heated on charcoal in the reducing flame, a white metal speedily appears, and the charcoal becomes covered with a yellow incrustation. Heated in a glass tube, with concentrated sulphuric acid, it blackens, carbonic and sulphurous acids being disengaged. The substance must, therefore, be some organic acid in combination with the oxide of one of the heavy metals.

*Examination for base.*—A portion is dissolved in dilute nitric acid, a clear solution is obtained.

I. To a portion of the solution, a drop of hydrochloric acid

is added; a white precipitate is formed, which, on the addition of water and the application of heat, is redissolved, but which is undissolved and unaltered by ammonia (chloride of lead).

II. To another portion of the solution, a drop of sulphuric acid is added; a white precipitate is formed, insoluble in dilute acids (sulphate of lead).

III. To another portion of the solution, chromate of potassa is added; a yellow precipitate is produced, soluble in potassa, but insoluble in dilute acids (chromate of lead).

In this case, the preliminary examination having pointed to *oxide of lead* as the probable base, special testing for that oxide was at once had recourse to.

*Examination for acid.*—The preliminary examination shows that the metallic base is combined with some organic acid. A portion of the substance is, therefore, digested with hydrochloric acid, and then boiled with carbonate of soda, in excess, filtered, and the filtrate exactly neutralized with hydrochloric acid; a sufficient quantity of ammonia is now added to give the fluid a feebly alkaline reaction, then muriate of ammonia and a drop or two of *chloride of calcium*: no precipitate, but on boiling it becomes turbid, and deposits a white precipitate; this is characteristic of *citric acid*.

The substance examined is, therefore, *citrate of lead*.

#### EXAMPLE 6.

*Examination of a Fluid consisting of several Bases and Acids, regard being had to the former only.*

*Preliminary.*—It is strongly acid, and of an olive green color: a few drops evaporated on platinum foil leave a brown residue; this residue, when strongly heated, fuses, but does not volatilize. Heated with carbonate of soda in the reducing flame, it fuses into a black globule, but there are no visible metallic particles. Heated with sulphuric acid, it gives off fumes of hydrochloric acid gas. Heated in a tube open at both ends, hydrochloric acid and chlorine gases are evolved; and, boiled with caustic potassa, it liberates ammoniacal gas.

#### A.

The addition of hydrochloric acid causes no precipitate or turbidity; absence of *silver* and *protoxide of mercury*, probably also of *lead*.

NOTE.—Had hydrochloric acid caused a precipitate, it may have consisted of *chloride of silver*, *chloride of lead*, or *protochloride of mercury*, either or all. It may also have been occasioned by *benzoic acid*, *uric acid*, *arsenious acid*, *antimonic acid*, and *basic salts of antimony and bismuth*. In either of these latter cases, however, the precipitate vanishes on the addition of a large excess of hydrochloric acid and boiling: this is not the case if the precipitate contains *silver* or *mercury*; which metals, if present, must be completely precipitated by adding excess of hydrochloric acid to the solution; and the precipitate, after having been washed and dried, must be tested for *mercury*, *silver*, and *lead*, as described at page 161. The *benzoic acid*, *uric acid*, &c. remain in solution, provided a sufficient quantity of hydrochloric acid has been added, and are detected in subsequent stages of the analysis.

## B.

A small portion of the solution, when agitated with solution of sulphuretted hydrogen, becomes black. A stream of the gas is, therefore, passed through about three-fourths of the whole solution until it smells strongly of it: a copious black precipitate is formed: present, some metal or metals of the fifth or sixth group, or of both.

NOTE.—Had the precipitate occasioned by sulphuretted hydrogen been of a milky white color, it would have been sulphur, and would have indicated *peroxide of iron*.

*Examination of the precipitate.*—It is separated by filtration from the solution, and well washed; it is then digested with sulphuret of potassium, the original fluid having indicated copper by testing with a clean knife blade; it is *not* completely dissolved.

NOTE.—Sulphuret of potassium is employed instead of hydrosulphuret of ammonia, because bisulphuret of copper is not altogether insoluble in the latter reagent.

B. 1. *Examination of the portion soluble in Sulphuret of Potassium.*—It is separated by filtration from the insoluble portion, diluted with distilled water, and boiled with acetic acid in excess, a precipitate is formed, which has a brownish black color; it certainly, therefore, contains *gold* or *platinum*, or both; and it may also contain all the other members of the sixth group.

B. 1, a. *Special testing for Gold.*—To a portion of the

original solution, a few drops of protochloride of tin, containing a little bichloride, are added; the solution acquires a reddish brown color: to another portion, concentrated by evaporation, solution of protosulphate of iron is added; no brown precipitate or coloration; absence of *gold*.

B. 1, b. *Special testing for Platinum*.—The reddish brown color produced in the last experiment on the addition of protochloride of tin is characteristic of *platinum*: a portion of the original solution is concentrated by evaporation, and, mixed with muriate of ammonia, a yellow crystalline precipitate is formed; presence of *platinum*.

B. 1, c. *Special testing for Arsenic*.—The black precipitate produced by acetic acid is well washed, and a portion, mixed with equal parts of nitre and carbonate of soda, dried at a gentle heat, and then carefully fused in a small porcelain crucible. The fused mass is digested with hot distilled water, filtered, nitric acid added in slight excess, and heat applied; the liquid remains perfectly clear, from which absence of *tin* may be inferred. Nitrate of silver is then added, and the fluid, after it is cool, is filtered; dilute ammonia is now carefully dropped on the surface of the solution contained in a test tube, and it is allowed to remain at rest for some time; no precipitate or brown coloring between the layers of liquid is perceptible; absence of *arsenic*, which is further confirmed by precipitating the remainder of the solutions by neutral acetate of lead, and examining the precipitate before the blowpipe on charcoal.

NOTE.—The fusion of the precipitate with nitre and carbonate of soda must be performed with great care, a violent explosion may otherwise take place. The best method of proceeding, is to mix the precipitate with twice or thrice its bulk of nitre and carbonate of soda, and to project it in small portions at a time, into a small Berlin capsule, in which a mixture of carbonate of soda and nitre is kept in a state of fusion over a lamp.

B. 1, d. *Special testing for Antimony*.—The remainder of the precipitate is boiled with hydrochloric acid, filtered, and concentrated by evaporation; a portion is mixed with water, there is not the slightest turbidity. Another portion, when mixed with solution of sulphuretted hydrogen, gives no orange-colored precipitate, indicating absence of *antimony*.

NOTE.—When *antimony* and *tin* are both present, they are



most safely detected thus. Into the hydrochloric solution of the precipitate, diluted with water, a rod of metallic zinc is placed; the *antimony* and *tin* become thereby reduced, and are deposited in a pulverulent form on the zinc, from which they are easily removed. The finely divided metals are digested with nitric acid, and the oxides thus formed are heated with a hot saturated solution of bitartrate of potassa, or with a solution of tartaric acid. If complete solution take place, *antimony* alone is present, and may be confirmed by sulphuretted hydrogen; if a residue remain after a protracted digestion, it consists of *peroxide* of tin, the presence of which is confirmed by reduction before the blowpipe, with a mixture of cyanide of potassium and carbonate of soda on charcoal.

B. 1, e. *Special testing for Tin*.—The remainder of the hydrochloric solution is evaporated to dryness, and the residue fused on charcoal, with a mixture of cyanide of potassium and carbonate of soda, before the reducing flame of the blowpipe; no metallic globules make their appearance; absence of *tin*.

The only metal present, therefore, of the sixth group, is *platinum*.

B. 2. *Examination of the portion insoluble in Sulphuret of Potassium*.—It is boiled with nitric acid; it dissolves completely with the exception of a light flocculent residue of sulphur; absence of *mercury*; there may, however, be present all the metals of the fifth group, with the exception of *silver*.

NOTE.—Had a black residue remained insoluble, or but very sparingly soluble in nitric acid, it would have consisted of sulphuret of mercury; a small quantity of *sulphate of lead* may also have been present. To ascertain whether the mercury existed in the compound in the state of *suboxide* or as *oxide*, the black residue should be heated in a glass tube: if it sublime without change or decomposition, the metal was in the state of oxide; if the sublimed sulphuret be mingled with globules of metallic mercury, it was in the state of suboxide.

B. 2, a. *Special testing for Copper*.—To a portion of the solution, ammonia in excess is added, a blue liquid is obtained. To another portion ferrocyanide of potassium is added, a chocolate brown precipitate is produced; presence of *copper*.

B. 2, b. *Special testing for Cadmium*.—To another portion of the solution ammonia is added, then hydrochloric acid in slight excess; the solution is then boiled with *carbonate of ammonia*: no white precipitate; absence of *cadmium*. Ammonia not having occasioned any precipitate in the nitric solution renders it unnecessary to test for *lead* and *bismuth*, neither of which can be present.

NOTE.—Had ammonia caused a precipitate, the nitric solution would have been tested for lead by dilute sulphuric acid; and for bismuth, by evaporating a portion to a small bulk, adding a few drops of hydrochloric acid, and mixing with a large quantity of water.

When *lead*, *bismuth*, *copper*, and *cadmium* are present in a solution, the two latter metals are very conveniently separated from the two former by cyanide of potassium, with which they form soluble double salts. The nitric solution of the sulphurets is precipitated by carbonate of potassa, and the moist and washed precipitate is digested with cyanide of potassium: the double salts which copper and cadmium form with cyanide of potassium are removed by filtration. The insoluble carbonates of lead and bismuth are boiled with diluted hydrochloric acid: the solution is divided into two parts; to one, sulphuric acid is added, sulphate of lead immediately precipitates: the other portion is concentrated by evaporation, filtered, and the filtrate dropped into water; a turbidity or milkiness indicates bismuth. Into the filtrate containing the double salts of copper and cadmium with cyanide of potassium, sulphuretted hydrogen is passed; which, provided there be present excess of cyanide of potassium, precipitates only sulphuret of cadmium, which is recognized by its behavior before the blowpipe. The sulphuret of copper remains dissolved, and may be precipitated by the addition of hydrochloric acid.

### C.

*Examination of the Filtrate from B.*—A few drops are evaporated upon a strip of platinum foil; a residue remains. A portion is rendered slightly alkaline by ammonia, and, disregarding a bulky precipitate that is thereby produced, *hydro-sulphuret of ammonia* is added; this occasions a copious black precipitate: the whole of the filtrate is therefore treated in the same manner, the reagent being slowly added till it

ceases to occasion a further precipitation. This precipitate may contain any or all of the metals of the third and fourth groups: it may, moreover, contain *phosphates*, *borates*, *oxalates*, and *hydrofluates* of the alkaline earths; the precipitate being black renders it certain that *iron*, *cobalt*, or *nickel*, either or all, must be present.

*Examination of the Precipitate by Hydrosulphuret of Ammonia.*—It is washed with water, to which a few drops of hydrosulphuret of ammonia have been added; it is then digested with dilute hydrochloric acid; it does not completely dissolve (presence of *cobalt* or *nickel*, or both). Nitric acid is then added, and the solution boiled and filtered: a small portion of the filtrate is mixed with sal-ammoniac, ammonia added, and heat applied, a dark-colored precipitate is formed; presence of *peroxide of iron*, *alumina*, *oxide of chromium*, *phosphate of magnesia*, and *phosphates*, *oxalates*, *hydrofluates*, and *borates* of the other *alkaline earths*, any or all, *iron certainly*, from the dark color of the precipitate. The whole of the filtrate is then treated in the same manner, and the precipitate filtered and washed.

C. 1, *Examination of the Precipitate by Ammonia.*—It is digested with caustic potassa, by which entire solution is not effected, a brown bulky mass remaining, which is separated by filtration.

C. 1, a. *Special testing of the Alkaline Solution for Oxide of Chromium.*—It is boiled for some time: no precipitate. A portion is then slightly acidified with hydrochloric acid, ammonia added, boiled, and the precipitate thereby occasioned, after being washed and dried, is heated with microcosmic salt in the blowpipe flame; the glass on cooling has no tinge of green; indicating absence of *chromium* in the alkaline solution.

C. 1, b. *Special testing of the Alkaline Solution for Alumina.*—It is supersaturated with hydrochloric acid, and then boiled with excess of ammonia, the precipitate, after having been well washed, is heated on charcoal before the blowpipe; moistened with solution of protonitrate of cobalt, and again strongly heated, a deep sky blue color is obtained on cooling; presence of *alumina*.

C. 1, c. *Special testing of the portion insoluble in Caustic Potassa for Sesquioxide of Iron.*—A portion is washed, and digested with hydrochloric acid; the solution, which must be

as nearly neutral as possible, is filtered, and to the clear solution a drop of ferrocyanide of potassium is added; a deep blue precipitate is formed; indicating *iron*.

NOTE.—To ascertain whether the iron existed in the original solution as protoxide or as peroxide, solution of perchloride of gold is added to a portion: if a brown powder of metallic gold be produced, it is a proof that the iron was in the state of *protoxide*; if, however, the original solution contained a protosalt of tin, this test is not altogether conclusive.

C. 1, d. *Special testing of the portion insoluble in Caustic Potassa for Sesquioxide of Chromium*.—Although no traces of chromium could be detected in the alkaline solution, it is, nevertheless, necessary to search for that metal in the insoluble residue, because, when sesquioxide of iron and sesquioxide of chromium are together submitted to the action of caustic potassa, they are acted on by that reagent in a manner regulated by their respective quantities. If, for instance, the quantity of oxide of iron be large, and that of oxide of chromium small, very little, if any, of the latter will be dissolved. But if the quantity of oxide of chromium be large, and that of oxide of iron small, the latter will accompany the former in its solution in the alkali. In the case before us, the quantity of sesquioxide of iron being evidently very considerable, it is very possible that it may be found to contain traces of sesquioxide of chromium; a small portion is therefore fused in a thin Berlin capsule with a mixture of nitre and carbonate of soda; when cold, it is digested with water: a colorless solution is however obtained, giving no colored precipitates with either nitrate of silver or acetate of lead: absence of *chromium*.

C. 1, e. *Special testing of the portion insoluble in Caustic Potassa for Phosphates, Oxalates, Hydrofluates, and Borates of Alkaline Earths*.—The remainder of the insoluble portion is dissolved in hydrochloric acid filtered, and tartaric acid having been added to prevent the precipitation of the sesquioxide of iron, excess of ammonia is added, a white precipitate is formed, indicating the *presence* of some one or more of the above salts.

C. 1, f. *Special testing for Oxalic Acid*.—A portion of the white precipitate, after being well washed, is heated to redness on platinum foil, by which any oxalate present will be converted into carbonate; the residue does *not*, however, effe-



vesce on the addition of a drop of hydrochloric acid; absence, therefore, of *oxalic acid*.

C. 1, g. *Special testing for Phosphoric Acid*.—Another portion of the white precipitate is dissolved in hydrochloric acid, sesquichloride of iron added, and then ammonia to alkaline reaction, a bulky reddish brown precipitate is produced, in which all the phosphoric acid (if any be present) is contained; the alkaline earth with which it was combined previously remaining in solution as chloride: the precipitate is thrown on a filter, and after being well washed is digested with hydrosulphuret of ammonia and again filtered; all the phosphoric acid (if any be present) is in the filtrate, as phosphate of ammonia: the clear liquid is accordingly treated with sal-ammoniac and sulphate of magnesia, by which a crystalline precipitate is produced, increasing on agitation; *phosphoric acid* is, therefore, present.

C. 1, h. *Special testing of the original Solution for Hydrofluoric Acid*.—A portion is evaporated to dryness, and the residue heated in a watch glass with concentrated sulphuric acid, a second watch glass being placed over the first; no roughening of the surface of the upper glass is observed after a considerable time; absence, therefore, of *hydrofluoric acid*.

C. 1, i. *Special testing of the original Solution for Boracic Acid*.—A portion is highly concentrated by evaporation, and digested with sulphuric acid and alcohol; on inflaming the mixture, the characteristic flame of boracic acid is not produced; absence, therefore, of *boracic acid*.

Phosphoric acid is, therefore, the only acid present in the white precipitate, and, by the treatment described in C. 1, g, this acid is removed from the earth or earths with which it was in combination, the metallic base or bases being retained in solution in the form of chlorides. This solution is, therefore, to be examined.

C. 1, k. *Special testing of the Solution (C. 1, g) for the Alkaline Earths and for Magnesia*.—It is digested with carbonate of ammonia mixed with a little caustic ammonia, the precipitate is filtered off, and the filtrate tested for magnesia by phosphate of soda; a crystalline precipitate makes its appearance on agitation; *magnesia* is, therefore, present. The precipitate, after being washed, is redissolved in hydrochloric acid, and divided into two parts; to one part solution of gypsum is added: no precipitate after standing for some time;

absence of *baryta* and *strontia*: to the other part oxalate of ammonia is added; an immediate precipitate ensues; presence of *lime*.

The white precipitate is, therefore, a mixture of *phosphate of lime* with *phosphate of magnesia*.

NOTE.—Had oxalic acid been found, the alkaline earth with which it was combined would have been detected thus: The ignited white precipitate (C. 1, f) is dissolved in hydrochloric acid, and to the clear solution caustic ammonia, free from carbonate of ammonia, added, the phosphate of the alkaline earth is precipitated, the chloride remains in solution, and is tested for in the usual manner.

C. 2. *Examination of the Filtrate from the Precipitate by Ammonia*.—It has a bluish tinge, from which the presence of nickel is inferred. It is digested with hydrosulphuret of ammonia, a precipitate is formed, which is filtered, washed, and dissolved in aqua regia.

C. 2, a. *Special testing for Oxide of Zinc*.—To the solution in aqua regia pure caustic potassa is added in excess, the clear alkaline liquor is then treated with sulphuretted hydrogen: no precipitate; absence of *zinc*: had a precipitate been formed, the presence of zinc must be confirmed by the blow-pipe.

C. 2, b. *Special testing for Oxide of Manganese*.—The precipitate thrown down by caustic potassa, which has an apple green color, having been well washed, is agitated for some time with a solution of carbonate of ammonia, containing a little caustic ammonia, complete solution takes place; absence, therefore, of *manganese*.

NOTE.—Had an insoluble residue remained, it must have been tested for manganese with carbonate of soda before the blowpipe.

C. 2, c. *Special testing for Cobalt*.—The ammoniacal solution (C. 2, b) is evaporated to dryness: redissolved in a few drops of hydrochloric acid, and again evaporated to a moist mass, a portion of which is heated with borax in the blowpipe flame, a yellow glass without a tinge of blue is formed; indicating absence of *cobalt*.

C. 2, d. *Special testing for Nickel*.—The remainder of the moist residue is dissolved in water and treated with cyanide of potassium: a precipitate is formed, soluble in excess of the cyanide, but, on the addition of dilute sulphuric acid, a greenish

precipitate again makes its appearance; indicating presence of *nickel*.

#### D.

*Examination of the Filtrate from the Precipitate of Hydro-sulphuret of Ammonia (C).*—A few drops are evaporated on platinum foil, a residue remains. To a small portion phosphate of soda and ammonia are added and strongly agitated; a precipitate occurs, indicating the presence of some one or more of the alkaline earths. Hydrochloric acid is then added to the whole filtrate, and it is boiled till it has lost all odor of sulphuretted hydrogen. It is filtered and boiled with excess of carbonate of ammonia mixed with a little caustic ammonia, the precipitate formed is examined for *baryta*, *strontia* and *lime*, and a portion of the filtrate for magnesia precisely as described above (C. 1, k.); *lime* and *magnesia* are found.

NOTE.—Had an immediate precipitate occurred on the addition of solution of gypsum, both *baryta* and *strontia* may have been present; both earths must, therefore, have been specially tested for as follows:—

*Special test for Baryta.*—A portion of the hydrochloric solution is heated with fluosilicic acid, the formation of a colorless crystalline precipitate either immediately or after a time indicates *baryta*.

*Special test for Strontia.*—Another portion of the hydrochloric solution is evaporated to dryness and redissolved in alcohol, the alcoholic solution is inflamed: if it burn with a carmine red flame, it indicates *strontia*.

*Examination for the fixed Alkalies.*—The remainder of the filtrate from the precipitate, occasioned by carbonate of ammonia, and which had not been tested for magnesia by phosphate of soda, is evaporated to dryness and ignited, and, magnesia having previously been proved to be present, the residue is dissolved in water, and *baryta* water added as long as any precipitation occurs: the solution is then boiled and filtered. Sulphuric acid is added to the filtrate in slight excess in order to remove the excess of *baryta*, and the solution is again filtered and evaporated to dryness.

E. 1. *Special testing of the residue for Potassa.*—It is dissolved in alcohol, and a portion of the solution is ignited; the flame has a distinct violet tinge, indicating the *absence* of soda and the presence of *potassa*. The remainder of the alcoholic

solution is mixed with chloride of platinum, a yellow precipitate immediately takes place, confirming the presence of potassa.

NOTE.—If the alcoholic flame had not been tinged violet, but rather yellow, *soda* must have been specially tested for by antimoniate of potassa; and, if magnesia had not been found, the treatment of the filtrate with baryta water might have been omitted, and the filtrate itself at once evaporated to dryness, and tested for alkalis.

*Ammonia* had been found in the preliminary examination.

The following were therefore the bases present in the mixture analyzed: oxides of *platinum*, *copper*, *iron*, *nickel*, and *aluminum*, *lime* and *magnesia*, in combination with *phosphoric acid*; also *lime* and *magnesia* in combination with some other acid; *potassa* and *ammonia*.

A systematic search for acids is next instituted, but as we have so fully described the principles on which this examination is conducted, both by general and by special testing, we deem it unnecessary to illustrate the process by any examples. The only acid with which there is any difficulty in a mixed compound insoluble in water, but soluble in acids, is *phosphoric acid*, the detection of which is sometimes troublesome, especially when *alumina*, *magnesia*, *lime*, *strontia* or *baryta* are present, together with metallic oxides, which cannot be precipitated except by hydrosulphuret of ammonia. In this case, and where there are also present metallic oxides that are precipitated by sulphuretted hydrogen, *Rose* gives the following method for the detection of phosphoric acid:—

The substance under examination is dissolved in nitric acid, and the metallic oxides capable of being precipitated by sulphuretted hydrogen are removed by that reagent. The filtered liquor is heated until all odor of sulphuretted hydrogen is removed; after which dilute sulphuric acid is added, which precipitates the *baryta* and *strontia*, and the *lime* also, if a sufficient quantity of alcohol be added. The liquor filtered from these earths is evaporated until all the alcohol has disappeared, and excess of caustic potassa is added, by which oxides of *iron*, *cobalt*, *nickel*, and *manganese* are precipitated: *magnesia* also, if present, is thrown down, carrying with it perhaps a small quantity of the phosphoric acid; but the greater portion remains in the filtered liquor in combination with the *alumina* and *oxide of zinc*, if the latter base be pre-



sent. If *alumina* alone be present, it may be precipitated in the form of *double silicate of alumina and potassa*, by adding to the alkaline liquor solution of *bisilicate of potassa*; (prepared by fusing together one part of silica and two and a half of carbonate of potassa;) the liquor filtered from this gelatinous precipitate contains the *phosphoric acid*, which may be detected by adding slight excess of hydrochloric acid, neutralizing by ammonia, and adding *chloride of calcium*; or by substituting nitric for hydrochloric acid, and precipitating by *acetate of lead*. Phosphate of lead is easily recognized by the blowpipe; the phosphoric acid, in phosphate of alumina, is also recognized by dissolving in nitric acid, adding to the solution nitrate of silver, and then just sufficient ammonia to neutralize the nitric acid, when a yellow precipitate of phosphate of silver will make its appearance. If *oxide of zinc* be present, it must be precipitated from the alkaline solution by hydrosulphuret of ammonia, taking care that there is sufficient potassa present to keep the phosphate of alumina in solution; the sulphuret of zinc having been removed, the hydrosulphuret of ammonia in the filtrate must be decomposed, and the method described above adopted for the detection of phosphoric acid.

If the substance under examination contain no alumina or magnesia, the metallic oxides capable of being precipitated by hydrosulphuret of ammonia are precipitated by that reagent, the liquor having been previously saturated with ammonia; the phosphoric acid is then detected in the filtered liquor in the usual manner. Rose observes that the analysis of the oxidized combinations which are insoluble in water may be rendered much more easy by fusing the compound with carbonate of soda. The acids are thus procured separate from the bases, and are found in the aqueous solution of the fused mass.

The analysis of insoluble *cyanides* and *ferrocyanides* is sometimes attended with difficulty when conducted in the usual manner: the detection of cyanogen in *simple cyanides* is sufficiently easy, as they are all decomposed by boiling with concentrated hydrochloric acid, cyanogen being evolved, which is recognized by its odor, and chlorides of the metallic bases being formed; but the decomposition of the class of *double cyanides* by means of an acid is not so simple. Fresenius, therefore, recommends that a different treatment should be adopted in their analysis. For this purpose he directs them

to be boiled with solution of carbonate of potassa, having previously removed by water everything soluble in that fluid; the solution is filtered, and the residue washed: this residue contains the bases, and is treated in the usual manner. The filtrate contains the cyanogen, and perhaps other acids; it may also contain iron, cobalt, manganese, and chromium, in the form of *ferrocyanide*, *cobalticyanide*, &c. of *potassium*. The cyanogen is recognized by mixing a portion of the filtrate with hydrochloric acid till it is strongly acid, and then adding solution of the double proto and perchloride of iron. If cyanogen be present, prussian blue precipitates. The metals are detected by evaporating another portion of the filtrate to dryness, with great excess of nitric acid, and fusing the residue (cautiously for fear of explosion); the *iron*, *manganese*, and *cobalt* become hereby oxidized, and are separated in the usual manner: the *chromium*, if present, is converted into chromic acid, and is obtained as soluble chromate of potassa.

Should the compound be insoluble in carbonate of potassa, it is boiled with caustic potassa, and the alkaline solution is treated with sulphuretted hydrogen. If any precipitate should be formed, it is removed, and the filtered liquor, having been acidified with hydrochloric acid, is again subjected to sulphuretted hydrogen, by which all sulphurets soluble in alkalis (sulphuret of tin, sulphuret of antimony, &c.) are removed: the filtrate is tested for *cyanogen*, *cobalt*, *iron*, *manganese*, *chromium*, and acids as above. If the object be merely to detect the bases in these insoluble cyanogen compounds, simple fusion with carbonates of soda and potassa will, in most cases, be sufficient, the metals are thus obtained either in their metallic state or combined with carbon. If the fusion be performed with nitre, the operator must guard carefully against the consequences of an explosion, which is very likely to occur.

## QUALITATIVE ANALYSIS OF NATURAL SILICATES.

The usual constituents of this extensive class of native substances are *silica*, *lime*, *magnesia*, *alumina*, *oxide of iron*, *oxide of manganese*, *alkali*, and *water*. Rare oxides, such as *yttria* and *glucina* (in *gadolinite*), *zirconia* (in *eudialite*), *lithia* (in *lepidolite*), are sometimes met with in silicious mine-

erals, and for these a special method of analysis must be pursued: but, in the absence of such oxides, a very simple course of examination is adopted.

The first constituent to be sought for is *water*, the presence or absence of which is ascertained by heating a portion of the mineral, finely pulverized, in a test tube, first gently, and then strongly in a flame urged by the blowpipe; water, if present, will rise, and be condensed in the upper portion of the tube.

From 50 to 100 grains of the mineral are next reduced to a coarse powder in the steel mortar, and then ground to the finest possible powder in the agate mortar. It is easy for the beginner to be deceived as to the degree of pulverization required; it does not in most cases suffice that the mineral shall be reduced to what may seem mere dust, but it must be ground down with water if necessary, till it has almost, or entirely, lost all grittiness between the teeth. With many minerals this can only be effected by elutriation, that is by grinding it with water into a paste in the agate mortar or on an agate slab, and then diffusing it through water in a tall jar, allowing it to stand for a short time, and then decanting the cloudy liquid, and collecting the fine powder, which after some time settles at the bottom of the vessel. It is always, however, better to avoid elutriation when the mineral can be brought to an impalpable powder in the dry way; but a very fine state of division is generally an indispensable condition for its decomposition, whether by hydrochloric acid or by fusion with an alkali.

If the silicate to be analyzed belong to that class which is decomposed by hydrochloric acid, the powder is drenched with this acid: a bulky gelatinous mass is with many (the zeolites, &c.) immediately formed without the application of heat, and on adding water, the silicic acid separates in flakes, leaving the bases with which it was combined dissolved in the form of chlorides. Other silicates, such as *stilbite* (silicate of alumina, lime and water), *pyrosmalite* (lime, tersilicate of oxide of iron and manganese), and *pitchblende* (uranium ore), &c., are only decomposed by prolonged digestion with hot acid, and then not completely, unless they are in an extremely fine state of division; the silicic acid in these cases separates in the form of a fine powder. If the silicate belong to that class which resists the action of acids, amongst which may be

mentioned *felspar*, *mica* and *talc*, it is fused in a platinum crucible with a mixture of five parts of carbonate of potassa and four of carbonate of soda, the fused mass is treated with water, and subsequently evaporated to dryness in a porcelain basin with excess of hydrochloric acid: the dry mass, when cold, is moistened with concentrated hydrochloric acid, and after standing for about an hour water is added; the bases present dissolve as chlorides, and the silicic acid remains in the form of an insoluble powder.

Some minerals, as *zircon* and *cyanite*, are only decomposed by fusion with caustic potassa.

When the mineral contains an alkali, it must be analyzed, by igniting it in a silver crucible with four or five times its weight of pulverized and dry nitrate of baryta; the fused mass, after supersaturation with hydrochloric acid and evaporation to dryness, is redissolved in water, filtered, and sulphuric acid added to precipitate the greater part of the *baryta*: carbonate of ammonia in excess is then added to separate the remainder of the baryta, together with the *alumina* and *peroxide of iron*, and, these precipitates having been filtered off, magnesia and the alkalis are sought for in the filtrate, as has been already recommended.

Silicious minerals containing alkali may also be analyzed, by mixing them with powdered fluor spar, and heating to incipient redness in a platinum dish with concentrated sulphuric acid, the silica passes off as *fluoride of silicium*: the dry mass is digested with water, precipitated with carbonate of ammonia, and proceeded with as above.

The bases are found in the hydrochloric solution after the separation of the silica in a very simple manner. If the blowpipe has shown that the mineral contains *iron*, that metal is brought to the state of sesquioxide by adding a few drops of nitric acid to the hydrochloric solution and heating; *ammonia* is then added in excess, *alumina* and *sesquioxide of iron* are thereby precipitated; the former is separated from the latter by digestion with caustic potassa, and its presence in the alkaline solution proved by the addition of *sal-ammoniac*, which produces a white flocculent precipitate.

To the filtrate from the precipitate by ammonia, *oxalate of ammonia* is added; a white precipitate indicates *lime*.

To the filtrate from the precipitate by oxalate of ammonia, *phosphate of soda* is added; the formation of a crystalline pre-



precipitate indicates *magnesia*. The operator must, however, be certain that the *whole* of the lime had previously been precipitated by oxalate of ammonia.

The alkalis are detected in the manner described (page 185), the method of proceeding depending on the presence or absence of *magnesia*.

Manganese is best recognized by the blowpipe.

For the detection of *glucina*, *yttria*, and other rare substances found in a few minerals, such as the *emerald*, *gadolenite*, *pyrothite*, &c., the student is referred to Rose's Manual of Chemical Analysis.\*

## QUALITATIVE ANALYSIS OF MINERAL WATERS.

The principal constituents are detected *qualitatively* in a brief and simple manner, the rarer substances are most conveniently found in the *quantitative* analysis, the method of conducting which will be subsequently described.

*Detection of free Carbonic Acid*.—Add to a portion of the water which has been recently collected and kept in a well-stopped bottle, a small quantity of *lime water*, if a precipitate be formed, which redissolves on the addition of a further quantity of the water, *carbonic acid* in a free state is present.

*Detection of sulphuretted Hydrogen*.—The odor of the water is, in most cases, a sufficient evidence of the presence of this gas, which is confirmed by adding to a small flask, nearly filled with the water, a few drops of solution of acetate of lead and well agitating, a black precipitate, or a more or less brown coloration of the fluid indicates sulphuretted hydrogen, or an alkaline sulphuret.

*Detection of Sulphuric Acid*.—A portion of the water is slightly acidified with hydrochloric acid and gently warmed, chloride of barium is then added, the formation of a white precipitate indicates sulphuric acid.

*Detection of Hydrochloric Acid*.—A portion of the water is acidified with nitric acid, warmed, and nitrate of silver added; a curdy precipitate, or a turbidity, indicates hydrochloric acid.

\* A new translation from the French, and the fourth German Edition, by A. Normandy.—William Tegg and Co.

*Detection of Nitric Acid.*—A considerable quantity of the water is evaporated to dryness, the residue is dissolved in a small quantity of water, and tested with protosulphate of iron and sulphuric acid. (See page 145 and 157).

*Detection of Iodine.*—A large quantity (four or five gallons) of the water is reduced to a small bulk by evaporation, and a portion of residual fluid is tested with starch paste and nitric acid. (See page 157).

*Detection of Bromine.*—Another portion of the residual fluid is treated with chlorine water and ether, as described page 157.

## DETECTION OF BASES.

*Detection of Lime.*—Add to a portion of the water oxalate of ammonia, and allow it to stand for a considerable time in a warm place; a white precipitate indicates *lime*.

*Detection of Magnesia.*—Concentrate the filtrate from the oxalate of lime, if necessary, by evaporation, and add to the clear residue ammonia and phosphate of soda; a crystalline precipitate indicates *magnesia*.

*Detection of Iron.*—Introduce into a flask of white glass, containing no lead, a quantity of the water, to which a few drops of hydrosulphuret of ammonia have been added; the formation of a black precipitate indicates iron. Or, should this test fail from the smallness of the quantity of that metal present, it may be detected by *tincture of nut galls*, a few drops of lime water being also added. As the iron generally exists in mineral waters in the form of carbonate of the protoxide, these tests should be applied as soon as possible after the water has been collected from the spring: if the presence of iron be indicated after the water has been boiled, the metal does not exist as carbonate, but as some other salt.

*Detection of Lime in the form of Bicarbonate.*—To a portion of the water muriate of ammonia is added, and then *ammonia*; the formation of white precipitate indicates bicarbonate of lime: should a notable quantity of iron be present, the precipitate has a more or less yellow tinge; and this is also the case if the water contain organic matter.

*Detection of Alkalies.*—Should the water contain iron, that metal must be brought to the state of sesquioxide by means

of chlorine: it is then precipitated together with all the other bases, but magnesia, by carbonate of ammonia: the further process for the detection of the alkalies is conducted precisely as described page 185.

*Detection of Ammonia.*—A few drops of hydrochloric acid are added to a considerable quantity of the water, which is then evaporated nearly to dryness, at a very gentle heat: the residue is tested for ammonia by caustic potassa or hydrate of lime, as before directed. Besides the above acids and bases, there are found occasionally in mineral waters the following substances: *lithia, alumina, strontia, oxides of manganese, zinc and copper*, amongst bases: and *sulphurous, boracic, phosphoric, hydrofluoric, and silicic acids* among electro-negative bodies. These bodies are never, however, found all together in the same water; and as they always exist in very small quantities only, they are, as before observed, best detected in the quantitative examination.

The student, after having carefully gone through the reactions described in the third chapter, "on the comportment of substances with reagents," is recommended to practice himself thoroughly in systematic qualitative examinations, commencing with simple arrangements of one acid and one base, and proceeding gradually to more complicated mixtures, following the course we have attempted to sketch out perspicuously in the preceding pages. The mixtures analyzed should be prepared by another person, and the operator must carefully guard himself against drawing hasty conclusions, as well as against arriving at results by any but the legitimate road. The preliminary examination will, in many cases, point out to him with certainty the composition of the substance he is examining: he should not on that account, however, neglect to perform the confirmative experiments, remembering that his object is to acquire a practical knowledge of the general system of analysis, and not merely to ascertain the composition of the substance. If he carefully and conscientiously follow the system here given, in all its details, and the advice we here offer him, we venture to assure him that in a short time he will find himself in a condition to undertake the qualitative examination of almost any substance that may be brought under his notice.

## QUALITATIVE DETECTION OF POISONS.

Poisons have been divided by toxicologists into three classes:—1. *Irritants*. 2. *Narcotics*. 3. *Narcotico-Irritants*. In the first class are included the mineral and certain vegetable acids; the alkalis; certain metals and salts; certain vegetable acids, as *croton oil*, *gamboge*, &c.; and certain animal poisons, such as *cantharides*, *poisonous fish*, and decayed and diseased animal matters. In the second class are comprised, *opium*, *hyoscyamus*, *narcotine*, *hydrocyanic acid*, *oil of bitter almonds*, *laurel water*, *cyanide of potassium*, *morphia*, &c.; and amongst those comprehended in the third class may be mentioned *nightshade*, *tobacco*, *hemlock*, *strychnia*, *nux vomica*, certain poisonous *fungi* and *mosses*, *poisonous grain*, *alcohol* and *ether*. Now, although the chemical evidence in charges of poisoning is generally considered as the most decisive of all branches of proof, it happens, unfortunately, that with few exceptions the present state of chemistry enables us to identify with certainty mineral poisons only; and the detection of these, disguised and obstructed as the action of reagents may be by the organic mixtures in which the poison has generally to be sought for, is, in many cases, by no means so simple, or so easy of execution, as may at first be imagined. The poisons to which we propose to confine ourselves in this section are the following:—The *mineral acids*; *oxalic acid*; *hydrocyanic acid*; *arsenic*; *mercury*; *lead*; *copper*; *antimony*; and *zinc*; and we shall endeavor to describe minutely the methods of detecting these substances both in simple fluids, and in complicated organic mixtures, as at present pursued by toxicologists.

## THE POISONOUS ACIDS.

## 1. SULPHURIC ACID.

For the properties of this acid in its concentrated state, see p. 124. The most striking character by which it may be recognized is that of its yielding sulphurous acid gas, of a peculiar pungent odor, when heated in contact with charcoal, cop-



per, or mercury. In its diluted state it is detected with the greatest facility by the precipitate which is formed on the addition of nitrate of baryta, or chloride of barium. This precipitate, when dried and ignited with charcoal, is converted into sulphuret of barium, which disengages sulphuretted hydrogen on the addition of diluted hydrochloric acid. It is hereby distinguished from seleniate and fluosilicate of baryta. The detection of sulphuric acid in organic mixtures is often attended with great difficulties; so much so, indeed, that, according to Dr. Christison, a satisfactory process still remains to be discovered. The difficulty arises, 1st, from the probable presence of neutral sulphates, together with some free acid, which would obviously give the same reaction with barytic salts as dilute sulphuric acid itself; 2d, from the possible presence of a bisulphate; and 3d, from the possible neutralization of the acid (in cases of poisoning) by the substances administered as antidotes. If the substance to be examined be a liquid, a small portion should be evaporated to dryness to ascertain whether it leaves any residue; if it does, the following experiment may be made, in order to learn whether the acidity of the liquid is wholly or in part occasioned by a bisulphate, or whether there is reason for supposing that the reaction with the barytic salt may have been occasioned by some neutral sulphate, the acidity being produced by some other acid. Weigh out two equal quantities of the liquid, precipitate one with nitrate of baryta, and determine the amount of sulphate of baryta formed; evaporate the other to dryness, calcine, redissolve in water, and, having added nitric acid, precipitate also with nitrate of baryta, and determine the amount of sulphate formed. Compare the weights of sulphate of baryta obtained in the two experiments; if they are the same, it is then tolerably clear that no sulphuric acid in a free state was present in the liquid under examination; but, if the quantity of sulphate obtained in the first experiment be greater than that in the second, the excess may fairly be set down to free sulphuric acid in the mixture. When the contents of the stomach and other complex mixtures have to be examined for sulphuric acid, the mixture should be boiled with distilled water; and having proved the existence of sulphuric acid, or a soluble sulphate, by nitrate of baryta, the whole should be distilled from an oil bath at  $240^{\circ}$ , and about four-fifths drawn over. The distillate should be tested for hydrochloric and

acetic acids, and the residue should be divided into three parts, one of which is to be tested for nitric acid, another for oxalic acid, and the remainder for sulphuric acid.

Sulphuric acid is sometimes maliciously thrown on articles of clothing; and in such cases the chemist is occasionally called upon to pronounce on the nature of the corrosive substance. Owing to its strong affinity for water, sulphuric acid remains on cloth and linen for a long time, keeping the stain in a moist state; and according to Mr. Taylor, it may be easily detected after many years' exposure. The process of analysis is very simple: the injured part is cut out, digested in distilled water, filtered, and the solution treated with nitrate of barytes. Mr. Taylor recommends the following method as delicate and easy of application: a minute quantity of the injured fabric is gently heated in a small glass tube, and a piece of paper, saturated with starch and moistened with a drop of *iodic acid*, is brought near the mouth of the tube; sulphurous acid is generated by the decomposition of the sulphuric acid, which, reacting on the iodic acid, liberates iodine, and the test paper becomes blue.

*Detection of free Sulphuric Acid in Wines.*—This cannot be effected by barytic salts, because all wines contain a greater or less quantity of the sulphates of potassa and lime. M. Lassaigne gives the following simple process, by which he states that he is able to detect one-thousandth part of sulphuric acid in red wine. When a piece of common glazed paper, which has been touched with pure wine, is dried at a gentle heat, the spotted portion is unaltered; whereas, if sulphuric acid be present, it reddens and becomes brittle and friable between the fingers when slightly rubbed, before the white paper becomes at all colored. Pure wine, to which nothing has been added, leaves, by spontaneous evaporation, a violet blue spot, whereas wine, to which sulphuric acid has been added, gives, by drying, a rose red spot.

## 2. NITRIC ACID.

For the properties of this acid in its concentrated state, see p. 144. The most simple test for it is the action of copper turnings, by which it is rapidly decomposed, deep red fumes of nitrous acid being evolved, and a green solution formed. The dilute acid is also decomposed by boiling with copper

turnings, unless a large proportion of water is present, the color of the solution being blue. Other tests for nitric acid are—1st, *morphia*, which is turned in a few seconds to a beautiful red by it, and, after a longer contact, bright yellow; 2d, *narcotin*, the solution of which organic base in sulphuric acid is changed from yellow to blood red; 3d, *brucine*, an alkaloid which occurs along with *strychnine* in *nux vomica*, and which is applied as a test for nitric acid in the following manner:—About a drachm of concentrated sulphuric acid, free from nitric acid, is to be placed in a small beaker; to this is added a few drops of the liquor supposed to contain nitric acid; the whole is mixed together with a glass rod, a small piece of brucine introduced, and the liquid well stirred. If nitric acid be present, a red color will immediately be developed, which will afterwards pass to yellow. If there be no nitric acid, the brucine will not dissolve. According to Berzelius, by this means the presence of  $\frac{1}{10000}$ th part of nitric acid may be detected in a liquid. 4th, *protosulphate of iron*. This test is best applied in the following manner:—Add to a small quantity of sulphuric acid the solution to be examined, in such a proportion that the quantity added should equal three-fourths of the bulk of the acid. When the mixture has become cool, drop in a concentrated solution of protosulphate of iron; if any nitric acid be present, it is immediately decomposed; nitric oxide is evolved, which produces a rose red, purple, or, if the quantity of nitric acid present be exceedingly small, a pink tint. One part of nitric acid in 24,000 parts of water may thus be detected. In testing for nitric acid, the liquid should be neutralized with potassa and evaporated to dryness. It should be observed whether crystals of nitre are formed on allowing the concentrated solution to cool. The dry residue should be mixed with an equal bulk of copper filings, introduced into a small glass tube, and heated with a few drops of sulphuric acid. The evolution of red fumes is quite conclusive as to the existence of nitric acid in the residue left on evaporation. Mr. Taylor wraps a minute portion of the suspected nitrate in a piece of the finest copper gauze, and drops the pellet thus formed to the bottom of a small tube; he then adds a drop of water and a drop of sulphuric acid. By this means, and using a tube only one-eighth of an inch in bore, he obtains satisfactory results with one-tenth of a grain of nitre. When nitric acid has to be tested for in thick and viscid organic

liquids, the mixture is digested with distilled water, and filtered, the clear liquid is evaporated to dryness with potassa, and treated with copper filings, or gauze and sulphuric acid, as above described. Nitric acid produces on the skin a yellow stain, which may be distinguished from any other spot of a similar color by the action of ammonia, which renders it for a time brighter. It acts powerfully on woolen cloth, staining it yellowish, or orange red, or brown, and entirely destroying its texture. To discover the presence of the acid, the injured parts are removed and digested in two or three successive portions of distilled water, the liquid is filtered, and, its acidity having been proved by litmus paper, it is evaporated to dryness with potassa, and the residue treated as above. It must be borne in mind that, in consequence of its volatility, and the facility with which it undergoes decomposition in contact with organic matter, we cannot hope, as in the case of sulphuric acid, to obtain chemical evidence of its presence after the lapse of a few weeks.

### 3. HYDROCHLORIC ACID.

For the properties of this acid, see p. 134. In searching for it in organic mixtures, Orfila boils, if necessary, with distilled water, filters, and distils at a gentle heat, till the residue acquires the consistence of a thin syrup; he then adds to the extract in the retort a slight excess of a strong solution of *tannin*, the object of which is to precipitate the organic principles, to which hydrochloric acid adheres with great obstinacy: he then continues the distillation nearly to dryness, at a temperature not above  $240^{\circ}$ , and examines the distillate for hydrochloric acid by nitrate of silver. In this operation it is necessary to guard against a fallacy which may arise from the presence of a neutral chloride, such as common salt and sulphuric acid, and which can, of course, be only obviated by proving the absence of sulphuric acid. The precipitate occasioned in a solution supposed to contain hydrochloric acid by nitrate of silver, may be *cyanide*, or *oxalate* of silver; these two salts are, however, easily distinguished from the *chloride* of the same metal. *Cyanide of silver* is soluble in hot nitric acid; it evolves hydrocyanic acid when digested in hydrochloric acid, and when heated in a small tube, it evolves a gas (cyanogen) which burns with a blue flame. *Oxalate of*



*silver* is completely dissolved in cold nitric acid, and when thoroughly dried and heated on thin platinum foil, it is dissipated in a white vapor with a slight detonation. *Chloride of silver* is quite insoluble in nitric acid and in caustic potassa, though it is very soluble in ammonia, and when heated on a strip of platinum foil, it fuses into a horny looking substance. *Iodic acid* also gives, with nitrate of silver, a precipitate, soluble in ammonia, but insoluble in nitric acid; it is, however, decomposed by caustic potassa, oxide of silver being separated. It is in the highest degree improbable that this acid should occur in any compounds which are the subject of toxicological investigation. Iodate of silver is immediately known from chloride of silver, by adding to the liquid starch and sulphurous acid, when the *blue iodide of starch* is produced.

#### 4. OXALIC ACID.

For the properties of this acid, see p. 148. It is soluble in from twelve to fourteen times its weight of water (Taylor). In its crystalline form it differs entirely from citric and tartaric, and other common vegetable acids; but it greatly resembles sulphate of magnesia, for which it has been often and fatally mistaken. Its taste is intensely acid, by which it is at once known from Epsom salts, which are well known to be strongly bitter; moreover, oxalic acid, when heated on platinum foil, is entirely volatilized, if pure; Epsom salts, on the other hand, loses only its water of crystalization. In testing for this acid, a portion of the fluid, having been proved to be acid by litmus paper, should be concentrated by evaporation, and ammonia added; a radiated crystalization of oxalate of ammonia should be produced, a property which, according to Dr. O'Shaughnessy, distinguishes it from every other acid. The best tests for oxalic acid are, 1st, *nitrate of silver*, which produces a precipitate in a solution containing only the  $\frac{1}{4000}$ th part by weight of oxalic acid (Taylor). The oxalate of silver is distinguished from the *citrate* and *tartrate* of that metal by its property of fulmination, and by its leaving, on ignition, no carbonaceous residue. 2d. *Sulphate of lime*, or any soluble lime salt, which occasions a white precipitate, readily soluble in nitric acid, not very easily dissolved in dilute hydrochloric acid, and quite insoluble in acetic, tartaric, and all vegetable acids. 3d. *Sulphate of copper*, which gives

a greenish white precipitate, not readily soluble in hydrochloric acid. Neither of the mineral acids is precipitated by this test, nor is acetic, tartaric, or citric acid affected by it. When this poison has been received into the stomach, the well-known antidotes, magnesia and chalk, will probably have been administered. The following process for detecting it, under these circumstances, may be advantageously followed.

The suspected fluid is macerated with distilled water, and allowed to remain at rest for some time; the supernatant liquid, if not acid, may be thrown away; the residue is made into a thin paste with water, and boiled for two or three hours with about a twentieth of its weight of carbonate of potassa, till the organic matter is all dissolved. By this operation the oxalate of lime or magnesia will have become decomposed, and the fluid will contain oxalate of potassa. It is filtered when cold, then rendered faintly acidulous with nitric acid, again filtered, and the filtrate rendered very faintly alkaline with carbonate of potassa. It is now a third time filtered, and the clear liquor treated in the following manner. Acetate of lead is added as long as any precipitate is formed; the precipitate is collected on a filter, washed, and dried between bibulous paper. It consists of oxalate of lead, together with organic matter in union with oxide of lead. It is stirred up very carefully while moist with water, and sulphuretted hydrogen gas is transmitted briskly through it for an hour; the lead is thus removed as sulphuret, and the solution contains oxalic acid tolerably pure. The sulphuret of lead is removed by filtration; the filtrate is boiled, evaporated to dryness, redissolved in water, filtered, and the clear solution tested for oxalic acid, by nitrate of silver and sulphate of lime (Christison). Mr. Taylor modifies this proceeding, and shortens the process, by digesting the precipitated oxalate of lead in hydrosulphuret of ammonia, taking care not to use a great excess; he thus obtains the oxalic acid in the filtered liquid in the form of oxalate of ammonia. By this process, Dr. Christison states that he has detected a grain of oxalic acid in a decoction of an ounce of beef in six ounces of water; and two grains of oxalate of lime in a similar decoction, in which some fragments of beef were purposely left, to complicate the process. Mr. Taylor obtains equally satisfactory results, by digesting the precipitated oxalate of lead in water containing a small quantity of sulphuric acid. Sulphate of

lead is formed, and oxalic acid set free; the latter is separated by filtration, together with the excess of sulphuric acid; it is cautiously neutralized by ammonia, and, when quite clear, tested with nitrate of silver and sulphate of lime. The presence of sulphate of ammonia does not in the least interfere with the action of these tests.

### 5. HYDROCYANIC ACID.

For the properties of this acid, see p. 140. Its chemical tests are, 1st, *nitrate of silver*; 2d, *sulphate of copper*; 3d, *protosulphate of iron*; 4th, *hydrosulphuret of ammonia*, with *persalt of iron*. The properties of cyanide of silver have been mentioned above. It is identified in the most marked manner, by its yielding cyanogen gas, which burns with a blue flame, by simply heating it in a glass tube. One-tenth of a grain, corresponding with about one-fiftieth of a grain of anhydrous acid, will thus furnish good evidence. (Taylor.) Cyanide of silver is insoluble in cold nitric acid; but by boiling it is decomposed, nitrate of silver being formed, and hydrocyanic acid set free. *Sulphate of copper*, when added to a fluid containing hydrocyanic acid, rendered alkaline with potassa, gives a greenish precipitate, becoming nearly white on the addition of hydrochloric acid: this precipitate is cyanide of copper. According to Lassaigne, this test will discover hydrocyanic acid, when dissolved in 20,000 parts of water: but as the precipitate is white, it has not much toxicological value. When a solution of *protosulphate of iron* is added to a liquid containing hydrocyanic acid, rendered slightly alkaline by potassa, a grayish green precipitate is produced; and on adding diluted hydrochloric or sulphuric acid, and agitating, *Prussian blue* is formed and precipitated. This test is free from all objections: it will act in cases where nitrate of silver gives no precipitate; and it possesses this great advantage over the last-named test, that it is applicable in circumstances under which nitrate of silver might give rise to embarrassment; as, for instance, where the poison has to be sought for in fluids containing common salt. For the method of applying the hydrosulphuret of ammonia test, see p. 142. When hydrocyanic acid is to be sought for in organic mixtures, Mr. Taylor urges the importance of obtaining evidence of its presence before resorting to the process of dis-

tillation, in order to avoid an objection which may be raised, to the effect that the acid might have been a product of distillation. He gives the following method, which he finds to succeed with the blood, muscles, and viscera, as well as with the liquid contents and solid substance of the stomach. The liquid is acidulated with sulphuric acid and placed in a wide-mouthed bottle, the aperture of which is capable of being covered with a watch-glass, or a saucer of white porcelain. The inside of the glass or saucer is moistened with nitrate of silver and placed over the mouth of the bottle: if hydrocyanic acid be present, the spots of nitrate will become white in the course of a few seconds, or in from ten minutes to a quarter of an hour, according to the quantity of poison present, and the closeness of the test to the liquid. No heat need be applied to the liquid: a temperature of  $64^{\circ}$  suffices for the result, but the warmth of the hand accelerates the action. Mr. Taylor mixed *two-thirds of a grain* of anhydrous hydrocyanic acid with *eight ounces* of porter, and obtained a well-defined deposit of cyanide of silver in the watch-glass in a quarter of an hour, and by substituting in the watch-glass weak caustic potassa for nitrate of silver, and after a few minutes adding sulphate of iron and hydrochloric acid, he obtained prussian blue from *two-thirds* of a grain of anhydrous hydrocyanic acid mixed with eight ounces of porter. The process was equally successful with the stomach of a dog, after it had been thoroughly washed with water, and had been removed from the body twenty-four hours. These experiments prove the great volatility of the poison, and the diffusibility of its vapor. The silver test serves the analyst as a guide, for Mr. Taylor finds that, unless the white film is formed on the nitrate of silver, the application of the prussian blue test will also fail. Prussian blue may even be procured from the cyanide of silver; for this purpose caustic potassa is added to the film of cyanide in the watch-glass, and heat applied; the cyanide is dissolved, and brown oxide of silver precipitated; to the filtered liquid sulphate of iron is added, and after a time dilute sulphuric acid, prussian blue is immediately produced. When it is found necessary to distil the fluid, *Lassaigue* and *Christison* acidulate with sulphuric acid, and distil from a vapor bath till one-eighth part of the fluid has passed into the receiver. The tests are then applied to the distillate; if the quantity of poison is small,



nitrate of silver or potassa may be placed in the receiver to fix the acid as it passes over.


Liebig makes the following remarks on this fearful poison:—"Its rapid action on the blood is very remarkable. Comparatively large quantities of the acid in aqueous solution may be taken into the digestive apparatus without producing any very perceptibly noxious effects; while the same quantity inhaled as vapor causes immediate death. Thus a cat can bear the administration of from two to three drops of anhydrous hydrocyanic acid diluted with from four to six ounces of water, without being in the least affected by it. If two drops of the anhydrous acid be inserted into the mouth of the same animal, taking care at the same time to prevent it from breathing by stopping its mouth and nostrils, no perceptible effect is produced; but the cat dies the very instant it is permitted to breathe, and consequently as soon as the vapor of the acid gets into the lungs."

With respect to the quantity of hydrocyanic acid requisite to destroy life, the matured opinion of Mr. Taylor is, that a quantity of Scheele's acid (at five per cent.), *above twenty drops* (i. e. *one grain of anhydrous acid*), or an equivalent portion of any other acid, would commonly prove fatal. Even less than this—seven-tenths of a grain might, under favorable circumstances, destroy life. The largest dose from which an adult has been known to recover is *forty minims* at three and a quarter per cent., which is equivalent to about a grain and a third of anhydrous acid. It may be well to observe that the acid of commerce differs much in strength, according to the process by which it has been prepared, and independently of decomposition by keeping. The medicinal acid long used in this country is intended to be an imitation of that of *Vauquelin*, which contains 3·3 per cent.; but the London College of Physicians have improperly (as Dr. Christison observes) altered the strength to two per cent.: that of *Giese*, which keeps well, is of the same strength as the first; that of *Schrader* contains only one per cent.; that of *Göbel* 2·5 per cent.; that of *Ittner* ten per cent.; that of *Robiquet* fifty per cent. Of the alcoholic solutions the best known are,—that of *Schrader*, which contains about 1·5 per cent. of pure acid; that of the *Bavarian Pharmacopœia*, which contains four per cent.; that of *Duflos* nine per cent.; that of *Pfaff* ten per cent.; and that of *Keller* twenty-five per cent. The medicinal dose is from a

minim to two minims of *Scheele's acid*, and from three to five minims of the London Pharmacopœial acid gradually increased.

Every grain of anhydrous acid yields five grains of cyanide of silver. Suppose one hundred grains of a sample to have yielded forty-five grains of cyanide, it follows that the acid contains nine grains of anhydrous acid to ninety-one grains of water. To procure an acid containing two per cent. of anhydrous acid, would require the addition of nine grains of anhydrous acid to 441 grains of water: now, as the acid in question contains already ninety-one grains of water in every one hundred grains, it is evident that we need only add 350 grains of water to every one hundred grains of the acid, in order to prepare an acid of two per cent. strength,  $441 - 91 = 350$ .

With strong acids, hydrocyanic acid undergoes the same decomposition as metallic cyanides do with caustic alkalis; with the elements of water, its elements are transposed into formic acid and ammonia, thus:—



one equivalent of hydrocyanic acid and three equivalents of water produce one equivalent of formic acid and one of ammonia.

## THE POISONOUS METALS.

### 6. ARSENIC.

Of all poisons this is by far the most important, being the one which, on account of its cheapness, and the facility with which it is procured, is the most commonly resorted to, both by the suicide and the murderer. From the parliamentary return of the cases of fatal poisoning brought before the coroners of England in two years ending with 1838, it appears that no less than a hundred and eighty-five cases of poisoning by white arsenic occurred, being more than all the others put together, with the exception of opium and its compounds. This fearful disclosure has induced toxicological chemists to pay especial attention to the methods of detecting the compounds of this metal in organic mixtures; their investigations have been attended with the happiest results, and the detection of  $\frac{1}{144}$ th part of a grain of arsenious acid even in such sub-

stances as gruel, milk, and porter, can now with certainty be effected. In page 96, *et seq.*, the chemical characters of arsenious acid, and its comportment with reagents, have been described; as also most of the important processes that have been proposed for detecting it in organic mixtures. A few additional particulars may be appropriately introduced here. First, with respect to the taste of arsenious acid, we have stated that it is "without smell and almost without taste, though if kept for some time in contact with the tongue, it induces a slightly bitter taste, leaving one of sweetness;" this description certainly accords with our own experience, and is made, moreover, on the high authorities of Dr. Christison and Mr. Taylor; Professor Orfila, however, continues to describe the poison as having "a rough, not corrosive, slightly styptic taste, perceptible after a few seconds; very persistent, and attended with salivation." These sensations must, as Dr. Christison observes, be either imaginary, or else the indications of an organ peculiarly constituted, as it is certain that in general the poison makes no impression on the palate at all, and that most of the persons who have been criminally or accidentally poisoned by it, have not been aware of any taste in swallowing the poisoned food. It must, indeed, be regarded as an unfortunate circumstance that arsenious acid is so destitute of taste; had the contrary been the case, many lives would undoubtedly have been saved.

*Second.*—With respect to the solubility of arsenious acid, we have observed that a great diversity of opinion exists on the subject, and that the transparent and opaque varieties exhibit a marked difference in their degrees of solubility in water. Mr. Taylor's latest experiments on the subject gave the following results:—Hot water, cooling from  $212^{\circ}$  on the poison in powder, dissolves about the 400th part of its weight, being in the proportion of nearly a grain and a quarter of arsenious acid to a fluid ounce of water. Water boiled for an hour on the poison, and allowed to cool, holds dissolved the fortieth part of its weight, or about twelve grains to an ounce. Cold water allowed to stand for many hours on the poison, does not dissolve more than from the 1000th to the 500th part of its weight; that is, half a grain to one grain of arsenic to nearly one fluid ounce of water. The presence of organic matter in a liquid considerably impairs its solubility; thus Dr. Christison found that a cup of tea left beside the fire, at the tempe-

perature of  $200^{\circ}$ , for half an hour, upon two grains of arsenious acid, did not entirely dissolve even that small quantity. It may be well to mention that the appearance of arsenious acid, as it crystalizes out of an aqueous solution, greatly resembles that of *pounded sugar*.

*Third.*—The quantity of arsenic necessary to destroy life:—This has been variously stated. It has been alleged by some writers that *four* and even *two* grains of arsenious acid may prove fatal to a man. The smallest fatal dose on record, however, is *four and a half grains*, which destroyed a child four years old in six hours; and Dr. Christison quotes a case, on the authority of Valentini, in which *thirty* grains of the oxide in powder killed an adult in six days. There is no doubt, however, that death may be occasioned by a much smaller quantity than this; and that, though some constitutions will of course be more affected by the poison than others, so small a quantity as a grain, or even half a grain, may produce very alarming consequences. Mr. Taylor thinks that the cases on record warrant the conclusion that *three grains* are very likely to prove fatal to an adult; he refers to a case in which a gentleman took rather more than *two grains* in a glass of port wine; violent vomiting and other alarming symptoms occurred, though the effects were undoubtedly modified by the circumstances of the poison having been received on a full stomach. It is well worthy of remark, that, by certain mechanical admixtures, arsenic in moderate doses may be entirely deprived of its poisonous properties. It was shown by *Orfila* that if certain insoluble powders, such as clay, are introduced into the stomach immediately after arsenic has been swallowed, the violent effects may be greatly mitigated, if not altogether prevented; the cause of which appears to be referable to the envelopment of the arsenical powder by the inert substance, and the consequent prevention of its coming into contact with the membrane of the alimentary canal. Dr. Christison observes that the sparing solubility of arsenious acid occasions its influence to be greatly modified by the condition of the stomach as to food at the time it is swallowed. If the stomach be empty, it adheres to the villous coat, and acts with great energy; if the stomach be full at the time, the first portions that come in contact with the inner membrane may cause vomiting before it can be diffused, so that the whole or greater part is discharged. He quotes a case, on the authority of *Wibmer*,



where a man swallowed *an ounce and a half* of arsenic after a hearty meal, had merely a severe attack of vomiting with subsequent colic, and got well in four days; and another case, on the authority of *Mr. Kerr*, in which nearly *three quarters of an ounce* were retained after a meal for two hours, without causing any serious mischief.

*Fourth.—Antidotes to the Poison:—*There is but one substance which can at all be considered as a chemical antidote to arsenic; viz., the hydrated sesquioxide of iron; its precise mode of action is by no means well understood; it has already been alluded to in page 96. Dr. Christison recommends that it should be kept in readiness in every druggist's establishment, as it cannot be prepared when wanted without great loss of time. The quickest way to make it is to dissolve the common anhydrous sesquioxide in dilute sulphuric acid, aided by a gentle heat; to decompose the hot solution with an excess of strong ammonia; to filter off the fluid by means of a cloth filter, and wash the precipitate well with warm water; and then to let it drain thoroughly, squeezing out as much of the water as possible by compression. This substance was announced by Drs. *Bunsen* and *Berthold* in 1834, as an effectual remedy, even when given some time after the arsenic has been swallowed; it must be administered in large quantities, it having been ascertained by Dr. Douglas MacLagan, that, in order to remove one part of arsenic from a state of solution, twelve parts of the oxide in a moist state are required, and sixty parts if it has been previously dried; the presence of ammonia also seems necessary, in order to effect an insoluble combination with the arsenic. Mr. Alfred Taylor does not appear to place much reliance on the antidotal effects of this substance; "numerous recoveries," he says, "are said to have occurred under the use of this alleged remedy; but, so far as I have been able to ascertain in severe cases, emetics and the stomach pump were also freely used; and in the lighter cases recovery would probably have equally taken place without it. It is to the use of emetics and the stomach pump that we must chiefly rely, in treating a case of arsenical poisoning; viscid and mucilaginous liquids may also be freely exhibited, as these will serve to suspend the powder mechanically, and sheathe the coats of the stomach from its action."

*Fifth.—Tests for Arsenic:—*The following observations may be useful in addition to what has already been said on

this subject, pp. 97, *et seq.*:—When the poison is obtained in the state of arsenious acid, it may be reduced to the metallic condition by igniting it in a small glass tube with some reducing agent. Dr. Christison employs a soda flux, made by grinding crystals of carbonate of soda with one-eighth of their weight of charcoal, and then heating the mixture gradually to redness, so as to drive off all the water. Mr. Taylor recommends, as the most convenient, the residue of the tartrate or acetate of soda (incinerated in a covered platinum crucible) which consists of carbon and carbonate of soda. He prefers this to cyanide of potassium, inasmuch as it does not deliquesce, and may be kept for years without change. Two or three parts of the flux should be employed to one of arsenious acid; the tube should be of hard German glass, about three inches long, and one-eighth of an inch in diameter; the metal sublimes, and forms a ring, of an iron-gray color, on the cool part of the tube; a peculiar odor, very similar to that of garlic, is at the same time perceptible. The physical properties of the metallic crust are very characteristic, sufficiently so to enable the operator to distinguish arsenic from any other substance capable of being sublimed by a low red heat. The surface next the glass has the appearance of polished steel; it is somewhat darker in color, but of equal brilliancy; the inner surface, when examined with a lens, appears brilliantly crystalline, like the fracture of cast-iron. On applying the flame of a spirit lamp to the crust, it disappears, settling on the cooler portion of the tube, and it may be chased up and down the tube by the flame, until it is entirely reconverted into arsenious acid, which, when viewed through the lens, appears in the form of little octahedral crystals of adamantine lustre, on which triangular facets may be distinguished. Dr. Christison remarks that the characters of the arsenical crust are distinct when weighing only a 300th of a grain, and that a crust of this weight, a tenth of an inch broad and four times as long, may show characteristically all the physical peculiarities of an arsenical sublimate a hundred times larger. A few of the principal objections, if objections they can be called, that have been raised against this test must be alluded to. 1st. A deposit of charcoal may, it is said, be mistaken for arsenic; but not only is there no similarity whatever between the two deposits, that of charcoal being brown, and without the least lustre, but any doubt that might exist on the

subject may at once be removed by submitting the deposit to the action of the spirit flame. 2d. Preparations of *antimony* and *zinc*, it has been alleged, yield sublimes closely resembling the arsenical crust; but Dr. Christison and Dr. Turner have shown that no preparation of either of these metals can be reduced to a metallic state, either by charcoal or black flux, with the fullest red heat of the blowpipe. 3d. *Cadmium* is a metal which is said to form a metallic sublimate like arsenic. It is hardly within the bounds of possibility that the toxicologist should encounter any preparation of this metal, it being a rare substance, and not used in medicine in any way. It is true, however, that oxide of cadmium may be reduced and sublimed, but the sublimate is altogether different from arsenic; its lustre resembles that of tin, and it is generally surrounded with a brown margin of reproduced oxide. It evolves no odor, and, when heated, it does not volatilize, but turns brown. 4th. It has been said by Mr. Donovan that the action of the flux on glass which contains lead causes a stain similar to an arsenical crust: this objection is overruled by employing German glass, which contains no lead; but the metallic lead stain, besides differing altogether from arsenic in appearance, is easily distinguished from the latter by its comportment under heat, it is fixed; whereas the arsenical crust is volatile. Lastly, it has been said that a crust may be produced from the arsenic contained in the tube. This, however, is absolutely impossible: arsenic is undoubtedly sometimes used in glass making, and it is just possible that a trace of it may be retained in some opaque glasses or enamels; but in an extended inquiry into the subject, which was undertaken by the Parisian Academy of Medicine at the request of the French government, the poison could not be detected by any process of analysis in any of the clear glass met with in commerce, the whole having been volatilized during the manufacture.

In cases where the quantity of arsenious acid is so minute as to be scarcely ponderable, Mr. Taylor suggests that it should be dropped into a dry and warm tube, not more than an eighth or a tenth of an inch in diameter, and well-dried charcoal in the proportion of about three or four times its bulk dropped upon it. The upper part of the charcoal should be brought to a high temperature before the arsenious acid is heated. In this way distinct arsenical sublimes may, he

says, be procured, the weight of which is considerably less than the 1000th part of a grain.

With regard to the *liquid tests* for arsenic when the poison is in solution, it may be remarked that, though objections may be raised to each individually, their combined evidence cannot be otherwise than conclusive: for example, a solution of *phosphoric acid* is precipitated by ammonio-nitrate of silver, exactly like a solution of arsenic; but ammonio-sulphate of copper gives no precipitate, or one of a pale *blue* color with phosphoric acid, while the precipitate which the same reagent occasions in solutions of arsenic is of a rich green color: again, ammonio-sulphate of copper strikes a green precipitate in certain organic fluids like arsenite of copper, though no arsenic be present: but the same solutions would fail to give the characteristic rich yellow precipitate with ammonio-nitrate of silver, and the lemon yellow precipitate with sulphuretted hydrogen; Dr. Christison is, therefore, of opinion that the use of these liquid tests in the present modes of analysis for arsenic has been unjustly neglected: the method is not only extremely convenient and delicate, but by using small tubes it is easy to operate with precision on minute portions of a suspected fluid. The sulphuretted hydrogen test is one of extreme delicacy: it begins to give a yellow tinge when the liquid contains only the 4000th part of a grain of arsenious acid in ten drops of water, the arsenic therefore forming about the 40,000th part of the solution (Taylor). Dr. Christison says that it acts on arsenious acid in a hundred thousand parts of water. The proper color of the precipitate is lemon or sulphur yellow, which when vegetable or animal matter is present acquires a shade of white or brown. The evidence is not considered complete unless the sulpharsenious acid is reduced, and a metallic mirror of arsenic formed. This is best effected in the manner described page 97. In applying Marsh's process, Dr. Christison arranges a bent tube containing a little distilled water over the flame, by which he obtains a solution of arsenious acid, which he subsequently examines by the liquid reagents. A solution containing a millionth part of arsenious acid will, he says, readily part with it in the form of arseniuretted hydrogen, and the slightest trace of that gas in the hydrogen is indicated by the method he pursues. MM. Danger and Flandin, likewise, burn the gas in connection with a cooled receiver, in order to obtain a solu-



tion of arsenious acid. It has also been proposed to conduct the arseniuretted hydrogen over dried oxide of copper, instead of burning it: the gas is absorbed without the aid of heat, and is afterwards obtained by heating the oxide of copper in a tube. Mr. Taylor does not speak very favorably of Berzelius's modification of Marsh's apparatus, described page 99; its advantages are not, as he thinks, compensatory for the inconveniences attending its use. Of Reinsch's process (see p. 102),\* on the other hand, he speaks in the highest terms, considering it of all the methods of detecting arsenic the most simple, speedy, and easy of execution. Mr. Taylor employs the finest copper gauze or woven wire instead of copper foil. The surface thus presented to the arsenical liquid is very great, and after the deposit has taken place he dries it first by pressure between folds of blotting paper, and then above the flame of a lamp: he then rolls it into a small compass, and introduces it into a reduction tube, where it is slowly heated, and octahedral crystals of arsenious acid are thus obtained. In this way Mr. Taylor has detected the 144th part of a grain of arsenious acid in two fluid drachms of gruel, milk, porter, and other organic liquids in so many different experiments. It has also been thus easily separated from wine, brandy, and the liquid contents of a person poisoned by arsenic. He recommends it as a *trial* test when examining organic liquids supposed to contain the poison; for which purpose the liquid, after having been filtered through muslin, cotton, or paper, should be strongly acidulated with hydrochloric acid, and boiled with a slip of bright copper; should the brightness of the metal remain unimpaired at the expiration of half an hour, no arsenic, or only an extremely minute quantity, can be present; should, however, the copper be covered with a gray deposit, it must be dried and heated in a reduction tube, with the view of procuring from it crystals of arsenious acid. Dr. Christison, also, in speaking of Reinsch's process, says, "It is the best yet proposed for the detection of arsenic in solution." He directs the fluid to be mixed with one-tenth of its volume of hydrochloric acid, and to be heated to boiling before the copper is introduced, otherwise the metal may become tarnished, though no arsenic be present: in the

\* [This is a very delicate test, as was made manifest in several recent toxicological cases in which I assisted Prof. J. C. Booth.—C. M.]

feeblest solutions, ten or fifteen minutes elapse before arsenic is visibly deposited, and forty minutes should be allowed for complete deposition.

In all medico-legal inquiries, it is necessary to perform a preliminary experiment with distilled water, and the hydrochloric acid used, in order to be sure that the latter is perfectly free from traces of the poison. According to Dr. Christison, this process will detect at least the 250,000th part of arsenic in solution; and it removes from the fluid every particle of the poison, as none can afterwards be discovered in it, even by Marsh's method. It is not subject to any fallacy; for, though solutions of bismuth, tin, zinc, and antimony, produce a coating more or less similar to the arsenical one, still the subsequent conversion of the metallic arsenic into arsenious acid, and the examinations of a solution of the latter by liquid tests, completely puts aside these sources of error. It must be observed that the non-formation of a crust on the copper is perhaps not absolute proof of the *absence* of arsenic, since, according to Fresenius and Von Babo, all nitrates and various salts of mercury and other metals render the separation of arsenic by copper difficult, or even impossible. It is a fact of especial importance in a medico-legal point of view, that a person may have died from the effects of arsenic, and yet not a trace of the poison be found in the stomach or its contents. In such cases the solid parts of the body, the liver, and the blood, will have to be examined; and the best method of preparing the substances for the reception of the sulphuretted hydrogen test is that proposed by Fresenius and Von Babo. (See p. 104.) When, however, Reinsch's process is to be followed, the plan recommended by Dr. Christison is this:—Cut the viscus into very small pieces, and boil them in a mixture of one part of pure hydrochloric acid and ten of water for two hours, or till the whole of organic matter becomes a soft magma. The liquid is then to be strained, and the residue pressed: if the quantity of liquid be large, it may be concentrated by evaporation: the copper gauze or foil should then be introduced; should a deposit be formed after half an hour or an hour, it is treated as above directed. The assertion of M. Couerbe, and afterwards of Orfila, that arsenic sometimes exists naturally in the human body, has been proved to have been founded in error.

## 7. MERCURY.

Although this metal is not, in its metallic form, possessed of noxious properties, most of its preparations are poisonous in an eminent degree, scarcely less so, indeed, than the compounds of arsenic. The most important salt of mercury, in a toxicological point of view, is *corrosive sublimate*, which in its power is somewhat similar to arsenious acid. Like the latter, it has been known to have been received into a full stomach in large quantities, without producing fatal consequences; and, like arsenic also, it has been known to destroy life in so small a quantity as three grains. Mr. Taylor thinks that, under favorable circumstances, from three to five grains, or even less, would destroy an adult. The general characters of corrosive sublimate are as follows:—It is generally met with either in the form of a heavy white powder, or in heavy crystalline cakes. It is permanent in the air, but slowly decomposed by the light of the sun, a gray insoluble powder being formed. Its taste is strongly styptic, metallic, and acrid, so that it is impossible for the smallest quantity of it to be received into the mouth without the individual becoming aware of it; in which it differs strikingly from arsenious acid, which, as has been already observed, has scarcely any taste. It is very soluble in water, and speedily sinks in it, wherein again it differs remarkably from arsenic. According to *Thenard*, it is soluble in 20, and according to *Orfila*, in 11 parts of temperate water. From Mr. Taylor's experiments it results, that 100 parts of a cold saturated solution hold dissolved six grains of the salts. Its solution faintly reddens litmus paper. Boiling alcohol dissolves its own weight of corrosive sublimate, and retains, on cooling, a fourth part. It is very soluble in ether, which takes up a third of its weight, and is capable of abstracting it from its aqueous solution,—a property which is sometimes taken advantage of in toxicological investigations.

*Chemical Tests for Corrosive Sublimate in a Solid State.*

1. Heated on platinum foil it fuses, and is dissipated in white fumes, leaving no residue. 2. Heated in a test tube, it sublimes and condenses in a white crystalline mass. 3. When dropped into a solution of caustic potassa or soda, it becomes yellow, oxide of mercury and chloride of potassium or sodium

being formed. This reaction with potassa and soda distinguishes it at once from *calomel*, which becomes black on the addition of the fixed caustic alkalies, *suboxide of mercury* being formed. 4. Ammonia dropped on corrosive sublimate occasions no discoloration; with calomel, on the other hand, an immediate blackening takes place. 5. Dropped into a solution of hydrosulphuret of ammonia, it turns black. 6. When solution of iodide of potassium is dropped upon corrosive sublimate, a fine crimson color is produced: the same reagent brought into contact with calomel gives rise to a dirty olive green color. 7. Rubbed on a plate of polished copper with a mixture of one part of hydrochloric acid and two of water, a silvery stain is produced, which entirely vanishes on the application of heat. 8. Heated with three or four parts of calcined carbonate of soda in a small tube, similar to that employed for the reduction of arsenic, a ring of bright globules of mercury is sublimed; the tube must be quite dry. This test is conclusive, there being no other metal capable of being sublimed in globules. The residue in the tube is common salt, as may be proved by dissolving it in water, and adding to the solution nitrate of silver.

*Chemical Tests for Corrosive Sublimate in Solution.*

1. *Sulphuretted hydrogen gas* transmitted through the solution causes a dark brownish black precipitate of sulphuret of mercury, which is insoluble in nitric acid. If the solution be concentrated, the precipitate which is first formed by sulphuretted hydrogen has a white or yellowish tinge, by which it is, according to Pfaff, distinguished from all other metals that are thrown down black from their solutions, by this reagent. Hydrosulphuret of ammonia gives a similar precipitate, which, according to some chemists, passes slowly to a bright cinnabar red. The sulphuret of mercury, when dried and heated with carbonate of soda or metallic silver, readily furnishes a ring of pure metallic mercury. According to Dr. Christison, sulphuretted hydrogen detects corrosive sublimate where its proportion does not exceed a 35,000th of the solution. The test is not, however, to be considered conclusive without a reduction of the sulphuret; since several other metals give black precipitates with sulphuretted hydrogen. 2. *Solution of caustic potassa* occasions in solutions of corrosive sublimate a precipitate which is first reddish, but becomes



yellow on the addition of an excess of the alkali; when dried, it is easily reduced by being heated *alone* in a test tube. 3. *Protochloride of tin*. This reagent occasions a precipitate which is at first white, and consists of *calomel*; a part of the chlorine of the corrosive sublimate having been abstracted by the protochloride of tin, which consequently becomes bichloride.

The white color of this precipitate speedily changes to gray, and becomes finally nearly black. If the solution be very dilute the precipitate is grayish black from the first. On warming the liquid it becomes clear, and a heavy precipitate, consisting for the greater part of metallic mercury, subsides. The presence of the metal may be demonstrated by throwing the precipitate on a filter and squeezing it gently between folds of bibulous paper, by which the minute globules generally cohere into one or two large ones. Dr. Christison says that protochloride of tin will affect solutions which contain only 80,000th of the salt. It is not liable to any fallacy; being neither suspended in its action by the coexistence of any saline compounds, or by the presence of most animal or vegetable substances. 4. Iodide of potassium causes a beautiful pale scarlet precipitate, which rapidly deepens in tint: this precipitate is soluble both in iodide of potassium and also in corrosive sublimate itself; it is dissolved also by common salt, nitre, and probably also by other neutral salts; according to *Devergie*, when skilfully used, it acts where the salt forms only a 7000th of the solution. 5. On immersing a polished plate of copper in a solution of corrosive sublimate acidulated with hydrochloric acid, it soon becomes coated with the reduced metal, which may be readily obtained in globules by heating the copper (gauze) in a reduction tube. Dr. Framp-ton recommends *powdered silver* as a substitute for copper, by which more satisfactory results are obtained, and a larger quantity of mercury procured in the sublimate. 6. *The galvanic test*. On placing a drop of a strong solution of corrosive sublimate on a gold coin, and touching the latter through the solution with an iron point, the mercury will be deposited on the coin in the form of a bright silvery stain. This elegant test has been modified in a variety of ways. By the following process of *Devergie*, distinct indications are obtained where the poison does not form more than an 80,000th part of the water. A thin plate of gold, and another of tin, a few lines

broad, and two or three inches long, being closely applied to one another by silk threads at the ends, and then twisted spirally, this small galvanic pile is left for twenty-four or thirty-six hours in the solution previously acidified with hydrochloric acid; upon which the gold is found whitened, and mercury may be obtained in globules by heating the gold in a tube. For facility of application, an important condition is, that the quantity of fluid should not exceed three or four ounces, because in a larger quantity, the pile of the size stated cannot remove the whole of the mercury.

*Detection of Corrosive Sublimate in Organic Mixtures.*

From the researches of *M. Boullay* and *Professor Orfila*, it appears that various vegetable fluids, extracts, &c., possess the power of decomposing corrosive sublimate, a portion of the chlorine being gradually disengaged in the form of hydrochloric acid; the salt is consequently converted into calomel, which is deposited in a state of mixture, or combination with vegetable matter. It has been further shown by *Professor Tadei* of Florence, that *gluten* possesses the same property in a remarkable degree, and that that vegetable principle is capable of removing the poison completely from its solution, forming with it a ternary compound of *protochloride of mercury* and *gluten*. Among soluble vegetable principles *albumen*, *casein*, and *gelatin* possess similar properties; hence solution of albumen constitutes a convenient and effectual antidote against the effects of the poison. Various *insoluble* animal principles have been likewise shown to act on corrosive sublimate in the same manner as vegetable gluten, and this chemical action appears to be the source of the corrosive property of the poison. With these facts before us, it is evident that, in examining cases of poisoning by corrosive sublimate, we must not always expect to find it in a state of solution, even though it may have been received into the stomach in considerable quantities. The attention of the toxicologist must, therefore, be directed to both the liquid and the solid portions.

1. *Examination of the Liquid Portion.*—It is filtered from the solid matter, and a portion tested with protochloride of tin, or by the galvanic test. Should evidence of the poison be thus obtained, the remainder of the solution is mixed with half its volume of ether and well agitated: on allowing it to stand some time the greater part of the ether rises to the sur-

face, and may be removed by a pipette. It should then be filtered, and evaporated to dryness, or distilled; and the residue, being redissolved in water, is submitted to the proper tests. Mr. Taylor does not find this process to answer unless the poison is present in a moderately large proportion. He therefore recommends to acidulate the suspected fluid with hydrochloric acid, and to immerse in it a narrow slip of finely laminated zinc, round which a spiral slip of fine gold foil has been twisted: if at the end of five or six hours the gold still retains its bright color, no corrosive sublimate is present. Should it, on the other hand, be tarnished, it is washed, first in ether, and then in water, dried and heated in a small reduction tube to obtain a sublimate of the metal.

2. *Examination of the Insoluble Matters.*—They are boiled with distilled water, and the liquid having been filtered is tested as above described. Should no trace of the poison be thus obtained, Dr. Christison triturates the whole of the insoluble matters with protochloride of tin, and collects and washes the coagulum formed; he then boils it with a moderately strong solution of caustic potassa in a glazed porcelain vessel till all the lumps have disappeared. The animal and vegetable matters, and oxide of tin united with them are thus dissolved, and a powder of metallic mercury, generally easily discernible with a small magnifier, subsides. To separate it, the solution is allowed to remain at rest at a temperature little short of ebullition for fifteen or twenty minutes, the vessel is then filled up with hot water, and the fatty matters which float on the surface skimmed off. After two or three effusions the black powder is transferred to a smaller vessel, and finally dried, and sublimed in a small tube. By this mode of operating, Dr. Christison has detected a quarter of a grain of corrosive sublimate mixed with two ounces of beef, or with five ounces of new milk, or porter, or tea, made with a liberal allowance of cream and sugar. He has also thus detected a tenth part of a grain in four ounces of the last mixture, that is in 19,200 times its weight. Mr. Taylor directs that the coagulum obtained by triturating the organic mixture with protochloride of tin should be well boiled in strong hydrochloric acid previous to digesting it with caustic potassa, in order to separate the mercury from the oxide of tin and organic matters, and to estimate it quantitatively. In cases where the quantity of poison is small, he has found this mode of treatment to be

troublesome and not unattended with risk. In such cases, he prefers the galvanic test, by which he states that he has detected one-sixteenth part of a grain of corrosive sublimate dissolved in one ounce of organic liquid, and obtained metallic mercury from it in less than half an hour; and he does not think it possible to conceive a case where, in an analysis of this kind, the galvanic test would not be immediately applicable. In the *Comptes Rendus*, 31 Mars, 1845, MM. Danger and Flandin have described their method of extracting mercury from the *liver* of an animal poisoned by corrosive sublimate: the process is nothing more than a modification of the galvanic test, but the experiments are valuable as proving the absorption of the poison. Their process is as follows:—The animal substance finely cut up is heated to about  $212^{\circ}$ , with one-third or half its weight of strong sulphuric acid; in an hour or two the whole forms a dark carbonaceous-looking liquid. It is allowed to cool, and chloride of lime gradually added. The liquid becomes whiter and more viscid. The quantity of chloride used is about equal to the weight of the sulphuric acid: it is added until the whole appears like a white calcareous mass. The dried residue is then digested in absolute alcohol, which dissolves the mercurial compound. It is now diluted with water, and the earthy residue repeatedly washed, the liquids being afterwards mixed and concentrated. The concentrated liquid is placed in a funnel terminating at an angle of  $90^{\circ}$  in a capillary point—the galvanic plates of gold and tin being introduced into the contracted part of the funnel. In this way every drop of the liquid comes in contact with the metals, and the gold is slowly covered with mercury. They state that they have thus detected the metal in a solution containing the 100,000th part. According to Mr. Taylor, it is easy to detect corrosive sublimate in organic solids by simply boiling them with *copper gauze*\* and a few drops of hydrochloric acid.

It must be observed that *Orfila* takes an exception to the employment of tin and gold as the galvanic elements, and on these grounds:—"Some *tin*," he says, "may, after a time, be dissolved, and precipitated on the gold, and thus simulate the appearance of mercury; the whitened gold, when exposed

\* Prof. J. C. Booth detected, by means of Reinsch's test, in the stomach of an exhumed corpse which had been buried eleven months, the mercury given in the form of calomel during the sickness preceding death.



to heat, may even recover its golden color; the whitening of the gold does not, therefore, absolutely demonstrate the existence of a mercurial compound in the suspected substance; and, if the fluid metal cannot be afterwards obtained in distinct globules, the evidence must be regarded as inconclusive."

When corrosive sublimate is contained in organic substances (albumen, &c.) insoluble in water, *Rose* recommends to digest them in *ammonia* in preference to *potash*, the mercury being subsequently precipitated on copper much more readily from an ammoniacal than from a potash solution; and, in cases where ammonia fails to effect a solution, he prefers the following method of treatment to the ordinary one of digesting with nitric acid:—The dried substance mixed with about a quarter of its weight of carbonate of potassa is introduced into a capacious retort, and distilled at a heat gradually increasing to redness: the mercury rises and is condensed in the neck of the retort, where it can easily be distinguished from the brown viscid empyreumatic oil which passes over at the same time. If the organic matter contained only slight traces of mercury, the whole of the metal is found in the neck of the retort, none passing with the oil into the receiver.

### 8. COPPER.

The chemical tests for salts of copper when in a state of solution are:—1. *Ammonia*, which produces a pale blue precipitate dissolving in excess, and forming a fine blue solution. 2. *Sulphuretted hydrogen*, or *hydrosulphuret of ammonia*, which occasion a dark brownish black precipitate. 3. *Ferrocyanide of potassium*, which gives a rich claret red precipitate. 4. A slip of *polished iron*, which, when immersed in the solution, speedily becomes covered with a coating of reduced copper. And, 5. *The galvanic test*, in applying which a drop of the suspected liquid is placed on a strip of platinum or silver, and touched with a zinc wire, when metallic copper is immediately deposited on the platinum or silver plate if any salt of that metal be present in solution.

All the salts of copper are possessed of poisonous properties; the two most commonly known are the sulphate (blue vitriol), and the subacetate (verdigris). It is not often that the medical jurist is called upon to examine cases of wilful

poisoning with salts of copper, as their deep color and strong metallic taste unfit them for the purposes of the murderer.

*Detection of Copper in Organic Mixtures.*—It was long ago shown by *Orfila* that albumen, milk, tea, coffee, &c., possess the property of decomposing solutions of the salts of copper, throwing down the oxide in union with various proximate principles. He also found that red wine, bile, vomited matters, and the tissues composing the stomach, although they do not decompose the soluble copper salts, alter materially the action of reagents on them. The following method, however, is applicable to all cases. If the suspected substance be a liquid it is filtered, and, as a trial test, a clean needle is suspended in it, and allowed to remain for some hours; if, at the expiration of that time, no red coating should be deposited on it, it is certain that no detectable quantity of the poison is present. That the presence of a large quantity of organic matter does not interfere with the action of this simple test, is proved by the following experiment of Mr. Taylor. He dissolved one-third of a grain of sulphate of copper in water, and mixed the solution with four ounces of thick gruel. Ammonia produced no effect on this liquid, and ferrocyanide of potassium gave only a faint reddish brown discoloration. Two drops of diluted sulphuric acid were added, and a bright needle suspended in the liquor by a thread: in twenty-four hours the needle was covered with a distinct film of copper. The quantity of copper salt here present was less than the six-thousandth part of the solution. If, then, the needle has indicated copper, a stream of sulphuretted hydrogen is passed through the liquor, and the precipitated sulphuret of copper washed, dried, and digested with strong nitric acid, by which it is converted into a mixture of nitrate and sulphate; it is filtered off from the separated sulphur, and the blue solution submitted to the above-mentioned tests for the detection of the metal. If the substance to be examined is too viscid for filtration, Dr. Christison passes it through a muslin sieve, adds two volumes of rectified spirit when cool, and then filters. Another process may be adopted. The filtered liquid is placed in a platinum crucible, dilute sulphuric acid added, and a strip of zinc introduced, wherever the platinum is touched by the zinc metallic copper is deposited, and after having in this way coated the platinum capsule, the surplus liquid is poured off,

and the capsule well washed out; a few drops of nitric acid, with a small quantity of water, may be used to dissolve out the copper. In this way a pure solution of nitrate of copper may be obtained, and the metal, if in moderate quantity, may thus be separated from the most complex organic fluids.

But all these processes may fail to give any proofs of the existence of copper, and yet the poison may be present in a state of intimate union with some organic principles, or with the mucous membrane of the stomach, in which case it would be insoluble. The following process must then be adopted. The solid substance is cut into small pieces, and added in successive portions to an equal weight of nitric acid; the mixture is then heated in a porcelain basin, with a fifteenth of chlorate of potassa. After the whole has been added, the product is heated till it becomes dark red and thick. The charring being complete, the carbonaceous mass is pulverized, then boiled with nitric acid diluted with its own volume of water, evaporated to dryness, redissolved, and the clear filtered solution tested with reagents. It must be mentioned, however, that objections have been raised against this mode of treatment, or rather against the conclusions that might be drawn from them, on the ground that copper exists *naturally* as a constituent part of many animal and vegetable substances, and more especially in the organs of the human body. *Meissner* and *Sarzeau* have examined a great many vegetable substances, and the latter chemist states that he has succeeded in separating metallic copper from *cinchona bark*, *madder*, *coffee*, *wheat*, and *flour*. *Devergie*, *M. O. Henry*, and *Orfila* assert that they have detected traces of copper by the process of incineration, in the bodies of animals not poisoned with the preparations of that metal. *Chevreul*, on the other hand, could detect no traces of copper in beef, veal, or mutton, and more recently *MM. Danger* and *Flandin* have positively denied that copper is ever found naturally in the human body. An extensive inquiry into this subject was undertaken by *M. Boutigny*, who thinks that he has traced the presence of copper in vegetable substances to its existence in the manures used for raising the different crops, and in animal substances either to their having been preserved or prepared in copper vessels, or to the animals having been fed on vegetables which had received a cupreous impregnation from the cause above mentioned. Another chemist traced the copper

which made its appearance in his experiments to the filtering paper he was using. Mr. Taylor remarks, in reference to this subject, that in a practical view the objection amounts to nothing, since there would be very few cases in which all the chemical evidence rested on the incineration of the viscera, abundant proofs of the poison being generally afforded by an analysis of the contents of the stomach; the normal copper said to exist in food has not been found to form more than the 100,000th part of the food examined; and if the imputation of poisoning were well founded, and copper were discovered at all, the metal would be in infinitely larger proportion, so as to leave no doubt of its actual admixture.

A not unfrequent cause of accidental poisoning by salts of copper arises from the action of certain articles of food on the metal when used for culinary purposes. Pure water may be kept for any length of time in a clean copper vessel, without becoming in the least impregnated with the metal, provided the air be excluded; if, however, air has access, a hydrated carbonate, mixed with oxide of copper, is gradually formed. If the water contains common salt, or various other saline matters, it is found to exert a greater or less action on the metal, and to become impregnated with it. It appears, however, from the experiments of *Falconer* and *Eller*, that milk, tea, coffee, beer, cabbage, potatoes, and sundry other vegetables, do not exert the least action on clean copper vessels, even by long boiling; but, if the vessel is not thoroughly clean, all acid substances dissolve the carbonate that encrusts it, especially if left in it for some time. Oily and fatty matters, also, if left for some time in copper vessels, become contaminated to such an extent as to acquire a nauseous coppery taste and a distinct green color.

It was observed by *Dr. Falconer* that syrup of lemons might be boiled for fifteen minutes, in copper or brass pans, without acquiring any sensible impregnation; but if it was allowed to cool, and remain in the pans for twenty-four hours, the impregnation was discoverable by the test of metallic iron, and was perceptible to the taste. *Proust* made the same observations with regard to food prepared in copper vessels; and *Dr. Christison* quotes a fatal accident which occurred from a servant having left some sour kroust for only a couple of hours in a copper vessel which had lost the tinning. As a general rule, no articles of food which contain saline, acid, or oily



principles, should be prepared in copper vessels. Vinegar is occasionally found to contain traces of copper; and it is a well-known fact that sulphate of copper is sometimes employed for the purpose of giving a rich green color to preserved fruits and vegetable pickles; the presence of the poisonous metal is easily detected by the iron test. In many old cookery books, halfpence are directed to be put amongst the pickles, to give them a fine green color. In order to prevent accidental impregnations, copper vessels employed in cookery are coated with an alloy of tin and lead; there is no danger to be apprehended from the latter metal, for, although some of its salts are poisonous, it has been ascertained that the substances which possess the property of dissolving lead cannot attack that metal before the whole of the *tin* in the alloy is oxidated. Sulphate of copper was, some years ago, extensively employed in France by bakers, who used it to accelerate the panary fermentation; the proportion required being an ounce of the salt in two pints of water for every hundred weight of dough. Some chemists have denied that sulphate of copper possesses any such property as that imputed to it by the French bakers; but, from the experiments of *Meylink*, it appears that not only does the fermentation of the dough take place more quickly, but that the adulterated loaves, when taken out of the oven, are much whiter and much better raised than those not adulterated; he found that, if more than eight grains of the salt were added to half a Flemish pound of dough, it could be detected by a peculiar taste and a slight green color. He found, moreover, that the employment of the salt of copper, even in the small proportion of one grain, had the singular effect of bringing about the complete fermentation of the dough with considerably less loss of weight than occurs in the common process of baking; the loss in the sound and in the adulterated loaves being in the proportion of 116 to 100. These remarkable results appear to require confirmation; but, if they are correct, the object of the French bakers in employing sulphate of copper is easily explained, the practice being a fraud on the public, by enabling them to make their loaves of a standard weight with a less allowance of nutritive material. It does not appear that this practice has extended to England. A case of poisoning by copper, from the use of German silver, which contains fifty per cent. of copper, is mentioned by Mr. Taylor. It appears that a spoon made of

this material had been left in an earthenware vessel in which eels had been cooked with butter and vinegar; and chemical analysis showed that the cupreous poison had thereby been introduced.

## 9. LEAD.

The preparations of this metal, which require the particular attention of the toxicologist, are the *protoxide*, the *carbonate*, the *acetate*, and the *subacetate*.

For the chemical properties of *litharge* (protoxide of lead), see page 83. It is extensively used in the arts, and is occasionally brought under the notice of the toxicological chemist in consequence of its intentional, as well as its accidental, introduction into articles of food and drink. The vegetable acids, and alkaline and fatty substances, dissolve the protoxide of lead, forming salts of a poisonous character; and as earthenware vessels employed for culinary purposes are well known to be glazed with litharge, the accidental adulterations of food and liquids which have been prepared or allowed to remain for some time in such vessels, are not of uncommon occurrence. Pies which have been baked in a newly glazed vessel have been known to become contaminated with oxide of lead, and to have occasioned the peculiar symptoms of lead poisoning in the persons partaking of them. The presence of the deleterious metal in the food, in cases of this kind, is proved by moistening the articles with hydrosulphuret of ammonia, by which they become of a more or less brown color; and lead is detected in the glaze of the vessels by boiling in them acetic acid or caustic potash, by which the oxide becomes dissolved. Cases of poisoning by the accidental impregnation of articles of drink with oxide of lead would probably be more frequent, but for the property possessed by some vegetable substances, particularly those containing tannin or gallic acid, of forming insoluble compounds; but, as a general rule, no substances used for food should be kept in leaden vessels, neither should liquids containing free acid, or in which a vegetable acid is likely to be formed, be kept for any length of time in a newly glazed earthenware vessel. Dr. Christison relates a case in which lead colic, paralysis, and death were occasioned by eating the cream which formed on milk kept in a leaden cistern. Wines have been accidentally impregnated with oxide of lead, in consequence of the bottles having been

cleaned with shot, and some of the pellets left behind; the impregnation is not very likely to occur to any injurious extent in good wine, such as port or sherry, but in acid wines, such as currant or gooseberry, a sufficient quantity of the oxide might be dissolved to produce serious consequences. Wines have been also designedly adulterated with oxide of lead, to remove their acidity, and to give them a sweet taste; this fraud was formerly practiced to a considerable extent. It was detected and exposed in France by Fourcroy. In this country it does not appear to have been pursued to any material extent; though, before the poisonous nature of lead compounds was generally known, British wines must have been frequently adulterated, for, in an old cookery book, quoted by Sir G. Baker, the following recipe occurs:—

“*To hinder Wine from turning.*—Put a pound of melted lead in fair water into your cask, pretty warm, and stop it close.”

Cider, also, is apt to become impregnated with salts of lead, in consequence of the metal being used for various purposes in the construction of the cider house; and although the source of the contamination was long ago pointed out by Sir George Baker, so recently as 1841, a set of cases which presented the incipient symptoms of lead colic were traced by *MM. Chevalier and Ollivier* to cider having been adulterated with lead to the amount of nearly two grains and a half per quart, in consequence of a publican having kept his cider for two days in a vessel lined with lead. The poisonous salt was found to be *malate*. *New rum* is often found to contain lead, which it derives from the worm of the still; this action might probably be prevented by alloying the lead with *tin*. *Old rum*, on the contrary, never contains the poison; a circumstance which affords a good illustration of the action of *tannin* in precipitating the metal in an insoluble form, for *Dr. Traill* states that the rum intended for immediate consumption is collected at once from the still into glass bottles, while that intended to be kept is received into oak casks.

When *oxide of lead* has to be looked for in liquids containing organic substances, a little nitric acid should be added previous to filtration, in order to redissolve any insoluble compound formed by the salts of lead with albumen and other organic principles; sulphuretted hydrogen is then transmitted through the clear liquor: if a dark-colored precipitate is

formed, the whole is boiled and the precipitate collected on a filter. It is washed and dried, and then boiled with strong nitric acid, by which the sulphuret of lead is wholly or in part converted into nitrate, which, being soluble in water, is filtered, neutralized by ammonia, and submitted to the general reagents as previously directed. Should it be necessary to examine the insoluble matters, they are to be cut in small pieces and incinerated in a crucible, with four parts of black flux; any lead that may be present will be found fused into a small button at the bottom of the crucible, and may be removed from the carbonaceous matters by washing with water. If the metal is in the form of dry oxide, it is readily detected by the blowpipe on charcoal, or by mixing it with paste, spreading the mixture on a piece of card, drying and burning it, when metallic lead is immediately produced.

Poisoning by *carbonate of lead* is very common amongst white lead manufacturers and painters, the poison finds its way into the system continuously and insidiously in minute quantities, inducing the complaint known as *colica pictonum* and paralysis. Cases of this form of poisoning have not been so frequent in the manufactories of white lead since the practice has been adopted of grinding the carbonate in water. Dr. A. T. Thompson considers that the *carbonate* is the only compound of lead which possesses poisonous properties; and that, if any other salt in small doses becomes so, it is in consequence of its conversion into carbonate in the body. This opinion is not, however, adopted by Dr. Christison, or by Mr. Alfred Taylor. Carbonate of lead is known by the following properties:—1. It is blackened by sulphuretted hydrogen; 2. It is soluble with effervescence in nitric acid. If, however, as is frequently the case with the commercial carbonate, it contains sulphate of lead or sulphate of baryta, the two latter substances remain undissolved by the nitric acid. The presence of oxide of lead in the nitric acid solution is proved by the tests formerly mentioned. 3. It is decomposed when ignited on platinum foil, leaving oxide of lead of a yellow color; 4. It is reduced on charcoal by the blowpipe, metallic lead being produced.

The *acetate of lead* (*sugar of lead*) is the salt most frequently employed for criminal purposes, though there are but few cases on record of its having been so used. It is not by any means an active poison, and has been administered me-



dicinally in quantities of from thirty to forty grains daily without any serious effects. In appearance it greatly resembles loaf sugar; it has a sweet taste, succeeded by one of astringency: it is very soluble in water. An emetic of sulphate of zinc is recommended as the best antidote in cases of poisoning by it. Milk or albumen may likewise be administered in large quantities; these substances precipitating the oxide of lead in an insoluble form. The soluble alkaline sulphates, those of soda and magnesia, may also be given, but carbonates should be avoided, the carbonate of lead being poisonous. *Goulard's extract (the diacetate)*, which contains more oxide of lead than the neutral acetate, is a much more powerful poison than the latter. It cannot readily be procured in a solid or crystalline state, and its solution is distinguished from that of acetate of lead by its being precipitated by solution of *gum acacia*.

Among the most important forms of poisoning by lead is that occasioned by the action exerted by pure water on the metal. That water is liable to acquire noxious properties by traveling through lead pipes was known to the Roman architect, *Vitruvius*, who, it is believed, lived in the time of *Julius Cæsar* and *Augustus*. *Galen* also condemns the use of lead pipes on the grounds that the water transmitted through them acquires poisonous properties. The conditions under which lead becomes corroded by water were first made the subject of investigation by *Dr. Lambe*, and the inquiry was afterwards taken up by *Geyton-Morveau*; these two chemists, however, came to opposite conclusions from their researches: the former asserting that spring waters possess the greatest power of corrosion in consequence of their saline ingredients, and the latter stating that some natural waters hardly attack the metal at all, being prevented from doing so by the salts they hold in solution. *Dr. Thomson*, of Glasgow, who subsequently examined the subject, sided with *Dr. Lambe* with respect to the action of spring water on lead, but maintained that the metal was not dissolved, but merely held in suspension. In this conflicting state of the evidence on a matter of such great practical importance, *Dr. Christison* undertook an extended investigation of the whole subject of the action of different waters on lead, and some valuable observations have still more recently been made by *Colonel Yorke* and *Mr. Taylor*.

It appears that distilled water, from which all gases have been expelled by boiling, if excluded from contact with the air, has no action on lead; if, however, air, free from carbonic acid, be allowed to have access, a quantity of white matter is soon formed, which goes on increasing for some time, and finally settles as a white powder at the bottom of the vessel; this white powder consists of the hydrated oxide; but, if the surface of the water be exposed to the open air, the substance formed consists of minute brilliant pearly scales, and is a basic carbonate, composed, according to the analysis of Dr. Christison, of two equivalents of neutral carbonate and one of hydrated protoxide; a minute quantity of lead, amounting, according to Colonel Yorke's experiments, to a 10,000th part, is dissolved by the water. It results from these observations that distilled water cannot with safety be kept in leaden vessels; and it is important further to state, that the distilled waters of aromatic plants possess a power of acting on lead to an extent equal to that of water itself; hence these preparations should never be preserved in leaden vessels. All neutral salts possess, in a greater or less degree, the property of impairing the corrosive power of water; thus, according to the experiments of Dr. Christison,  $\frac{1}{10000}$ th part of sulphate of lime,  $\frac{1}{2000}$ th of muriate of soda, and  $\frac{1}{30000}$ th of phosphate of soda exert a preservative power. Mr. Taylor found that, when sulphate of lime formed not more than  $\frac{1}{5000}$ th part of the weight of the water, no carbonate of lead was formed. The preservative power depends upon the acid and not the base of the salt. In the case of sulphate of lime, sulphate of lead appears to be formed, which invests the metal, and thus protects it from the action of water; so that a water which affords a copious precipitate with a salt of baryta, which is not redissolved by free acid, is not very likely to become impregnated to any serious extent by passing through lead pipes or by standing in leaden vessels. Rain and snow water, as might be supposed, act upon lead almost as rapidly as distilled water; hence rain water collected from leaden roofs and gutters, particularly if recently erected, is unfit for cooking purposes. As most spring waters contain muriates and sulphates, their action on lead is generally inconsiderable; it is always, however, advisable to have a careful analysis of the water made before it is allowed to be conveyed through leaden pipes or preserved in leaden vessels. If the water does not

contain the requisite amount of sulphates or muriates, it must not be considered safe for domestic purposes after it has been allowed to come into contact with lead. An effectual protection has, however, lately been introduced by a patent invention for covering lead pipes both externally and internally with a thin coating of *tin*. It may, lastly, be observed, that though it may be practically safe to keep some waters in leaden cisterns, it may be unsafe to use covers of this metal, because the water which condenses on the covers must be considered as pure water, and thus white lead may be formed and introduced into the water.

#### 10. ANTIMONY.

The only preparation of this metal that is likely to occasion accidents from its incautious use is *Tartar Emetic*. The characters by which it may be known are the following:—As commonly met with in commerce, it is a white or yellowish white powder; it is soluble in fourteen parts of cold, and two of boiling water (Taylor); its taste is acrid and metallic; its solution in water decomposes by keeping; when heated in a porcelain crucible it chars, and the charred mass may be reduced by strong ignition in a hard glass tube, but no sublimate is formed; when boiled with strong hydrochloric acid and metallic copper, it is decomposed, and antimony is deposited on the copper; the aqueous solution of tartar emetic is precipitated in the form of *sub-nitrate* by dilute nitric acid, the precipitate is redissolved by excess of nitric acid and also by *tartaric acid*; it is *not* precipitated by ferrocyanide of potassium; *sulphuretted hydrogen* throws down a sulphuret of antimony of an orange yellow color; if the solution be very dilute the color may be yellow, but it is at once distinguished from sulphuret of arsenic by its solubility in strong hydrochloric acid, and subsequent precipitation by the addition of water. Tartar emetic is likewise precipitated by *hydrosulphuret of ammonia*, which is not the case with a solution of arsenic. When a solution of tartar emetic is introduced into a flask containing the materials for generating hydrogen gas, it is decomposed, a gaseous compound of antimony and hydrogen being formed; if this gas be allowed to pass along a horizontal tube of hard German glass, and the tube be heated to redness at a certain point, decomposition of the gas will take place at that spot; on both sides of which a brilliant mirror of antimony

will be deposited. For the method of distinguishing this deposit from the mirror formed by arsenic under similar circumstances, see under the tests for arsenic.

When tartar emetic has to be sought for in organic mixtures, it may be necessary to examine the solid as well as the liquid portions, in consequence of the property possessed by certain organic principles, particularly such as contain *tannin*, of forming with oxide of antimony insoluble precipitates. The subject of analysis is acidulated with hydrochloric and tartaric acids and filtered. As a trial test, a piece of paper may be dipped in the clear liquid, and then immersed in hydrosulphuret of ammonia; the production of an orange stain indicates antimony. The whole of the filtrate is now treated with sulphuretted hydrogen, and the precipitate, after being well washed, is boiled with strong hydrochloric acid, and the solution mixed with a large quantity of water; the formation of a dense white precipitate is characteristic of antimony (the oxychloride). Should no indication of antimony be obtained from the liquid portion, the solid residuum on the filter must be boiled for some time with a strong solution of tartaric acid, filtered, and treated precisely as above. It may still be necessary to examine the tissues of the body. *Orfila* proceeds thus:—The thoroughly dried viscera, &c., are boiled with concentrated nitric acid until dissolved; the mass is then evaporated to dryness and carbonized; the carbonized residue is digested with nitro-muriatic acid, by which all the antimony is converted into chloride; a portion is then examined in Marsh's apparatus for an antimonial sublimate, and another portion, after being evaporated to dryness, is moistened with hydrosulphuret of ammonia. In this way *Orfila* succeeded in obtaining proof that antimony is absorbed; he thus detected it in the liver.

It must be remembered that, as preparations of antimony are used as medicine, it is not the discovery of small quantities of the metal that can be received as a proof of the intentional poisoning, as in the case of arsenic. Mr. Taylor says that tartar emetic is by no means as poisonous as it is often described to be, and that, though in doses of from half an ounce to an ounce or less it must be regarded as an irritant poison, it has been administered in doses of forty grains in twenty-four hours to an adult without occasioning any serious mischief.



## 11. ZINC.

This metal is used in medicine in the form of sulphate. It acts as an emetic, and as such is frequently administered in cases of poisoning by other substances. When given in overdoses, it acts itself as an irritant poison, and has destroyed life; but that it may be received into the stomach in considerable quantities without producing any serious consequences, is evident from the circumstance of Dr. Babington having administered to a patient *thirty-six grains* three times a day, for several weeks, without even sickness being produced. Regarded as a poison, therefore, sulphate of zinc does not claim much notice; but it is necessary that the toxicologist should be familiar with its action with reagents, in consequence of its medicinal use, and the probability of his encountering it while searching in the contents of the stomach for more formidable poisons. For the behavior of solutions of oxides of zinc with reagents, see above. The most characteristic test is the action of sulphuretted hydrogen, by which it is precipitated *white*. In order to precipitate it effectually, the oxide should be precipitated and redissolved by ammonia, and the gas then passed into the alkaline solution. Mr. Taylor warns the analyst to beware of mistaking a *yellow* precipitate, which may be produced by sulphuretted hydrogen in solutions of oxide of zinc, for *arsenic*, an error which has been committed; zinc sometimes contains traces of *cadmium*, which metal is precipitated yellow by sulphuretted hydrogen. Sulphuret of cadmium is distinguished from sulphuret of arsenic by its insolubility in hydrosulphuret of ammonia.





To the aqueous or nitric solution add  $HCl$  in excess, and boil.

The precipitate may contain

$AgCl$ ,  $PbCl$ , and  $Hg_2Cl$ .  
Wash, dry, and divide into three portions.

| 1.                                                                                                                                 | 2.                                                                                       | 3.                                                                                                                            |
|------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------|
| Mix with $NaO$ , $CO_2$ and heat in the inner blow-pipe flame; a metallic reduction accompanied by a yellow incrustation indicates | Digest with $KO$ , $CO_2$ it becomes black, indicating $Hg_2Cl$ Confirm by the blowpipe. | Digest with $NH_3$ and super-saturate the clear ammoniacal solution with $NO_5$ . A white precipitate is produced, indicating |
| Pb                                                                                                                                 |                                                                                          | Ag                                                                                                                            |

The solution

Pass a stream of  $HS$  through the solution till it smells strong.  
Digest the precipitate with  $NH_4S$ , or with

The insoluble portion may contain  
 $Pb$ ,  $Hg$ ,  $Bi$ ,  $Cu$ , and  $Cd$ , in the form of sulphurets.  
Boil with  $NO_5$ ; a black residue remains undissolved. Wash, dry, and in a hard glass tube.

| a.                                                                                                                                     | b.                                                                                                                 | c.                                                                                                                                                                                                                           |
|----------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| It sublimes without change or decomposition. $Hg$ was present in the original solution as $HgO$<br>Confirm by blowpipe the presence of | It sublimes, leaving a white powder, which, when moistened with $NH_4S$ turns black, presence of<br>$PbO$ , $SO_3$ | It sublimes; the of $HgS$ being in globules of metallic $Hg$ was present in original solution as $H$ reaction is not, likely to occur; since $Hg$ had existed in a substance as would have been noted in the form by $HCl$ . |
| $Hg$                                                                                                                                   |                                                                                                                    |                                                                                                                                                                                                                              |

Precipitate the nitric solution of the sulphurets by  $KO$ ,  $CO_2$  and digest washed and moist precipitate with  $KCy$  in excess.

The precipitate may contain  
 $Pb$ , and  $Bi$  in the form of carbonates.

Boil with diluted  $HCl$

To one part of the solution add  $SO_3$ , a white precipitate is produced, indicating

Pb

Confirm by the blow-pipe.

The remainder of the solution is concentrated by evaporation, and then mixed with a large quantity of water, a milkiness is produced, indicating

Bi

The solution may contain  
 $Cu$  and  $Cd$ , in the form of double salts with  $KCy$ .

Pass into the solution a stream

A precipitate is formed, indicating

Cd

Confirm by the blow-pipe.

The solution may contain  
 $Cu$   
Add  
 $CuS$  is precipitated by drops of add  $NH_3$  the solution blue color



DETECTION OF BASES.—TABLE I.

solution may contain all the other bases.

Filter strongly of it; filter off the precipitate, and treat the filtrate as directed in Table II.  
or with  $KS$ , should the preliminary examination have indicated  $Cu$ .

The solution may contain

$Au$ ,  $Pt$ ,  $Sb$ ,  $As$ , and  $Sn$ , in the form of sulphurets:—

Filter from the insoluble portion; dilute with distilled water, and boil with excess of  $HO, \bar{A}$ . If a precipitate be produced, collect a portion, and wash and heat it over the flame of a spirit lamp on platinum foil; if it burn with a blue flame, and is volatilized without leaving any residue, it consists merely of  $S$ , and no further examination of it need be made; but if it leave a residue, and if the precipitate has a black or brownish-black color, all the members of the 6th group may be present.

Proceed as under:—

|  | 1.                                                                                                                                                                                                                    | 2.                                                                                                                                         | 3.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4.                                                                                                                                                                                                                                                                                                                                                                | 5.                                                                                                                                                                                 |
|--|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | To a portion of the original solution add $Sn\ Cl$ containing a little $Sn\ Cl_2$ : a purple color is produced. To another portion of the original solution add $FeO, SO_3$ a brown precipitate is formed, indicating | To a portion of the original solution concentrated by evaporation, add $NH_4\ Cl$ , a yellow crystalline precipitate is formed, indicating | Mix a portion of the black precipitate produced by $HO, \bar{A}$ , with three times its bulk of $KO, NO_5$ and $NaO, CO_2$ . Project the mixture a little at a time into a Berlin crucible, in which a mixture of $KO, NO_5$ and $NaO, CO_2$ is kept in a state of fusion over a lamp. Digest the fused mass with distilled water; filter; add excess of $NO_5$ and apply heat: then add $AgO, NO_5$ . Filter the solution when cold, and then add very dilute $NH_3$ . A brown precipitation or coloring indicates | Dissolve the remainder of the black precipitate in $HCl$ . Place in the solution a bar of metallic zinc; a pulverulent deposit takes place: remove it and digest with $NO_5$ . A white precipitate is formed; digest with a strong solution of $2\ HO, \bar{T}$ . Filter; into the clear solution pass $HS$ . An orange colored precipitate is formed, indicating | Dry the residue of 4, insoluble in $2\ HO, \bar{T}$ and ignite on charcoal in the reducing flame with $K\ Cy$ and $NaO, CO_2$ . A ductile metallic globule is produced, indicating |
|  | $Au$                                                                                                                                                                                                                  | $Pt$                                                                                                                                       | $As$                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | $Sb$                                                                                                                                                                                                                                                                                                                                                              | $Sn$                                                                                                                                                                               |
|  |                                                                                                                                                                                                                       |                                                                                                                                            | Confirm by the blow-pipe.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                    |





*Treatment of the filtrate from*

Evaporate a few drops on p

Add  $\text{NH}_4\text{Cl}$ , and  $\text{NH}_3$ , then  $\text{NH}_4\text{S}$  as lon

*The precipitate may contain*

$\text{Al}_2\text{O}_3$ ,  $\text{Cr}_2\text{O}_3$ ; also Zn, Ni, Mn, Co, and Fe, in the form of *sulphurets*.

It may likewise contain *phosphates*, *borates*, *oxalates*, and *hydrofluates* of the alkaline earths

*Digest with dilute HCl*

If it does not completely dissolve, Co or Ni, or both, are present.

*Add  $\text{NO}_5$ , boil and filter.*

Test a small portion of the filtrate with  $\text{NH}_3$ , if a precipitate is formed, *add to the whole solution  $\text{NH}_4\text{Cl}$ , and excess of  $\text{NH}_3$*

*The precipitate may contain*

$\text{Al}_2\text{O}_3$ ,  $\text{Cr}_2\text{O}_3$ ,  $\text{Fe}_2\text{O}_3$ , and the alkaline earths in the form of *phosphates*, &c.

*Digest with KO*

*The solution may contain*

$\text{Al}_2\text{O}_3$ , and  $\text{Cr}_2\text{O}_3$   
Boil for some time, a precipitate is formed, indicating

$\text{Cr}_2\text{O}_3$

Confirm by the blowpipe.  
Supersaturate the solution with HCl

Then boil with *excess of  $\text{NH}_3$*

A precipitate is formed, indicating

$\text{Al}_2\text{O}_3$

Confirm by blowpipe.

*The precipitate may contain*  
 $\text{Fe}_2\text{O}_3$ ,  $\text{Cr}_2\text{O}_3$ , and the *phosphates*, &c. of the alkaline earths:

Dissolve in as small a quantity of HCl as possible.

Filter, and add to the solution, which must be as nearly neutral as possible,

*$\text{K}_2\text{Cfy}$*

A blue precipitate is formed, indicating

$\text{Fe}_2\text{O}_3$

Wash and fuse another portion with

$\text{KO}$ ,  $\text{NO}_5$ , and  $\text{NaO}$ ,  $\text{CO}_2$  when cold, digest with

water: a yellow solution is obtained giving a *yellow* precipitate with  $\text{PbO}$ ,  $\text{A}$ , indicating

$\text{Cr}_2\text{O}_3$

(Consult C. 1 d, page 182.)  
Consult also C. 1 e, et seq., for the methods of detecting the *phosphates*, &c. of alkaline earths.

*The solution may contain*  
 $\text{ZnO}$ ,  $\text{MnO}$ ,  $\text{NiO}$ , and  $\text{CoO}$

Digest with  $\text{NH}_4\text{S}$

Wash the precipitate, dissolve it in *agua regia*, the clear solution with  $\text{KO}$

*The solution may contain*  
 $\text{ZnO}$

Treat with HS

A white precipitate is formed, indicating

Zn

Confirm by blowpipe.

*The precipitate may contain*  
 $\text{MnO}$ ,  $\text{CoO}$ , and  $\text{NiO}$

Wash and agitate with  $\text{NH}_4\text{O}$ ,  $\text{CO}_2$

The precipitate is

$\text{MnO}$ ,  $\text{CO}_2$

Confirm by the blowpipe.

The solution may contain

$\text{CoO}$ , and  $\text{NiO}$   
Evaporate to dryness, redissolve in a

$\text{HCl}$   
Again evaporate to dryness, divide the residue

Heat one portion with borax in the blowpipe flame, a blue bead is obtained, indicating

Co



# DETECTION OF BASES—(continued.) TABLE II.

to form a precipitate by HS (Table I.)

on platinum foil; a residue remains.

as a precipitate continues to form, and digest.

The solution may contain  
The alkalis and alkaline earths.

Evaporate a few drops on platinum foil: a residue remains. Test a small quantity of the solution with 2 NaO, HO, PO<sub>5</sub>, and NH<sub>3</sub>, a precipitate is formed.

Boil the whole solution with HCl till it has lost all odor of HS; filter and boil with excess of  
NH<sub>4</sub> O, CO<sub>2</sub>, mixed with NH<sub>3</sub>

The precipitate may contain  
EaO, SrO, and CaO  
Dissolve in a small quantity of  
HCl

Filter and divide into three portions.

The solution may contain  
MgO, KO, and NaO  
Add to a portion  
2 NaO, HO, PO<sub>5</sub>

| 1.                                                                                                                                                   | 2.                                                                                                                                                                                                                                                                                                                                 | 3.                                                                                                                                                                                                                 |
|------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Add a concentrated solution of<br>CaO, SO <sub>3</sub><br>an immediate precipitate is formed, indicating<br>BaO<br>Confirm by hydrofluosilicic acid. | Add hydrofluosilicic acid as long as a precipitate continues to be formed, filter, and add to the filtrate<br>KO, SO <sub>3</sub><br>A white precipitate is formed, indicating<br>SrO<br>Confirm by the crimson tinge which another portion of the HCl solution, when evaporated to dryness, communicates to the flame of alcohol. | Add NaO, SO <sub>3</sub> as long as any precipitation takes place: filter; neutralize with<br>NH <sub>3</sub><br>then add<br>NH <sub>4</sub> O, $\overline{O}$<br>A white precipitate is formed, indicating<br>CaO |

The precipitate is  
2 MgO, NH<sub>4</sub> O, PO<sub>5</sub>  
+ aq.  
indicating  
MgO

The solution may contain KO, and NaO  
Evaporate to dryness, ignite, redissolve in water, and add BaO as long as any precipitation takes place. Boil, filter, and add HO, SO<sub>3</sub> to remove the excess of BaO; again filter and evaporate to dryness; redissolve the residue in water, and divide into two portions.

| 1.                                                                                                               | 2.                                                                                            |
|------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------|
| Add PtCl <sub>2</sub> with a few drops of<br>HCl<br>A yellow crystalline precipitate is formed, indicating<br>KO | Add KO<br>SbO <sub>5</sub><br>A granular crystalline precipitate is formed, indicating<br>NaO |

NH<sub>3</sub> is detected by adding KO in excess to the original solution and boiling.





Add

 $BaCl$ *The precipitate may be* $BaO, SO_3$  $BaO, PO_5$  $BaO, BO_3$  $BaO, O,$  $BaF$ *Digest with HCl*A white residue of  $BaO, SO_3$  remains, indicating $SO_3$ To the solution filtered from the  $BaO, SO_3$ , and neutralized by  $NH_3$ , add $CaCl$ *The precipitate may be* $CaO, PO_5$  $CaO, BO_3$  $CaO, O$  $CaF$ *Digest with  $\overline{A}$* *The residue may contain* $CaO, O$  $CaF$ *Add HCl**The residue is* $CaF$ Confirm by heating a portion of the original substance in a tube with sand and  $HO, SO_3$   
 $HF$ *The solution may contain* $CaO, O$ *Add  $NH_3$* 

A white precipitate is produced indicating

 $O$ Confirm by adding  $HO, SO_3$  to the original solution and heating;  $CO$  is evolved, which burns with a blue flame.*The solution may contain* $CaO, PO_5$  $CaO, BO_3$ *Add  $NH_3$* If a precipitate is formed it is a proof of the presence of  $PO_5$ ; or of  $BO_3$ ; but if no precipitate takes place it is a proof of the absence of  $PO_5$ , but not of  $BO_3$ ; since  $CaO, BO_3$  would not precipitate if a large quantity of ammoniacal salts were present. $PO_5$  must be specially tested for in the original solution with  $NH_3, NH_4 Cl$ , and  $MgO, SO_3$ ;  $BO_3$  must be specially tested for in the original solution by the green alcohol flame.*Detection of  $NO_5$* Mix a portion of the original solution with  $HO, SO_3$ , and add a crystal of  $FeO, SO_3$ ; a brown halo is produced indicating $NO_5$ 

Confirm by boiling with

 $SO_3$  and  $Cu$   
Red fumes are evolved.*Detection of  $ClO_5$* Heat a portion of the original substance with *dilute HCl* a deep pungent yellow gas is disengaged, which explodes on the contact of flame, disengaging  $Cl$ , indicating $ClO_5$ Confirm by heating a small portion of the original substance with  $KCy$ , an explosion ensues.—(This experiment requires to be performed with care.)*Detection of  $ClO$* Treat a portion of the original substance in the solid form with  $\overline{A}$  in the cold,  $Cl$  is evolved, indicating $ClO$ *Detection of  $NO_3$* Heat a portion of the original solution gently with  $HO, SO_3$ ,  $O$  is evolved and red fumes are given off, indicating the probable presence of $NO_3$ Confirm by the reactions with *chloride of gold and nitrate of mercury.*

(See p. 147.)



DETECTION OF INORGANIC ACIDS.—TABLE III.  
*original solution.*

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |  |                                                                                                                                                                                                                                                                                                                                                             |  |                                                                                                                                                                                                                     |  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| <p>Add<br/> <math>AgO, NO_5</math><br/> <i>The precipitate may be</i><br/> <math>AgO, PO_5</math><br/> <math>AgO, BO_3</math><br/> <math>AgO, O</math><br/> <math>AgCl</math><br/> <math>AgBr</math><br/> <math>AgI</math><br/> <math>AgCy</math><br/> <math>AgCsy</math></p>                                                                                                                                                                                                                   |  | <p><i>Add <math>NO_5</math></i></p>                                                                                                                                                                                                                                                                                                                         |  | <p><i>The residue may consist of</i><br/> <math>AgCl</math><br/> <math>AgCy</math><br/> <math>AgCsy</math><br/> <math>AgI</math><br/> <math>AgB</math><br/> <i>Gently heat with excess of <math>NH_3</math></i></p> |  |
| <p><i>The solution may contain</i><br/> <math>AgCl</math><br/> <math>AgCy</math><br/> <math>AgBr</math><br/> <i>Add <math>NO_5</math></i></p>                                                                                                                                                                                                                                                                                                                                                   |  | <p><i>The residue may be</i><br/> <math>AgI</math><br/> <math>AgCsy</math></p>                                                                                                                                                                                                                                                                              |  | <p><i>Detection of I</i><br/> Test the original solution with <math>HgCl</math> and with starch paste.</p>                                                                                                          |  |
| <p><i>Precipitated</i><br/> <math>AgCl</math><br/> <math>AgCy</math><br/> <math>AgBr</math></p>                                                                                                                                                                                                                                                                                                                                                                                                 |  | <p><i>Detection of Csy</i><br/> Add to the original solution of <math>Fe_2Cl_3</math>, it is colored blood-red, indicating</p>                                                                                                                                                                                                                              |  | <p>Csy</p>                                                                                                                                                                                                          |  |
| <p><i>A</i><br/> Bromine has been found in the preliminary examination.<br/> Test the original solution for <math>HCy</math><br/> with a mixture of a proto- and a persalt of iron, excess of <math>KO</math> and <math>HCl</math><br/> A blue precipitate is formed, indicating</p>                                                                                                                                                                                                            |  | <p><i>B</i><br/> Bromine has not been found in the preliminary examination.<br/> Wash, dry, and ignite the precipitate; boil with <math>NO_5</math>.</p>                                                                                                                                                                                                    |  | <p>The solution may contain <math>AgO, NO_5</math>, occasioned by the reduction of the <math>AgCy</math><br/> <i>Add <math>HCl</math></i><br/> A white precipitate is formed, indicating</p>                        |  |
| <p><math>HCy</math><br/> <i>Detection of Bromine.</i><br/> Remove the I from the original solution by a mixture of <math>FeO, SO_3</math> and <math>CuO, SO_3</math>. Precipitate the excess of <math>FeO</math> and <math>CuO</math> by <math>KO</math>; pass a stream of Cl through the solution, and agitate with ether.<br/> Evaporate the ethereal solution to dryness and treat the residue with <math>SO_3</math> and <math>MnO_2</math>.<br/> Brown vapors are produced, indicating</p> |  | <p><math>HCy</math><br/> Confirm with the original solution by 1st. The Prussian blue test; 2d. Heat a few drops of the original solution for some time with <math>NH_4 S</math>; a film of S appears on the watch-glass; a drop of <math>Fe_2Cl_3</math> added produces a deep red color, owing to the formation of <i>Sulphocyanide of Potassium.</i></p> |  | <p>The residue is <math>AgCl</math> indicating <math>HCl</math></p>                                                                                                                                                 |  |
| <p>Br</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |  |                                                                                                                                                                                                                                                                                                                                                             |  |                                                                                                                                                                                                                     |  |





# COURSE OF ANALYSIS FOR THE DETECTION

To a neutral

|                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                          |                                                                                                                       |                                                                                                                                                                                      |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p><i>Add Ba Cl</i></p> <p><i>The precipitate may be</i></p> <p>BaO, SO<sub>3</sub><br/>BaO, PO<sub>5</sub><br/>BaO, BO<sub>3</sub><br/>BaO, <math>\overline{O}</math><br/>BaO, <math>\overline{T}</math><br/>BaO, <math>\overline{Ci}</math><br/>BaF</p> <p><i>Add HCl</i></p> | <p>To the solution filtered from BaO, SO<sub>3</sub>, and neutralized by NH<sub>3</sub></p> <p><i>Add CaCl</i></p> <p><i>The precipitate may contain</i></p> <p>CaO, BO<sub>3</sub><br/>CaO, <math>\overline{O}</math><br/>CaO, PO<sub>5</sub><br/>CaO, <math>\overline{T}</math><br/>CaF</p> <p><i>Divide it into two portions.</i></p> |                                                                                                                       | <p><i>The solution may contain</i></p> <p>CaO, <math>\overline{Ci}</math></p> <p>Boil for some time, a white precipitate is formed, indicating</p> <p><math>\overline{Ci}</math></p> |
| <p>A white precipitate is formed indicating</p> <p>SO<sub>3</sub></p>                                                                                                                                                                                                           | <p>To one part add</p> <p><math>\overline{A}</math></p>                                                                                                                                                                                                                                                                                  | <p>To the other part add</p> <p>KO</p>                                                                                |                                                                                                                                                                                      |
|                                                                                                                                                                                                                                                                                 | <p><i>The residue may be</i></p> <p>CaO, <math>\overline{O}</math><br/>CaF.</p> <p><i>Add HCl</i></p>                                                                                                                                                                                                                                    | <p><i>The solution may be</i></p> <p>CaO, BO<sub>3</sub><br/>CaO, PO<sub>5</sub></p> <p><i>Add NH<sub>3</sub></i></p> | <p><i>The residue may be</i></p> <p>CaO, BO<sub>3</sub><br/>CaO, PO<sub>5</sub><br/>CaO, <math>\overline{O}</math><br/>CaF</p>                                                       |
| <p><i>The residue is</i></p> <p>CaF indicating</p> <p>HF</p>                                                                                                                                                                                                                    | <p><i>The solution may contain</i></p> <p>CaO, <math>\overline{O}</math></p> <p><i>Add NH<sub>3</sub></i></p> <p>A white precipitate is formed, indicating</p> <p><math>\overline{O}</math></p>                                                                                                                                          | <p>See last Table.</p>                                                                                                | <p><i>The solution may contain</i></p> <p>CaO, <math>\overline{T}</math></p> <p>Boil for some time, a white precipitate is formed, indicating</p> <p><math>\overline{T}</math></p>   |
|                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                          |                                                                                                                       |                                                                                                                                                                                      |
|                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                          |                                                                                                                       |                                                                                                                                                                                      |
| <p><i>Special Test for</i></p> <p>Acid.</p> <p>Heat a portion of original substance with NO<sub>5</sub> nearly to dryness and then add NH<sub>3</sub></p> <p>A purple color is produced, indicating</p> <p><math>\overline{U}</math></p>                                        |                                                                                                                                                                                                                                                                                                                                          |                                                                                                                       |                                                                                                                                                                                      |



# DETECTION OF ORGANIC ACIDS.—TABLE IV.

a neutral solution.

| <i>Add AgO, NO<sub>5</sub></i><br><i>The precipitate may be</i>                                                                                                                                                          |                                                                   | <i>Add Fe<sub>2</sub> Cl<sub>3</sub></i>                                                                                                                                                                                                                                                     |                                                                                                                                                                                |                                                                                                                                                                                                      |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>The solution may contain</i><br>AgO, BO <sub>3</sub><br>AgO, PO <sub>5</sub><br>AgO, $\overline{O}$<br>AgO, $\overline{T}$<br>AgO, $\overline{Ci}$<br>AgBr<br>AgI<br>AgCy<br>AgCsy<br>Add NO <sub>5</sub> and digest. | <i>The residue may be</i><br>AgCl<br>AgBr<br>AgI<br>AgCy<br>AgCsy | <i>The precipitate may be</i><br>Light brown { Fe <sub>2</sub> O <sub>3</sub> , 3 $\overline{S}$<br>Fe <sub>2</sub> O <sub>3</sub> , 3 $\overline{Bz}$<br>Black { Fe <sub>2</sub> O <sub>3</sub> , $\overline{Qt}$<br>Fe <sub>2</sub> O <sub>3</sub> , $\overline{G}$<br>Add NH <sub>3</sub> |                                                                                                                                                                                | <i>The deep red color may be occasioned by HCsy</i><br>$\overline{A}$                                                                                                                                |
|                                                                                                                                                                                                                          |                                                                   | <i>The residue is Fe<sub>2</sub> O<sub>3</sub></i>                                                                                                                                                                                                                                           | <i>The solution may contain.</i><br>$\overline{S}$<br>$\overline{Bz}$<br>$\overline{Qt}$<br>$\overline{G}$<br>combined with NH <sub>3</sub><br><i>Divide into three parts.</i> | <i>Detection of HCsy</i><br>Boil the original solution with SO <sub>3</sub><br>The liquor becomes of a red brown color, and by continued boiling deposits a yellow powder, indicating<br>HCsy        |
| <i>The solution may contain</i><br>AgO, BO <sub>3</sub><br>AgO, PO <sub>5</sub><br>AgO, $\overline{O}$<br>AgO, $\overline{T}$<br>AgO, $\overline{Ci}$                                                                    | <i>The residue may be</i><br>AgCl<br>AgBr<br>AgI<br>AgCy<br>AgCsy | To one part add <i>alcohol</i> and <i>Ba Cl</i><br>A white precipitate is formed, indicating<br>$\overline{S}$                                                                                                                                                                               | To another part evaporated to a small bulk add <i>HCl</i><br>A white crystalline precipitate is formed, indicating<br>$\overline{Bz}$                                          | The third part exposed to the air changes to red, indicating<br>$\overline{G}$<br>Add dilute SO <sub>3</sub><br>A thick precipitate is formed, indicating<br>$\overline{Qt}$<br>Confirm by gelatine. |
|                                                                                                                                                                                                                          |                                                                   | See the other Table.                                                                                                                                                                                                                                                                         |                                                                                                                                                                                | <i>Detection of <math>\overline{A}</math></i><br>Heat the original solution with SO <sub>3</sub> and alcohol, acetic ether is evolved, indicating<br>$\overline{A}$                                  |

*Test for Uric acid.*  
at a distance with  
to dryness,  
then  
NH<sub>3</sub>  
A pale color  
indicating

$\overline{U}$



# PART II.

## QUANTITATIVE ANALYSIS.

---

### CHAPTER I.

ON THE QUANTITATIVE ESTIMATION OF SUBSTANCES, AND  
THEIR SEPARATION FROM EACH OTHER.

THE following Table, exhibiting the *Names, Symbols, and Chemical Equivalents*, or combining Proportions, by Weight, of all those Substances at present considered as Elementary, according to the latest Authorities, is taken from the new edition of Graham's "Elements of Chemistry."

| Names of Elements. | Symbol. | Equivalents. |                |
|--------------------|---------|--------------|----------------|
|                    |         | Oxygen=100.  |                |
|                    |         | Hydrogen=1.  | Hydrogen=12.5. |
| Aluminum . . .     | Al      | 13.69        | 171.17         |
| Antimony . . .     | Sb      | 129.03       | 1612.90        |
| Arsenic . . .      | As      | 75.          | 937.5          |
| Barium . . .       | Ba      | 68.64        | 858.01         |
| Bismuth . . .      | Bi      | 70.95        | 886.92         |
| Boron . . .        | B       | 10.9         | 136.2          |
| Bromine . . .      | Br      | 78.26        | 978.3          |
| Cadmium . . .      | Cd      | 55.74        | 696.77         |
| Calcium . . .      | Ca      | 20.          | 250.           |
| Carbon . . .       | C       | 6.           | 75.            |
| Cerium . . .       | Ce      | 46.          | 575.           |
| Chlorine . . .     | Cl      | 35.5         | 443.75         |
| Chromium . . .     | Cr      | 28.15        | 351.82         |
| Cobalt . . .       | Co      | 29.52        | 368.99         |
| Copper . . .       | Cu      | 31.66        | 395.70         |
| Didymium . . .     | .       | ...          | .....          |

| Names of Elements. | Symbol. | Equivalents. |                               |
|--------------------|---------|--------------|-------------------------------|
|                    |         | Hydrogen=1.  | Oxygen=100.<br>Hydrogen=12.5. |
| Erbiun . . .       | ...     | ...          | .....                         |
| Fluorine . . .     | F       | 18.70        | 233.80                        |
| Glucinum . . .     | Gl      | 26.6         | 331.26                        |
| Gold . . .         | Au      | 98.33        | 1229.16                       |
| Hydrogen . . .     | H       | 1.           | 12.5                          |
| Ilmenium . . .     | ...     | ...          | .....                         |
| Iodine . . .       | I       | 126.36       | 1579.50                       |
| Iridium . . .      | Ir      | 98.68        | 1233.5                        |
| Iron . . .         | Fe      | 28.          | 350.0                         |
| Lanthanum . . .    | Ln      | 48.          | 600.0                         |
| Lead . . .         | Pb      | 103.56       | 1294.50                       |
| Lithium . . .      | Li      | 6.43         | 80.37                         |
| Magnesium . . .    | Mg      | 12.67        | 158.35                        |
| Manganese . . .    | Mn      | 27.67        | 345.9                         |
| Mercury . . .      | Hg      | 100.07       | 1250.9                        |
| Molybdenum . . .   | Mo      | 47.88        | 598.52                        |
| Nickel . . .       | Ni      | 29.57        | 369.68                        |
| Niobium . . .      | ...     | ...          | .....                         |
| Nitrogen . . .     | N       | 14.          | 175.00                        |
| Norium . . .       | ...     | ...          | .....                         |
| Osmium . . .       | Os      | 99.56        | 1244.49                       |
| Oxygen . . .       | O       | 8.           | 100.00                        |
| Palladium . . .    | Pd      | 53.27        | 665.9                         |
| Pelopium . . .     | ...     | ...          | .....                         |
| Phosphorus . . .   | P       | 32.02        | 400.30                        |
| Platinum . . .     | Pt      | 98.68        | 1233.50                       |
| Potassium . . .    | K       | 39.00        | 487.5                         |
| Rhodium . . .      | R       | 52.11        | 651.39                        |
| Ruthenium . . .    | Ru      | 52.11        | 651.39                        |
| Selenium . . .     | Se      | 39.57        | 494.58                        |
| Silicium . . .     | Si      | 21.35        | 266.82                        |
| Silver . . .       | Ag      | 108.00       | 1350.00                       |
| Sodium . . .       | Na      | 22.97        | 287.17                        |
| Strontium . . .    | Sr      | 43.84        | 548.02                        |
| Sulphur . . .      | S       | 16.0         | 200.00                        |
| Tantalum . . .     | Ta      | 92.30        | 1153.72                       |
| Tellurium . . .    | Te      | 66.14        | 801.76                        |
| Terbium . . .      | ...     | ...          | .....                         |
| Thorium . . .      | Th      | 59.59        | 744.90                        |



| Names of Elements. | Symbol. | Equivalents. |                               |
|--------------------|---------|--------------|-------------------------------|
|                    |         | Hydrogen=1.  | Oxygen=100.<br>Hydrogen=12.5. |
| Tin . . .          | Sn      | 58.82        | 735.29                        |
| Titanium . . .     | Ti      | 24.29        | 303.66                        |
| Tungsten . . .     | W       | 94.64        | 1183.00                       |
| Uranium . . .      | U       | 60.00        | 750.                          |
| Vanadium . . .     | V       | 68.55        | 856.89                        |
| Yttrium . . .      | Y       | 32.2         | 402.51                        |
| Zinc . . .         | Zn      | 32.52        | 406.59                        |
| Zirconium . . .    | Zr      | 33.62        | 420.20                        |

In describing the methods to be pursued for bringing the several substances mentioned in the above table into a state fit for estimation, and separating them quantitatively from other substances, we shall follow, as nearly as possible, the same arrangements which we adopted in treating of the comportment of substances with reagents, viz., by arranging them into a series of Groups. With respect to the Bases there will be no difficulty in following out this method; in treating of the Acids, a variation may probably appear desirable.

## I. BASES.

### GROUP 1.

*The Metals of the Alkalies proper, Potassium, Sodium, Ammonium, Lithium.*

#### *Potassium.*

This metal is quantitatively determined as *sulphate, chloride, nitrate*, and as *double chloride of platinum and potassium*.

*Quantitative determination as Sulphate.*—Potassium is in general estimated in the form of this salt when no other bases are present; the solution containing it must be carefully evaporated to dryness, and the residue dried for some time before it is transferred to a platinum crucible to be ignited; this precaution is necessary to guard against a loss from decrepitation. It fuses at a strong red heat without volatilization, or decomposition. Its composition is

|                               |     |       |     |       |
|-------------------------------|-----|-------|-----|-------|
| One equivalent of KO          | ... | 47    | ... | 54.02 |
| One do. of SO <sub>3</sub>    | ... | 40    | ... | 45.98 |
|                               |     | <hr/> |     |       |
| One do. of KO,SO <sub>3</sub> |     | 87    |     | 100   |

If the solution contain excess of sulphuric acid, the *hydrated bisulphate* is obtained by evaporation: this salt must be reduced to the neutral sulphate, which is done by igniting it in a platinum crucible containing a fragment of carbonate of ammonia, and loosely shut with its cover; the excess of sulphuric acid flies off in an atmosphere of carbonate of ammonia; a gentle ignition must be continued till the salt assumes the solid state, the neutral sulphate being far less fusible than the acid sulphate.

*Quantitative estimation as Nitrate.*—When the alkali exists in a solution in the form of nitrate it may be weighed as such; it should not be fused, as it is thereby capable of being partially decomposed. It is anhydrous. Its composition is

|                               |     |       |     |       |
|-------------------------------|-----|-------|-----|-------|
| One equivalent of KO          | ... | 47    | ... | 46.54 |
| One do. of NO <sub>3</sub>    | ... | 54    | ... | 53.46 |
|                               |     | <hr/> |     |       |
| One do. of KO,NO <sub>3</sub> |     | 101   |     | 100   |

*Quantitative estimation as Chloride.*—Potassium may likewise be weighed in the form of this salt, when it exists as such in a solution, it should not be heated above feeble redness, and the crucible should be loosely covered, or a loss may be sustained. Its composition is

|                     |     |       |     |       |
|---------------------|-----|-------|-----|-------|
| One equivalent of K | ... | 39    | ... | 52.34 |
| One do. of Cl       | ... | 35.5  | ... | 47.66 |
|                     |     | <hr/> |     |       |
| One do. of KCl      |     | 74.5  |     | 100   |

*Quantitative estimation as double Chloride of Platinum and Potassium.*—For this purpose the alkali must be in the state of chloride; the solution is evaporated to a small bulk, and excess of bichloride of platinum and free hydrochloric acid added; the mixture is then evaporated to dryness on the water bath, and the crystalline residue digested with spirits of wine, which removes the excess of bichloride; it is then transferred to a weighed filter, washed with spirits of wine and dried at 212°. Its composition is

|                                  |     |        |     |       |
|----------------------------------|-----|--------|-----|-------|
| One equivalent of K              | ... | 39     | ... | 15.97 |
| One do. of Pt                    | ... | 98.68  | ... | 40.41 |
| Three do. of Cl                  | ... | 106.5  | ... | 43.62 |
|                                  |     |        |     | <hr/> |
| One do. of KCl+PtCl <sub>2</sub> |     | 244.18 |     | 100   |

If the operator be certain that no other base but potassa is present, and that it exists in the solution in the state of neutral sulphate or as chloride, it may then be determined in an indirect manner, by estimating the sulphuric acid as sulphate of baryta, or the chlorine as chloride of silver, and calculating the amount of alkali present from the quantity of sulphuric acid or of chlorine thus obtained.

### *Sodium.*

This metal is quantitatively determined as *sulphate, carbonate and chloride*.

*Quantitative estimation as Sulphate.*—The same method is followed as with sulphate of potassa. It does not decrepitate. Its composition is

|                                |     |       |     |       |
|--------------------------------|-----|-------|-----|-------|
| One equivalent of NaO          | ... | 30.97 | ... | 43.63 |
| One do. of SO <sub>3</sub>     | ... | 40.00 | ... | 56.37 |
|                                |     |       |     | <hr/> |
| One do. of NaO,SO <sub>3</sub> | ... | 70.97 | ... | 100   |

*Quantitative estimation as Chloride.*—The salt must be well dried before it is ignited, to prevent decrepitation; the crucible should be loosely covered. Its composition is

|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Na | ... | 22.97 | ... | 39.28 |
| One do. of Cl        | ... | 35.50 | ... | 60.72 |
|                      |     |       |     | <hr/> |
| One do. of NaCl      | ... | 58.47 | ... | 100.  |

*Quantitative estimation as Carbonate.*—As carbonate of soda does not attract moisture from the air so rapidly as the corresponding potassa salt, sodium may be weighed as such. It may be fused without volatilization or decomposition. Its composition is

|                                |     |       |     |       |
|--------------------------------|-----|-------|-----|-------|
| One equivalent of NaO          | ... | 30.97 | ... | 58.46 |
| One do. of CO <sub>2</sub>     | ... | 22.00 | ... | 41.54 |
|                                |     |       |     | <hr/> |
| One do. of NaO,CO <sub>2</sub> | ... | 52.97 | ... | 100   |

*Separation of Soda from Potassa.*—The only method that yields accurate results is to determine the potassa in the form of double chloride of platinum and potassium, and to estimate the soda either *directly* or *indirectly*. The following is the method of proceeding:—The mixed alkalies are converted into chlorides; in most cases this may be done by simply digesting and evaporating with hydrochloric acid; if, however, the alkalies are combined with sulphuric acid, that acid must first be precipitated by chloride of barium, and the excess of baryta removed by carbonate of ammonia mixed with a little caustic ammonia; the solution is filtered, and the filtrate is evaporated to dryness, and ignited: the residue is redissolved in hydrochloric acid, and the alkalies are thus brought to the state of chlorides.

If the alkalies are combined with *phosphoric acid*, the solution is evaporated to dryness, ignited, redissolved in water, and precipitated by neutral *nitrate of silver*, the fluid is filtered from the precipitated phosphate of silver, and the excess of nitrate of silver is removed by hydrochloric acid.

If the alkalies are in combination with *boracic acid*, the best method of separating them is by decomposing the boracic acid into gaseous fluoride of boron: for this purpose the dry compound is digested in a platinum crucible with three or four parts of pure powdered fluor spar and concentrated sulphuric acid, and the heat is continued as long as fumes continue to be evolved; the alkalies are thus converted into sulphates, which are changed into chlorides as above directed.

The mixed alkaline chlorides, being carefully weighed, are dissolved in a small quantity of water and mixed with excess of an aqueous solution of bichloride of platinum; the solution is evaporated to dryness on the water bath, and the dry mass is treated with a mixture of sulphuric ether and spirits of wine; the potassium is estimated as above described; the spirits of wine poured on the evaporated residue must acquire a yellow color; if it does not, it is a proof that sufficient bichloride of platinum has not been added, and the experiment must be repeated with a fresh portion. *Berzelius* recommends to mix the dry chlorides with  $3\frac{3}{4}$  times their weight of the crystalized double chloride of platinum and sodium, a quantity just sufficient to convert the whole mass into double chloride of platinum and potassium, supposing it to consist *entirely* of chloride of potassium; the process is conducted precisely as



before. The soda is either calculated from the difference between the quantity of chloride of potassium found and the original weight of the mixture analyzed, or in a *direct* manner as follows:—The filtrate from the double potassium salt is mixed with solution of *sal ammoniac* in excess, and strong alcohol added; all the platinum salt is thus removed, and the colorless filtrate being evaporated to dryness, the residue is gently ignited and weighed as *chloride of sodium*.

*Pagenstecher's method of estimating the amount of Soda in crude Potash.*—This is founded on the property possessed by a saturated solution of sulphate of potassa of still dissolving a large amount of sulphate of soda. A certain weight of the sample to be examined is mixed with water, and sulphuric acid added to it until the liquid has an acid reaction; it is then evaporated to dryness, and the residue ignited and weighed. The powdered saline mass is well agitated in a graduated cylinder with six times its weight of a concentrated solution of sulphate of potassa, the liquid drawn off the sediment with a syphon, and the same quantity of the solution of the sulphate of potassa again poured over the residue. After some time the residue is brought upon a weighed filter, the funnel covered during filtration, the filter, when the liquid has drained off, weighed moist, and then, after being dried at  $212^{\circ}$ , the difference is the evaporated water of the solution of sulphate of potassa, the degree of concentration of which is known. It is known, therefore, how much of the salt was dissolved in the evaporated water; this quantity is subtracted from the weight of the saline residue. If the potassa was free from soda, the weight of the sulphate of potassa now remaining must be the same as that first obtained; but if it contained soda, this has been removed as sulphate of soda, and the weight of the first saline residue has been reduced. From the loss the amount of the soda present can be calculated; if the loss =  $V$ , the amount of the soda is calculated thus:—

$$\text{As } 70.97(\text{NaO}, \text{SO}_3) : 52.97(\text{NaO}, \text{CO}_2) :: V : X$$

$X$  = the amount of carbonate of soda present in the specimen.

It should, however, be observed that when soda is used to adulterate potassa, a kind is employed that contains about 20 per cent. of sulphate of soda. Before making the weighings, it is well to take the specific gravity of the filtered solution of the sulphate of potassa; if it is the same as before it can have

removed nothing, and if it has taken up sulphate of soda its density has naturally been raised.—*Chem. Gaz.*, Jan. 1848.

*Indirect separation of Potassa from Soda.*—This method is founded on the difference which exists between the combining numbers of potassium and sodium, and is applicable to both sulphates and chlorides. It is deduced from the following considerations:—Suppose the alkalies to be in the state of sulphates, and 100 grains of the mixture to have yielded 152.8 grains of sulphate of barytes = 52.6 grains of sulphuric acid. Let the quantity of *sulphate of potassa* present be called A, and that of *sulphate of soda* B: then

$A + B = 100$ , or  $100 - B = A$ . That is the proportion of sulphate of potassa in the mixture is the weight of the mixture analyzed *minus* the proportion of sulphate of soda:—

Now one part of sulphate of potassa  
contains . . . . .4598 sulphuric acid.  
And one part of sulphate of soda  
contains . . . . .5637 do.

The 52.6 grains of sulphuric acid found in the mixture must, therefore, be  $(A \times .4598) + B \times .5637$ : that is, the number of units present of *sulphate of potassa* multiplied by the quantity of sulphuric acid in *one* unit, added to the number of units present of *sulphate of soda* multiplied by the quantity of sulphuric acid in *one* unit:—

$$(A \times .4598) + (B \times .5637) = 52.6 \text{ consequently}$$

$$A = \frac{52.6 - (B \times .5637)}{.4598};$$

but A has been shown above to be  $= 100 - B$ ; substituting this value, therefore, for A, we have

$$100 - B = \frac{52.6 - B \times .5637}{.4598}$$

$$\text{or, } 100 \times .4598 - (B \times .4598) = 52.6 - (B \times .5637)$$

$$\text{or, } 45.98 - (B \times .4598) = 52.6 - (B \times .5637)$$

and, putting the two B's on the same side of the equation, we have

$$(B \times .5637) - (B \times .4598) = 52.6 - 45.98$$

$$\text{or, } B = \frac{52.6 - 45.98}{.5637 - .4598} = \frac{6.62}{.1039} = 63.7.$$

The mixture contains, therefore, 63.7 per cent. of sulphate of soda, and 36.3 per cent. of sulphate of potassa.

Suppose the alkalies to be in the state of chlorides, and 133

grains of the mixture to have given 287 grains of chloride of silver = 71 grains of chlorine:

Then let the quantity of chloride of potassium be A

And that of chloride of sodium B

then  $A + B = 133$ ; and  $A = 133 - B$ .

Now one part of chloride of potassium

contains . . . . . 4766 chlorine.

And one part of chloride of sodium

contains . . . . . 6072 do.

Therefore, as before,

$$71 = (A \times .4766) + (B \times .6072),$$

$$\text{consequently } A = \frac{71 - (B \times .6072)}{.4766};$$

$$\text{or, } 133 - B = \frac{71 - (B \times .6072)}{.4766};$$

$$\text{or, } 133 \times .4766 - (B \times .4766) = 71 - (B \times .6072);$$

$$\text{or, } 63.38 - (B \times .4766) = 71 - (B \times .6072);$$

$$\text{and } (B \times .6072) - (B \times .4766) = 71 - 63.38;$$

$$\text{therefore } B = \frac{71 - 63.38}{.6072 - .4766} = \frac{7.62}{.1306} = 58.34.$$

The mixture is, therefore, composed of 58.34 grains of chloride of sodium, and 74.66 grains of chloride of potassium.

From the above calculations the following rule for the indirect determination of soda and potassa, when together present in a mixture, in the state of sulphates, is derived:—

From the *quantity of sulphuric acid subtract the product obtained, by multiplying the weight of the mixture into the quantity of sulphuric acid in a unit of sulphate of potassa, and divide the remainder by the difference between the quantity of sulphuric acid in a unit of sulphate of soda, and the quantity in a unit of sulphate of potassa; the quotient is the quantity of sulphate of soda in the mixture.*

*Example.*—In 100 grains of a mixture of the two sulphates, 50 grains of sulphuric acid are found.

$$\frac{50 - (100 \times .4598)}{.5637 - .4598} = \frac{50 - 45.98}{.1039} = \frac{4.02}{.1039} = 38.69 = \text{the sulphate of soda; consequently, } 100 - 38.99 = 61.31 = \text{the sulphate of potassa.}$$


The same rule applies to the determination of the alkaline chlorides, substituting chlorine for sulphuric acid; the results

are tolerably accurate, but the determinations of sulphuric acid and chlorine require to be made with the greatest care.

*Alkalimetry.*—The commercial value of the several varieties of potash and soda depends entirely on the amount of carbonated or caustic alkali which they contain; it is important, therefore, to the purchaser of these articles to be in possession of a simple and expeditious method of determining, with tolerable accuracy, the amount of available alkali in the crude salt—a complete chemical analysis of such a heterogeneous mixture requiring great skill and time. Two methods are adopted for this purpose:—The first, that of *Gay Lussac*, depends on the constant saturating power of sulphuric acid of a certain determinate strength, being founded in common with every other process involving chemical combination or decomposition on the law of definite proportions: the second, that of *Fresenius and Will*, depends on the determination of the amount of carbonic acid evolved from a given weight of the salt, during its decomposition by sulphuric acid.

1. *Modification of the method of Gay Lussac.*—*Preparation of the standard acid:* 170.1 grains of pure carbonate of soda, obtained by igniting the best bicarbonate in a platinum crucible, are dissolved in four or five ounces of hot distilled water: common oil of vitriol is diluted with ten or twelve parts of water, and when cold, the burette, Fig. 6, which is accurately divided into 100 equal parts, each division corresponding to 10 grain measures of water, is filled to 0 with the diluted acid; the solution of carbonate of soda is transferred into a small beaker, and a sufficient quantity of infusion of litmus added, to communicate to it a distinct blue color; the acid is then poured gradually from the burette into the alkaline liquor, until the blue color changes to distinct red, which it does by a very slight excess of sulphuric acid; the addition of the acid, when the point of saturation is nearly attained, must be made with great care, and the operator must be careful not to mistake the wine red color, which the liquor assumes from the evolution of carbonic acid, for the distinct red produced by a slight excess of the sulphuric acid. As this mistake may, however, be made, it is better towards the close of the operation, after the addition of every drop of acid, to moisten

Fig. 6.






a glass rod with the test liquid, and make a streak with it on blue litmus paper. As soon as an excess of sulphuric acid has been employed, the paper remains red after being dried, which is not the case if the reddening has been occasioned by carbonic acid; the test liquor being saturated, the quantity of acid which has been required to produce the effect is accurately observed: suppose it to be 90 measures, this, then, is the quantity equivalent to 170.1 grains of carbonate of soda, or 100 grains of soda. A standard acid is thus prepared, the precise strength of which is known, but as it is more convenient to have an acid 100 measures of which shall be equal to 100 grains of soda, every division of which on the burette represents, therefore, a grain of soda, the 90 measures are made up to 100 by the addition of 10 measures of water, and a stock of acid is then prepared, any vessel accurately divided into 100 equal parts serving for the purpose. When a sample of commercial soda has to be tested, 100 grains taken from different parts of the mass are carefully weighed out, dissolved in water, and filtered, if necessary, from any insoluble residue; the solution is then neutralized with the standard acid in the manner and with the precautions above described, and of course the number of measures required represents in grains the quantity of carbonate of soda in the specimen: thus, suppose 47 measures of acid are required, the sample is at once seen to contain 47 per cent. of soda = 80.38 per cent. of carbonate; the same method may be employed in analyzing carbonate of potassa, and the different variety of pearl-ashes, but as the equivalent number of potassium is higher than that of sodium, a different calculation becomes necessary, though the same test acid may be used: thus, the equivalent number of sodium is 22.97, that of soda being 30.97, and that of carbonate of soda 52.97; the equivalent number of potassium is 39, that of potassa 47, and that of carbonate of potassa 69. The same quantity, therefore, of acid that is required to neutralize 30.97 grains of soda, would neutralize 47 grains of potassa; but as these numbers bear very nearly the ratio of two to three, the calculation becomes very simple: we have only to multiply the number of divisions of the burette required to saturate 100 grains of the potash specimen by three, and divide by two, to get the per centage amount of potassa with sufficient accuracy for most practical purposes: thus, suppose 30 measures of acid are required, the

sample contains  $\frac{30 \times 3}{2} = 45$  per cent. of potassa = 66 per cent. of carbonate.

There are, however, one or two circumstances, besides the unavoidable errors of manipulation, which prevent this method from attaining a high degree of accuracy. Both the soda and pearl-ash of commerce contain a variety of impurities; soda contains *sulphate of soda, chloride of sodium, sulphuret of sodium, basic silicate of soda, hydrate of soda, hyposulphite*, and sometimes *sulphite of soda*: of these *sulphuret of sodium*, which may be detected by the odor of sulphuretted hydrogen evolved on moistening the specimen with sulphuric acid, *silicate of soda, hyposulphite* and *sulphite of soda*, (which may be detected by dissolving a portion of the specimen in sulphuric acid, colored with a few drops of chromate of potassa, the solution becomes green if either of the two latter salts is present,) all these salts interfere with the accuracy of the results. It is true that by heating the specimen with chlorate of potassa, the sulphuret of sodium, as well as the sulphite and hyposulphite of soda, becomes converted into sulphate, which is without any influence in the operation; but another source of inaccuracy is at the same time introduced, inasmuch as the hyposulphite of soda, if present, upon its conversion into sulphate, decomposes one equivalent of carbonate of soda, thus:—



The carbonate under examination becomes then underestimated, while the error arising from the presence of basic silicate of soda is without remedy. The method next to be described overcomes these difficulties, and is, moreover, after a little practice, more easy of execution.


2. *Method of Fresenius and Will.*—The alkalimetric process above described seeks its object by determining the amount of *alkali*, calculating it from the measure of acid which it requires for its neutralization. In the method now to be described the result is obtained by determining the quantity of *carbonic acid* with which the alkali was combined.

The process is conducted as follows:\* *a* and *b* are two flasks. Wide-mouth medicine bottles even may be employed.

\* A New Method of Alkalimetry, &c., by Drs. C. R. Fresenius and H. Will. Edited by J. Lloyd Bullock. 1844. Taylor and Walton.

*b* must have a capacity of from  $2\frac{1}{2}$  to 3 ounces of water: it is advisable that *a* should be somewhat smaller, say of a capacity of about  $1\frac{1}{2}$  to 2 ounces. Both flasks are closed by means of doubly perforated corks: these perforations serve for the reception of the tubes, *c*, *d*, and *e*. All these tubes are open at both ends; when operating, the end of the tube *d* is closed by means of a small piece of wax. The substance to be examined is weighed and projected into the flask *b*, into which water is then poured to the extent of one-third of its capacity. *a* is filled with common English sulphuric acid to about half its capacity. Both flasks are then corked, and the apparatus is weighed. The air in the whole apparatus is then rarefied by applying suction to the tube *e*; the consequence is, that the sulphuric acid contained in *a* ascends into the tube *c*, and thus a portion of it flows over into *b*; immediately upon its coming into contact with the carbonate contained in this flask the evolution of carbonic acid begins briskly. The peculiar construction of the apparatus compels the carbonic acid evolved to pass through the sulphuric acid contained in *a*, before it is permitted to escape through the tube *e*, this being the only aperture of the apparatus. It is obvious that this transmission through sulphuric acid will retain all the moisture with which the carbonic acid may be charged more completely than could be done in any other manner. Upon the influx of the sulphuric acid the fluid in *b* becomes heated, and expands together with the air contained in the flask: upon cooling, both acquire their original volume again, owing to which a new portion of sulphuric acid flows over into *b* as soon as the evolution of gas has ceased: the process is, however, expedited by applying suction to the tube *e* every time the evolution of gas ceases, and in this way the operation may be accomplished in a few minutes. When the carbonate is completely decomposed (which is immediately ascertained by no further evolution of gas taking place upon the influx of fresh portions of sulphuric acid into *b*), a somewhat larger quantity of the sul-

Fig. 7.



phuric acid contained in *a* is, by means of renewed suction, made to pass over into *b*: the fluid in this flask becomes hereupon heated to such an extent as to expel all the carbonic acid which it had absorbed in the course of the operation. As soon as the evolution of gas has completely ceased, the aperture of the tube *d* is opened by taking off the piece of wax and suction applied to the tube *e*, until all the carbonic acid still contained within the apparatus is replaced by air. The apparatus is then allowed to cool, wiped dry, and weighed. The loss of weight indicates, with the greatest possible exactness, the amount of carbonic acid which was contained in the test specimen. A common apothecary's balance, that will turn with one-sixth of a grain, is sufficiently delicate for weighing not only the whole apparatus, but the test specimen also; and it is not one of the least of the advantages of this method, that it enables the operator to experiment on a much larger scale than is possible in an ordinary analysis. The quantity of the sample employed is recommended by the author to be 6.29 grammes (=97 grains) of potash, and 4.84 grammes (=74.7 grains) of soda, these quantities containing in their state of purity exactly 2 grammes (=30.88 grains) of carbonic acid; consequently, every 2 centigrammes (= .3088 grains) of carbonic acid that are given off, indicate *one* per cent. of carbonate; all trouble of calculation is thus avoided. Previous to submitting the sample to analysis, it must be thoroughly dried by exposure to heat over a lamp for about five minutes in a Berlin crucible, and allowed to cool with the cover on: it must also be ascertained whether any insoluble earthy carbonates are present, which is done by dissolving the specimen in water, filtering and well washing the residue: if the sample contain sulphuret, sulphite, or hyposulphite of the alkali, a teaspoonful of *yellow chromate of potassa* is added to the solution in the flask, which decomposes both the sulphurous acid and the sulphuretted hydrogen at the moment of their liberation, all the products of the decomposition, viz: sulphate of chromium, water, and sulphur, remaining in the apparatus. The amount of caustic soda, and potassa, present in the specimen, the determination of which is of great importance, is found by comparing the quantity of carbonic acid evolved from a given weight of the alkali in its ordinary state with that evolved from a similar quantity after it has been mixed in a moist state with carbonate of ammonia, and dried



at a high temperature, by which means all the caustic alkali becomes carbonated. Should any *bicarbonates* be present, they are converted into neutral carbonates, by the application of a gentle red heat: in order to ascertain their presence the solution to be examined is mixed with solution of ehloride of calcium in excess, filtered, and ammonia added to the filtrate, a turbidity indicates the presence of bicarbonate.

The presence of free soda in the commercial article is detected by the alkaline reaction which the solution of the sample exhibits after the addition of chloride of barium in excess. Drs. Fresenius and Will apply the same method to the analysis of carbonates, the bases of which form insoluble compounds with sulphuric acid. The apparatus is, however, somewhat modified, in order to allow of the introduction of nitric acid in the place of sulphuric acid into the bottle *b*. For this purpose the tube *d* is expanded to a bulb in its upper part, and drawn out to a fine point at its lower end; it must be adjusted into the cork of *b* in such a manner as to allow of its being raised or depressed, still, however, preserving the bottle airtight. It is filled with dilute nitric acid, and a wax stopper having been inserted into its upper aperture it is introduced into the cork, so that its point just reaches the surface of the water in *b*, through which the carbonate to be analyzed is diffused. The nitric acid is prevented from escaping from the tube by the wax stopper. The whole apparatus is weighed, the tube *d* is then cautiously depressed, so that its point nearly reaches the bottom of the flask, and by removing the wax stopper the nitric acid gradually escapes into *b*, occasioning the decomposition of the carbonate, the liberated carbonic acid escaping through the tube *e*, and becoming deprived of moisture by the sulphuric acid in *a*, previous to escaping through *e*. When the decomposition is complete, the carbonic acid which has been absorbed by the water in *b* is expelled by plunging the apparatus into hot water, air having been previously drawn through the flasks by suction at the tube *e*. As soon as the whole is cool the flasks are wiped dry and weighed. The loss indicates the amount of carbonic acid. It is scarcely necessary to say that nitric acid is here employed, in consequence of its forming soluble compounds with the bases of such carbonates as may require to be analyzed in this apparatus, viz: those of lime, strontia, and baryta.

It having been stated on the authority of the American

chemists, *Messrs. Rogers*,\* that sulphuric acid is capable of absorbing a large amount of carbonic acid, and that the elegant alkalimetric method of Drs. Fresenius and Will must in consequence be involved in serious errors, the author of this Treatise made and published† some experiments on the subject; the results being of a perfectly satisfactory character, he has thought it worth while to reproduce them here.

Carbonate of soda, prepared by igniting the pure bicarbonate, was first analyzed.

*Ex. 1.*—70 grains lost 28.99 grains of carbonic acid = 41.41 per cent.

*Ex. 2.*—64.6 grains lost 26.8 grains = 41.48 per cent.

Theory requires 41.54 per cent.

Carbonate of potassa, prepared by igniting the pure bicarbonate.

*Ex. 1.*—79.24 grains lost 25.2 grains of carbonic acid = 31.81 per cent.

*Ex. 2.*—90.55 grains lost 28.84 grains = 31.84 per cent.

Theory requires 31.88 per cent.

Carbonate of strontia, analyzed by the method, with nitric acid, above described.

78.84 grains lost 22.75 grains of carbonic acid = 29.75 per cent.

Theory requires 29.8 per cent.

Some experiments were afterwards instituted, with the view of ascertaining whether there was, in fact, *any* absorption of carbonic acid by the sulphuric acid, and the result showed that if such were the case the quantity absorbed must be very trifling, and incapable of interfering in any way with the success of any experiment in which sulphuric acid is employed as a desiccating agent for carbonic acid.

### *Ammonium.*

*Ammonia* is estimated as *chloride of ammonium*, and as double *chloride of platinum and ammonium*; in the analysis of organic substances it is sometimes determined from the volume of nitrogen gas which is produced by its decomposition.

*Quantitative estimation as Chloride.*—When the alkali exists in a solution, either in an uncombined state, or as car-

\* Chemical Gazette, March 15th, 1848.

† Ibid., May 1st, 1848.

bonate, or combined with a weak volatile acid, or as chloride, it may be weighed in the form of the latter salt, for which purpose slight excess of hydrochloric acid is added to the solution, which is evaporated to dryness on the water bath, the residue being heated thereon till it ceases to lose weight; at this temperature the loss from volatilization is almost inappreciable. Its composition is

|                                   |     |      |     |       |
|-----------------------------------|-----|------|-----|-------|
| One equivalent of $\text{NH}_4$   | ... | 18.0 | ... | 33.65 |
| One do. of Cl                     | ... | 35.5 | ... | 66.35 |
| <hr/>                             |     |      |     |       |
| One do. of $\text{NH}_4\text{Cl}$ | ... | 53.5 | ... | 100   |

*Quantitative estimation as double Chloride of Platinum and Ammonium.*—Ammoniacal salts, soluble in alcohol, may be analyzed by converting the ammonium into a double salt, with bichloride of platinum; for this purpose the solution is supersaturated with hydrochloric acid, and an aqueous solution of bichloride of platinum added, the mixture is evaporated to dryness, and the residue treated precisely as the corresponding potassium salt; it is washed on a weighed filter, with alcohol, and dried at  $212^\circ$ , and its composition is

|                                                |     |        |     |       |
|------------------------------------------------|-----|--------|-----|-------|
| One equivalent of $\text{NH}_4$                | ... | 18.00  | ... | 8.06  |
| One do. of Pt                                  | ... | 98.68  | ... | 47.72 |
| Three do. of Cl                                | ... | 106.50 | ... | 44.22 |
| <hr/>                                          |     |        |     |       |
| One do. $\text{NH}_4\text{Cl} + \text{PtCl}_2$ |     | 223.18 |     | 100   |

When this double salt is heated to redness it is entirely decomposed, metallic platinum in a fine spongy form alone remaining; this operation may, therefore, be performed on it in order to control the previous determination; the ignition must be carefully effected in a thin Berlin crucible; a gentle heat being first applied, and gradually increased until the organic matter of the filter is entirely destroyed. The crucible should be covered at first, but the cover must be removed towards the close of the operation, the crucible being then placed obliquely, in order to favor the access of air; every 100 parts of platinum correspond to 8.06 of ammonium, or 7.61 of ammonia.

Ammoniacal salts, insoluble in alcohol, are analyzed by igniting them with a mixture of caustic soda and hydrate of


lime;\* the ammonia is liberated from its previous combination, and is received into and condensed in hydrochloric acid; it is subsequently estimated as double chloride of platinum and ammonium, in the manner already described. The process is conducted as follows:—The salt to be analyzed having been thoroughly dried in the water bath, is weighed, and intimately mixed with a sufficient quantity of soda-lime to fill one-half a combustion tube of hard German glass, about 14 or 16 inches long, and half an inch internal diameter; in the operation of mixing, forcible pressure must be carefully avoided, or the ammoniacal salt will undergo partial decomposition, even in the cold; the combustion tube is drawn out to a point, and bent obliquely upward at its closed end, soda lime is first introduced so as to occupy about an inch of the end of the tube; this is followed by the mixture, the remainder of the tube is filled to within an inch of the top with soda lime that has served to rinse out the mortar, and, finally, a stopper of recently ignited asbestos is inserted; the tube is now laid in a horizontal position on the table, and a few smart taps given to it, in order to open a channel above the mixture for the passage of the ammoniacal gas. The condensing apparatus, containing a small quantity of hydrochloric acid, is now attached to the tube by means of a perforated cork, the combustion tube is placed in the furnace, and the whole apparatus having been proved to be air-tight, the tube is gradually heated with red-hot charcoal, commencing at the interior portion, and proceeding gradually towards the closed end, until the tube is red-hot throughout its whole length; when the evolution of ammonia has ceased, the point of the combustion tube is quickly broken off, and air drawn through the apparatus, so as to bring the whole of the ammonia into the hydrochloric acid. The only source of error to be apprehended in conducting this operation arises from the powerful affinity subsisting between hydrochloric acid and ammonia, in consequence of which the acid is apt to rush back with violence, and enter the combustion tube, thus spoiling the whole analysis. The inventors of the method, Drs. Will and Varrentrapp, recommend mixing the substance analyzed with an

\* Prepared by slaking a weighed amount of the best caustic lime with solution of soda of such a strength that there shall be about one part of hydrated soda to two of anhydrous caustic lime; the mixture is heated to feeble redness in a Hessian crucible, pulverized, and kept in a well-closed phial.



equal amount of sugar, which gives rise to the evolution of other and more permanent gases serving to dilute the ammonia. The accident may, however, be better prevented by employing a capacious condensing apparatus, provided with an extra bulb, as seen in Fig. 8, which shows the disposition

Fig. 8.



of the whole apparatus, and using a moderate quantity of hydrochloric acid; or even better, by employing a condensing apparatus recommended by Mr. Warren de la Rue, and described in the Memoirs of the Chemical Society, with which the recession of the acid into the combustion tube is rendered almost impossible. The operation being over, the contents of the condensing apparatus are transferred to an evaporating basin, and the apparatus repeatedly rinsed out with water; bichloride of platinum in excess is then added, and the remainder of the process conducted as has been already directed.

*Separation of Ammonia from Potassa and Soda.*—When all three alkalies are present in combination with the same volatile acid, the ammoniacal salt may be expelled from a weighed portion of the mixture by careful ignition, and the amount of ammonia calculated from the loss of weight. If the mixture contain ammonia in the form of chloride or carbonate, it may likewise be expelled by heat from the salts of the other alkalies, but if the ammonia be present in combination with a non-volatile acid, or if the mixture cannot be dried at a temperature insufficient to expel ammonia, it must be determined by combustion with soda-lime, and the other alkalies must be estimated from a separate portion, having pre-

viously gently ignited it to expel all the ammonia. If no potassa be present, ammonia may be separated from soda by bichloride of platinum.

### *Lithium.*

This metal is generally estimated in the form of *phosphate of soda and lithia*, the composition of which is

|                             |     |        |       |       |
|-----------------------------|-----|--------|-------|-------|
| Two equivalents of NaO      | ... | 61.94  | ...   | 16.34 |
| Two do. of LiO              | ... | 28.86  | ...   | 7.61  |
| Four do. of PO <sub>5</sub> | ... | 288.08 | ...   | 76.05 |
|                             |     | <hr/>  | <hr/> |       |
|                             |     | 378.88 |       | 100   |

According to *Rammelsberg*, however, the double phosphate of soda and lithia is a salt of very variable composition, and perfectly useless for quantitative purposes. If there be no other base present, lithia may be estimated as sulphate, the composition of which is

|                            |     |       |       |      |
|----------------------------|-----|-------|-------|------|
| One equivalent of LiO      | ... | 14.43 | ...   | 26.5 |
| One do. of SO <sub>3</sub> | ... | 40.00 | ...   | 73.5 |
|                            |     | <hr/> | <hr/> |      |
|                            |     | 54.43 |       | 100  |

*Separation of Lithia from Potassa and Soda.*—From an accurately weighed quantity of the mixture, the potassa is precipitated as chloride of platinum and potassium; the excess of platinum is removed from the filtered solution by sulphuretted hydrogen, or by evaporating to dryness and igniting the residue. According to *Rose*, the lithia is then precipitated as phosphate of soda and lithia, and the amount of soda is calculated from the loss sustained by the whole. *Rammelsberg*, however, considering the double phosphate of soda and lithia as unworthy of confidence in a quantitative determination, recommends to convert the soda and lithia into chlorides, and to digest them with a mixture of anhydrous alcohol and ether, equal parts of each, in which chloride of lithium is easily soluble, while a mere trace only of chloride of sodium is dissolved. An accurate method of quantitatively determining lithia in the presence of the other alkalies is, however, yet a desideratum.

## GROUP 2.

*The Metals of the Alkaline Earths:—Barium, Strontium, Calcium, and Magnesium.*

*Barium.*

*Oxide of barium* or *baryta* is weighed as *carbonate* and *sulphate*, most frequently as the latter, which is completely insoluble in water, and in all diluted acids.

*Quantitative estimation as Sulphate.*—To the solution containing the earth, heated to  $212^{\circ}$ , dilute sulphuric acid is added as long as precipitation is occasioned; the fluid is well agitated, poured into a beaker or a Phillips' precipitating jar, and allowed to stand till it is settled, and the supernatant fluid become quite clear: it is then transferred to a filter, the amount of ash yielded by which is known, and washed with hot distilled water until the wash water\* no longer produces any precipitate with chloride of barium; it is then dried and ignited, the heat being continued until the organic matter of the filter is completely destroyed, and the contents of the crucible perfectly white; when quite cold, it is weighed. Its composition is

|                                |     |        |     |       |
|--------------------------------|-----|--------|-----|-------|
| One equivalent of BaO          | ... | 76.64  | ... | 65.7  |
| One do. of SO <sub>3</sub>     | ... | 40.00  | ... | 34.3  |
|                                |     | <hr/>  |     | <hr/> |
| One do. of BaO,SO <sub>3</sub> | ... | 116.64 |     | 100   |

*Quantitative determination as Carbonate.*—In certain cases the precipitation of baryta by sulphuric acid is inadmissible; it is then thrown down in the form of carbonate by carbonate of ammonia, mixed with a little caustic ammonia; the precipitate is allowed to settle in a warm place, and it is washed on the filter with water, rendered slightly alkaline by ammonia. It may be heated to redness, without losing carbonic acid.

\* The addition of strong alcohol to the washed precipitate prevents a passage of any particles through the filter. The after use of water for washing does not then give a turbid filtrate.

Its composition is

|                            |     |       |     |       |
|----------------------------|-----|-------|-----|-------|
| One equivalent of BaO      | ... | 76.64 | ... | 77.69 |
| One do. of CO <sub>2</sub> | ... | 22.00 | ... | 22.31 |
|                            |     | <hr/> |     | <hr/> |
|                            |     | 98.64 |     | 100   |

Baryta is estimated as *carbonate* when it exists in combination with an organic acid: the salt is carefully ignited in a platinum crucible, first covered, and afterwards, with free access of air, the heat is continued till the residue is perfectly white; it is then allowed to cool, moistened with carbonate of ammonia, and again gently ignited.

*Separation of Baryta from the Alkalies.*—The compound is dissolved in water or in hydrochloric acid, if necessary; and the baryta precipitated as *sulphate*, the alkalies being in this case obtained also in the state of sulphates by evaporating the filtered solution; or as *carbonate*, in which case the alkalies may be obtained as chlorides, which is the most convenient form if they have subsequently to be separated from each other.

#### *Strontium.*

*Oxide of Strontium.*—*Strontia* is also weighed as *sulphate* and as *carbonate*; it is precipitated in the form of both salts precisely as baryta; but, as sulphate of strontia is not altogether insoluble in water, spirits of wine are added to the fluid, to diminish its solubility: when this is inadmissible, it is better to precipitate the earth as carbonate, washing the salt on the filter with water containing ammonia and carbonate of ammonia.

The composition of sulphate of strontia is

|                                |     |       |     |       |
|--------------------------------|-----|-------|-----|-------|
| One equivalent of SrO          | ... | 51.84 | ... | 56.44 |
| One do. of SO <sub>3</sub>     | ... | 40.00 | ... | 43.56 |
|                                |     | <hr/> |     | <hr/> |
| One do. of SrO,SO <sub>3</sub> | ... | 91.84 |     | 100   |

The composition of carbonate of strontia is

|                            |     |       |     |       |
|----------------------------|-----|-------|-----|-------|
| One equivalent of SrO      | ... | 51.84 | ... | 70.20 |
| One do. of CO <sub>2</sub> | ... | 22.00 | ... | 29.80 |
|                            |     | <hr/> |     | <hr/> |
|                            |     | 73.84 |     | 100   |



*Separation of Strontia from Baryta.*—The hydrochloric solution of the earths is mixed with excess of hydrofluosilicic acid, and allowed to remain at rest for some hours: the crystalline precipitate of silico-fluoride of barium is collected on a weighed filter, washed and dried at  $212^{\circ}$ : the strontia in the filtrate is estimated either as sulphate or as carbonate.

The composition of silico-fluoride of barium is

|                                        |        |       |                  |
|----------------------------------------|--------|-------|------------------|
| One equivalent of Ba                   | ...    | 68.64 | 46.98=52.45 BaO; |
| One do. of Si                          | ...    | 21.35 | 14.60            |
| Three do. of Fl                        | ...    | 56.10 | 38.42            |
| <hr/>                                  |        |       |                  |
| One do. of (BaFl, SiFl <sub>2</sub> )* | 146.09 | 100   |                  |

*Separation of Strontia from the Alkalies.*—This is effected in the same manner as the separation of baryta.

### Calcium.

*Oxide of Calcium, or Lime,* is estimated as *sulphate* and as *carbonate*. As sulphate of lime is soluble to a considerable extent in water, it is necessary to add to the solution about to be precipitated by sulphuric acid twice its volume of alcohol, and to wash the sulphate of lime on the filter with spirits of wine: it is ignited previous to weighing.

The composition of sulphate of lime is

|                                 |     |    |     |       |
|---------------------------------|-----|----|-----|-------|
| One equivalent of CaO           | ... | 28 | ... | 41.17 |
| One do. of SO <sub>3</sub>      | ... | 40 | ... | 58.83 |
| <hr/>                           |     |    |     |       |
| One do. of CaO, SO <sub>3</sub> | ... | 68 | ... | 100   |

*Quantitative determination as Carbonate.*—If the lime salt be soluble in water, and if the solution be perfectly neutral, oxalate of ammonia is added as long as a precipitate is produced; the oxalate of lime is allowed to settle completely, which usually requires some hours; the vessel (a beaker, or a Phillips' precipitating jar) being covered, and placed in a warm situation, it is then filtered, and the salt, having been thoroughly washed with hot water, is dried and exposed to a dull red heat for about twenty minutes; the oxalate of lime is by this means converted into carbonate; but, as it is possible that it may have lost carbonic acid during ignition, it is safer,

\* According to *Lerzelius* the formula of silico-fluoride of barium is (3BaFl, 2SiFl<sub>3</sub>).

before weighing, to moisten it with a few drops of solution of carbonate of ammonia, to evaporate to dryness on the water bath, and again expose it to a very gentle ignition.

The composition of carbonate of lime is

|                   |     |     |                      |     |     |
|-------------------|-----|-----|----------------------|-----|-----|
| One equivalent of | CaO | ... | 28                   | ... | 56  |
| One               | do. | of  | CO <sub>2</sub>      | ... | 44  |
| <hr/>             |     |     |                      |     |     |
| One               | do. | of  | CaO, CO <sub>2</sub> | 50  | 100 |

If, however, the lime salt can only be held in solution by a free mineral acid, or if it will not bear the addition of excess of ammonia without a precipitation taking place, as is the case with *phosphate of lime* for example, the lime is best estimated as sulphate, because, oxalate of lime being soluble in mineral acids, it would be impossible to precipitate it from a solution containing free nitric or hydrochloric acid; oxalate of lime is, however, insoluble, or nearly so in *acetic acid*, and likewise in *oxalic acid*. According to *Fresenius*, very accurate results may, therefore, be obtained by adding to the hydrochloric solution of the lime salt sufficient ammonia to occasion a slight precipitate, then a drop or two of hydrochloric acid to redissolve this precipitate, then oxalate of ammonia in excess, and finally, *acetate of potassa*, a portion of which becomes decomposed by the free hydrochloric acid, liberating a corresponding quantity of *acetic* or *oxalic* acid, in which, as before observed, oxalate of lime is almost entirely insoluble.

*Separation of Lime from Baryta.*—This is best effected by adding to the acid solution of the two earths very diluted sulphuric acid, as long as precipitation occurs; if the sulphuric acid be sufficiently diluted, no lime will be precipitated.

*Separation of Lime from Strontia.*—This is effected with some difficulty; the only good method is that recommended by *Stromeyer*, which is based on the complete solubility of nitrate of lime in absolute alcohol, and the insolubility of nitrate of strontia in the same menstruum. The two earths are converted into nitrates, excess of nitric acid being carefully avoided, the solution is evaporated to dryness in a flask that can be closed, and the residue digested for several hours with absolute alcohol: being frequently shaken, the mixture is then filtered, and the undissolved residue washed with alcohol; both earths are then estimated as sulphate.

*Separation of Lime from Baryta and Strontia.*—When all three earths are together in a solution, the baryta is first precipitated by hydrofluosilicic acid, the lime and the strontia are obtained from the solution filtered from the silico-fluoride of barium in the form of sulphates, by the addition of sulphuric acid and evaporation to dryness—the mixed sulphates are fused in a platinum crucible with three times their weight of mixed carbonates of potassa and soda: the fused mass is extracted with water, and the earths are thus obtained in the state of carbonates. They are next converted into nitrates, and separated by alcohol, as above directed.

*Separation of Lime from the Alkalies.*—The process for effecting this is very simple: the lime is separated by oxalate of ammonia with the usual precautions; the filtered solution is evaporated to dryness, and ignited to expel the ammoniacal salts; the residue is dissolved in water, and the alkalies determined according to the method already described.

### *Magnesium.*

*Oxide of magnesium* or *magnesia* is weighed as *sulphate*, or *pyrophosphate*, and sometimes as pure *magnesia*.

*Quantitative estimation as Sulphate.*—The earth is determined in the form of this salt when no other fixed constituent is present; the solution containing it is mixed with excess of sulphuric acid, evaporated to dryness, and ignited in a platinum crucible; the residue is again treated with dilute sulphuric acid, evaporated to dryness, and again gently ignited; the residue is pure anhydrous sulphate of magnesia, the composition of which is

|                               |     |       |     |       |
|-------------------------------|-----|-------|-----|-------|
| One equivalent of MgO         | ... | 20.67 | ... | 34.07 |
| One do. of SO <sub>3</sub>    | ... | 40.00 | ... | 65.93 |
| <hr/>                         |     |       |     |       |
| One do. of MgOSO <sub>3</sub> | ... | 60.67 | ... | 100   |

*Quantitative estimation as Pyrophosphate.*—Muriate of ammonia is added to the solution, then ammonia in excess; should a precipitate hereupon occur, a fresh quantity of muriate of ammonia is added, by which the precipitate is redissolved; solution of phosphate of soda is then dropped into the mixture as long as precipitation takes place. The whole is well agitated, and allowed to repose for several hours; the precipitate is collected on a filter, the amount of ash furnished

by which is known, and washed with water containing about one-eighth of ammonia, in which the *basic phosphate of magnesia* and *ammonia* ( $\text{PO}_5\text{MgO}, \text{NH}_4, \text{O} + 24 \text{ aq.}$ ) is scarcely sensibly soluble; the washed salt is dried and carefully ignited, together with the filter; the latter requires considerable time for incineration, which is best effected by cutting in strips and burning it on the lid of the crucible. The composition of the ignited salt is

|                                       |     |        |     |       |
|---------------------------------------|-----|--------|-----|-------|
| Two equivalents of $\text{MgO}$       | ... | 41.34  | ... | 36.46 |
| One do. of $\text{PO}_5$              | ... | 72.02  | ... | 63.54 |
| <hr/>                                 |     |        |     |       |
| One do. of $2\text{MgO}, \text{PO}_5$ |     | 113.36 |     | 100   |

*Separation of Magnesia from Baryta and Strontia.*—The two latter earths are precipitated by carbonate of ammonia, a sufficient quantity of sal ammoniac having previously been added to the solution to prevent the precipitation of the magnesia: the precipitated carbonates of baryta and strontia are dissolved in hydrochloric acid, and the baryta separated from the strontia by hydrofluosilicic acid, the magnesia is determined in the filtrate as pyrophosphate; if no strontia be present, the baryta may be precipitated as sulphate.

*Separation of Magnesia from Lime.*—There are several methods of effecting this. 1st. By *oxalate of ammonia*. Sal ammoniac is added to the solution of the two earths, then slight excess of ammonia; the lime is then precipitated by oxalate of ammonia, with the proper precautions, and the magnesia in the filtrate determined as pyrophosphate. 2d. By *sulphate of lime*. For this purpose the two earths must be in the state of sulphates; the mixture, having been ignited, is digested with a saturated solution of sulphate of lime, and the insoluble residue washed on a filter with the same salt; the whole of the sulphate of magnesia is thus removed, the sulphate of lime being quite insoluble in a saturated solution of sulphate of lime remaining on the filter: it is heated to redness and weighed; and from the difference in weight, before and after the operation, the amount of sulphate of magnesia is calculated. 3d. By *chlorate of potassa*. The hydrochloric solution of the two earths is evaporated to dryness, and ignited in a platinum crucible: chlorate of potassa is then added in small quantities at a time, until the evolution of chlorine ceases. The mass on cooling is extracted with water,



which dissolves the chloride of calcium, and leaves a residuum of pure magnesia, the chloride of magnesium having, under the influence of heat, aided by the chlorate of potassa, been completely decomposed: the lime is determined in the aqueous solution by oxalate of ammonia.

*Separation of Magnesia from the Alkalies.*—The best method is the following, recommended by *Berzelius*:—The bases are brought to the state of chlorides, to a concentrated solution of which finely powdered and perfectly pure red oxide of mercury is added in excess, mutual decomposition of the chloride of magnesium and of the oxide of mercury takes place, *chloride of mercury* being formed, which combines with the alkaline chlorides, forming a soluble double salt; and *magnesia*, which remains undissolved, on extracting the evaporated and ignited mass with water. The solution, filtered from the magnesia, is evaporated to dryness, and heated, to expel the chloride of mercury: the alkaline chlorides alone remain, which are separated from each other as directed (page 238); the *magnesia* may be contaminated with undecomposed oxide of mercury, from which, however, it is readily freed by heat. This method is well adapted for the analysis of *mineral waters, soils, &c.* The following method, proposed by *Liebig*, also gives accurate results; baryta water is added to the hydrochloric solution to alkaline reaction, magnesia is thereby precipitated, *baryta* being a stronger base than *magnesia*, in consequence of which, it deprives it of its electro-negative element; to the solution, filtered from the precipitated magnesia, carbonate of ammonia, mixed with caustic ammonia, is added, the excess of baryta is thereby removed, and is filtered off; the alkalies are contained in the filtrate in the form of chlorides, and are separated from each other in the usual manner.

### GROUP 3.

*Aluminum, Glucinum, Yttrium, Thorium, Zirconium.  
Chromium.*

*Aluminum.*

*Alumina* is precipitated from its solutions by ammonia, or carbonate of ammonia, sal ammoniac having been previously

added and heat applied. The precipitate, which is very bulky, requires long-continued washing with hot water, its ignition must be carefully performed in order to avoid loss by spiriting. It shrinks very much in drying. Its composition is

|                                    |     |       |     |       |
|------------------------------------|-----|-------|-----|-------|
| Two equivalents of Al              | ... | 27.38 | ... | 53.29 |
| Three do. of O                     | ... | 24.00 | ... | 46.71 |
| <hr/>                              |     |       |     |       |
| One do. of $\text{Al}_2\text{O}_3$ | ... | 51.38 |     | 100   |

It is never weighed in any other form than as pure alumina.

*Separation of Alumina from the Alkaline Earths and Alkalies.*—To the hydrochloric solution of the mixture muriate of ammonia is added, then ammonia quite free from carbonic acid; the alumina is precipitated, carrying with it a little magnesia; it must be separated by filtration as rapidly as possible, the funnel being covered with a glass plate to prevent the access of carbonic acid, which would determine the precipitation of the earthy carbonates: the precipitate on the filter is well washed with hot water, it is then, while still moist, dissolved in hydrochloric acid, and boiled with excess of pure potassa; the small quantity of magnesia remains undissolved, and, having been separated from the alkaline ley by filtration, it is well washed, dissolved in a small quantity of hydrochloric acid, and added to the solution containing the alkaline earths and the rest of the magnesia. The potassa ley contains the whole of the alumina, which is precipitated by adding excess of hydrochloric acid, and, finally, supersaturating with ammonia: the alkaline earths and alkalies are separated from each other in the manner directed in the last section. The success of this process depends on the freedom of the ammonia from carbonic acid, and on the rapid filtering and careful washing of the precipitated alumina. If alumina has to be separated from baryta only, the latter earth may effectually be removed by sulphuric acid.

*Separation of Alumina from Lime only.*—The alumina is precipitated by ammonia free from carbonic acid, with the precautions just prescribed; and the lime in the filtrate is precipitated by oxalate of ammonia.

*Separation of Alumina from Magnesia alone.*—This may be effected by either of the following methods:—If the quantity of magnesia be small, the mixture of the two earths may be dissolved in hydrochloric acid, excess being avoided, and

the solution boiled with excess of caustic potassa, by which the alumina is dissolved, magnesia remaining behind. If the quantity of magnesia be considerable, sal ammoniac is added to the hydrochloric solution of the two earths, and the alumina is precipitated by ammonia; but, as it carries with it a small quantity of magnesia, it must be redissolved in hydrochloric acid and treated with caustic potassa as above; it is not safe to treat at once the hydrochloric solutions of the earths with excess of caustic potassa when the quantity of magnesia is considerable, it being in this case very difficult to separate them by an alkaline ley. The best method of separating *alumina* from *magnesia* is probably to precipitate the former by bicarbonate of potassa, and to estimate the magnesia in the filtrate as *pyrophosphate of magnesia*: the alumina precipitated in this manner carries with it a portion of potassa, which it is almost impossible to remove by washing; it must, therefore, be redissolved in hydrochloric acid and reprecipitated by carbonate of ammonia.

#### *Glucinum.*

*Oxide of Glucinum.*—*Glucina*, like *alumina*, is only weighed in its pure form as precipitated from its solution by *caustic ammonia*. Its composition is

|                                      |     |      |     |       |
|--------------------------------------|-----|------|-----|-------|
| Two equivalents of Gl                | ... | 53.0 | ... | 68.83 |
| Three ditto of O                     | ... | 24.0 | ... | 31.17 |
| <hr/>                                |     |      |     |       |
| One ditto of $\text{Gl}_2\text{O}_3$ | ..  | 77   |     | 100   |

*Separation of Glucina from Alumina.*—Two methods have been proposed. The first depends on the solubility of *glucina* in carbonate of ammonia, and the insolubility of *alumina* in that reagent. The solution containing the two earths is mixed in a flask with a very considerable excess of a concentrated solution of carbonate of ammonia, the flask is closed, and occasionally shaken; when it is observed that the precipitate ceases to diminish in bulk, the *alumina* is separated by filtration, and the filtrate evaporated to dryness, and ignited to expel the ammoniacal salts; the residue, provided no other base or fixed acid be present, is pure *glucina*: or both the earths may be together precipitated by ammonia, and the precipitate digested with carbonate of ammonia till the glucina is entirely dissolved.

The second method is to dissolve both earths in a hot and concentrated solution of caustic potassa, to allow the ley to cool, and then to dilute it considerably with water, and again boil; the *glucina* is in this manner precipitated, while the *alumina* remains in solution.

The third method is that proposed by *Berthier*. The earths are dissolved in sulphuric acid, the solution concentrated, and sulphate of ammonia added, which causes the separation of the greater portion of the alumina in the form of an *alum*: to the decanted and diluted liquid *sulphate* of ammonia is added; and it is boiled until sulphurous acid ceases to be liberated; the alumina is entirely precipitated, and the glucina remains in solution, and may afterwards be precipitated by ammonia: or both earths may be together precipitated by ammonia, and, while moist, treated with sulphurous acid, which redissolves both, but on boiling the solution the alumina is completely precipitated.

The separation of glucina from *lime*, *magnesia*, and the *alkalies*, is effected in the same manner as the separation of alumina.

### *Yttrium.*

*Oxide of Yttrium*, or *Yttria*, is weighed as the pure earth, in which state it is precipitated by caustic alkalies; it must, however, be observed, that when it is dissolved in nitric or in sulphuric acid, *potassa* must be the precipitant employed; in the latter case it is, according to *Wohler*, almost impossible to procure it free from sulphate of potassa. Its composition is

|                     |     |      |     |       |
|---------------------|-----|------|-----|-------|
| One equivalent of Y | ... | 32.2 | ... | 80.09 |
| One do. of O        | ... | 8.0  | ... | 19.91 |
| <hr/>               |     |      |     |       |
| One do. of YO       | ... | 40.2 | ... | 100   |

*Separation of Yttria from Alumina and Glucina.\**—This is easily accomplished by digesting the mixture of the three earths in caustic potassa in which *yttria* is insoluble.

*Separation of Yttria from Magnesia and the Alkalies.*—

\* *Berthier's* mode of separating Glucina from Yttria is to add sulphite of ammonia to their solution, and boil the mixture. The basic sulphite of Yttria which falls is insoluble in water, and the glucina may be precipitated from the residual solution by ammonia.



From *magnesia yttria* is separated by caustic ammonia, sal-ammoniac having been previously added to the solution; from the alkalies it is separated precisely in the same manner as *alumina*.

### *Thorium.*

Of *Oxide of Thorium* or *Thorina*, little is known: from *alumina* it is distinguished by its insolubility in caustic potassa, and as it is completely precipitated from its solutions by ammonia, even in the presence of sal-ammoniac, it may thus be separated from *magnesia* and *lime*. *Thorina* forms, with sulphate of potassa, a double salt, quite insoluble in sulphate of potassa; this salt may, therefore, be employed to separate it from most other substances, but it must be concentrated, hot, and in excess; the double salt, after being washed with a cold and saturated solution of sulphate of potassa, is dissolved in boiling water, and the *thorina* precipitated by caustic potassa. Its composition is

|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Th | ... | 59.59 | ... | 88.16 |
| One do. of O         | ... | 8.00  | ... | 11.84 |
|                      |     |       |     | <hr/> |
| One do. of ThO       | ... | 67.59 |     | 100   |

### *Zirconium.*

*Oxide of Zirconium*, or *Zirconia*, is precipitated from its solutions by *ammonia* and by *caustic potassa*; the latter is the best precipitant, the former often throwing down subsalts instead of the pure earth. Sulphate of potassa added in crystals and in sufficient quantity to saturate the liquid, which must be first completely neutralized by potassa, throws down the whole of the earth in the form of a double salt; it must be washed with water containing ammonia, and then boiled with caustic potassa, which leaves hydrate of *zirconia* in a pure state. Its composition is

|                                           |     |       |     |       |
|-------------------------------------------|-----|-------|-----|-------|
| Two equivalents of Zr                     | ... | 67.24 | ... | 89.37 |
| Three do. of O                            | ... | 8.00  | ... | 10.63 |
|                                           |     |       |     | <hr/> |
| One do. of Zr <sub>2</sub> O <sub>3</sub> | ... | 75.24 |     | 100   |

The solubility of *zirconia* in bicarbonate of potassa affords a means of separating it from *alumina*, lime, *magnesia*, strontia, baryta and the fixed alkalies; but an accurate method of

separating it from *yttria* and *glucina* remains to be discovered.

### *Chromium.*

*Oxide of Chromium* is usually estimated quantitatively in its pure state; the solution containing it is heated to the boiling temperature, and, ammonia being added in slight excess, it is boiled for about half an hour, or until the solution is perfectly colorless; the precipitate is collected on a filter, washed with boiling water, dried, and ignited. Its composition is

|                                    |     |       |     |       |
|------------------------------------|-----|-------|-----|-------|
| Two equivalents of Cr              | ... | 56.30 | ... | 70.11 |
| Three do. of O                     | ... | 24.00 | ... | 29.89 |
| <hr/>                              |     |       |     |       |
| One do. of $\text{Cr}_2\text{O}_3$ | ..  | 80.30 |     | 100   |


The ignition of this oxide must be performed with care, as at a particular temperature it suddenly becomes incandescent with a sort of explosion, whereby a portion may be projected from the crucible. The crucible should be closed with its cover.

When chromium exists in a solution in the form of chromic acid, it may be estimated as chromate of baryta, or chromate of lead, by adding respectively nitrate of baryta or nitrate of lead to the solution; it may also be precipitated by proto-nitrate of mercury, the resulting chromate being decomposed by ignition into mercury, oxygen, and oxide of chromium; from the weight of the latter the quantity of chromic acid may be calculated; it is better, however, to reduce the chromic acid to oxide of chromium in the solution previous to precipitating it, which is done by concentrating the solution and boiling it with excess of hydrochloric acid, mixed with alcohol, till the liquid assumes a pure green color. The reduced oxide of chromium is precipitated by ammonia, after the alcohol has been expelled by a gentle heat.

*Estimation of Chromium in its compounds by Carbonic Acid.*—This method has lately been proposed by *H. Vohl*,\* and is applicable to the determination of the metal whether occurring in the form of oxide or as chromic acid, but when the metal exists as oxide of chromium, it must in the first


\* Liebig's *Annalen*, September 1847, and *Chem. Gaz.*, January 1st, 1848.

place be converted into chromic acid, the process depending on the conversion of oxalic into carbonic acid by the oxygen furnished by the reduction of chromic acid into oxide of chromium; thus



for each equivalent of chromic acid, three equivalents of carbonic acid are formed, or 66 parts by weight for 50.31 parts of chromic acid. To determine the amount of carbonic acid, the author employs the alkalimetical apparatus of Fresenius and Will (page 244.) If merely the chromium has to be determined, any oxalate may be taken, but, if the alkalies are to be determined in the residuary liquid, oxalate of ammonia or baryta is employed. The analysis is very simple: when the chromium exists in the compound in the form of acid, the salt is taken then just as it is, and the process is precisely the same as in the analysis of manganese (to be described further on). If the salt is a chloro-chromate, before allowing the sulphuric acid to pass over, oxide of mercury must be mixed with the salt, to prevent the elimination of chlorine or muriatic acid: after the operation the amount of chlorine can be determined from the perchloride of mercury by nitrate of silver, and the quantity of chlorochromic acid contained in the salt calculated from it.

The determination is less simple when the salt contains oxide of chromium. In the first place, the oxide must be converted into chromic acid, and this is best effected in the following manner:—The salt to be examined is dissolved in water, and caustic potassa added to it until the whole of the hydrated oxide of chromium has redissolved; upon which, keeping the solution cold, chlorine is passed into it until the green color is changed into a yellowish red one; an excess of potassa is now added to this liquid, which is evaporated in the water-bath, and heated to faint redness in a platina crucible. The whole of the chlorate of potassa is decomposed, chromate of potassa and chloride of potassium remaining; these are dissolved, transferred with oxide of mercury into the apparatus, and the operation conducted as with chromates. The amount of oxide of chromium can be easily calculated from the quantity of carbonic acid which has escaped; 6 equivalents of carbonic acid are set free for each equivalent of oxide of chromium:—



In analyzing a salt in which both chromic acid and oxide of chromium occur, two determinations must be made. In the first place, the carbonic acid is determined, which the salt yields as it is, and the chromic acid calculated from the amount; upon which the liquid is treated as a salt of the oxide, the quantity of carbonic acid first obtained subtracted from that last obtained, and the amount of oxide of chromium calculated from the difference.

This method will, according to *M. Vohl*, render it possible for every one to submit to analysis those compounds of chromium which occur so frequently adulterated in commerce.

*Separation of Oxide of Chromium from Alumina.*—The usual method is to fuse the mixture of the two oxides with twice its weight of carbonate of soda, and twice and a half of its weight of nitre;\* the oxide of chromium becomes converted into alkaline chromate, which is extracted with water, and the alumina which remains undissolved is freed from alkali by dissolving in hydrochloric acid, and precipitating by ammonia. According to Dr. Schaffhaeutl, however, a portion of alumina in this process always dissolves along with the alkaline chromate; he therefore recommends to convey the precipitate obtained by adding ammonia to the solution containing the two oxides into a hot concentrated solution of caustic potassa, and to boil the whole down till near solidification; when quite cold, water is added, and the whole of the alumina dissolves without carrying with it a trace of oxide of chromium.

*Separation of Oxide of Chromium from the rest of the Alkaline Earths.*—This is also effected by fusing the mixture with carbonate of soda and nitre, the earths are thus obtained in the form of carbonates, and are to be separated from each other.

*Separation of Oxide of Chromium from the Alkalies.*—The oxide of chromium is precipitated by ammonia, sal-ammoniac having previously been added to the solution. The alkalies are determined in the filtrate according to the directions previously given.

\* Prof. J. C. Booth recommends bisulphate of potassa as the best flux for Chromic ores.



## GROUP 4.

*Zinc, Nickel, Cobalt, Manganese, Iron.**Zinc.*

*Oxide of Zinc* is precipitated from its solutions, for the purpose of quantitative estimation, by carbonate of soda, or by hydrosulphuret of ammonia; in either case it is subsequently brought to the state of oxide, in order to be weighed.

*Precipitation as Basic Carbonate.*—Carbonate of soda is added in excess to the solution, which is then boiled for some time; if, however, ammoniacal salts be present, a considerable excess of carbonate of potassa must be added, and the solution must be evaporated to dryness at the boiling temperature; in order to decompose the ammoniacal salts, the dry mass is well washed with hot water, and the residue, which is basic carbonate of zinc ( $3\text{HO}, \text{ZnO} + 2\text{ZnO}, \text{CO}_2$ ), is strongly ignited, by which it becomes converted into oxide.

*Precipitation as Sulphuret.*—The solution, if it be acid, is first supersaturated with ammonia, the alkali being added in sufficient quantity to redissolve the oxide of zinc, which first precipitates; hydrosulphuret of ammonia is then added till it no longer occasions a precipitate, and the sulphuret of zinc, which is white, and very voluminous, is allowed completely to subside before filtration; the sulphuret is washed with water containing hydrosulphuret of ammonia, and then digested with concentrated hydrochloric acid until the solution ceases to smell of sulphuretted hydrogen; the resulting chloride of zinc is then precipitated as basic carbonate, and subsequently converted into oxide in the manner and with the precautions just described: it is to be observed, that it must not be neglected to examine whether the filtrate from the carbonate of zinc is free from *oxide of zinc*, which is done by adding to it a few drops of hydrosulphuret of ammonia; the formation of a white bulky precipitate indicates the presence of dissolved oxide of zinc, which must be collected and treated as above. The composition of *oxide of zinc* is

|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Zn | ... | 32.52 | ... | 80.25 |
| One do of O          | ... | 8.00  | ... | 19.75 |
|                      |     | <hr/> |     | <hr/> |
| One do of ZnO        | ... | 40.52 | ... | 100   |

*Separation of Oxide of Zinc from Oxide of Chromium.*—The solution is mixed with tartaric acid, *excess* of potassa is then added, and the clear solution is precipitated with colorless sulphuret of potassium; the sulphuret of zinc is treated as above, the oxide of chromium is contained in the filtrate, and is obtained by evaporating it to dryness and fusing the ignited residue with nitre and carbonate of soda; the alkaline chromate thus obtained is treated as directed (p. 264); then both the oxides are combined with acids that form soluble salts with baryta; their separation can, according to *Fresenius*, be accomplished by digesting the acid solution for several hours with excess of artificially produced *carbonate of baryta*: the whole of the oxide of chromium is removed, and is mixed with the excess of carbonate of baryta, from which it is separated by dissolving in hydrochloric acid, and adding excess of sulphuric acid; the *oxide of zinc* remains in solution, and is precipitated by carbonate of potassa.

*Separation of Oxide of Zinc from Alumina.*—The solution containing the two oxides is supersaturated with ammonia, alumina is precipitated, and oxide of zinc remains in solution. If, to a solution of the mixed oxides, excess of *cyanide of potassium* be added, heat being avoided, alumina is precipitated, and oxide of zinc retained in solution. If to a solution of the two oxides in sulphuric acid, excess of *acetate of baryta* be added, and then sulphuretted hydrogen passed into the solution, sulphuret of zinc is precipitated, while alumina remains dissolved; the sulphuret of zinc is separated from the sulphate of baryta by digesting the mixture in hydrochloric acid, the oxide of zinc is then precipitated from the solution as basic carbonate, and the alumina is precipitated by ammonia.

*Separation of oxide of Zinc from Magnesia.*—Sal-ammoniac is added to the solution, and then sufficient ammonia to retain both oxides in solution: the zinc is precipitated from the ammoniacal solution by hydrosulphuret of ammonia, and the magnesia in the filtrate determined in the usual manner. Another plan which has been proposed is to precipitate both oxides by carbonate of potassa; and then, having added a sufficient quantity of cyanide of potassium to dissolve the zinc, the whole is evaporated to dryness at a boiling temperature, a little more carbonate of potassa having first been added: on treating the dry mass with water, the magnesia remains undissolved, and the *zinco-cyanide of potassium* is held in solution.

*Separation of Oxide of Zinc from the Alkalies and Alkaline Earths.*—The bases are all brought into the state of acetates by adding *acetate of baryta* to the sulphuric acid solution as above described: the zinc is precipitated by hydrosulphuret of ammonia. To separate *oxide of zinc* from *lime*, *baryta*, and *strontia*, it has been recommended to treat the mixed solution with carbonate of potassa, until it acquires an alkaline reaction, then to add excess of cyanide of potassium, and apply heat: the earthy carbonates remain undissolved, while that of zinc is taken up. The solution is boiled with hydrochloric and nitric acids, until all hydrocyanic acid is expelled, and the oxide of zinc is then precipitated with carbonate of soda, those precautions being taken which are necessary when a salt of ammonia is present.

#### *Nickel.*

*Oxide of Nickel* is precipitated from its solutions either as *hydrated oxide* by caustic potassa, or as *sulphuret* by hydrosulphuret of ammonia: in either case it is converted into anhydrous *protoxide* to be weighed.

*Precipitation as Hydrated Protoxide.*—Pure solution of caustic potassa is added, and the solution heated to boiling; the voluminous apple-green precipitate, which is formed, requires protracted washing with hot water; after which it is dried and ignited: ammoniacal salts do not interfere with the precipitation of oxide of nickel by caustic potassa, but with carbonate of potassa it is not so complete.

*Precipitation by Hydrosulphuret of Ammonia.*—The complete precipitation of nickel in the state of sulphuret by hydrosulphuret of ammonia is not easy, in consequence of the partial solubility of sulphuret of nickel in that reagent. To insure success the hydrosulphuret of ammonia must be perfectly saturated and colorless, and not added in great excess; the vessel must be covered, and placed in a warm situation; the fluid above the precipitate should be free from color; the sulphuret of nickel is washed on the filter with water, to which a few drops of hydrosulphuret of ammonia have been added; it is then dried, transferred to a beaker, and digested at a gentle heat (until completely dissolved) with concentrated aqua regia; the filter is burnt, and its ashes added to the solution: this is better than digesting the filter and precipitate together in aqua regia; since, as *Fresenius* observes, the

presence of organic matter prevents the complete precipitation of oxide of nickel by caustic alkali: the solution filtered from the separated sulphur is precipitated by potassa, washed, dried, and ignited.

The composition of anhydrous protoxide of nickel is

|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Ni | ... | 29.57 | ... | 78.76 |
| One do. of O         | ... | 8.00  | ... | 21.24 |
| <hr/>                |     |       |     |       |
| One do. of NiO       | ... | 37.57 |     | 100   |

*Separation of Oxide of Nickel from Oxide of Zinc.*—Several methods have been proposed:—1st. *Berzelius's Method.* The greater part of the oxide of zinc is first extracted by caustic potassa; the residue, after being well washed and heated, is mixed with pure *pulverized sugar*, and carefully carbonized in a porcelain crucible. The crucible is then surrounded with magnesia in a larger Hessian crucible, and heated for an hour in a blast furnace as strongly as possible. The oxides are reduced, and the zinc is driven off in vapor; the nickel is dissolved in nitric acid, evaporated to dryness in a platinum crucible, and ignited. The loss of weight gives the quantity of oxide of zinc. The principal point to be attended to is to extract all the potassa from the mixed oxides: the sugar must be perfectly pure, with which view it should be crystallized from an alcoholic solution.

2d. *Ullgren's Method.*—The oxides are precipitated by carbonate of soda, the whole evaporated, and the residue gently heated, so that they remain perfectly insoluble when the mass is treated with water. The oxides are washed and dried, and then being placed in a tube, with a bulb, are reduced by hydrogen at a low red heat; the tube is allowed to cool, while a continuous current of hydrogen is passed through it; it is then closed at one end by fusion, filled with a concentrated solution of carbonate of ammonia, corked up, and placed in a warm situation for twenty-four hours; the *oxide of zinc*, which is not reduced, is dissolved in the carbonate of ammonia; the oxide of nickel is reduced, and the metal, after being well washed with carbonate of ammonia, is dried and weighed; the oxide of zinc is obtained from the ammoniacal solution by evaporation. The oxides must be finely pulverized before they are exposed to the action of hydrogen gas.

3d. *Rose's Method.*—The mixed oxides, after having been



ignited, are placed in the bulb of a reduction tube, which communicates on the one side with an apparatus, from which dry hydrochloric acid gas is liberated, and, on the other, with a flask containing a very dilute solution of ammonia. As soon as the air is expelled the bulb is gradually heated to redness, the oxides are converted into chlorides, the chloride of nickel remains in the bulb, and the volatile chloride of zinc passes into the solution of ammonia, in which it dissolves. The oxides are then determined in the usual manner. This method, though tedious and somewhat complicated, yields very accurate results.

4th. *Smith's Method*.—The oxides are converted into acetates; and, excess of acetic acid being added, sulphuretted hydrogen is passed through the solution, by which the whole of the zinc is precipitated as sulphuret, while the oxide of nickel remains in solution: this method, which is well adapted for the analysis of *German silver*, the constituents of which are *copper*, *zinc*, and *nickel*, has been found by *M. Louyet* to yield very accurate results.

*Separation of Oxide of Nickel from Oxide of Chromium*.—The mixed oxides are fused with nitre and carbonate of soda; the oxide of chromium is thus converted into *chromic acid*, and is dissolved on boiling with water as alkaline chromate.

*Separation of Oxide of Nickel from Alumina*.—Excess of cyanide of potassium is added, heat being avoided; alumina is precipitated, and oxide of nickel retained in solution; according to Berthier, on adding *sulphite of ammonia* to a solution of the two oxides, the alumina only is precipitated.

*Separation of Oxide of Nickel from Magnesia*.—This is effected in the same manner as the separation of oxide of zinc from the same earth.

*Separation of Oxide of Nickel from Baryta, Strontia, and Lime*. Cyanide of potassium is added in excess, and then carbonate of potassa, the whole is boiled, and the insoluble carbonates separated by filtration from the *nickel cyanide*. The solution is boiled with hydrochloric acid until all the hydrocyanic acid is expelled; potassa in excess is then added, and the solution boiled till all the ammonia is liberated, the oxide of nickel is then precipitated by potassa.


*Cobalt.*

This metal is precipitated from its solutions either by caustic potassa, or by hydrosulphuret of ammonia; it is weighed either as *oxide* or in the *metallic state*; when great or even moderate accuracy is required, it must be estimated in the latter form, as the ignited hydrated protoxide is of indefinite composition, varying according to the degree of heat employed.

*Precipitation as Hydrated Protoxide.*—The solution is boiled with excess of caustic potassa; the precipitate, which at first is bluish, becomes, after long boiling, of a dirty rose red color; if ammoniacal salts are present, they must be decomposed, and the ammonia discharged by long-continued boiling, with great excess of caustic alkali; the precipitated hydrate requires long-continued washing with hot water, on being dried and ignited it turns black: in this state it is weighed; if the operator has determined on reducing it to reguline cobalt, he proceeds in the following manner.

*Reduction of Oxide of Cobalt to Reguline Cobalt.*—The

Fig. 9.



small Berlin crucible *d*, Fig. 9, having been carefully weighed, a certain known quantity of the previously weighed oxide is introduced, and the weight of the crucible again accurately noted; a stream of hydrogen gas, dried by passing through the U-shaped chloride of calcium, tube *b*, is then caused to flow through the apparatus, from the flask *a*, and a flame applied to the crucible containing the oxide; the heat must at first be gentle; but it must gradually be raised to full redness, this high temperature being necessary to prevent the reduced

metal from acquiring a pyrophoric property, which would cause it to inflame on coming in contact with atmospheric air; the hydrogen reduces the metallic oxide, giving rise to a proportional amount of water, which escapes in the form of steam between the top of the crucible and its cover, and at the aperture through which the tobacco-pipe, *c*, enters. When it is seen that water no longer continues to form, the flame is removed from the crucible, and it is allowed to cool, while a stream of hydrogen still continues to pass over it; the crucible is then again weighed, and from the amount of reduced metal obtained the quantity contained in the whole of the protoxide precipitated is calculated. If a sufficiently high temperature has not been employed, the reduced cobalt oxidizes at common temperatures, but if a full red heat has been employed, it absorbs oxygen very slowly.

*Precipitation as Sulphuret.*—Sal ammoniac is added to the solution, then slight excess of ammonia, and finally hydrosulphuret of ammonia as long as precipitation takes place; the resulting sulphuret of cobalt is washed with water, containing a little sulphuret of ammonium, then digested with aqua regia, and precipitated by potassa, precisely as sulphuret of nickel. The hydrated oxide, after being washed, dried, and ignited, is reduced by hydrogen in the manner just described. *Rose* recommends that, in the presence of ammoniacal salts, cobalt should always be precipitated by hydrosulphuret of ammonia.

*Separation of Cobalt from Nickel.*—Several methods have been proposed by different chemists, but until recently Phillips' process was the one generally preferred, and is as follows:—

1. *Method of Phillips.*—Both oxides are dissolved in an acid, and the solution supersaturated with ammonia, having previously added a sufficient quantity of sal ammoniac, to prevent any precipitation from taking place; the solution, which has a sky-blue color, is largely diluted with water, which should have been previously well boiled, to free it from atmospheric air: caustic potassa is added to the hot solution, and the vessel is closed with a cork; *oxide of nickel* is precipitated, and *oxide of cobalt* remains in solution; when the former has completely settled, the supernatant liquid, which should have a rose-red color, is poured through a filter, and the oxide of nickel washed with hot water, ignited, and weighed; the oxide

of cobalt in the filtrate is precipitated by hydrosulphuret of ammonia: the reason why it is necessary to dilute the solution of the two oxides with water, free from atmospheric air, is, that oxide of cobalt in an ammoniacal solution is converted into peroxide of cobalt, which, precipitating as a black powder; would contaminate the oxide of nickel. The more dilute the solution is, the less easily does the oxide of cobalt become oxidized. When a large quantity of ammoniacal salt is present, the quantity of caustic potassa required to precipitate the oxide of nickel is very considerable. According to Fresenius, the separation by this method is not complete, the cobalt invariably containing traces of nickel, and the precipitated nickel often traces of cobalt.

2. *Liebig's Method*.—This is founded on the following considerations:—When any salt of cobalt is warmed with cyanide of potassium, and an excess of hydrocyanic acid, it is converted into the *percyanide of cobalt and potassium*, or *cobalticyanide of potassium*,  $(\text{Co}_2\text{Cy}_6\text{K}_3)$  the aqueous solution of which does *not* undergo any decomposition by boiling with either of the mineral acids. On the other hand, the precipitate produced by cyanide of potassium in solutions of salts of nickel is redissolved by cyanide of potassium, but the solution *is* decomposed by dilute sulphuric acid, cyanide of nickel being precipitated. When, therefore, a mixture of a cobalt and a nickel salt containing free acid is treated with excess of cyanide of potassium, and slightly warmed, we obtain in solution the double cyanide of nickel and potassium, and cobalticyanide of potassium,  $(\text{NiCy} + \text{KCy}) + (\text{Co}_2\text{Cy}_6\text{K}_3)$  and on adding dilute sulphuric acid in the cold, three cases present themselves.

1st. If the cobalt and nickel exist in the solution in the proportion, by weight, of *two* cobalt to *three* nickel, we have in the solution,  $3(\text{NiCy}, \text{KCy}) + (\text{Co}_2\text{Cy}_6\text{K}_3)$  and the three equivalents of nickel replacing the three equivalents of potassium, in the cobalticyanide of potassium, produce cobalticyanide of nickel,  $(\text{Co}_2\text{Cy}_6\text{Ni}_3)$  which is precipitated of a bluish white color, leaving in the solution no trace of either cobalt or nickel.

2d. If the solution contain *less* nickel than corresponds to the above proportions, a certain quantity of cobalticyanide of potassium remains in solution, while cobalticyanide of nickel is still precipitated.



3d. If the solution contain *more* nickel than corresponds to the above proportions, cobalticyanide of nickel is still precipitated, together with the excess of cyanide of nickel, which, by long boiling with hydrochloric acid, is completely converted into chloride of nickel, which remains in solution.

Now cobalticyanide of nickel, though insoluble in hydrochloric acid, is decomposed by boiling with caustic potassa into protoxide of nickel, and cobalticyanide of potassium, thus,  $\text{Co}_2\text{Cy}_6\text{Ni}_3 + 3\text{KO} = \text{Co}_2\text{Cy}_6\text{K}_3 + 3\text{NiO}$ , and chloride of nickel is also decomposed by caustic potassa into protoxide of nickel and chloride of potassium. Hence, the following method of analyzing mixtures of cobalt and nickel, which is applicable to all proportions.

Hydrochloric acid is added to the solution of the metals, and then cyanide of potassium in such excess that the precipitate at first formed is redissolved, the whole is boiled, adding from time to time hydrochloric acid, until hydrocyanic acid ceases to be evolved. Caustic potassa is then added in considerable excess, and the boiling continued until the hydrated protoxide of nickel is completely precipitated; it is then filtered, the filtrate contains the whole of the cobalt in the form of cobalticyanide of potassium; it is evaporated to dryness with excess of nitric acid, the residue fused, and treated with hot water: peroxide of cobalt remains, which is dissolved in hydrochloric acid, and the solution treated as already directed.

In analyzing ores of nickel, which contain small quantities only of cobalt, considerable excess of hydrochloric acid must be taken to precipitate the cyanides dissolved in cyanide of potassium, and the mixture must be continued in ebullition for a full hour.

*Rose's Method.*—This is founded on the greater tendency in the protoxide of cobalt than in the protoxide of nickel to pass to a higher degree of oxidation. Both metals are dissolved in hydrochloric acid; the solution must contain a sufficient excess of free acid: it is then diluted with much water; if 20 or 30 grains of the oxide are operated on, about 2 lbs. of water are added to the solution. As cobalt possesses a much higher coloring power than nickel, not only in fluxes, but also in solutions, the diluted solution is of a rose color, even when the quantity of nickel present greatly exceeds that of the cobalt. A current of chlorine is then passed through

the solution for several hours;\* the fluid must be thoroughly saturated with it, and the upper part of the flask above the liquid must remain filled with the gas after the current has ceased. Carbonate of baryta in excess is then added, and the whole allowed to stand for 12 or 18 hours, and frequently agitated; the precipitated peroxide of cobalt and the excess of carbonate of baryta are well washed with cold water, and dissolved in hot hydrochloric acid; after the separation of the baryta by sulphuric acid, the cobalt is precipitated by hydrate of potassa, and, after being washed and dried, is reduced in a platinum or porcelain crucible by hydrogen gas, in the manner shown in Fig. 9. The fluid filtered from the superoxide of cobalt is of a pure green color; it is free from any trace of cobalt. After the removal of the baryta by means of sulphuric acid, the oxide of nickel is precipitated by caustic potassa. To insure accurate results, it is indispensably necessary to wait a considerable time, at least 12, or even better, 18 hours after the addition of the carbonate of baryta, as the superoxide of cobalt is precipitated very slowly.

*Another Method.*—The two oxides are covered with prussic acid, and then potassa added till a portion remains undissolved. The solution is kept boiling for a quarter of an hour, moist hydrated oxide of mercury is then added till a portion remains undissolved; a green precipitate occurs containing all the nickel, with the excess of oxide of mercury. By ignition, pure oxide of nickel remains. Acetic acid is added to the filtrate to acid reaction; it is then precipitated with blue vitriol. The blue precipitate contains all the cobalt; this is dried, ignited, redissolved in hydrochloric acid; the copper, precipitated by sulphuretted hydrogen, and then from the filtrate the cobalt by potassa. The method depends upon the fact, that *nickelo*-cyanide of potassium is decomposed by oxide of mercury, while *cobalto*-cyanide of potassium experiences no change.

*Separation of Oxide of Cobalt from Oxide of Zinc.*—The above method may, according to Rose, be employed for the separation of these two oxides; and also for that of other oxides from oxide of cobalt, which are strongly basic, and which are not converted into superoxides: oxide of zinc may,

\* Mr. Henry employs a solution of *bromine* till the solution smells strongly of it; he finds this to answer equally well with the chlorine, and the process is rendered less tedious and unpleasant.

likewise, be separated from oxide of cobalt by *Liebig's* process with cyanide of potassium, cobaltcyanide of zinc is gradually dissolved in boiling hydrochloric acid, and a clear solution is obtained: on the addition of caustic potassa and boiling, both the cobalt and the zinc are retained in solution, the former as cobaltcyanide of potassium, and the latter as oxide; and, from the solution, zinc is precipitated by sulphuretted hydrogen; the methods of *Berzelius*\* and *Ullgren*,† for the separation of oxide of nickel from oxide of zinc, may likewise be employed for the separation of oxide of cobalt.

\* This method is employed by Berzelius for separating completely oxide of zinc from oxide of cobalt, and oxide of nickel. It can, of course, be resorted to for separating oxide of zinc, when mixed with only one of these oxides:—

After having separated the greatest portion of the oxide of zinc by boiling the mixture with a solution of caustic potash, the residuum is washed with cold water, and then with boiling water, until all the potash is removed. The oxide is heated to redness, and weighed. It is then intimately mixed in a platinum crucible, with pulverized sugar. [Such as will leave no ashes after ignition.] (*Berzelius* advises the operator to take the crystals of sugar deposited from an alcoholic solution; but the sugar-candy of commerce, when chosen in perfectly defined and colorless crystals, leaves no appreciable trace of ashes.)

The sugar is carefully carbonized; the porcelain crucible with the cover on, is put in a Hessian crucible, and the space between the two crucibles is filled up with caustic magnesia, the latter crucible, also covered over, is exposed for one hour in a wind furnace to the strongest heat possible. The oxides are reduced by this treatment; the cobalt and the nickel remain in the state of carburets, and the zinc volatilizes completely. The two metals left behind are dissolved in nitric acid, and the solution is evaporated to dryness in the water bath in a counterpoised platinum crucible, the residuum is ignited to bright redness, and the oxide is weighed. The loss of weight indicates the quantity of oxide of zinc expelled.

One of the principal conditions of success in this experiment is, that the mixture of the oxides be perfectly washed before being ignited, for, if it still contains potash, the latter acts upon the porcelain crucible; it is advisable to test by boiling water, whether the oxides, after having been ignited, and before being mixed with sugar, contain potash, because, should any be left, it might, as yet, be eliminated by a renewed washing.

† *M. Ullgren's* method is as follows:—The solution of the oxides of zinc, of cobalt, and of nickel, is precipitated by carbonate of soda, having previously separated the earthy and other metallic oxides which might be present. The whole is then evaporated to dryness at a gentle heat, so that by adding water, the carbonate of soda alone dissolves. The oxides are then collected on a filter, washed, weighed, and reduced in a glass tube at a dark red heat, by means of hydrogen gas. When water ceases to be produced, the tube is allowed to cool, the current of hydrogen gas being continued all the time. One of the extremities is then closed by means of the blow-pipe, and it is filled with solution of carbonate of ammonia; it is corked up and maintained for two days at a temperature of about 40° Cent. (104° Fahr.) The carbonate of ammonia dissolves the oxide of zinc completely, which has not been reduced by the hydrogen gas at the low temperature which was sufficient for the reduction of the two other oxides, and the cobalt and nickel, free from zinc, are washed with carbonate of ammonia. The

*Separation of Oxide of Cobalt from Oxide of Chromium.*—This is effected in the same manner as the separation of oxide of nickel from oxide of chromium.

*Separation of Oxide of Cobalt from Alumina.*—Cyanide of potassium is added, heat being avoided; the cobalt is dissolved as cobalticyanide of potassium, and the alumina precipitated; according to *Berthier*, the separation may likewise be effected by sulphite of ammonia.

*Separation of Oxide of Cobalt from the Alkaline Earths.*—This is effected in the same manner as the separation of the oxide of nickel.

### *Manganese.*

This metal is quantitatively estimated as *protoxide*, as *red oxide*, or as *proto-sulphate*.

*Quantitative estimation as Protoxide.*—*Ebelman* prefers reducing the higher oxides of manganese to the state of protoxide for the purpose of weighing. To perform the experiment, he introduces the oxide into a small platinum crucible, the lid of which has a small platinum tube in the centre, through which a current of dry hydrogen gas is conveyed by means of a green glass tube, of a diameter nearly equal to that in the crucible cover (see Fig. 9), heat is applied by means of a spirit-lamp; the reduction is complete after a few minutes, and a rapid current of gas is passed into the crucible while cooling; the oxide obtained is quite pure; it dissolves in hydrochloric acid without rendering it black, and without disengaging chlorine. Its composition is

|                       |     |       |     |       |
|-----------------------|-----|-------|-----|-------|
| One equivalent of Mn. | ... | 27.67 | ... | 77.57 |
| One do. of O          | ... | 8.00  | ... | 22.43 |
| <hr/>                 |     |       |     |       |
| One do. of MnO        | ... | 35.67 |     | 100   |

*Quantitative estimation as Red Oxide.*—The solution is heated to boiling with excess of carbonate of soda. Should ammoniacal salts be present, the solution must be treated in the same manner as in the precipitation of carbonate of zinc,

ammoniacal liquor is carefully evaporated; the oxide of zinc is left behind, and it is then ignited and weighed.

It is essential to the success of this operation, that the oxides submitted to this reductive process, be in a very fine state of division, in order that all the oxide of zinc may be in contact with the carbonate of ammonia.



under similar circumstances; the precipitate is thoroughly washed, dried, and ignited, by which it is decomposed into the red oxide (manganoso—manganic oxide); sometimes the solution is precipitated with caustic potassa, and the hydrated protoxide thus formed is converted into red oxide by strong ignition; it must be remembered, however, that hydrated protoxide of manganese is soluble in sal-ammoniac. It is sometimes convenient also to precipitate manganese as sulphuret, by adding colored hydrosulphuret of ammonia to the solution to which sal-ammoniac and ammonia have been added, the precipitate, having been washed with water containing hydrosulphuret of ammonia, is digested with hydrochloric acid, and the solution precipitated by carbonate of ammonia.

The composition of red oxide of manganese is

|                                                 |     |        |     |       |
|-------------------------------------------------|-----|--------|-----|-------|
| Three equivalents of Mn                         | ... | 83.01  | ... | 72.17 |
| Four do. of O                                   | ... | 32.00  | ... | 27.83 |
|                                                 |     |        |     | <hr/> |
| One do. of $\text{MnO} + \text{Mn}_2\text{O}_3$ | ..  | 115.01 |     | 100   |

*Quantitative estimation as Sulphate.*—Oxide of manganese is converted into protosulphate in the same manner and with the same precautions as magnesia: the salt must be ignited very feebly, or it will lose sulphuric acid. Its composition is

|                                      |     |       |     |       |
|--------------------------------------|-----|-------|-----|-------|
| One equivalent of MnO                | ... | 35.67 | ... | 47.13 |
| One do. of $\text{SO}_3$             | ... | 40.00 | ... | 52.87 |
|                                      |     |       |     | <hr/> |
| One do. of $\text{MnO}, \text{SO}_3$ | .   | 75.67 |     | 100   |

*Separation of Oxide of Manganese from Oxides of Cobalt and Nickel.*—Rose's original method, which, though complicated, gives very accurate results, is the following:—The metals are first precipitated together as oxides by caustic potassa, they are then ignited, weighed, and converted into chlorides by introducing them into a bulbed tube, and transmitting over them a current of dry hydrochloric acid gas, a moderate heat being at the same time applied: it requires a long time thus to convert the oxides completely into chlorides; when the conversion is complete, dry hydrogen gas is passed through the apparatus, the bulb containing the chlorides being strongly heated, the hydrogen displaces the chlorine from the chlorides of cobalt and nickel, forming with it hydrochloric acid gas; and the operation must be continued

as long as white clouds are formed, on holding a glass rod that has been dipped in ammonia at the end of the apparatus where the excess of gas escapes: the hydrogen is allowed to pass through the tube till it is quite cold, the chloride of manganese, which has not been decomposed by the process, is dissolved out by water; the reduced cobalt and nickel are washed with very dilute hydrochloric acid, and, finally, with water; the two metals are then separated from each other by one of the methods above given, and the manganese is precipitated from the solution of the chloride, to which has been added the washings from the cobalt and nickel by carbonate of soda.

*Rose* states that *nickel* may be conveniently separated from manganese in the same manner as cobalt, namely, by chlorine and carbonate of baryta. A method of separating oxide of cobalt from oxide of manganese was proposed by *Barreswil*: it consists in adding carbonate of baryta to the solution, and then passing a current of sulphuretted hydrogen through it, by which, according to *Barreswil*, cobalt only is precipitated; this method has not, however, been found successful by other chemists. A plan for the separation of oxides of cobalt and nickel from oxide of manganese was proposed by *Wakenroder*, and has obtained the approval of *Rose*: it is based on the fact that, although nickel and cobalt are not precipitated from their acid solutions by sulphuretted hydrogen, their sulphurets precipitated by hydrosulphuret of ammonia are *not* dissolved by very dilute hydrochloric acid. The acid solution of the three oxides is made ammoniacal, and the metals are precipitated by hydrosulphuret of ammonia: the solution is then rendered slightly acid by dilute hydrochloric acid; the sulphuret of manganese is dissolved with facility, small portions also of the sulphuret of cobalt and nickel may also be dissolved, but they may be removed by reprecipitating the solution with ammonia and hydrosulphuret of ammonia, and treating it anew with dilute hydrochloric acid.

*Manganese from Cobalt (Liebig's Method).*—The metals are precipitated by cyanide of potassium, an excess of which redissolves the cyanide of cobalt, and a part also of the proto-cyanide of manganese, while another portion remains undissolved, this is filtered off and washed: the filtrate is heated to ebullition, a few drops of hydrochloric acid, insufficient,

however, to acidify the solution, are added from time to time, and the manganese and cobalt are separated from one another in the same manner as nickel is separated from cobalt.

*Ebelman* has recently proposed to separate manganese from cobalt or nickel, by exposing the mixture of the oxides to a current of dry sulphuretted hydrogen, at a temperature a little below redness. The oxides are converted into sulphurets, the sulphuret of manganese is dissolved by very weak hydrochloric acid, in the cold. The smallest quantity of cobalt may, he says, be detected in this manner. He applies the same process to the separation of arsenic from tin.

*Separation of Oxide of Manganese from Oxide of Zinc.*—The oxides are dissolved in excess of acetic acid, and the zinc is precipitated by sulphuretted hydrogen; the solution must be acid, and contain no other acid but acetic.

*Separation of Oxide of Manganese from Oxide of Chromium.*—This is effected in the same manner as the separation of oxide of zinc from oxide of chromium.

*Separation of Oxide of Manganese from Alumina.*—Cautic potassa is added in excess to the solution, which is then boiled; the alumina, which is at first precipitated with the oxide of manganese, is redissolved, and is determined in the filtrate in the usual manner; the oxide of manganese is dissolved in hydrochloric acid, and precipitated as carbonate. According to *Berthier*, alumina may be separated from oxide of manganese by boiling with *sulphite of ammonia*.

*Separation of Oxide of Manganese from Magnesia.*—Muriate of ammonia is added in sufficient quantity to the solution, and the manganese is precipitated as sulphuret by hydrosulphuret of ammonia; the filtrate contains the whole of the magnesia; it is acidulated with hydrochloric acid, and boiled, to decompose the excess of hydrosulphuret of ammonia, filtered to separate the sulphur, and the magnesia determined in the filtrate as sulphate (provided no other base be present), or as double phosphate of ammonia and magnesia.

*Separation of Oxide of Manganese from Lime.*—When the quantity of oxide of manganese present is small, the solution is mixed with muriate of ammonia, and, oxalate of ammonia having been added, the solution is quickly filtered; the lime is thus separated as oxalate, and is determined in the usual manner: the oxide of manganese in the filtrate is precipitated by hydrosulphuret of ammonia, but, if the quan-

tity of oxide of manganese be considerable, this method will not be successful, as a portion of that metal would be precipitated both as oxide and as oxalate, together with the lime; in this case, the solution having been mixed with muriate of ammonia and caustic ammonia, the manganese is precipitated by hydrosulphuret of ammonia, and filtered quickly, both funnel and receiving vessel being covered, to prevent the formation of carbonate of lime; the filtrate is digested with hydrochloric acid, to destroy the excess of hydrosulphuret of ammonia, then supersaturated with ammonia, and the lime precipitated as oxalate.

*Separation of Oxide of Manganese from Alumina, Magnesia, and Lime.*—When all three earths are contained in a solution, together with oxide of manganese, the method of separation depends on the quantity of the latter present; if it be small, the alumina is first precipitated by caustic ammonia, sal ammoniac in sufficient quantity having been previously added to the solution; the alumina carries with it small quantities both of magnesia and of lime, from which it is separated by digestion with caustic potassa; in filtering the alumina, care must be taken to guard both funnel and receiving vessel as much as possible from the air, to prevent the precipitation of carbonate of lime; the filtrate from the alumina is mixed with oxalate of ammonia, by which the lime is separated. The oxide of manganese and the magnesia are contained in the filtrate from the oxalate of lime, and are separated from each other as above directed; the small quantities of magnesia and oxide of manganese which had been precipitated with the alumina, and which remain undissolved in the alkaline ley, are dissolved in hydrochloric acid, and added to the filtrate from the oxalate of lime. When the quantity of oxide of manganese is considerable, it is separated from the filtrate from the alumina, by hydrosulphuret of ammonia, the solution filtered from the sulphuret of manganese is boiled with hydrochloric acid, to decompose the excess of hydrosulphuret of ammonia; ammonia added, and the lime precipitated as oxalate. The solution filtered from the oxalate of lime contains the magnesia which is precipitated, and estimated in the usual manner. The small quantities of magnesia and oxide of manganese which have been precipitated, together with the alumina, having been removed




by caustic potassa, are dissolved in hydrochloric acid, and estimated separately.

*Examination of Commercial Oxide of Manganese, to ascertain its practical value.*—Several methods have been proposed.

*First Method.*—By estimating the amount of chlorine evolved during the solution of the ore in hydrochloric acid, the value of the oxide being in exact proportion to the quantity of chlorine produced. Three methods of estimating the chlorine have been employed.


1 (a). By noting the quantity of protosulphate of iron which it peroxidizes. If the oxide of manganese be perfectly pure, 43.67 parts (one equivalent) will produce 35.5 parts (one equivalent) of chlorine, which will peroxidize 278 parts (two equivalents) of crystalized protosulphate of iron, thus:—




Hence 25 grains of pure oxide of manganese yield chlorine sufficient to peroxidize 159 grains of protosulphate of iron; 25 grains of the powdered specimen are weighed out, and a quantity not less than 359 grains of crystalized protosulphate of iron. The oxide of manganese is thrown into a flask containing about one ounce of strong hydrochloric acid slightly diluted, and a gentle heat applied. The protosulphate of iron is gradually added in small quantities to the acid, so as to absorb the chlorine as it is evolved, and the addition of that salt continued till the liquor, after being heated, gives a *blue* precipitate with *red prussiate of potassa*, and has no smell of chlorine, which are indications that the protosulphate of iron is present in excess; by weighing what remains of this salt, the quantity that has been added is ascertained, say  $m$  grains. If the whole of the specimen consisted of peroxide, it would require 159 grains of protosulphate of iron, and that quantity would therefore indicate 100 per cent. of peroxide; but, if a *portion* of the manganese only is peroxide, a proportionally smaller quantity of the protosulphates will be consumed, and that quantity will give the real proportion of peroxide, by the proportion, as  $159 : 25 :: m$  to the quantity required.

1 (b). The chlorine evolved is passed through water in which *lime* is diffused; *chloride of lime* is formed; a certain quantity of protosulphate of iron is dissolved in water, and

the solution of chloride of lime is added thereto, until the iron liquor ceases to strike a blue color with a drop of solution of red prussiate of potash: then, comparing the quantity of the solution of chloride of lime required with the quantity that was produced, the quantity of chlorine generated, and hence the total quantity of available oxygen, is known. The theory of the process may be expressed as follows:—



the liberated chlorine combines with the lime, forming  $\text{CaO}$ ,  $\text{Cl}$ , and



1 (c). *Baumann* conveys the chlorine into a solution of nitrate of silver, and calculates the amount of real peroxide of manganese in the specimen from the quantity of chloride of silver formed.

*Second Method.*—By converting *oxalic acid* into carbonic acid by means of the second atom of oxygen which the peroxide of manganese contains.  $\text{MnO}_2 + \text{C}_2\text{O}_3$ , producing  $\text{MnO}$ , and  $2\text{CO}_2$ , 100 grains of the specimen are introduced into a weighed flask, and 150 grains of oxalic acid dissolved in 500 grains of water are poured upon it; to this 350 grains of oil of vitriol are to be added, and the orifice of the flask closed by a cork, through which passes a tube containing fragments of recently fused chloride of calcium; the weight of this cork and tube are to be included in the tare of the flask. On the addition of the oil of vitriol, a brisk effervescence takes place, owing to the escape of carbonic acid, which, passing over the fragments of chloride of calcium in the tube, is dried, so that the gas alone passes off. When the action slackens, a gentle heat may be applied, until all the oxide of manganese has dissolved; the small quantity of a light brownish sediment, which generally falls, is easily distinguished from the particles of black oxide. As soon as the action is quite over, the flask is allowed to cool, and as it still contains a quantity of carbonic acid gas, this is removed by taking out the cork, and blowing air gently into the flask by a glass tube; the cork is then to be replaced, and the flask with its contents weighed; the difference of weight represents the amount of carbonic acid evolved; *one-fourth* of the oxygen of which had been derived from the peroxide of manganese by its conversion into protoxide, which remains combined with sulphuric acid in the liquor, and the quantity of peroxide in the

100 grains of the one are thus directly found. *Example.*—Suppose the flask and the materials together to weigh 1876 grains, and after the action has terminated 1816.5 grains: the loss, 59.5 grains, is carbonic acid, consisting of 16.3 grains of carbon, and 43.2 grains of oxygen; the oxygen derived from the mineral is, therefore,  $\frac{43.2}{4} = 10.8$ , which

represents 59 grains of pure peroxide of manganese in 100 grains of the substance experimented upon.

3d. *Method of Fresenius and Will.\**—This is founded on the same principle. A certain weighed quantity of finely powdered manganese is projected into B, (see *fig. 7*.) and about  $2\frac{1}{2}$  parts of *neutral oxalate of potash*, prepared by saturating the common binoxalate with carbonate of potash, and crystalizing, or two parts of neutral oxalate of soda, and as much water added as will fill about one-third of the flask; the apparatus is then prepared as directed in p. 245, B is then closed, the apparatus weighed, and, by sucking the tube *e*, some sulphuric acid is made to pass from *a* into *b*. The evolution of carbonic acid commences immediately, and in a very uniform manner: as soon as it stops, some more sulphuric acid is sucked over from *a* into *b*, and the operation thus continued till all the manganese is completely decomposed: this operation will require from six to ten minutes: its completion is ascertained not only by no further evolution of carbonic acid taking place upon a further influx of sulphuric acid into *b*, but also by no black powder remaining at the bottom of the flask: some more sulphuric acid is then sucked over into *b*, in order to heat the fluid contained therein, so as completely to expel all the carbonic acid evolved during the course of the operation; the wax stopper is then removed from *a*, and the tube *d* sucked until the air no longer tastes of carbonic acid; the apparatus is then allowed to cool and weighed. The entire examination may thus, according to the authors, be performed in a quarter of an hour; from the loss of weight of the apparatus, (the amount of carbonic acid expelled,) the amount of available oxygen is found, or what, in fact, is the same, the amount of peroxide contained in the manganese under examination, ac-

\* *New Method of Alkalimetry*, by Drs. Fresenius and Will, edited by J. Lloyd Bullock, page 116, *et seq.*

cording to the following arrangement. *Two* equivalents of carbonic acid stand to *one* equivalent of peroxide of manganese in the same proportion as the amount of carbonic acid found stands to  $x$ ,  $x$  being the quantity of real peroxide contained in the specimen. Let us suppose that our experiment had been made with four grammes (61.76 grs.) of manganese, and that we had obtained 3.5 grammes (54.03 grs.) of carbonic acid. The arrangement would be

$$4 : 43.67 :: 3.5 : x$$

$$x = 3.47.$$

Thus, four grammes of the manganese containing 3.47 grammes of peroxide, 100 parts of the same substance must contain 86.7 parts. To render, however, this calculation unnecessary, we need only ascertain what amount of manganese must be taken to make the number of centigrammes of carbonic acid obtained immediately indicate the per centage amount of peroxide. The calculation must, therefore, be


$$4 : 43.67 :: 100 : x$$

$$x = 0.993.$$

Thus, if we take 0.993 grammes (15.33 grains) of the specimen, the number of centigrammes of carbonic acid expelled will indicate the per centage amount of peroxide. But as the quantity of carbonic acid obtained would be too minute to admit of a direct determination of its weight, it is advisable to take a multiple of 0.993 grammes, and to divide the number of centigrammes of carbonic acid obtained by the same number, which has served as a multiplier. The multiple by 3, *i. e.* 2.98 grammes, is deemed by the authors the quantity best adapted for the examination. Should the manganese contain carbonated alkaline earths, which is sometimes the case, it must undergo a preliminary process previous to the examination. To ascertain the presence or absence of carbonate of lime or baryta in the manganese under examination, it is sufficient to moisten a sample powder with dilute nitric acid; their presence is certain if any effervescence take place. The specimen, in that case, is treated as follows:—2.98 grammes of the specimen is projected into *b*, covered with very dilute nitric acid, one part acid to twenty parts of water, and allowed to stand at rest for a few minutes; the supernatant fluid is then poured upon a small paper filter, the manganese remaining in the flask is repeatedly washed with water, as well as the solid particles on the filter, (the super-



nant water being always poured on the filter,) and the latter then thrown into *b*, taking care not to lose a particle of manganese; the further operation is conducted as usual. The neutral oxalate of potash is preferable to free oxalic acid, or to binoxalate of potash, since, when employing the former substance, the evolution of carbonic acid commences only upon the influx of sulphuric acid into *b*, whilst free oxalic acid or binoxalate of potash, begin to evolve carbonic acid immediately upon coming into contact with manganese and water; and this would, of course, interfere with the correctness of the results, rendering it almost impossible to determine the exact weight of the apparatus before the commencement of the operation. Such is the method of examining ores of manganese proposed by the German chemists: the results are most accurate, and the manipulation is so simple, that it will no doubt entirely supersede all the other methods that have been described. It will be observed that, from the almost absolute identity of the equivalent number of carbonic acid multiplied by 2,  $22 \times 2 = 44$ , with that of peroxide of manganese, 43.67, the calculation of the quantity of real peroxide in a specimen of manganese becomes a problem of the utmost simplicity; and that, if we take 100 grains of the specimen, the loss of weight in *grains* will denote the per centage proportion of pure peroxide. One atom of peroxide of manganese,  $\text{MnO}_2 = 43.67$  contains one atom of oxygen, separable by sulphuric acid, and capable of converting one atom of oxalic acid into two atoms of carbonic acid. Thus:—



Dr. Ure recommends 250 grains of oxalate of potash to 100 grains of the sample.

Ebelmen's method is to treat the oxide of manganese with muriatic acid; the chlorine disengaged is received in a solution of pure sulphurous acid, part of which acid is converted into sulphuric acid. When the reaction is completed, solution of chloride of barium, and a little muriatic acid, are poured in the liquor; the muriatic acid being employed for dissolving the sulphite of baryta, which is produced simultaneously with the sulphate, and which, being but sparingly soluble, would remain mixed with it; the liquor is then boiled, for the purpose of expelling the excess of sulphurous acid, filtered, and

the precipitate of sulphate of baryta is dried, from the weight of which the quantity of the peroxide of manganese contained in the sample is calculated: 100 of sulphate of baryta corresponds to 37.5 of peroxide of manganese.

A simple manner of analyzing manganese is the following. A certain quantity of the purified and well-dried manganese is introduced into a small counterpoised retort, to which a counterpoised tube, containing chloride of calcium, is adapted. After calcining it, the augmentation of the weight of the chloride of calcium indicates the quantity of water which has volatilized, and which proceeds from the hydrated sesquioxide, a portion of which is always contained in the peroxide: the diminution of the weight of the retort indicates how much water and oxygen have escaped. Yet it is not possible, by merely calcining in the retort, to convert the peroxide of manganese completely into manganoso-manganic oxide; wherefore the contents of the retort must be emptied in a small platinum crucible and therein ignited, until, after repeatedly weighing it, the weight remains constant. The mass becomes thus completely converted into manganoso-manganic oxide. If the ignition is carried on with a spirit-lamp with circular wick, small quantities only must be operated upon, and the mass must be kept red hot for a long time, in order to obtain a complete conversion. When the quantity of the mass is considerable, an ordinary fire is used. 100 of oxygen disengaged, represent 818.85 of pure peroxide. Whence it may be seen that great precision is required in this experiment, since a small quantity of oxygen corresponds to a great quantity of peroxide. 100 parts of water evaporated, correspond to 981.76 of hydrate of sesquioxide.

### *Iron.*

This metal is, under all circumstances, weighed as sesquioxide,\* if it exist in the solution in the form of a protosalt, it must be peroxidized by heating with nitric acid as long as fumes of nitrous vapor are discharged: ammonia is the pre-

\* Liebig proposes a direct means of estimating iron in the dry way as follows:—The finely powdered ore is mixed with cyanide of potassium and carbonate of potassa, and then heated in a porcelain crucible to high redness. The alumina and silica remain with the scories, and the reduced metal may be separated by washing with cold water and then weighed.


precipitant employed, as the oxide precipitated by potassa or soda is always contaminated by a certain quantity of the alkali, from which it is almost impossible to free it by washing: the hydrated sesquioxide shrinks greatly on drying, and, by ignition, loses all its water. Iron is sometimes precipitated as sulphuret by hydrosulphuret of ammonia: the solution must not contain free acid: it must be well washed on the filter with water, to which a few drops of hydrosulphuret of ammonia have been added, the funnel being protected from the air with a glass plate to prevent a portion of the sulphuret from becoming oxidized into sulphate, which would dissolve and be carried through the filter: the washed sulphuret is, together with the filter, digested with dilute hydrochloric acid, filtered, and the filtrate peroxidized by nitric acid and precipitated by ammonia. When iron has to be separated from other bases, it is sometimes precipitated by *succinate of ammonia*: the solution must be very exactly neutralized by ammonia, the alkali being added in drops in a very diluted state until the small quantity of sesquioxide of iron which it precipitates is not redissolved by applying a gentle heat, the supernatant liquid possessing a red color; the neutral succinate of ammonia is then added, upon which succinate of peroxide of iron of a brown color is precipitated; it is filtered when quite cold, and washed first with cold water, and, finally, with a warm solution of ammonia, in order to remove a portion of the succinic acid: it is then dried and ignited in a current of air, in order thoroughly to peroxidize the iron. The sesquioxide of iron is—

|                                           |     |    |     |     |
|-------------------------------------------|-----|----|-----|-----|
| Two equivalents of Fe                     | ... | 56 | ... | 70  |
| Three do. of O                            | ... | 24 | ... | 30  |
| <hr/>                                     |     |    |     |     |
| One do. of Fe <sub>2</sub> O <sub>3</sub> | ... | 80 | ... | 100 |

*Separation of Peroxide of Iron from Protoxide of Iron.*—

This is attended with very great difficulties, and can only be accomplished when the compound is soluble in acids. When no other base but iron is present, as, for example, in native magnetic iron ore, *Rose* directs that a weighed quantity of the substance should be dissolved in hydrochloric acid, and, having boiled with nitric acid to peroxidize the whole of the iron, it is to be precipitated by ammonia; the increase of weight is owing to the acquisition of oxygen, which has com-

bined with the protoxide of the compound, and is *half as much in quantity* as the oxygen previously existing in the protoxide, for the protoxide of iron, on being fully converted into peroxide, acquires one-half more oxygen than it already possessed.



Thus, then, finding first the quantity of oxygen gained by the substance operated on, we find next the quantity of oxygen belonging to the protoxide existing in the compound, and from this it is easy to calculate the quantity of the protoxide. When this is found, the quantity of peroxide contained in the substance is learned from the difference in weight between the quantity of the compound submitted to analysis and the quantity of protoxide made out by calculation. It is easy, however, to see that, as the proportion of protoxide of iron is generally very small in comparison with that of peroxide, the greatest accuracy in experimenting is necessary, in order to arrive at correct results, a very trifling error becoming a very considerable one in the subsequent calculation of the quantity of protoxide.

Another method, given by *Rose*, for determining the quantity of oxygen in a compound consisting merely of protoxide and peroxide of iron, is by converting the oxides into metallic iron by igniting them in a current of dry hydrogen gas, and determining not only the quantity of iron revived, but also the weight of the water formed.


To determine experimentally the quantity of peroxide of iron in a soluble compound of peroxide and protoxide, a weighed quantity of the pulverized mixture is introduced into a flask, the whole of the atmospheric air from which is then expelled by a current of carbonic acid gas; hydrochloric acid sufficient to dissolve the compound is then added, and the flask quickly and securely closed. Solution being effected, recently prepared perfectly clear sulphuretted hydrogen water is added in excess, and the flask again closed, and allowed to remain at rest for some days; the peroxide of iron is reduced to protoxide by the sulphuretted hydrogen, and a proportional quantity of sulphur is deposited; this is carefully collected on a small weighed filter, washed and dried at a gentle heat; the filter must be protected from the atmosphere during the process of filtration; from the weight of the sulphur the quantity of oxygen that has entered into combination with



the hydrogen of the decomposed sulphuretted hydrogen is found, this oxygen was derived from the peroxide of iron; and, by multiplying it by three, the whole quantity of oxygen that was present in the substance in the form of sesquioxide of iron is found. Every sixteen grains of sulphur that are deposited indicate the abstraction of three grains of oxygen, and the presence of seventy grains of sesquioxide in the specimen.

Another method of analyzing a mixture of the two oxides is the following, given by *Fresenius*:—A known quantity of the finely divided substance is introduced into the flask A (Fig. 10), which is then filled with carbonic acid through the tube *d*; hydrochloric acid, not in great excess, is then added through the funnel *c*, and

Fig. 10.




the solution of the compound assisted by heat; a stream of carbonic acid passing all the time through the apparatus, hot water is next added, and the solution boiled and allowed to cool; pure recently precipitated carbonate of baryta is now mixed into a milky fluid, and poured into the flask through the funnel till it predominates; the whole mixture is then digested at a very gentle heat. The flask is filled

with boiling water nearly up to the end of the tube *b*, which, being depressed as far as necessary into the liquid, the clear fluid is drawn off; the tube is then raised, and the flask again filled with boiling water; when the precipitate has settled, the clear fluid is again drawn off by the syphon *b*; the flask is then rinsed out with boiling water, and the precipitate thrown on a filter, and well washed with boiled water, as much as possible out of access of air: the amount of peroxide of iron in the washed precipitate is then determined. The liquid is drawn off by the syphon, and the filtrate from the precipitate contains the whole of the dissolved protoxide of iron; the so-

lution is concentrated, the iron peroxidized, and, finally, precipitated after the removal of the *baryta*.

*Indirect Method of determining the quantity of Protoxide of Iron in a mixture of Protoxide and Peroxide.*—*Rose's Method.*—A weighed portion of the substance is dissolved in hydrochloric acid in a flask, which has previously been filled with carbonic acid gas; the solution being effected, solution of *chloride of gold and sodium* is added in excess, and the flask closed; reduction takes place, and metallic gold is precipitated, which is collected, washed, ignited, and weighed; from the quantity obtained, the quantity of oxygen, which was necessary to convert the protoxide of iron into peroxide, is ascertained by calculation, thus:—



one equivalent of precipitated gold corresponds to six equivalents of protochloride or protoxide of iron.

*Fuch's Method.*—A weighed portion of the substance is dissolved, as in *Rose's* method, in hydrochloric acid, in a flask which has previously been filled with carbonic acid gas; a weighed slip of clean copper is introduced, and the flask, having been filled nearly to the brim with boiled water, accurately closed; the mixture is digested until the fluid becomes colorless, or nearly so; the slip of copper is then removed from the flask, dried, and weighed; the diminution in weight indicates the amount of chlorine consumed to convert the original protochloride of iron into perchloride, every equivalent of copper corresponding to an equivalent of chlorine, and every one equivalent of chlorine converting *two* equivalents of protochloride of iron into perchloride  $2\text{FeCl} + \text{Cl} = \text{Fe}_2\text{Cl}_3$ ; it follows that every equivalent of dissolved copper corresponds to two equivalents of perchloride of iron in the solution, or, what amounts to the same, to two equivalents of peroxide of iron present in the analyzed substance. The quantity of iron actually present in the specimen must be determined by peroxidizing a solution of a weighed quantity, and precipitating by ammonia. The method is founded on the fact that, when air is excluded, hydrochloric acid is incapable of dissolving copper; but that on the addition of peroxide of iron, or when that substance is already present in the mixture, the acid dissolves a quantity of copper corresponding thereto.

*Separation of Iron from Manganese.*—The iron in the solution is first brought to the state of sesquioxide, and is then

precipitated by succinate or benzoate of ammonia, a sufficient quantity of sal-ammoniac having previously been added; the precipitated succinate is treated in the manner already described, and the manganese in the filtrate is precipitated by carbonate of soda. Another method of separation is by digesting the solution of the two metals with excess of recently precipitated carbonate of baryta, which throws down the iron as basic carbonate of peroxide; the washed precipitate is dissolved in hydrochloric acid, the baryta separated by sulphuric acid, and the iron precipitated by ammonia; the filtrate from the basic carbonate of peroxide of iron contains the manganese, together with a soluble baryta salt; the latter is removed by sulphuric acid, and the manganese precipitated by carbonate of soda.

*Separation of Iron from Cobalt and Nickel.*—The iron is peroxidized, and precipitated by succinate or benzoate of ammonia, and the cobalt and nickel in the filtrate separated and estimated by one of the methods described (page 279).

*Separation of Iron from Zinc.*—The iron in the solution is peroxidized by nitric acid, the solution is evaporated to dryness, and all excess of acid removed; the residue is dissolved in acetic acid; free acetic acid is added, and the zinc precipitated by sulphuretted hydrogen; the precipitated sulphuret of zinc should have a pure white color.

*Separation of Iron from Chromium.*—*Rose's Method.*—To the solution of the two metals a sufficient quantity of tartaric acid is added, to prevent the precipitation of either of the metals by potassa;\* that alkali is then added, and the iron precipitated by sulphuret of potassium; the solution filtered from the sulphuret of iron contains the oxide of chromium: it is evaporated to dryness, ignited, fused with carbonate of soda and nitre, and the chromium in the alkaline chromate thus formed determined as directed (page 264).

*Berthier's Method.*—The oxides are precipitated by ammonia or carbonate of ammonia; and, while still moist, digested with slight excess of sulphurous acid; the whole of the iron dissolves, and also a certain quantity of the oxide of chromium, while the remainder of this latter metal is converted into pure subsulphite. The solution is boiled until it is de-

\* Rose directs ammonia to be added, and the iron to be precipitated by hydrosulphuret of ammonia; but, according to Fresenius, tartaric acid does not prevent the precipitation of oxide of chromium by ammonia.

colorized, when it only contains iron. To precipitate this metal, the sulphurous acid is expelled, either by sulphuric acid or by aqua regia; an alkali or an alkaline carbonate is then added, or the iron is precipitated by an alkaline hydrosulphuret without expelling the sulphurous acid.

*Liebig's Method.*—A mixture of the two metals in solution is first saturated with sulphuretted hydrogen, to be certain that the iron is contained in the liquid as protoxide, (an addition of a few drops of hydrosulphuret of ammonia answers the purpose,) and then thrown down by cyanide of potassium, and an excess of the latter added; the iron then dissolves immediately as ferrocyanide of potassium, while the oxide of chromium remains behind.

*Analysis of Chromic Iron Ore.*—The finely levigated mineral is fused with caustic, or preferably bisulphated potassa (*Booth*), (alkaline carbonate will not do). The fused mass is extracted with water, which dissolves the chromate of potassa, together with the excess of potassa; the oxide of iron remains behind, together, perhaps, with a small quantity of the undecomposed ore, which is separated from the sesquioxide of iron by hydrochloric acid: from the hydrochloric solution the iron is precipitated by ammonia, and the chromic acid in the aqueous solution is reduced to sesquioxide of chromium by hydrochloric acid and alcohol: if the mineral contained alumina, it will be found in the aqueous solution with the alkaline chromate, and will be precipitated together with the oxide of chromium, from which it is separated in the manner described (at page 266.)

*Separation of Iron from Yttria.*—*Scherer's Method.*—To a neutral solution, oxalate of potassa is added: a white crystalline precipitate, consisting of the double oxalate of yttria and potassa, is gradually formed, which, by ignition, is converted into yttria and carbonate of potassa; the mixture is dissolved in hydrochloric acid, diluted with much water, and the yttria precipitated by caustic ammonia: it must be well washed with boiling water, after which it may be ignited and weighed.

*Berthier's Method.*—The moist hydrates are boiled with sulphurous acid, the yttria is deposited, and the iron remains in solution; to prevent the formation of an ochreous deposit from the action of the air, the solution should be boiled in a flask with a long neck, and when no more sulphurous acid is



disengaged, it should be filled with boiling water and corked: when it has become cold the liquid is decanted on to a filter replaced by boiling water, and finally filtered and edulcorated.

*Separation of Iron from Alumina.\**—The solution containing the two oxides (the iron being in the state of sesquioxide) is concentrated by evaporation, and digested with excess of caustic potassa, in which the alumina alone dissolves. *Dr. Knop* recommends the addition of a suitable quantity of hydrosulphuret of ammonia to the alkaline ley, or when practicable, the direct precipitation of the two oxides with hydrosulphuret of ammonia, the precipitate being washed with water containing hydrosulphuret of ammonia, and the alumina subsequently extracted with potassa, to which a few drops of hydrosulphuret of ammonia have been added, in order to obtain at once a perfect precipitation and separation of these two bodies. According to *Berthier*, the method above described for separating iron from yttria may also be applied for separating the same metal from alumina.

*Separation of Sesquioxide of Iron from Magnesia.*—Muriate of ammonia is added to the solution, then caustic ammonia; the iron is precipitated, carrying with it a small portion of the magnesia, from which it is freed by again dissolving in hydrochloric acid; and, after exactly neutralizing with ammonia, precipitating by succinate or benzoate of ammonia, the magnesia in the filtrate from the first and second operations is determined as pyrophosphate.

*Separation of Sesquioxide of Iron from Protoxide of Manganese, Magnesia, Alumina, Lime, and Fixed Alkali.*—Muriate of ammonia is first added to the solution, the *sesquioxide of iron* and *alumina*, together with small portions of protoxide of manganese and magnesia, are precipitated by ammonia; it is filtered as quickly and with as little exposure to the air as possible. The precipitate, after being well washed, is dissolved in hydrochloric acid, excess being avoided. The solution is supersaturated with caustic potassa and digested. Alumina dissolves, and is precipitated from the alkaline ley in the manner directed (at page 260). To the filtrate from the first precipitate by ammonia oxalate of ammonia is added, by which the lime is separated. The filtrate from the oxalate of lime contains the greater part of the magnesia, and



\* See Chapter VI.

protoxide of manganese, and the alkali; the residue, insoluble in caustic potassa, consists of sesquioxide of iron, together with small quantities of protoxide of manganese and magnesia. After being well washed it is dissolved in hydrochloric acid, diluted with water, neutralized with ammonia, and the sesquioxide of iron precipitated by succinate of ammonia. The filtrate is added to the filtrate from the oxalate of lime, concentrated by evaporation, and the protoxide of manganese precipitated by hydrosulphuret of ammonia; the filtrate from the sulphuret of manganese containing the magnesia and the alkali is warmed to decompose the excess of hydrosulphuret of ammonia. It is filtered from the sulphur, and evaporated to dryness with sulphuric acid; the magnesia and alkali are hereby converted into sulphates. The mixture is ignited in a platinum crucible with a fragment of carbonate of ammonia, in order to convert the bisulphates into neutral sulphates; the mixture is weighed, dissolved in water, and acetate of baryta added in sufficient quantity to remove all the sulphuric acid in the form of sulphate of baryta. The mixture is warmed, and the sulphate of baryta filtered off. The filtrate contains acetates of magnesia and alkali, together with the excess of acetate of baryta: it is evaporated to dryness and ignited in a platinum capsule; by this treatment the acetates are converted into carbonates; the carbonate of the alkali present being soluble is easily removed by hot water, the solution may be evaporated to dryness, and the alkali converted into and weighed as *sulphate*. The carbonates of baryta and magnesia remain undissolved; they are dissolved in hydrochloric acid, the baryta separated by sulphuric acid, the filtrate evaporated to dryness, and the magnesia estimated as sulphate. This method of separating magnesia from alkalies, given by Rose, is very tedious, and requires considerable dexterity in manipulation in order to yield accurate results; it is, therefore, far preferable, instead of converting the magnesia and alkali into sulphates, to convert them into chlorides, and to treat the solution with red oxide of mercury, as directed (p. 259).

*Quantitative determination of Iron in Iron Ores.*—The method proposed by *Fuch* has already been alluded to, (p. 292.) The specimen is dissolved in strong and pure hydrochloric acid and peroxidized, either by cautiously adding crystals of chlorate of potassa, or by passing a current of chlorine through the liquor, till a drop of it let fall into a solution of

red prussiate of potash gives no tinge of blue. It is then to be boiled for a few minutes, to expel the excess of chlorine, and a weighed quantity of pure copper introduced; the boiling is to be continued without intermission till the liquor passes off to a pale yellow green. When no further change of color is observed to take place, the flask must be filled up with hot water, and the copper removed, washed in cold water, dried and weighed. This method requires great care to give results at all approaching to accuracy, and is altogether inapplicable in the presence of arsenic acid. The method which has generally been resorted to, consists in performing, on a small scale, the operations carried on in the blast furnace for the production of the metal, namely, by mixing the ore with fluxes varying with the nature of the ore, and exposing it in a crucible lined with charcoal to an intense long-continued heat. The button of cast iron thus obtained indicates the richness of the ore: but as the flux may occasionally retain appreciable quantities of iron, which may also be disseminated throughout the ores, and, moreover, as the metallic button obtained may be contaminated by *carbon, silicium, phosphorus, arsenic and manganese*, it is evident that no great dependence can be placed on the result of this process.

*Method of Marguerite.*—This is based on the employment of a normal test solution, and on the reciprocal action of the salts of *protoxide of iron* and *permanganate of potassa* (chameleon mineral), whereby a quantity of the latter is decomposed exactly proportionate to the quantity of iron. The ore is dissolved in hydrochloric acid, and the metal brought to the minimum of oxidation, which is done by treating the solution with *sulphite of soda*, and boiling to expel the excess of sulphurous acid; the solution of permanganate of potassa is then added cautiously until the pink color appears, and the number of divisions of the burette required for the purposes accurately noted. The theory of the process is as follows:—



one equivalent of permanganate of potash is equal to two equivalents of protoxide of manganese, one of potassa, and five of oxygen, and these five equivalents of oxygen suffice to peroxidize ten equivalents of protoxide of iron. There must be a sufficient quantity of free acid present, to keep in solution the peroxide of iron formed, as also the potassa and prot-

oxide of manganese. The whole of the iron must be at the *minimum* of oxidation, and the excess of sulphurous acid must be expelled; if the latter precaution be neglected, an erroneous result will be obtained, as the sulphurous acid will itself take oxygen from the permanganic acid, and thus react in the same manner as iron. The author found that the only two metals that interfered with the process are *copper* and *arsenic*, which, if present as arsenic acid and peroxide of copper, might, by the action of the sulphurous acid, become reduced to *arsenious acid* and *protoxide of copper*, which would afterwards withdraw oxygen from the permanganic acid; but, by a slight modification of the general process, both of these sources of error may be obviated. The operation is carried on as usual, except that, after having boiled the solution to expel the excess of sulphurous acid, a piece of pure laminated *zinc* is added, which, acting upon the hydrochloric acid, disengages hydrogen; arsenic and copper are hereby reduced to the metallic state. When the solution of the zinc is complete, the precipitated particles of arsenic and copper are removed by filtration, and the clear liquor proceeded with as before.

To prepare the permanganate of potassa, 7 parts of chlorate of potassa, 10 parts of hydrate of potassa, and 8 parts of peroxide of manganese, are intimately mixed; the manganese must be in the finest possible powder, and the potash, having been dissolved in water, is mixed with the other substances, dried, and the whole heated to very dull redness for an hour. The fused mass is digested in water, so as to obtain as concentrated a solution as possible, and dilute nitric acid added, till the color becomes of a beautiful violet; it is afterwards filtered through asbestos, in order to separate the oxide of manganese which it holds in suspension. The solution must be defended from the contact of organic matter, and kept in a glass-stoppered bottle. To convert the solution into a test liquor of known value, a certain quantity, say 10 grains, of pure iron, such as harpsichord wire, is dissolved in pure hydrochloric acid; after the disengagement of hydrogen has ceased, and the solution is complete, the liquor is diluted with about half a pint of cold water, and the solution of the permanganate of potassa added, until a slight pink color becomes manifest, and the number of divisions of the burette necessary to produce this effect carefully noted; this number is then



employed to reduce into weight the result of an analysis of ore.

*Separation of Phosphoric Acid from Iron.\*—Berthier's Method.*—The compound is dissolved in hydrochloric acid, and sulphurous acid, *sulphite of ammonia*, and *alum* in sufficient quantity added; the solution is then boiled, the alumina of the alum is precipitated, carrying with it the phosphoric acid. If arsenic be present, it remains wholly in solution, in the state of arsenious acid.

*Determination of the amount of Carbon in Cast Iron.*—The specimen is pulverized in a steel mortar, mixed with a sufficient quantity of oxide of copper, and burned, as in the method for determining the carbon in organic substances; the combustion is perfect, and the results are accurate.†

*Determination of Sulphur in Iron.*—*Dr. Bromies* employs an apparatus similar to that of Will and Varrentrap for nitrogen analyses. Instead, however, of two bulbs there are four, in order that the sulphuretted hydrogen evolved during the solution of the iron in dilute sulphuric, may be completely absorbed by the *ammoniacal solution of silver* with which the bulbs are filled. The silver is estimated in the form of sulphuret of silver.

### Uranium.

This metal is generally precipitated from its solutions by caustic ammonia. The precipitate, which is yellow, is washed on the filter with a dilute solution of muriate of ammonia; it is then dried and heated, by which it is converted into the green oxide, the composition of which is

|                      |     |    |     |       |
|----------------------|-----|----|-----|-------|
| One equivalent of Ur | ... | 60 | ... | 88.23 |
| One do. of O         | ... | 8  | ... | 11.77 |
|                      |     | —  |     | —     |
| One do. of UrO       |     | 68 |     | 100   |

*M. Ebelmen* has published the following remarks on the determination of this metal.‡ The tendency of the oxide of uranium to combine with bases, gives rise to its frequently

\* See Chap. VI.

† Prof. R. E. and W. B. Rodgers use a mixture of bi-chromate of potassa and sulphuric acid, which, when applied in large excess to finely powdered graphite, rapidly converts it into carbonic acid—*Ch. Gaz.*, vi. 356.

‡ *Ann. de Chim. et de Phys.*, Juin, 1842; and *Chem. Gaz.*, vol. i. p. 207.

carrying down along with it, in its precipitation by ammonia, bases which are not precipitated when alone by that reagent, such as barytes and lime. If the liquid contains much potash, a considerable quantity is often found in the precipitate, which is easily recognized by the orange yellow colour perceptible at various parts of the heated precipitate. Sulphuretted hydrogen separates uranium from a great number of metals. The oxide may be separated very easily from the peroxide of iron by means of carbonate of ammonia; but those metals whose oxides dissolve in part or wholly in carbonate of ammonia, such as *manganese*, *zinc*, *cobalt*, and *nickel*, have been regarded difficult of separation from uranium. The use of the carbonates of soda and of potash affords a very exact and simple means of effecting their removal; for urinate of potash is not soluble in the subcarbonate of potash, but it dissolves completely, and in very little time, in a liquid saturated with a bicarbonated alkali. When a solution of a salt of uranium is precipitated with a slight excess of carbonate of potash, and the liquid diluted with water, the whole of the uranium is dissolved, and imparts to it a yellow color. In both cases the double salt of potash is formed. The carbonate of *zinc*, *cobalt*, and *manganese* are, on the contrary, insoluble in carbonate of potash. To effect their separation the solution may be thrown down, either by potash, the precipitateedulcorated and digested with bicarbonate of potash, which will only dissolve the oxide of uranium, or by slight excess of carbonate of potash, the precipitate being collected on a filter, and washed as long as the liquor which passes through is colored. On adding to a solution of the phosphate or arseniate of uranium, in an excess of carbonate of potash, a known quantity of sesquioxide of iron dissolved in nitric acid, those two acids may be completely separated from the uranium, and their proportion determined by the increase in weight of the peroxide of iron. The oxide of uranium may also be separated by potash, and the phosphoric and arsenic acids left in solution.

To separate the oxide of uranium in solution, it may be saturated with hydrochloric acid, boiled to expel the carbonic acid, and the uranium precipitated by ammonia; but as the liquor contains much potash the precipitate retains a certain quantity, and is not entirely converted into the state of green oxide, which makes it necessary to redissolve it, and precipitate again with ammonia.

To extract uranium with great precision from the urinate of potash dissolved in hydrochloric acid, the whole is evaporated to dryness in a platinum crucible gradually heated, and a current of dry hydrogen conveyed into it as long as the gas which is given off possesses an acid reaction. The double chloride of potassium and uranium is converted into uranium (so called) in the form of a black powder, which is separated by washing from the chloride of potassium.

*Separation of Uranium from Nickel, Cobalt, and Zinc.*—When the oxide of uranium in its preparation from *pitchblende* is so far purified as to be dissolved in carbonate of ammonia, *Wohler* directs to mix hydrosulphuret of ammonia with the solution as long as a black precipitate falls; in this way the nickel, cobalt, and zinc are entirely separated, no uranium being precipitated. According to *Berthier*, uranium is completely separated from *iron, manganese, cobalt, nickel, and zinc*, by boiling the solution after the addition of sulphate of ammonia. The whole of the uranium precipitates in yellow grains as basic sulphite.

*Analysis of Pitchblende.*—Of the various methods which have been employed by different chemists, the following, adopted by *Arfwedson*, seems on the whole the best. The mineral is reduced to fine powder, and digested with boiling aqua regia; the solution is evaporated on a water bath, to expel the excess of acid, then diluted with water, and precipitated by sulphuretted hydrogen, sulphurous acid being previously added to reduce the arsenic acid to arsenious acid: *arsenic, copper, lead, and bismuth* are in this manner precipitated. The solution is filtered, the excess of sulphuretted hydrogen expelled by boiling, and ammonia added; the precipitate thereby formed is washed and dissolved, while yet moist, in carbonate of ammonia, peroxide of iron remains undissolved, and is separated by filtration. The solution is evaporated till the ammonia is volatilized, whereupon the peroxide of uranium is rendered insoluble; it is washed, dried, and calcined in a platinum crucible, by which it becomes converted into *urano-uranic oxide* of a green color. The urinates of lime, zinc, cobalt or nickel, which may have been present in the solution, are not decomposed by the calcination; they are readily dissolved, however, by dilute hydrochloric acid, which acid serves, therefore, to separate them from the urano-uranic oxide, which is thus obtained pure. It is washed first with dilute acid, and then with distilled water.

From the metallic urينات in solution in hydrochloric acid oxide of uranium may be obtained. For this purpose the solution is precipitated by ammonia, the dried precipitate is reduced by hydrogen gas, and treated immediately with hydrochloric acid, which dissolves all the foreign metals, leaving protoxide of uranium insoluble.

## GROUP 5.

*Lead, Silver, Mercury, Bismuth, Cadmium, Copper, Palladium.*

### *Lead.*

This metal is completely precipitated from its acid solutions by *sulphuretted hydrogen*; it is also precipitated by *sulphuric acid*, by *carbonate of ammonia*, by *oxalate of ammonia*, and by *hydrochloric acid*, and it may, therefore, be weighed as *sulphuret*, *sulphate*, *chloride*, and as *oxide*, the latter being produced by igniting with free access of air the carbonate and oxalate.

*Precipitation as Sulphuret.*—A stream of washed sulphuretted hydrogen gas is transmitted through the solution, rendered slightly acid with nitric acid until it is completely saturated, a gentle heat is then applied, and the precipitated sulphuret is filtered as quickly and with as little access of air as possible, in order to avoid the decomposition of a portion of the sulphuretted hydrogen, which would occasion a precipitation of sulphur; as it is difficult, even with great care, to prevent this, it is better to convert the washed sulphuret of lead into sulphate, which is done by transferring it, filter and all, into a beaker, and pouring on it concentrated and fuming nitric acid, the sulphur becomes hereby oxidized into sulphuric acid; a gentle heat is applied to assist the action, the mixture is carefully transferred into a small Berlin crucible, and a few drops of sulphuric acid being added, it is evaporated to dryness and ignited. The composition of sulphate of lead is

|                                 |     |        |     |       |
|---------------------------------|-----|--------|-----|-------|
| One equivalent of PbO           | ... | 111.56 | ... | 73.61 |
| One do. of SO <sub>3</sub>      | ... | 40.00  | ... | 26.39 |
|                                 |     | <hr/>  |     |       |
| One do. of PbO, SO <sub>3</sub> |     | 151.56 |     | 100   |



With respect to the precipitation of lead by sulphuretted hydrogen, the following observations have been made by *Dr. Vogel*. In precipitating lead with sulphuretted hydrogen it is usual to warm the liquid, to prevent any of the precipitate from passing through the filter, but this may give rise to considerable loss. If sulphuretted hydrogen be passed through a moderately strong solution of acetate of lead, until the filtered liquor contains no more metal, and is consequently not rendered turbid either by sulphuretted hydrogen or by sulphuric acid, and if the liquor be now warmed, a further precipitate is produced by sulphuretted hydrogen after filtration; the liberated acetic acid evidently decomposes the sulphuret of lead. The same is the case with nitrate of lead, and remarkably so with the chloride. This is of considerable importance where lead has to be separated from chlorides, and where it cannot be precipitated by sulphuric acid. With *mercury* and *bismuth* no such decomposition of the sulphuret occurs, and only in a slight degree with *antimony*. The above behavior may even be employed for the separation of some metals. If, for example, sulphuretted hydrogen be passed into a liquid containing *nitrate of bismuth* and *nitrate of lead*, until no further precipitate occurs, and the whole be then heated to boiling, the sulphuret of lead is entirely redissolved, while the sulphuret of bismuth is not attacked. The lead may then be precipitated from the solution by sulphuric acid.

*Precipitation of Lead by Sulphuret of Sodium.*—A method of estimating lead by means of a normal solution of sulphuret of sodium has been proposed by *Domonté*, and is described by him as simple, quick, and accurate, and well adapted for the examination of *white lead* and *acetate of lead*, substances which, as met with in commerce, are often greatly adulterated. To prepare the normal solution of sulphuret of sodium, about 300 grains are dissolved in a pound of water, a certain known quantity of lead is dissolved in nitric acid, precipitated, and redissolved by caustic potassa; the solution of sulphuret of sodium placed in a graduated burette is added carefully to the alkaline solution, which is maintained at a temperature near to ebullition. Each addition of the sulphuret produces a black precipitate of sulphuret of lead; from time to time the liquid is boiled, and the precise point at which a drop of the reagent produces no further precipitate is carefully ob-

served. The number of divisions of the burette which have been required represents the value of the lead employed in the experiment: thus, suppose 10 grains of lead to have been used, and 30 burette divisions of the alkaline sulphuret have been consumed, then, in all analyses of commercial products, for every 30 divisions of the burette that are required the operator may infer that 10 grains of lead are present.

The author does not find the success of the experiment to be interfered with by the presence of *tin*, *antimony*, *arsenic*, *iron*, *cobalt*, *nickel*, or *zinc*. The first three metals are not precipitated by an alkaline sulphuret; in the presence of excess of free alkali, *zinc* is precipitated *after* the lead, but the color of the sulphuret being white, renders its presence rather an advantage than otherwise; *copper* complicates the process. It is necessary in the first place to determine this metal by the method of *Pelouze* (to be described hereafter). *Domonté* then makes a synthetic assay on a mixture formed of a weight of copper equal to that found by experiment, and of lead equal in weight to that employed in preparing the standard solution. This assay shows by how many divisions the plumbimetric liquor ought to be diminished on examining the alloy. The number is, in fact, the difference between the results of the assay of pure lead, and those of the assay of the mixture of lead and copper. This being done, he examines the alloy in the ordinary way. *Bismuth* cannot be separated from lead in this way, but, commercially speaking, it is not likely that this metal will be found to occur as a contamination, its higher price being a guarantee.

*Quantitative estimation as Sulphate.*—When lead is to be weighed in the form of this salt, the solution is precipitated by dilute sulphuric acid, and then mixed with twice its volume of alcohol, sulphate of lead not being altogether insoluble in water; it is collected on a filter, on which it is washed with spirits of wine. Its composition has been given above.

*Quantitative estimation as Oxide.*—(a.) *Precipitation as Carbonate.*—Carbonate of ammonia, mixed with a little caustic ammonia, is the precipitant employed, and the solution is heated; it is washed on the filter with pure water, and afterwards ignited in a porcelain crucible, by which it is converted into protoxide of lead. The precipitate is removed as completely as possible from the filter, and the latter is ignited

alone, the residue being afterwards mixed with the ignited precipitate; the object of this is to prevent the reduction of a portion of the protoxide of lead by the organic matter of the filter. The same observation applies to the sulphate.

(b.) *Precipitation as Oxalate.*—Rose prefers *oxalate of ammonia* as the precipitant of oxide of lead from its solutions, which must be either neutral or weakly ammoniacal. The precipitated oxalate of lead is converted into protoxide by ignition in an open porcelain crucible, having, as in the two former cases, been removed as much as possible from the filter, the latter being ignited alone.

The composition of protoxide of lead is

|                            |        |       |       |
|----------------------------|--------|-------|-------|
| One equivalent of Pb . . . | 103.56 | . . . | 92.82 |
| One do. of O . . .         | 8.00   | . . . | 7.18  |
| <hr/>                      |        |       |       |
| One do. of PbO . . .       | 111.56 |       | 100   |

*Quantitative estimation as Chloride.*—The solution is precipitated by excess of hydrochloric acid, concentrated by evaporation in the water bath, and the residue washed with absolute alcohol, mixed with ether. As chloride of lead is volatilizable, it must not be ignited, but dried at a high temperature, at a gentle heat. Its composition is

|                            |        |       |       |
|----------------------------|--------|-------|-------|
| One equivalent of Pb . . . | 103.56 | . . . | 74.47 |
| One do. of Cl . . .        | 35.50  | . . . | 25.53 |
| <hr/>                      |        |       |       |
| One do. of PbCl . .        | 139.06 |       | 100   |

Lead is completely separated from the metals that have hitherto been treated of by means of sulphuretted hydrogen; the solution must be acidified with nitric acid, and considerably diluted.

### *Silver.*

This metal is weighed as *chloride*, as *sulphuret*, as *cyanide*, or in its pure *metallic* state.

*Quantitative estimation as Chloride.*—To the solution contained in a long-necked flask, and acidified with nitric acid, hydrochloric acid is added in excess; the whole is then well agitated, and allowed to remain for several hours in a warm place: the clear fluid is carefully separated by decantation from the precipitated chloride, which is then washed with

water acidulated with hydrochloric acid. It is then transferred to a weighed porcelain crucible, in which the washing is continued with distilled water till all traces of acid are removed, the various washings are collected in a beaker, and, if the whole be not perfectly clear, it must be allowed to stand in a warm place for several hours, and the precipitate, if any should form, must be added to the contents of the porcelain crucible. The chloride of silver, having been perfectly washed, is heated to incipient fusion, and weighed; it may afterwards be completely removed from the crucible by reducing it by means of dilute sulphuric acid and zinc. Should the quantity of chloride obtained in the experiment be small, it may be advisable to collect it on a filter, from which it should, after washing, be removed as completely as possible, and the filter, with the residue remaining on it, burnt, on the cover of the crucible, the ashes mixed with the bulk of the chloride, which is then heated to incipient fusion in a counterpoised porcelain crucible as before. According to *Rose*, it is not admissible to precipitate silver by the *chlorides of potassium, sodium, or ammonium*, as these salts, particularly the latter, are capable of retaining traces of silver in solution. In cases where the presence of much chloride of ammonium is unavoidable, *Gay Lussac* and *Liebig* recommend to evaporate the solution filtered from the chloride of silver nearly to dryness, and to treat the residue with nitric acid; on exposing the whole to heat, the alkaline chlorides are converted into nitrates, while the small quantity of chloride of silver remains unaltered, and does not dissolve when the mixture is diluted.

The composition of chloride of silver is—

|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Ag | ... | 108.0 | ... | 76.26 |
| One do. of Cl        | ... | 35.5  | ... | 24.74 |
| One do. of AgCl      |     | 143.5 |     | 100   |

*Quantitative estimation as Sulphuret.*—Washed sulphuretted hydrogen gas is transmitted through the solution as long as a precipitate continues to form; the whole is then warmed, and allowed to settle; it is finally collected on a weighed filter, washed as rapidly as possible out of contact of air, and dried at  $212^{\circ}$ . Silver may likewise be precipitated as sulphuret from neutral and alkaline solutions by hydrosulphuret of ammonia; but, as in this case the precipi-



tated sulphuret is invariably accompanied by sulphur, it is necessary to convert it for weighing into chloride, by digesting it with nitric acid, and then precipitating it with hydrochloric acid.

The composition of sulphuret of silver is

|                      |     |     |     |       |
|----------------------|-----|-----|-----|-------|
| One equivalent of Ag | ... | 108 | ... | 87.09 |
| One do. of S         | ... | 16  | ... | 12.91 |
| <hr/>                |     |     |     |       |
| One do. of AgS       |     | 124 |     | 100   |

*Quantitative estimation as Cyanide.*—Cyanide of potassium is added in sufficient quantity to redissolve the precipitate which is at first formed, dilute nitric acid is then added, and a gentle heat applied, by which the whole of the cyanide of silver is re-precipitated. It is washed and dried at  $212^{\circ}$ .

The composition of cyanide of silver is

|                      |     |     |     |      |
|----------------------|-----|-----|-----|------|
| One equivalent of Cy | ... | 26  | ... | 19.4 |
| One do. of Ag        | ... | 108 | ... | 80.6 |
| <hr/>                |     |     |     |      |
| One do. of AgCy      |     | 134 |     | 100  |

Silver, when combined with organic acids, is estimated in the metallic state, to which it is reduced by igniting the salt in a porcelain crucible. The heat should be gentle at first, and the cover on, to prevent loss during the ignition. The lid is afterwards removed, and a strong heat applied for a considerable time, in order to effect complete combustion of the carbon of the organic acid. *Silver* is completely separated from all the metals of the first four groups by sulphuretted hydrogen. The solutions must, in all cases, be acid. From *lead* it may be separated by hydrochloric acid, the solution having previously been largely diluted with water to prevent the precipitation of chloride of lead; or by heating the solution containing both metals with *cyanide of potassium*, which precipitates the lead in the state of carbonate, retaining the silver in solution, as *argento cyanide of potassium*. The silver is subsequently precipitated in the form of cyanide of silver by the addition of nitric acid.

*Estimation of Silver in Alloys by a Standard Solution of Common Salt.*—This method, which was introduced several years ago by *Gay Lussac*, and which is extensively employed in France, consists in dissolving a certain known weight of

the alloy in pure nitric acid, and in determining the exact quantity of a standard solution of common salt, which is required completely to precipitate the silver, the proportion of silver is determined by the volume of the standard solution used. A burette, similar to that shown in *fig. 6*, is employed for measuring the volume of the test liquor, which is added, drop by drop, to the nitric solution of the alloy, until no further precipitation takes place. The number of divisions of the burette required to precipitate a certain weight of pure silver is previously determined. The presence of *copper* and *lead* does not, in the least, interfere with the accuracy of the process; there is, however, one metal which may introduce error, though its presence in silver alloys is very rare, viz., *mercury*, which might be precipitated by the test solution, together with the chloride of silver, in the form of calomel. To avoid this inconvenience, *M. Levol* supersaturates the nitric solution of the alloys with caustic ammonia; he then adds the normal test liquor, and supersaturates the excess of ammonia with acetic acid; he states that by this modification he is able, either with the presence or absence of copper, to estimate accurately silver containing a tenth part of its weight of mercury. The presence of mercury in the precipitate of the chloride of silver, is rendered evident by its non-coloration under the influence of light. *M. Gay Lussac* simplifies this process, by adding to the nitric solution of silver the ammonia and acetic acid at one and the same time, but in sufficient quantity to saturate the whole of the nitric acid, both that in combination with the silver, and that in the free state. He finds acetate of soda to answer quite as well as acetate of ammonia. In preparing the standard solution of salt, it is convenient in practice to have it of such a strength that 100 divisions of the burette shall correspond exactly to 10 grains of pure silver; or, if the operator prefer the continental system of weight and measure, it should be of such a strength that 100 cubic centimetres are required to precipitate 1 gramme of pure silver, and the burette employed should be divided into 1000 parts, so that each division may correspond with a thousandth part of the saline solution. All trouble of calculation is thus dispensed with, since the number of divisions required to effect the complete precipitation, indicates an equal number of thousandths of silver in the alloy operated

upon. In preparing the saline solution, *Gay Lussac* dissolves common culinary salt in a certain quantity of water, and then determines with the greatest care the quantity required to precipitate 1 gramme of pure silver; this being determined, he dilutes the solution with pure water, and brings it to such a strength that 100 cubic centimetres shall be equivalent to 1 gramme of silver; then, suppose 28 cubic centimetres of the first solution are required, this is mixed with  $\frac{72}{28}$  of its volume of distilled water to form the standard liquor: and he finds it convenient in practice to dilute a portion of this normal liquor still further with 9 times its volume of water, so that, when the solution of the alloy is nearly precipitated, it may be completed with a more diluted saline solution, an excess of a few drops of which could do no harm, and 10 cubic centimetres of which correspond with one of the first solution. In these determinations by volume, *temperature* exercises an influence on the result which ought not to be neglected; the dilatation of the two liquors for every variation of temperature may, however, be ascertained once for all, and *Gay Lussac* has calculated and published tables on the subject, which show the changes of volume for each degree above and below  $+15^{\circ}$  Centigrade, as the normal temperature; he has also described a convenient apparatus for the whole analytical process.\* *Berzelius* remarks, that this method is susceptible of greater accuracy than that of cupellation; it effects, moreover, a great saving of time, since several assays may be made at once. On the other hand, it is not so applicable to the determination of small quantities of silver as the process of cupellation; its use is, therefore, confined, in a great measure, to the examination of large ingots and silver coin. It may be observed that the correctness of the results depends not only on the dexterity of the operator, but also upon the exact observation of the moment when the complete precipitation has been effected.

Among the various other methods of separating *silver* from *copper*, two† may be specially noticed. *The first* consists in

\* *Ann. de Chim. et de Phys.*, vol. lviii. p. 218; and vol. lxiii. p. 334.

† *Haidlen* and *Fresenius* separate silver from copper by adding cyanide of potassium to the solution of the two metals until the precipitate redissolves. A current of sulphuretted hydrogen is then passed into the liquor, the excess of gas expelled by heat, and a little more cyanide added. The silver is thus precipitated while the copper remains in solution.

fusing the argentiferous copper with  $2\frac{1}{2}$  parts of lead, and cooling the fused mass in thick round cakes. These cakes are then introduced into a furnace of peculiar construction, and the heat is raised sufficiently high to fuse the alloy of silver and lead, but not to fuse the copper. On cooling, the whole of the silver is found combined with the lead, from which it is separated by cupellation. *The second Method* consists in dissolving the argentiferous copper in sulphuric acid, in a platinum vessel, and in precipitating the silver from the solution by means of plates of copper; the precipitated silver, which is in the form of a gray metallic powder, is washed and fused with a mixture of nitre and borax; it is thus purified from the copper which may have been precipitated with it. The method has two advantages; *first*, the copper is recovered in a marketable form (that of blue vitriol); and, *second*, the gold, amounting to from  $\frac{1}{1000}$  to  $\frac{1}{1200}$ th part, is saved, this metal remaining undissolved by the sulphuric acid.

*Analysis of Alloys of Silver by Cupellation.*—This method, which is the one usually adopted at the mint, and by refiners, and which, as above observed, is well adapted for the examination of very small quantities of silver alloys, where no very great accuracy is required, consists essentially in this. The noble metals *silver*, *gold*, and *platinum* are capable of withstanding the action of the air, even at high temperature; the base metals, on the other hand, become, under similar circumstances, oxidized. It is not possible, however, entirely to remove the oxidable metals from silver by heat alone, in consequence of the protective action of the latter; the alloy is, therefore, mixed with a certain quantity of pure lead, and heated in a small vessel formed of bone earth, called a *cupel*; now the oxide of lead is fusible, and possesses the property of dissolving the oxides of the base metals. On heating the mixture, therefore, to bright redness, the foreign metals present in the alloy become oxidized, are dissolved by the fused oxide of lead, and absorbed by the cupel; while, if the operation has been carefully conducted, a button of pure silver remains.

The *cupel*, which is best made of a mixture of finely levigated ashes of birch wood and calcined bones, is thus prepared:—The ash, slightly moistened, is laid in a brass mould somewhat deeper than that of the cupel intended to be made; in this is placed a curved and polished steel pestle, which is



then struck smartly with a hammer. The operator must be careful to put as much ash into the mould as is required to make the cupel *at once*; it is otherwise apt to separate in layers when it comes to be heated. The little vessel thus made is dried with great care, and heated to redness before it is used. One part, by weight, of the cupel, absorbs, during the process of cupellation, the oxide formed by two parts of lead. The assayist is thus furnished with a guide to the size of the cupel required for any particular experiment. In mixtures of lead and *copper*, only one part of copper is reduced to scoriæ by six parts of lead; but when the copper is alloyed with silver, a much larger quantity of lead is required. The quantity of lead necessary for different proportions of copper and silver has been determined. The results of the experiments made on this subject are thus given by *Berzelius*;<sup>\*</sup> 1 part of copper alloyed with 30 parts of silver, requires 128 parts of lead; with 15 parts of silver, 96 of lead; with 7 of silver, 64 of lead; with 4 of silver, 56 of lead; with 3 of silver, 40 of lead; with 1 of silver, 30 of lead; with  $\frac{1}{3}$  of silver, 20 of lead; and with  $\frac{1}{15}$  of silver, 17 of lead. It is scarcely necessary to mention that the lead employed in assaying must be perfectly free from silver, or, if it does contain any of that metal, the quantity must previously be determined with the greatest care.

The alloy to be examined is beat to a thin leaf by a polished hammer on a polished anvil, and being cut into small square pieces and accurately weighed, it is enveloped in a piece of thin lead, the weight of which is also known. The muffle is placed in one of the apertures of the assay furnace, and as soon as one-half of the bottom is red hot, the empty cupel is introduced, and advanced gradually into the muffle till it is itself red hot; a weighed piece of lead is then introduced, and, when it is melted, the assay, enveloped in its covering of lead, is carefully introduced; the heat is then somewhat diminished, taking care, however, not to reduce it below the melting point of the vitrified lead; all the imperfect metals are gradually dissolved, and the fluid glass, which they form with the oxide of lead, soaks into the cupel, producing an appearance called circulation, by which the operator judges whether the process be going on well. As soon as a play of colors is perceived on

<sup>\*</sup> *Traité de Chimie*, vol. ii. p. 488.

the melted metallic button, the mouth of the muffle is partially closed with a piece of charcoal, until it is perceived that the surface of the molten globule is clear and brilliant. It is allowed to remain for some minutes in the cupel, in order that the whole of the oxide of lead, &c., may be absorbed by the bone ash, after which it is allowed gradually to solidify; it is then removed, and, having been cleansed from all adhering oxide of lead, is weighed. The loss of weight indicates of course the quantity of copper and other oxidable metals originally present in the alloy. The instant of the disappearance of the last traces of the oxidable metals is known by the melted silver globule becoming suddenly whiter, or flashing, as it is technically termed. In this manner the silver which accompanies the lead in galena is extracted; but, previous to submitting the sample to the operation of cupellation, advantage is taken of the remarkable fact, that the quantity of silver may be concentrated in a comparatively small quantity of lead by crystalization. It has been ascertained that the silver is not diffused uniformly through all the lead, but combined in atomic proportions with a certain quantity of it forming an alloy, which is then mixed with an excess of lead. This alloy is more fusible than lead, so that when a large basin of lead containing a small quantity of silver is melted, and allowed to cool very slowly, so as to crystalize, the portions which first solidify are pure lead; and these portions being removed with iron colanders, all the silver remains in the mother liquor. The process must be stopped, however, before this begins to congeal. By a succession of crystalizations of this sort, the great excess of lead is gradually got rid of, and the quantity to be oxidized at the cupel diminished in a corresponding degree.\* Dr. Percy proposes to separate both silver and gold from their ores by means of hyposulphite and chloride of lime. Ch. Gaz. 6.354.

### *Mercury.*

This metal is in general most conveniently weighed in its *metallic state*. It may also be estimated in the form of *calomel* (subchloride), and as *sulphuret*.

\* Kane's Chemistry.

*Quantitative Estimation as Metallic Mercury.*

1. *Reduction by the dry way.*—The solid mercurial compound is heated in a tube of hard glass, with an excess of soda lime, precisely in the same manner and with the same precautions as are observed in the analysis of ammoniacal salts (see page 249). The open end of the combustion tube is drawn out, and bent at a somewhat obtuse angle, in order that it may be inserted into a flask containing water, into which the mercury is received; when the analysis is over, the fluid metal is collected into one large globule, by agitating the flask; it is then decanted into a porcelain capsule, and the adhering water having been removed by blotting paper, it is dried in vacuo over sulphuric acid, without the application of heat.

In their experiment for the determination of the atomic weight of mercury, *Erdmann* and *Marchand* adopted the following somewhat complicated method of reducing the oxide, their object being the attainment of the greatest accuracy.\* A combustion tube about 3 feet long, was drawn out in front to an open point, from 9 to 10 inches in length, and curved downwards. A loose stopper of copper shavings, which had been first oxidized by heating them while exposed to the air, and then reduced in a current of hydrogen, was introduced through the other end, and thrust forward to near the point. This copper was followed by a stratum five to six inches in length, of small fragments of strongly ignited sugar charcoal, from which every trace of dust had been carefully removed by sifting, and then the oxide (which had previously been strongly ignited in a current of air so as to remove every trace of mercurial vapor) was introduced. To advance to the front every trace of oxide which might have remained adherent to the hinder portions of the tube, it was finally rinsed with pulverulent copper: the tube, thus arranged, was treated precisely in the same manner as in organic analysis, and then placed in a long furnace. To the hinder extremities a broad tube, filled with chloride of calcium, was fixed by means of a caoutchouc tube; to this was applied a Liebig potash apparatus, filled with sulphuric acid, and at last a large gasometer filled with carbonic acid. The

\* *Journal für Praktische Chemie*, xxxi. p. 385.

point in front of the tube was connected by a caoutchouc tube with a weighed recipient, destined to receive the mercury, and in the arm proceeding from the last bulb of the latter there was placed some gold leaf, to retain any trace of mercurial vapor which had not been condensed in the bulb. A gentle stream of the dry carbonic acid gas was first allowed to pass from the gasometer through the apparatus, the tube was then immediately surrounded with incandescent charcoal, proceeding from the front towards the hinder part in the same manner as in an organic analysis. The carbon in the anterior portion of the tube is seen to burn at the expense of the liberated oxygen, and the mercury, which distils over in the current of carbonic acid, collects perfectly bright in the recipient. On the combustion of the charcoal some water is formed, which passes over along with the mercury. This water is entirely removed, as well as the carbonic acid contained in the apparatus, by a current of atmospheric air at the close of the operation. By this mode of analysis these chemists obtained from four experiments the following numbers:—92.594, 92.596, 92.598, and 92.596, the mean of which, 92.596, gives as the equivalent number of mercury the figure 100.07.

A modification of this process, consisting in the employment of a current of hydrogen gas to assist in the reduction of the mercurial compound, has been adopted by *M. Millon*.\*

Hydrogen gas, he observes, is more easily obtained in a regular current than most other gases, and it greatly facilitates the decomposition of all mercurial compounds: it favors the expulsion of the water which accompanies the reduction, and likewise the condensation of the mercury in the expansion of the tube in which it is to be collected and weighed. The process is conducted as follows:—The dry gas is passed through a tube containing copper turnings heated to redness—a plan which was found the most efficacious for preserving the perfect metallic lustre of the mercury, while it also insured the purification of the hydrogen. On leaving the tube with the copper turnings, the gas enters the tube containing the mercurial salt. This tube should be from fourteen to sixteen inches long, and of the diameter of an ordinary tube for organic analysis. At a small distance from its free extremity, it is contracted, and then again contracted and drawn out at the

\* *Ann. de Chim.*, 1846.



point and curved upwards: it thus presents a space of from three to four inches between the two contractions.

A little asbestos is first placed in the tube next the first contracted part; then caustic lime in small fragments to the extent of from six to eight inches: the mercurial compound is next introduced, the quantity of which may vary from 15.5 to 62 grains, and then the tube is filled with caustic lime similar to the other. The tube is now placed in the furnace used for organic analysis: it receives the current of hydrogen at its wider and uncontracted extremity, and heat is applied in the usual manner. The ignited charcoal is gradually approached to the part of the tube containing the mercurial compound, and then a few pieces are placed behind it to prevent the condensation of the metal there. The water is first seen in the portion of the tube between the contractions: it is dissipated by gently heating it. This part of the tube is then allowed to cool, and the mercury now makes its appearance, condensing in its turn without any difficulty. At the end of the operation the part of the tube containing the mercury is separated by slightly moistening the heated tube; the portion of the tube is weighed with the mercury it contains; the metal is then poured out, the tube is rinsed out by nitric acid; it is then washed, dried, and weighed again. The difference between the two weights gives the weight of the mercury. The author states that by this mode of operating he has been able to propel 45 to 60 grains of mercury from one extremity of the tube to the other, condensing it between the contracted parts without the smallest loss. Two analyses of chloride of mercury yielded 73.87 and 73.82 per cent. of mercury, figures which give as the atomic weight of mercury 100.07, the same as that obtained by *Erdmann* and *Marchand*.

2. *Reduction in the Moist Way.*—The best reducing agent for this purpose is *protochloride of tin*. The process is conducted as follows:—The mercurial compound, if a solid, is digested with strong hydrochloric acid, a concentrated solution of protochloride of tin, which has been rendered perfectly clear by the addition of a few drops of hydrochloric acid, is then added. The whole is boiled, but only for a few minutes, to avoid the risk of the volatilization of a portion of the mercury in company with the aqueous vapors. On cooling, the mercury is usually found deposited in the form of a black

precipitate, the supernatant fluid is removed by a syphon, and the precipitate is boiled with weak hydrochloric acid, on which it generally loses its pulverulent appearance, and becomes converted into running globules. It is washed, first with very dilute hydrochloric acid, and finally with distilled water; it is then received into a porcelain crucible, dried, first with bibulous paper, and lastly over sulphuric acid in the manner already directed. When mercury has to be estimated in a liquid containing nitric acid, it is necessary to destroy this acid, before a correct determination can be made: this is done by adding hydrochloric acid gradually to the solution and concentrating by evaporation. The nitric acid is thus destroyed, free chlorine being at the same time disengaged, and the addition of the hydrochloric acid must be continued as long as the odor of chlorine is perceptible: protochloride of tin is then added, and the remainder of the operation is conducted in the manner already described. It is very difficult to obtain correct results when the solution contains much nitric acid. Wherever it is admissible, therefore, it is advisable to precipitate the mercury as sulphuret by sulphuretted hydrogen, or colorless hydrosulphuret of ammonia, having previously nearly neutralized the solution with potassa, and mixed it with excess of cyanide of potassium.

Other reducing agents, such as *phosphorous* or *sulphurous* acids, may be employed in the place of protochloride of tin, and *Rose* remarks, that the former would be preferable to the tin salt, could it be procured easily in sufficient quantities. It may be added at once to a mercurial solution containing nitric acid, which it destroys, with the aid of heat, more effectually than hydrochloric acid. It is, moreover, easier to obtain mercury in large globules by these acids than when protochloride of tin is employed.

*Quantitative estimation as Subchloride.*—This method, which is extremely tedious, and which is only employed in certain cases where other methods are inadmissible, is directed by *Fresenius*\* to be applied in the following manner:—The solution of the mercurial compound is mixed with hydrochloric acid in excess, potassa is then added until the excess of acid is nearly neutralized, and then excess of *formiate of soda*, after which it is allowed to remain for four days at rest

\* Quantitative Analysis, p. 212.

at a temperature of from  $140^{\circ}$  to  $176^{\circ}$ . It is then collected on a filter which has been dried at  $212^{\circ}$ , and weighed. The filtrate is again allowed to stand for twenty-four hours, and should any fresh precipitate form, it is added to the first; the same process is repeated until the filtrate remains perfectly clear. The whole is then washed, dried at  $212^{\circ}$ , and weighed. Care must be taken to confine the temperature to  $170^{\circ}$ , since otherwise metallic mercury might separate; should this be the case, the precipitate will exhibit a grayish appearance, and the experiment must, under such circumstances, be considered a failure.

The composition of subchloride of mercury is

|                                   |     |        |     |        |
|-----------------------------------|-----|--------|-----|--------|
| Two equivalents of Hg             | ... | 200.14 | ... | 84.97  |
| One do. of Cl                     | ... | 35.50  | ... | 15.03  |
|                                   |     | <hr/>  |     | <hr/>  |
| One do. of $\text{Hg}_2\text{Cl}$ |     | 235.64 |     | 100.00 |

*Quantitative estimation as Sulphuret.*—A stream of washed sulphuretted hydrogen is transmitted through the acid solution of the salt; in solutions of the *suboxide*, the precipitate formed is black at once; but, when a compound of *oxide* of mercury is under examination, in the beginning of the experiments white-colored compounds of mercurial salts, with sulphuret of mercury, are produced: the addition of larger quantities of the gas causes the precipitate to assume various colors, but it ends in becoming pure black. If the whole of the mercury exists in the original solution as *oxide*, it may be determined in the state of *sulphuret*, with which view the precipitate, occasioned by sulphuretted hydrogen, is received on a weighed filter, quickly washed with cold water, dried at  $212^{\circ}$ , and weighed; but if the mercury, or any portion of it, existed as *suboxide*, it is inadmissible to estimate it as subsulphuret, because it is liable to be partly decomposed, even by a gentle heat, into sulphuret of mercury and metallic mercury; and as the latter may be partly volatilized by a very gentle heat, an error of greater or less amount would be introduced (Rose). The sulphuret containing a *minimum* of sulphur must, therefore, undergo further treatment, as follows:—It is collected on a filter, and transferred, filter and all, into a wide-mouthed flask, capable of being closed by a glass stopper. A small quantity of dilute hydrochloric acid is then poured into the flask, and a slow current of chlorine conducted

into the solution; the sulphuret is hereby decomposed into *chloride*, *sulphuric acid*, and *free sulphur*, as soon as the latter is observed to have a clear yellow color; the stream of chlorine is stopped, and the flask is exposed to a gentle heat to expel the free chlorine; it is then filtered off from the sulphur, and the mercury in the filtrate is estimated by protochloride of tin.

Mercury may also be separated from neutral or alkaline solutions by hydrosulphuret of ammonia; an excess of the precipitant does not dissolve the precipitate in the cold; the sulphuret must, subsequently, be treated with chlorine, and the metal estimated in the manner just described. It must be observed that, in the presence of *sesquioxide of iron* or of *chromic acid*, oxide of mercury cannot safely be weighed as sulphuret, in consequence of the free sulphur with which it would be accompanied: it must be treated with chlorine and protochloride of tin, and estimated in the metallic state.

The composition of sulphuret of mercury is

|                      |     |        |     |       |
|----------------------|-----|--------|-----|-------|
| One equivalent of Hg | ... | 100.07 | ... | 86.21 |
| One do. of S         | ... | 16     | ... | 13.79 |
|                      |     |        |     | <hr/> |
| One do. of HgS       | ... | 116.07 |     | 100   |

#### *Separation of Oxides of Mercury from Oxide of Lead.*

1. *By Sulphuretted Hydrogen Gas.*—The two metals are first precipitated together as sulphurets from a diluted solution; the mixed sulphurets are dried, and introduced into a bulb blown in a tube of hard glass, the weight of which, before and after the introduction of the sulphurets, is accurately taken. The tube is connected with an apparatus for generating chlorine, and a stream of the gas, dried by passing through a tube filled with chloride of calcium, is sent through the tube. When the whole apparatus is filled with chlorine, the bulb containing the sulphurets is gently heated, upon which the chloride of mercury volatilizes, and is completely separated from the chloride of lead. The sublimed chloride of mercury is driven forward by the flame of a small spirit lamp, and received in a vessel containing water. As soon as all appearance of sublimation ceases, the tube leading from the bulb to the receiver is cut off with a file, and any crystals which may have collected in it are washed into the flask. The chloride



of mercury dissolved in the receiver is precipitated by protochloride of tin, and the chloride of lead remaining in the bulb is determined by first weighing it together with the bulb, and then dissolving it out and weighing the bulb alone.

2. *By Cyanide of Potassium.*—This method, which is far more simple and easy of execution than the one just described, is conducted as follows:—The diluted solution of the two oxides is mixed with carbonate of soda, and then heated with excess of cyanide of potassium; the whole of the lead is precipitated in the state of carbonate, while the mercury remains in solution in the form of double cyanide of mercury and potassium. The solution is filtered off from the insoluble lead salt and precipitated by sulphuretted hydrogen.

3. *By Hydrochloric Acid.*—All the mercury present in the compound must be in the form of *oxide*. The dry mixture is treated with hydrochloric acid, and evaporated to dryness at a gentle heat. Alcohol, mixed with ether, is added to the residue, and the whole is digested: chloride of mercury alone dissolves. The insoluble chloride of lead is received on a filter, washed with alcohol, dried, and weighed. The alcoholic solution of chloride of mercury is evaporated to expel the alcohol and ether, and the mercury is then precipitated by protochloride of tin.

4. *By Sulphuric Acid.*—The solution is concentrated, and mixed with excess of sulphuric acid: after the lapse of several hours, it is filtered. The precipitated sulphate of lead is washed first with dilute sulphuric acid, and then with alcohol. The mercury in the filtrate is precipitated by protochloride of tin.

#### *Separation of Oxides of Mercury from Oxide of Silver.*

1. *By Hydrochloric Acid.*—For this purpose the mercury must be in the state of *oxide*, suboxide of mercury being precipitated by hydrochloric acid. To insure this, the compound is digested with nitric acid, hydrochloric acid is then added in slight excess, and the precipitated chloride of silver is collected and weighed with the precautions prescribed (page 306). The mercury in the solution is precipitated by protochloride of tin, the nitric acid having been previously destroyed by chlorine.

2. *By Cyanide of Potassium.*—The solution is nearly neutralized with potassa; excess of cyanide of potassium is then

added, by which the precipitate which first forms is entirely redissolved, and the solution contains the double cyanides of silver and potassium, and of mercury and potassium. On adding nitric acid the cyanide of potassium is decomposed, the silver is precipitated in the form of cyanide of silver, while the cyanide of mercury remains in solution; the former is separated by filtration, and from the filtrate the mercury is precipitated by sulphuretted hydrogen.

3. *By Chlorine*.—This is effected precisely in the same manner and with the same apparatus as is employed in the separation of oxide of mercury from *oxide of lead*; chloride of silver remains in the bulb, in which it is weighed, the bent tube, through which the volatilized chloride of mercury makes its escape into the receiver having been cut off. The fused chloride of silver must, after weighing, be removed from the bulb by zinc and sulphuric acid, in order that the weight of the latter may be taken.

*Separation of Suboxide of Mercury from Oxide of Mercury*.—The solution is diluted considerably with water, and the suboxide is precipitated as subchloride by hydrochloric acid: heat must be avoided. The subchloride, after standing for some time, is received on a weighed filter, and dried at a gentle heat. The oxide of mercury in the filtrate is precipitated by protochloride of tin. If the substance be a solid and insoluble, it is acted upon at a low temperature, with diluted nitric acid, until it is completely dissolved: hydrochloric acid is then added as before.

*Analysis of Amalgams*.—If the metal or metals with which the mercury is combined be not volatile, or oxidizable by heat with excess of air, the amount of mercury in the amalgam may be ascertained in the simplest manner by igniting it in a porcelain crucible. If, however, the metals are liable to alteration by exposure to heat in an open vessel, the ignition must be performed in a retort, the neck of which, after the volatilization of the mercury, must be closed up by the blow-pipe, while the retort is still ignited.

### *Bismuth.*

This metal is almost invariably weighed as oxide. It is precipitated from its solution in nitric acid by carbonate of ammonia; the solution should be diluted, and it should be heated nearly to boiling for a few minutes before it is filtered,

otherwise a portion of the oxide will be retained in solution by the precipitant. Neither carbonate of potassa nor carbonate of soda can be substituted for carbonate of ammonia; a portion of the former is carried down with the precipitate, and is not easily removed by subsequent washing, and the latter fails to effect a perfect precipitation. The carbonate of bismuth, having been washed, is separated from the filter and ignited in a porcelain crucible, by which it loses carbonic acid, and becomes converted into protoxide of a yellow color. The filter is burnt on the cover of the crucible, and its ashes added to the oxide.

The composition of protoxide of bismuth is

|                      |     |       |
|----------------------|-----|-------|
| One equivalent of Bi | ... | 70.95 |
| One do. of O         | ... | 8     |
| <hr/>                |     |       |
| One do. of BiO       | ... | 78.95 |

In the presence of sulphuric or hydrochloric acids bismuth cannot be effectually precipitated by carbonate of ammonia, as in the former case a basic sulphate, and in the latter a basic chloride, is at the same time precipitated, and neither of these salts can be subsequently decomposed even by protracted digestion with excess of carbonate of ammonia. In such cases it is necessary, in the first place, to mix the solution of the bismuth salt with acetic acid (water will not do, as it would cause the formation of an insoluble basic salt), and then to precipitate the bismuth in the form of sulphuret by sulphuretted hydrogen, or by hydrosulphuret of ammonia, having previously rendered the solution alkaline by the addition of caustic ammonia. The precipitated sulphuret, having been washed, is decomposed by digesting it, filter and all, with nitric acid; the solution is diluted with weak acetic acid, filtered, the filter washed with the same diluted acid, and the filtrate finally precipitated by carbonate of ammonia.

#### *Separation of Oxides of Bismuth from Oxides of Lead.*

1. *By Sulphuric Acid.*—An excess of sulphuric acid is added to the solution containing the two oxides, and heat is applied till the sulphuric acid begins to volatilize: it is then quickly filtered, and the sulphate of lead is washed with water acidulated with sulphuric acid. The sulphate of bismuth in

the filtrate is precipitated by carbonate of ammonia. The results are not very accurate, since sulphate of lead is not altogether insoluble even in dilute sulphuric acid.

2. *Ullgren's Process*.—The two oxides are together precipitated with carbonate of ammonia, and redissolved in acetic acid. A strip of *clean lead*, of known weight, is then put into the solution, so that the whole of it is covered. The vessel is closed, and allowed to stand for some hours. The bismuth is separated in the metallic state, and that which remains on the strip of lead is washed off, and the strip dried and weighed. It is brought on a filter and washed with water that has been boiled and allowed to cool; it is then dissolved in nitric acid, evaporated to dryness, ignited, and the oxide weighed. The solution of lead is precipitated with carbonate of ammonia, and the weight of the oxide determined from this is to be deducted, the oxide corresponding to the loss which the strip of lead has suffered during the operation.

3. *By Heat*.—The process is the same as that employed for the separation of *silver* from *mercurey* and *lead* from *mercury*, namely, by converting the metals into chlorides by heating them in an atmosphere of chlorine, and expelling the volatile chloride of bismuth by heat. Too high a temperature must be avoided, otherwise a portion of the chloride of lead may be also volatilized. The proportion of bismuth may be calculated from the loss of weight which the compound under examination experiences.

4. *Liebig's Method*.—To a cold solution of the nitrates of the two oxides *carbonate of lime* is added, which precipitates the bismuth, but not the lead.

*Separation of Oxide of Bismuth from Oxide of Silver.*

1. *By Hydrochloric Acid*.—Nitric acid is added to the solution, and then hydrochloric acid, which precipitates the silver as chloride. The bismuth in the filtrate is precipitated by sulphuretted hydrogen, the sulphuret decomposed by nitric acid, and, finally, precipitated by carbonate of ammonia.

2. *By Cyanide of Potassium*.—This reagent is added to the solution of the two oxides, whereupon the bismuth is precipitated as carbonate; the silver remains in solution as double cyanide of silver and potassium; it is separated by filtration from the carbonate of bismuth, and is, finally, precipitated as cyanide by the addition of nitric acid.



*Separation of Oxide of Bismuth from Oxide of Mercury.*—This also is effected by cyanide of potassium; the soluble argento-cyanide of potassium is decomposed by sulphuretted hydrogen, and the mercury may be determined as sulphuret.

### *Cadmium.*

This metal may be quantitatively estimated as *oxide* or as *sulphuret*.

*Estimation as Oxide.*—The solution under examination is precipitated by carbonate of potassa, and the resulting white carbonate of cadmium is decomposed by ignition into carbonic acid and water which escape, and oxide of cadmium which remains behind in the form of a brown powder. Ammoniacal salts interfere with the complete precipitation of oxide of cadmium by alkaline carbonates; carbonate of ammonia cannot, therefore, be employed as the precipitant. In precipitating oxide of cadmium by carbonate of potassa in the presence of ammoniacal salts, the same precautions must be taken as in the precipitation of carbonate of zinc under similar circumstances.

The composition of oxide of cadmium is

|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Cd | ... | 55.74 | ... | 87.45 |
| One do. of O         | ... | 8     | ... | 12.55 |
| <hr/>                |     |       |     |       |
| One do. of Cd O      | ... | 63.74 |     | 100   |

*Precipitation as Sulphuret.*—This may be effected either by sulphuretted hydrogen, or by hydrosulphuret of ammonia; in acid solutions the former reagent is employed. It should be largely diluted, and the gas allowed to pass slowly through the liquid for a long time; the resulting sulphuret is of a yellow or orange color, according as the solution has been more or less diluted. It is collected on a weighed filter, washed with distilled water, and dried at 212°.

The composition of sulphuret of cadmium is

|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Cd | ... | 55.74 | ... | 77.78 |
| One do. of S         | ... | 16.   | ... | 22.22 |
| <hr/>                |     |       |     |       |
| One do. of Cd S      | ... | 71.74 |     | 100   |

When hydrosulphuret of ammonia is employed as the precipitant, the sulphuret should be decomposed by digestion

with hydrochloric acid, and the solution precipitated with carbonate of potassa. It has been observed by *Dr. H. Reinsch*,\* that when a salt of cadmium is dissolved in hydrochloric acid, and then treated with sulphuretted hydrogen, no precipitate takes place till after the gas has been passed through the solution for a long time, and that then the precipitate is a combination of sulphuret of cadmium with chloride. On edulcorating with water the chloride is dissolved, and the yellow sulphuret is left on the filter. This observation shows the necessity of diluting the solution before passing the gas through it. I have observed, also, that in precipitating a hydrochloric solution containing copper, lead, bismuth, and cadmium by sulphuretted hydrogen, the three former metals are completely thrown down before the chloride of cadmium is at all decomposed; the filtered liquor gives no traces of either of the three first metals, but on continuing to pass the gas slowly through it for a long time the cadmium is precipitated of its characteristic yellow color.

*Separation of Oxide of Cadmium from Oxides of Lead.*

1. *By Cyanide of Potassium*.—The diluted solution of the two oxides is first rendered slightly alkaline by carbonate of soda; cyanide of potassium is then added, and heat applied. The lead is precipitated as carbonate, the cadmium remains in solution as double cyanide of cadmium and potassium, and may be precipitated from the filtered solution by sulphuretted hydrogen.

2. *By Sulphuric Acid*.—The solution is concentrated, and excess of dilute sulphuric acid added; sulphate of lead precipitates, which is received on a filter and washed, first with dilute sulphuric acid, and, finally, with alcohol; the cadmium in the filtrate is precipitated by carbonate of potassa; the former method with cyanide of potassium gives the best results, in consequence of the partial solubility of sulphate of lead, even in dilute sulphuric acid.

*Separation of Oxide of Cadmium from Oxide of Silver.*

1. *By Hydrochloric Acid*.—To the diluted solution nitric acid is added, and then slight excess of hydrochloric acid, the

\* Jahrb. für Prakt. Pharm., xiii. p. 72; and Chem. Gaz, vol. v. p. 167.

liquor filtered from the precipitated chloride of silver contains the cadmium, and is precipitated by carbonate of potassa.

2. *By Cyanide of Potassium.*—The nitric solution of the two metals is rendered neutral by the addition of potassa; cyanide of potassium is then added in such quantity that the precipitate, which is at first formed, is entirely re-dissolved. To the clear solution excess of nitric acid is next added, whereupon the whole of the silver is precipitated as cyanide: the cadmium remains in solution, and may either be precipitated by hydrosulphuret of ammonia, having previously rendered it slightly alkaline by the addition of potassa, or the hydrocyanic acid may be expelled by evaporating with sulphuric acid, and the cadmium precipitated as carbonate by carbonate of potassa.

*Separation of Oxide of Cadmium from Oxide of Mercury.*—

This may be effected by *formiate of soda*, but the process is tedious, and requires considerable care. Hydrochloric acid is added to the solution, which is then nearly saturated with potassa; excess of formiate of soda is then added, and the solution is set aside for some days at a temperature not above  $170^{\circ}$ . The mercury precipitates in the form of calomel: the solution filtered from the subchloride of mercury contains the cadmium, which is then precipitated by carbonate of potassa. Cyanide of potassium may also be employed to separate these two oxides in the following manner:—The clear solution is rendered neutral by potassa, and an excess of cyanide of potassium is then added. To the solution of the two cyanides very dilute nitric acid is added, and the whole is boiled; the mercury salt is not decomposed: the cyanide of cadmium, on the other hand, is converted into nitrate, and may, consequently, be decomposed by carbonate of potassa: the filtrate, from the carbonate of cadmium, containing the oxide of mercury, may be precipitated by sulphuretted hydrogen.

*Separation of Oxide of Cadmium from Oxide of Bismuth.*—

This likewise is effected by cyanide of potassium, an excess of the cyanide is added, and heat applied, the whole of the bismuth is separated as carbonate, and the cadmium is precipitated either by sulphuretted hydrogen, or by carbonate of potassa, having previously boiled the solution, filtered from the carbonate of bismuth, with hydrochloric acid.

*Copper.*

In whatever manner copper may be precipitated from its solutions, it is invariably weighed as oxide. If the salt to be examined be soluble in water or in nitric acid, provided no organic substance be present, it is best precipitated by *caustic potassa*. The solution is considerably diluted, and raised to the boiling temperature in a capacious porcelain basin, and the caustic alkali gradually added as long as a brownish black precipitate is produced; the boiling is continued for a few minutes, and the precipitated oxide is then received on a filter, and washed with boiling water. The greater part of it is then removed from the filter and transferred to a platinum crucible, in which it is ignited. The filter, with its adhering oxide, is dried, burnt on the cover of the crucible, and the ashes added to the main bulk of the oxide. As oxide of copper absorbs moisture rapidly from the atmosphere, it must be weighed as soon as it is sufficiently cold to be placed in the scale of the balance, and it is advisable to allow the crucible to cool underneath a receiver by the side of a vessel containing concentrated sulphuric acid. If the solution be not dilute, the precipitation by caustic potassa is incomplete, as is rendered evident by the filtrate becoming discolored when mixed with sulphuretted hydrogen water: the same is the case if any organic matter be present; in either of these cases the filtrate must be concentrated by evaporation, precipitated by sulphuretted hydrogen, and the precipitate treated as will be presently described. The oxide on the filter must be well washed with boiling water, to remove all traces of the alkali, which is invariably carried down in company with the oxide during its precipitation.

The composition of oxide of copper is


|                      |     |       |     |       |
|----------------------|-----|-------|-----|-------|
| One equivalent of Cu | ... | 31.66 | ... | 79.73 |
| One do. of O         | ... | 8     | ... | 20.27 |
| <hr/>                |     |       |     |       |
| One equiv. of CuO    | ... | 39.66 |     | 100   |

*Precipitation as Sulphuret.*—The solution is acidified with hydrochloric acid, diluted with water, and a stream of washed sulphuretted hydrogen gas passed through it till it is perfectly saturated. The precipitated sulphuret is received on a filter and washed as quickly as possible with water impregnated



with sulphuretted hydrogen; it is removed as completely as possible, from the filter, which is then dried and ignited, and its ashes mixed with the bulk of the precipitate. The copper cannot be estimated as sulphuret, as that salt becomes partially oxidized during drying; it is therefore decomposed by digestion with dilute nitro-hydrochloric acid, and, the sulphur being separated, the solution is evaporated with sulphuric acid until the nitric acid is entirely expelled; a large quantity of water is then added, and the oxide is precipitated by caustic potassa at the boiling temperature. If the solution be neutral or alkaline, hydrosulphuret of ammonia may be employed as the precipitating agent.

*Levol's Method of determining Copper.*—This is a modification of the method proposed by *Fuch* for the quantitative estimation of iron (see page 292). The cupreous solution is introduced into a flask that can be accurately closed with a glass stopper; ammonia is added till the liquid assumes a transparent blue color, and the flask is then filled with water, from which all atmospheric air has been expelled by boiling; a clean and accurately weighed slip of copper is introduced into the bottle, which is immediately closed: when the liquor has become perfectly colorless, the slip is removed, washed, dried, and weighed; the diminution in weight which it has undergone, indicates the amount of copper originally present in the solution. The result which, when properly conducted, is very accurate, depends on the abstraction of one equivalent of copper from the slip by every equivalent of oxide of copper in the solution to form an equivalent of suboxide of copper, which forms with ammonia a colorless solution, thus—



It requires a considerable time to complete the process, which is obviously altogether inapplicable in the presence of foreign metals, which are capable of being precipitated by copper.

*Cassaseca's Method.*—This consists in dissolving the copper compound in an acid, adding an excess of ammonia to the solution, and comparing the tint furnished by this solution with those which a known weight of pure copper yields likewise in the state of ammoniuret.

*Pelouze's Method of Estimating Copper by Standard Solutions.\**—This mode of analysis was suggested to the author,

\* Comptes Rendus, Feb. 2, 1846.

by the accuracy and rapidity with which alloys of silver are analyzed by the process discovered by *M. Gay-Lussac* (page 308). He succeeded in effecting his object in several different ways, all based principally on the phenomena of precipitation and simultaneous decoloration. The following was the mode of proceeding which he finally adopted: a certain quantity of very pure copper is dissolved in nitric acid, the solution is diluted with water, and excess of ammonia added: a deep blue solution is obtained. On the other hand, some sulphuret of sodium (colorless crystalized hydrosulphate of soda of commerce) is dissolved in water and poured into a tube graduated and divided into tenths of cubic centimetres, the ammoniacal solution is heated to boiling, and the solution of the sulphuret gradually added. If we suppose that it required 31 cubic centimetres to decolorize 1 gramme of copper, we have a standard solution of known strength. To apply this to the analysis of copper alloys, a certain known weight is dissolved in aqua regia, the solution is supersaturated with ammonia, heated to boiling, and the standard solution of the sulphuret added until it is decolorized, taking care to add from time to time a little dilute ammonia to replace that which is evaporated. The decrease in the depths of the blue tint points out that the end of the experiment is more or less near, and when it is requisite to add the last portions of the sulphuret in drops. When the operation is supposed to be finished, the number of divisions employed for the decoloration is read off and compared with the number required to decolorize an equal weight of pure copper. It must be remarked that the ammoniacal liquor from which the copper has been precipitated does not long remain colorless, but gradually becomes blue in consequence of the sulphuret of copper becoming partially converted into sulphate, by the absorption of oxygen. This mode of operating is not, according to the author, liable to an error amounting to more than five or six thousandths, though still greater accuracy is obtained by completing the decoloration of the blue liquid with a very weak solution of sulphuret, precisely in the manner recommended by *Gay-Lussac* in his Analysis of Silver Alloys by Standard Solutions of Common Salt. Neither *tin*, *zinc*, *cadmium*, *lead*, *antimony*, *iron*, *arsenic*, nor *bismuth*, in any way interfere with the success of this process, not being in the least affected by the sulphuret of sodium while a trace of copper remains

to be precipitated; indeed the author found that when the sulphuret of zinc, cadmium, tin, lead, bismuth and antimony are placed in contact with an ammoniacal solution of sulphate of copper, they decolorize it, some in the cold, others with the assistance of heat, which proves very evidently that these sulphurets cannot exist, except, perhaps, for an instant, in a solution of copper. Their formation subsequently to the decoloration has no influence on the result of the analysis, as the termination of this is judged of by the decoloration of the liquid, without paying the least attention to the precipitates which subsequently form; or, if any attention *is* paid, it is only with a view to obtain some knowledge of the nature of the metals which accompany the copper. Thus, if any alloy consists of copper, lead, tin, and zinc, the presence of *zinc* is readily detected by the white precipitate which succeeds the black precipitate of sulphuret of copper, the lead and tin being precipitated at the outset by ammonia. *Cadmium*, like zinc, is precipitated immediately after the copper. The very moment the liquid is observed to be decolorated, a beautiful pure yellow precipitate of sulphuret of cadmium is formed if the addition of sulphuret be continued. If the alloy contains *silver*, that metal is previously precipitated from the nitric solution by hydrochloric acid. In this method of estimating copper, an important property of the ammonia, besides that of heightening the color, is, that it prevents the salts of copper being precipitated by *sulphites* and *hydrosulphites*, without which it would probably have been impossible to estimate the copper by means of solutions of the alkaline sulphurets, since these salts almost always occur in the alkaline sulphurets, and are, moreover, produced from them by contact with the air. A solution of sulphuret of sodium becomes weaker by contact with the air, but the alteration is very slow, nor is it necessary to change the liquid as long as any remains in the flask in which a quantity has been prepared. The only precaution to be taken—and it is one which applies to all standard solutions—is to determine previous to *each assay* the actual strength of the sulphuret with a known weight of pure copper. *M. Pelouze* states, in conclusion, that this method applied to the analysis of copper ores, yields results of the greatest accuracy, and that he entertains no doubt that it will render great services in the administration of the

Mint, the government foundries, and other metallurgical works.

*Separation of Oxide of Copper from Oxide of Lead.*

1. *By Cyanide of Potassium.*—To the diluted solution of the two oxides carbonate of soda is added in slight excess, and then cyanide of potassium, and heat applied. The lead precipitates as carbonate; the copper remains in solution in the form of double cyanide of copper and potassium: it is evaporated with sulphuric acid till all the hydrocyanic acid is expelled, then largely diluted with water, and precipitated at the boiling temperature by caustic potassa.

2. *By Sulphuric Acid.*—The solution is concentrated, and the oxide of lead precipitated by dilute sulphuric acid, the sulphate of lead is collected on a filter, and washed first with dilute sulphuric acid, and then with spirits of wine. The filtrate is boiled for some time, to drive off the alcohol, and finally precipitated by caustic potassa.

*Separation of Oxide of Copper from Oxide of Silver.*

1. *By Hydrochloric Acid.*—Nitric acid is added to the solution, the silver is then precipitated as chloride by hydrochloric acid, and the oxide of copper is thrown down from the filtrate by caustic potassa.

2. *By Cyanide of Potassium.*—The solution is neutralized with potassa, cyanide of potassium is then added till the precipitate which is first formed is entirely redissolved. To the clear solution nitric acid is added, which precipitates the silver completely as cyanide. The filtrate is evaporated with sulphuric acid till all the hydrocyanic acid is expelled, and the copper is finally precipitated by caustic potassa. *Fresenius* gives another method of treating the solution of the oxides of these two metals in cyanide of potassium. Sulphuretted hydrogen is passed into the solution, which precipitates only the silver, provided sufficient cyanide of potassium be present. The solution filtered from the sulphuret of silver is heated to expel the excess of sulphuretted hydrogen; cyanide of potassium is again added, and then, having completely decomposed this salt by evaporating with a mixture of sulphuric and nitric acids, the copper is precipitated by caustic potassa.

For the method of assaying alloys of silver and copper, see "*Silver.*"



*Separation of Oxide of Copper from Oxide of Mercury.*

1. *By Cyanide of Potassium.*—This is effected in the same manner as the separation of oxide of silver from oxide of copper; the solution of the two oxides in cyanide of potassium is treated with sulphuretted hydrogen, by which mercury alone is precipitated.

2. *By Formiate of Soda.*—Hydrochloric acid is added to the solution, which is then nearly neutralized with potassa, and the mercury precipitated as subchloride by formiate of soda, in the manner directed in treating of the separation of oxide of mercury from oxide of cadmium.

*Separation of Oxide of Copper from Oxide of Bismuth.*

1. *By Carbonate of Ammonia.*—On adding this reagent to the solution of the two oxides, in considerable excess, oxide of bismuth alone is precipitated; it is allowed to remain at rest for some time in a warm place, and then filtered, the oxide of bismuth being washed on the filter with carbonate of ammonia. The filtrate is gently evaporated to expel the excess of carbonate of ammonia, caustic ammonia is then added, and the oxide of copper is finally precipitated by caustic potassa. This method is not to be recommended, it being difficult to remove all traces of oxide of copper from the precipitated oxide of bismuth, even by protracted washing with carbonate of ammonia.

2. *By Cyanide of Potassium.*—Carbonate of soda is first added in slight excess to the solution, the oxide of bismuth is then precipitated in the form of carbonate, by heating with cyanide of potassium; the copper in the filtrate is determined by precipitating it by caustic potassa, having previously expelled the hydrocyanic acid by evaporating with sulphuric acid.

3. *By Chlorine.*—The solution of the two metallic oxides is precipitated by sulphuretted hydrogen, and the mixed sulphurets, having been washed and weighed, are introduced into a bulb, blown in a tube of hard glass, connected with an apparatus for generating chlorine. A stream of this gas is transmitted through the tube, which at the same time is heated by a spirit lamp, first gently, and then to redness; the sulphurets are thus converted into chlorine, and the chloride of bismuth, being volatile, is gradually expelled; it may be received into

a vessel containing water impregnated with hydrochloric acid, or the amount of oxide may be estimated by the loss of weight sustained by the analyzed substance. The apparatus employed may be the same as that used for separating mercury from lead, mercury from silver, or bismuth from lead. The chloride of copper remaining in the bulb is washed out with a little dilute nitric acid, evaporated with sulphuric acid, and finally precipitated by caustic potassa.

*Separation of Oxide of Copper from Oxide of Cadmium.*

1. *By Carbonate of Ammonia.*—This reagent is added in excess to the solution of the two oxides; carbonate of cadmium is precipitated, while oxide of copper remains in solution.

2. *By Cyanide of Potassium.*—This reagent is added until a clear solution is obtained, sulphuretted hydrogen is then passed through the mixture, by which the *cadmio-cyanide* is completely decomposed, sulphuret of cadmium being precipitated, while the whole of the sulphuret of copper remains in solution. The excess of sulphuretted hydrogen is expelled by heat, and a little more alkaline cyanide added. The copper may then be precipitated as sulphuret by the addition of an acid, or the double cyanide may be decomposed by evaporating with sulphuric acid, and the metal precipitated as oxide by caustic potassa.

*Separation of Oxide of Copper from Oxide of Zinc.—Analysis of Brass.*—Although oxide of zinc is, when alone, completely soluble in caustic potassa, this reagent cannot safely be employed to separate zinc from copper, since the oxide of copper invariably carries down with it a greater or less quantity of oxide of zinc. Sulphuretted hydrogen is, however, an effectual reagent for this purpose. The alloy, being dissolved in nitric acid, is treated with a current of the gas; sulphuret of copper alone precipitates, and from the filtrate the oxide of zinc may be completely thrown down, by boiling with carbonate of potassa, or by evaporating it to dryness, and igniting in a platinum crucible.

*Analysis of Phosphate or Arseniate of Copper.*—*Berthier's* method is to dissolve the compound in hydrochloric acid, and to boil the solution with *sulphite of ammonia*, whereupon the copper is thrown down as a *red subsulphite*, a minute trace only remaining in the solution. The same chemist has also proposed sulphite of ammonia as a means of separating oxide

of copper from the oxides of iron, manganese, nickel, and zinc; he adds excess of this salt, and boils; copper alone is precipitated. In analyzing brass he first separates the copper in this manner, and then precipitates the zinc by hydrosulphuret of ammonia.

### *Palladium.*

This metal is remarkable for its great affinity for *cyanogen*, on which property is founded a method of separating it from its solutions; *cyanide of mercury* is added, the solution having previously been neutralized with soda; a bright yellow precipitate is produced, which, by drying, becomes yellowish gray, and by ignition is decomposed, metallic palladium of a blue color remaining in the crucible. From all metals which are not precipitated by sulphuretted hydrogen, palladium may be separated by that reagent; the resulting sulphuret is converted by heat into basic sulphate, which, being dissolved in hydrochloric acid and neutralized with soda, is precipitated by cyanide of mercury.

*Separation of Palladium from Copper.*—In crude platinum ores palladium occurs in combination with copper. *Berzelius* gives the following process for separating these two metals.\*

Both metals are precipitated from an acid solution by sulphuretted hydrogen. The precipitated sulphurets are exposed to heat, while still moist, and roasted as long as they give off sulphurous acid; they are thereby converted into basic sulphates of oxides. These salts are dissolved in hydrochloric acid, the solution is mixed with chloride of potassium and nitric acid, and then evaporated to dryness. The dark saline mass thus produced contains chloride of potassium, chloride of copper and potassium, and chloride of palladium and potassium. The first two of these salts are to be extracted by alcohol, specific gravity 0.833; the palladium salt, being insoluble therein, remains behind. It is brought on a weighed filter, and washed with alcohol; it is then dried and weighed; it contains 28.84 per cent. of palladium. The saline mass may also be dissolved in water, and precipitated with cyanide of mercury. The alcoholic solution of the copper salt is evaporated to expel the spirit, the saline mass is redissolved in water, and the copper precipitated by caustic potassa.

\* Poggendorf's *Annalen*, B. xiii. p. 561; and Rose's *Manual of Analytical Chemistry*, translated by Griffin, p. 135.

Palladium has of late years been imported into this country from Brazil, alloyed with gold, some specimens containing 5 or 6 per cent. of palladium. The operation of refining is thus described by *Mr. Cock*.\* The gold dust is fused, in charges of about 7 lbs. troy, with its own weight of silver, and a certain quantity of nitre; the effect of this fusion is to remove all earthy matter, and the greater part of the base metals contained in the gold dust and in the silver melted with it. The fused mixture is cast into ingot moulds, and when cooled the flux or scoria is detached. Two of the bars thus obtained are then remelted in a plumbago crucible, with such an addition of silver as will afford an alloy, containing one-fourth its weight of pure gold, and which, first being well stirred to insure a complete mixture, is poured through a perforated iron ladle into cold water, and thus very finely granulated. It is then ready for the process of parting. For this purpose about 25 lbs. of the granulated alloy is placed in a porcelain jar upon a heated sand bath, and subjected to the action of about 25 lbs. of pure nitric acid, diluted with its own bulk of water; after the action of this quantity of acid, the parting of the gold is very nearly effected; but, to remove the least portions of silver, &c., about 9 or 10 lbs. of strong nitric acid are boiled upon the gold for two hours. It is then completely refined, and, after being washed with hot water, is dried and melted into bars containing 15 lbs. each.

The nitric acid gas, and the vapor of nitric acid arising during the above process, are conducted by glass pipes (connected with the covers of the jars) into a long stoneware pipe, one end of which slopes downwards into a receiver for the condensed acid, the other end being inserted into the flue for the purpose of carrying off the uncondensed gas.

The nitrate of silver and palladium, obtained as above, is carefully decanted into large pans, containing a sufficient quantity of solution of common salt to effect the precipitation as chloride of the whole of the silver, the palladium and copper remaining in solution in the mother liquor, which is drawn off, and, when clear, run off, together with the subsequent washings from the chloride of silver, into wooden vessels, and the metallic contents are then separated in the form of a black powder, by precipitation with sheet zinc, assisted by sulphuric

\* Proceedings of the Chemical Society, vol. i. p. 162.



acid. The chloride of silver, when washed clean, is reduced by the addition of granulated zinc and dilute sulphuric acid, washed on the filter with boiling water, dried and melted in plumbago crucibles without the addition of any flux. From the black powder obtained as above, the palladium is extracted by resolution in nitric acid and supersaturation with ammonia, by which the oxides of palladium and copper are first precipitated and then re-dissolved, while those of iron, lead, &c., remain insoluble. To the clear ammoniacal solution, hydrochloric acid in excess is then added, which occasions a copious precipitation of the yellow ammonia—chloride of palladium, from which, after sufficiently washing it with cold water and ignition, pure metallic palladium is obtained. The mother liquor and washings contain all the copper and some palladium, which are recovered by precipitation with iron.\*

#### *Rhodium.*

This metal is, according to Berzelius,† best estimated by the following process:—The solution is mixed with excess of carbonate of soda, and evaporated to dryness; the dry residue is then ignited in a platinum crucible. Upon dissolving the mass in water, peroxide of rhodium remains behind, which is brought upon a filter and washed, first with hydrochloric acid, and finally with water. It is then ignited with the filter, and subsequently reduced by hydrogen gas. The reduction is so easily effected that it is scarcely necessary to assist the action of the gas by the application of heat.

*Separation of Rhodium from Copper.*—Berzelius‡ directs to pour the solution into a flask which is furnished with a glass stopper, and to saturate it with sulphuretted hydrogen gas. The flask is then closed and allowed to remain for twelve hours in a warm situation. The sulphuret of copper is, in that time, fully, and the sulphuret of rhodium, for the most part, precipitated. The solution is filtered, and, being heated and evaporated, yields a fresh portion of sulphuret of rhodium, which

\* Palladium being precipitated from its *acid* solutions by sulphuretted hydrogen, it can thus be separated from iron and other metals not precipitable by this gas. The resulting sulphuret is roasted into basic sulphate, and dissolved in HCl acid. Upon the addition of a solution of cyanide of mercury to the solution, previously neutralized by soda, cyanide of palladium falls and may then be ignited.

† Poggendorf's *Annal*, B. xiii. p. 454; and Rose's *Manual of Analytical Chemistry*, translated by Griffin, p. 131.

‡ Berzelius' *Traité de Chimie*.

is added to the other sulphurets. These are placed, while still moist, in a platinum crucible, and roasted as long as sulphurous acid exhales. When the roasting is finished, the mass is subjected to the action of concentrated hydrochloric acid, peroxide of rhodium remains undissolved, and is reduced by hydrogen gas, the copper in the solution is precipitated by caustic potassa.

*Rhodium* exists together with *iridium*, *palladium*, *osmium*, &c., in platinum ores. It is extracted from the liquor from which the palladium has been precipitated by cyanide of mercury by the following process. Hydrochloric acid is added, and the solution is evaporated to dryness, the excess of cyanide of mercury is decomposed, and transformed into chloride. The dry saline mass is reduced to a very fine powder and washed with alcohol, sp. gr. 0.837. The double chlorides of sodium and platinum, sodium and iridium, sodium and copper, and sodium and mercury, are dissolved, but the double chloride of sodium and rhodium remains behind in the form of a fine red powder. It is washed with alcohol and decomposed by gently heating in a current of hydrogen gas, by which the chloride of rhodium is reduced, and the metal is subsequently separated from the chloride of sodium by water. Another method of treating the saline mass is to mix it with about twice its weight of carbonate of potassa, and to calcine the mixture. The residue is treated with water, and the copper dissolved out by hydrochloric acid. The residual mass is next mixed carefully with five times its weight of anhydrous bisulphate of potassa and heated to redness in a well-covered platinum crucible; the heat is continued till the mixture is about to solidify. The oxide of rhodium dissolves in the bisulphate of potassa. The saline mass is extracted with boiling water, and the process is repeated with fresh bisulphate as long as the salt continues to receive color; excess of carbonate of soda is poured into the aqueous extract, the whole is evaporated to dryness, and the residue is calcined; the residue is again treated with boiling water. Oxide of rhodium remains undissolved, and is then in a state to be reduced by hydrogen gas.

#### *Osmium and Ruthenium.*

The first of these metals, which is found in combination with *iridium* in platinum ores, is extracted by the following

process.\* The grains of *osmium-iridium*, which are exceedingly hard, are reduced to a very fine powder, which is then digested with hydrochloric acid, to remove the iron which has become rubbed from the mortar during the operation of trituration: it is then dried, mixed with nitre, and heated gradually to redness in a porcelain retort connected with a receiver containing caustic ammonia. During this operation, both metals become oxidized, and a portion of the oxide of osmium, or osmic acid, which is volatile, is carried forward with the nitric oxide gas, and condensed in the ammonia, to which it communicates a yellow color. Another portion is condensed on the sides of the receiver in the form of a crystalline mass. All disengagement of gas having ceased, the apparatus is allowed to cool, the receiver containing the ammonia is then removed, and the mass which remains in the retort is dissolved in water. The solution is of a deep brown color, and contains a combination of the two oxides with potassa. It must not be filtered, since the organic matter of the paper decomposes it. It is therefore at once distilled, at a gentle heat, in a retort connected with a receiver, and the greater part of the liquor drawn over. This liquor, which is colorless, and possessed of a strong and disagreeable odor, contains the osmium in the form of *osmic acid*. The following method of extracting *iridium* and *osmium* from the pulverulent residue, after digesting platinum ore with aqua regia, was proposed by *Wöhler*. The residue is mixed with an equal weight of dry and finely pulverized common salt, heated to redness in a long glass tube, and a stream of chlorine sent through, as long as it continues to be absorbed. In this operation the *titanate of iron* is not attacked, but there are formed compounds of iridium and osmium with chloride of sodium; much osmic acid is also disengaged, being expelled with the aqueous vapor introduced with the chlorine gas; this is condensed in a receiver containing ammonia, which is adapted to the tube. When no more chlorine is absorbed, the contents of the tube are treated with water, which dissolves the double salts of iridium and osmium. The solution has a deep red-brown color. The titanate of iron and other matters remain undissolved. The solution is then distilled, by which much osmic acid, arising from the decomposition of the chloride of osmium, is removed, and is

\* Berzelius's *Traité de Chimie*.

condensed in a receiver containing ammonia; when no more osmic acid passes over, the distillation is stopped, and the residual liquor, after being filtered, is mixed with excess of carbonate of soda, evaporated to dryness, and the residue feebly calcined. It consists of a mixture of suboxide of iridium with chloride of sodium; the latter is dissolved out by water. The suboxide of iridium is not, however, pure, it still contains a notable quantity of iron and of osmium; the former is removed by reducing the oxide to the metallic state in a current of hydrogen gas, and then acting on the residue with concentrated hydrochloric acid. Under this treatment the platinum residue loses in general from 25 to 30 per cent. of its weight: it is not, however, exhausted; and, by a second treatment with chloride of sodium, a farther amount of 5 or 6 per cent. of a mixture of osmium, iridium, and iron may be extracted. From the residue a small quantity of platinum may generally be dissolved out by aqua regia: it not unfrequently, also, contains chloride of silver, which may be separated by ammonia.

The following modification of this process has been recommended by *Fritzsche*.<sup>\*</sup> Equal portions of caustic potassa and chlorate of potassa are melted together in a very spacious porcelain crucible over a spirit lamp, and into the fused mass is conveyed about three times its weight of osmium-iridium, without first reducing it to powder. As soon as, on farther heating, the chlorate of potassa liberates oxygen, the fused mass begins to act on the osmium-iridium. The mass froths violently, so that the heat must be moderated when it becomes more tenacious; the action at last proceeds without any further heating, the mass becomes nearly black, and the operation is discontinued as soon as the frothing has ceased. During the whole operation, not a trace of osmium vapors is perceptible, but a slight evolution commences on the solidification of the mass, which is increased by farther heating; this, however, is unnecessary, so that there is scarcely any trouble with the vapors of osmic acid. Six hundred grammes of osmium-iridium may be fused with ease in a porcelain crucible capable of holding 2 lbs., with 100 grains of caustic potassa and chlorate of potassa, over a spirit lamp. The operation scarcely lasts an hour, and at least 50 grains are decomposed. On

<sup>\*</sup> Journ. für Prakt. Chem., xxxvii. p. 483; and Chem. Gaz., vol. iv. p. 319.



treating the fused mass with water, an orange-colored solution, containing *osmium* and *ruthenium*, is obtained, and a blackish-blue precipitate, which may very easily be separated by suspension from the undecomposed *iridium-osmium*.

By the above process of *Berzelius*, iridium cannot be completely separated from osmium, for, on heating the former while exposed to the air, vapors of osmic acid are always disengaged. In order to complete the separation of these two metals, the following method is employed by *Fremy*:\* 100 grammes of the residue of the platinum workings are mixed with 300 grammes of nitre; the mixture is introduced into a large crucible and kept for an hour at a red heat in a wind furnace. After this calcination the mass is poured out on a metallic plate, which operation should be performed in the open air, and it is even indispensable to cover the face, for without this precaution, the vapors of osmic acid would act violently on the skin. During the calcination with nitre, a certain quantity of osmic acid is lost, but it was found that the proportion of this acid which might be condensed would never repay the inconveniences of calcining in a porcelain crucible. The decanted mass, which contains the osmiat and iridiat of potassa, is treated in a retort with nitric acid, which liberates the osmic acid, which is condensed in a concentrated solution of potassa. The residue is treated with water, which removes the nitre, and it is then acted upon with hydrochloric acid, which dissolves the oxide of iridium. In this manner the osmium is obtained in the state of osmiat of potassa, and the iridium in that of soluble chloride. Into the solution of osmiat of potassa *Fremy* pours a small quantity of alcohol; the liquid becomes heated, acquires a red tint, and deposits a crystalline powder of *osmite* of potassa; in this case the osmium is frequently precipitated entirely from solution. The salt may be washed with alcohol, which does not dissolve it, and it then may be preserved without alteration. All the compounds of osmium may be prepared from it. On treating it with a cold solution of sal-ammoniac, it dissolves at first, and is then decomposed, giving rise to a new yellow salt, scarcely soluble in cold water. This salt, which is so easily prepared, affords, on calcination in a current of hydrogen, osmium perfectly pure.

\* Comptes Rendus, Jan. 22, 1844; and Chem. Gaz., vol. ii. p. 107.

To extract the *iridium*, *Fremy* treats the chloride obtained as above with sal-ammoniac, a reddish-brown precipitate is formed, consisting of a combination of the bichlorides of osmium and iridium with sal-ammoniac. To separate these two double salts a stream of *sulphurous acid* is passed into the water in which they are suspended, the double salt of iridium is decomposed, chloride of iridium is formed, which is very soluble in water; the double salt of osmium undergoes no change, it remains in the state of a red salt. The soluble salt of iridium crystalizes in large brown prisms out of solutions in sal-ammoniac; it is, therefore, easy to purify it when calcined in a current of hydrogen; it affords metallic iridium in a state of purity.

Besides *iridium* and *osmium*, another metal has been found in the platinum residues by *Professor Clauss*.<sup>\*</sup> It is called by its discoverer *ruthenium*. He prepared it in the following manner:—The residue, which had been once fused with nitre and extracted with water and acids, was mixed with an equal quantity of nitre, and kept at a white heat in a Hessian crucible for two hours. The mass was taken out while still red hot with an iron spatula, and, after cooling, was reduced to a coarse powder, which was extracted with distilled water, leaving it to stand with it till it became clear; the perfectly clear liquid, which was of a dark yellow color, was then decanted. It could not be filtered, since it was decomposed by the action of the organic matter of the paper. It contained *ruthenate*, *chromate*, and *silicate* of potassa, not a trace of either *rhodium* or *iridium*, and only a very minute trace of *osmate of potassa*. Nitric acid was cautiously added to this solution, until the alkaline reaction of the liquid had disappeared: oxide of ruthenium and potassa, and some silicic acid, were hereby precipitated in the form of a velvet black powder, while chromate of potassa remained undissolved. After edulcoration the oxide of ruthenium and potassa was dissolved in hydrochloric acid, and the solution was evaporated till the silica separated as a gelatinous mass. It was then diluted with water and filtered. It could not be evaporated to dryness for the more complete separation of the silica, because the chloride of ruthenium was thereby decomposed

<sup>\*</sup> *Bullet. de la Classe Physico-Math. de l'Acad. de St. Petersburg*, t. iii. p. 311; and *Chem. Gaz.*, vol. iii. p. 49.

into an insoluble protochloride. The filtered solution, which is of a beautiful orange yellow color, was evaporated down to a very small volume, and mixed with a concentrated solution of chloride of potassium, when the salt  $KCl_2 + RuCl_4$  separated in reddish-brown crystals. A further quantity was obtained by evaporating the liquid decanted from the crystals. The salt was further purified by recrystallization. *Clauss* has hitherto only been able to obtain the metal as a blackish-gray powder, which is considerably lighter than *iridium*: the aqueous solution of its chloride is precipitated in the form of a black oxide by ammonia, by which it is distinguished from all the other platina metals, none of which are precipitated by ammonia at the ordinary temperature. If a slip of zinc be inserted in a solution of the orange-colored chloride acidified with hydrochloric acid, a black metallic powder is after a time deposited, the liquid acquires a dark indigo blue color, but subsequently, after the whole of the metal is deposited, becomes colorless.

*Analysis of a mixture of Oxides of Lead, Bismuth, Silver, Copper, Mercury, and Cadmium.*—To a diluted solution carbonate of potassa is first added and then excess of cyanide of potassium; the oxides of *lead* and *bismuth* are precipitated in the form of carbonates, they are received in a filter, washed, dissolved in nitric acid, and the oxide of lead separated from the oxide of bismuth by dilute sulphuric acid, as directed (p. 321). The washing from the precipitated carbonates being mixed with the filtrate, excess of diluted nitric acid is added, the silver is precipitated as cyanide, in the form of which salt it is estimated. The filtrate from the cyanide of silver, together with the washings, are again neutralized by carbonate of potassa, a fresh quantity of cyanide of potassium is added, and a stream of sulphuretted hydrogen gas is passed through the solution, the *mercury* and the *cadmium* are precipitated as sulphurets: the whole of the sulphuret of copper is retained in solution by the cyanide of potassium, provided a sufficient quantity of that reagent has been added; to insure this, it is advisable to add a fresh portion after the action of the sulphuretted hydrogen. The precipitated sulphurets of mercury and cadmium, after being well washed on the filter, are decomposed by digestion with aqua regia, the solution is filtered off from the sulphur, nearly neutralized with potassa, and the mercury estimated as subchloride by formiate of soda, as

directed p. 316. The cadmium in the solution, filtered from the subchloride of mercury, is precipitated by carbonate of soda. The sulphuret of copper, which remains dissolved in the cyanide of potassium, is mixed with nitric acid and evaporated with the addition of sulphuric acid, until the whole of the hydrocyanic acid is expelled, the sulphate of copper retained in solution is finally precipitated at a boiling temperature by caustic potassa.

## GROUP 6.

*Antimony, Arsenic, Tin, Platinum, Iridium, Gold, Selenium, Tellurium, Tungsten, Vanadium, Molybdenum.*

### *Antimony.*

This metal is quantitatively estimated as *sulphuret*, as *antimonious acid*, and as *pure metal*.

*Precipitation as Sulphuret.*—The solution is diluted with water, and tartaric acid added only until the resolution of any basic salt which the addition of water may have precipitated. A stream of washed sulphuretted hydrogen gas is then conducted through the solution until it smells strongly of it, it is allowed to remain at rest for some time in a moderately warm situation till the excess of sulphuretted hydrogen has been expelled. If the solution under examination contain antimony in the state of oxide only, the precipitated sulphuret may be then collected on a weighed filter, washed thoroughly with distilled water, dried at  $212^{\circ}$ , and weighed. Its composition is

|                           |     |        |     |       |
|---------------------------|-----|--------|-----|-------|
| One equivalent of Sb      | ... | 129.03 | ... | 72.88 |
| Three do. of S            | ... | 48     | ... | 27.12 |
| <hr/>                     |     |        |     |       |
| One do. of $\text{SbS}_3$ | ... | 177.03 |     | 100   |

But if any of the higher oxides of antimony are also present, which will always be the case when the compound under examination is dissolved in aqua regia, correct results cannot be obtained by simply weighing the precipitated sulphuret, its composition being variable. In this case the sulphuret must be decomposed by nitric acid, and the amount of sulphur present determined by converting it into sulphuric acid in the



following manner:—The sulphuret is collected on a filter, dried at  $212^{\circ}$ , and its weight, filter included, accurately determined; a portion is then removed for analysis, the weight of this portion is noted; it is digested in a flask with fuming nitric acid, carefully added at first, the action generally being very energetic; hydrochloric acid is then added, and heat applied and continued for some time if a clear solution be obtained; it is diluted with water, tartaric acid being added to redissolve any basic salt which may be thereby precipitated. The sulphuric acid formed by the oxidation of the sulphur is precipitated in the form of sulphate of baryta by chloride of barium: it is received on a filter, well washed with boiling distilled water, ignited, and weighed: from the weight obtained the amount of sulphur is calculated, which, being deducted from the weight of the sulphuret of antimony operated on, gives the quantity of metal; should it happen that a portion of the sulphur escaped oxidation by the nitric acid, the solution will not be clear; in this case, the solution, having been diluted with water with the requisite addition of tartaric acid, is passed through a weighed filter, and the weight of the separated sulphur, after being well washed and dried on the filter at  $212^{\circ}$ , is added to that calculated from the sulphate of baryta. It may be observed, that it is easy to see whether sulphuret of antimony precipitated from the original solution by sulphuretted hydrogen is the sulphuret corresponding to  $\text{SbO}_3$ : a small weighed portion of it is boiled in a test tube with hydrochloric acid; if a clear solution is obtained, the sulphuret is  $\text{SbS}_3$ , and the remainder may at once be weighed and calculated; but if it does not completely dissolve, it contains a mixture of one or more of the higher sulphurets, and the residue must be treated as above directed. Two other methods have been proposed for treating the mixed sulphurets: one is to decompose them at a gentle heat in a current of dry hydrogen gas, by which operation the sulphur is removed partly as sulphur and partly as sulphuretted hydrogen, metallic antimony being left behind; the other is to heat the mixture in a small retort out of contact of air, by which all the higher sulphurets are converted into the lowest; neither of these methods, however, gives such correct results as the first. When the reduction process is adopted, it is impossible to regulate the heat so as to prevent the volatilization of a small portion of the antimony, and, in the process of heating

the sulphurets out of contact of air, a portion of  $\text{SbS}_3$  is volatilized, and another portion is reduced to oxide, which is sublimed together with the sulphur.

*Quantitative estimation as Antimonious Acid.*—The compound under examination is evaporated with nitric acid, and the residue ignited as long as it continues to lose weight. Its composition is

|                           |     |        |     |       |
|---------------------------|-----|--------|-----|-------|
| One equivalent of Sb      | ... | 129.03 | ... | 80.12 |
| Four do. of O             | ... | 32     | ... | 19.88 |
| <hr/>                     |     |        |     |       |
| One do. of $\text{SbO}_4$ | ..  | 161.03 |     | 100   |

*Separation of Antimony from Manganese, Iron, Zinc, Cobalt, Cadmium, Lead, Bismuth, Copper, Silver, and Mercury.*—This may be effected by hydrosulphuret of ammonia, in which the sulphuret of antimony *alone* is soluble. The concentrated solution of the oxides is first saturated with ammonia, and, disregarding the bulky precipitate which is thereby produced, hydrosulphuret of ammonia, containing excess of sulphur, is added, and the whole digested at a gentle heat: water is then added, and it is allowed to cool, the vessel being closed. When quite cold, it is filtered; the whole of the antimony is contained in the filtrate, from which it may be precipitated by hydrochloric acid. If the compound to be analyzed be a solid, it may frequently, according to *Fresenius*, be analyzed by fusing it with sulphuret of potassium, and treating the fused mass with water, when sulphuret of antimony alone will be dissolved. It is necessary, however, to observe, that sulphuret of mercury is not altogether insoluble in sulphuret of potassium, neither is sulphuret of copper altogether insoluble in hydrosulphuret of ammonia.

### *Arsenic.*

This metal, whether in the form of *arsenious acid* or in that of *arsenic acid*, may be quantitatively estimated by combining it with *protoxide of lead*; when in the form of arsenious acid, it is generally most conveniently weighed as *sulphuret*.

*Quantitative estimation by Protoxide of Lead.*—To insure the metal being in the state of arsenic acid, the compound under examination (which must contain no other acid) is digested with aqua regia, and carefully evaporated to dryness; the residue, after being somewhat more strongly heated

in a platinum crucible, is dissolved in water, and a known weight of recently ignited and pure protoxide of lead added; the mixture is carefully evaporated to dryness, and gently ignited: the amount of arsenic acid present is learned from the increase in weight, and from this the quantity of arsenic is calculated.

*Estimation as Sulphuret.*—For this purpose the arsenic must be in the form of *arsenious acid*, to insure which the solution of the compound should be mixed with a concentrated aqueous solution of *sulphurous acid*, and gradually heated to gentle ebullition in a flask; the heat must be maintained till the whole of the excess of sulphurous acid is expelled; hydrochloric acid is now added, and a stream of washed sulphuretted hydrogen is conducted through the liquid, till it smells strongly of it. It must not be immediately filtered, because the sulphuretted hydrogen liquor may hold in solution a portion of sulphuret of arsenic. It is set aside in a warm place, until the excess of sulphuretted hydrogen gas is expelled. *Fresenius* recommends that this be done by transmitting through the solution a stream of washed carbonic acid gas. The liquid, being freed from sulphuretted hydrogen, is passed through a weighed filter, washed with hot distilled water, dried at  $212^{\circ}$ , and weighed. Its composition is

|                                      |     |     |     |       |
|--------------------------------------|-----|-----|-----|-------|
| One equivalent of As                 | ... | 75  | ... | 60.97 |
| Three ditto of S                     | ... | 48  | ... | 39.03 |
| <hr/>                                |     |     |     |       |
| One ditto of $\text{As}_2\text{S}_3$ | ... | 123 | ... | 100   |


Should the process of treating the solution with sulphurous acid not have been adopted, and if there is reason for supposing that a portion of the arsenic may have been in a higher state of oxidation than that of arsenious acid, and if, moreover, there should be present certain other substances capable of decomposing sulphuretted hydrogen, such as *chromic acid*, *peroxide of iron*, &c., then the sulphuret of arsenic cannot be weighed for the purpose of estimating the metal, until after the excess of sulphur has been removed: this is done precisely in the same manner as has been directed in the case of sulphuret of antimony, with excess of sulphur, viz., by converting the free sulphur into sulphuric acid, and determining its amount in the form of sulphate of baryta.

*Levol's Method of Estimating Arsenic in the Copper and*

*Tin of Commerce, and in Bronzes.*—The arsenic is thrown down, in company with peroxide of tin, by nitric acid, and the arseniferous oxide of tin thus produced is reduced by hydrogen gas. The author found the reduction to take place readily at a dark red heat, the greater part of the arsenic being separated by sublimation, the small quantity still remaining with the tin is received by hydrochloric acid. The arseniuretted hydrogen yields on decomposition the whole of the arsenic retained by the tin. The best state for employing the tin for the purpose of collecting the arsenic, appeared to be that of a solution in cold weak nitric acid; the protoxide which is thus formed, remaining dissolved, readily comes into contact with the molecules of the arsenic; and, when the temperature is raised to convert it into peroxide, it seizes on the arsenic and carries it down with it. Arsenic and antimony oxidized with nitric acid likewise enter into combination, but the product is not entirely insoluble. *M. Levöl* has also published a method for the quantitative separation of the *arsenic* and *arsenious* acids; it is founded on the insolubility of the bi-basic arseniate of ammonia and magnesia ( $2\text{NH}_3, 2\text{MgO}, \text{AsO}_5 + 10\text{Aq.}$ ), a salt corresponding to the double ammonio-phosphate of magnesia, and which he obtained in the same way as the latter, viz., by adding a soluble ammonio-magnesian salt to the liquid containing arsenic acid, having previously rendered it ammoniacal; it is deposited in the form of very minute crystals on the sides of the vessel; its solubility is such that one part of arsenic acid, diluted with 56818 parts of water rendered ammoniacal, is made apparent shortly after the addition of a few drops of the concentrated solution of ammonio-sulphate of magnesia. Arsenious acid does not yield an insoluble double salt with ammonia and magnesia. The precipitate, on being dried and ignited, becomes  $2\text{MgO}, \text{AsO}_5 = 55.74$  per cent. of the new salt which represents 41.02 per cent. of arsenic acid. *M. Levöl* suggests the use of ammonio-magnesian salts in cases of poisoning by arsenic acid. The separation of *arsenious* from *arsenic* acid may, also, according to *Fresenius*, be effected satisfactorily in the following indirect manner:—The solution containing the two acids is divided into two equal portions; in one, the arsenic acid is reduced to arsenious acid by sulphurous acid, and the whole then precipitated by sulphuretted hydrogen: the precipitated sulphuret of arsenic is washed, dried at  $212^\circ$ , and



weighed. The arsenious acid in the other half of the solution is converted into arsenic acid by chlorine, for which purpose it is mixed with hydrochloric acid and solution of indigo, added till the fluid acquires a blue color. Chloride of lime, containing a known amount of chlorine, is then added from a weighed solution, until the blue color disappears: from the quantity consumed, the amount of chlorine used is calculated. This operation depends on the circumstance that every equivalent of arsenious acid requires two equivalents of chlorine to convert it, in the presence of water, into arsenic acid, thus—



By calculating the resulting quantity of arsenious acid upon sulphuret of arsenic, and subtracting the weight of this from the total weight obtained from the first portion of the analyzed solution, the amount of arsenic, originally contained in the latter, is found.

*Separation of Arsenic from the metals of the 5th Group.*

—This may be effected by hydrosulphuret of ammonia, having first precipitated the solution by sulphuretted hydrogen, the sulphuret of the metals of the 5th Group being insoluble in hydrosulphuret of ammonia. The dissolved sulphuret of arsenic is precipitated from its alkaline solution\* by acetic acid; but it must be remembered, that in this case it contains free sulphur, which must be removed and estimated in the manner already described. The separation of arsenic from the members of the 5th Group may likewise be effected by fusing the mixture with twice its weight of carbonate of soda, and twice and a half its weight of nitre; the arsenic is hereby converted into arsenic acid, which combines with the alkali, and may thus be dissolved out from the remaining metallic oxides; from lead, arsenic acid is separated by dissolving the compound in nitric acid and precipitating the lead by sulphuric acid, with the addition of alcohol.

*Separation of Arsenic from Antimony.*—When the compound of the two metals is in the reguline state, the arsenic may be expelled by heating out of contact of air; when, however, other metals are also present, this process cannot be adopted, since most other metals retain a part of the arsenic when at a red heat. In this case several methods have been proposed:—

1. The substance is dissolved in aqua regia, tartaric acid is added, and the antimony and arsenic are together precipi-

tated by sulphuretted hydrogen; the sulphurets are intimately stirred together, collected on a filter, dried at a very gentle heat, and weighed. From a weighed portion the amount of sulphur is determined by dissolving it in aqua regia, and having added tartaric acid and diluted with water, precipitating the sulphuric acid formed by chloride of barium. Another weighed portion of the mixed sulphurets is heated in a tube, through which a stream of hydrogen gas is passing: the excess of sulphur and the sulphuret of arsenic are expelled, leaving the sulphuret of antimony, which may then be weighed. This method, when carefully performed, is capable, according to *Rose*, of affording a result only about a half per cent. from truth: the proportion of arsenic present is calculated from the loss, the united weight of both metals having by the first experiment been determined in the state of sulphuret.

2. *Behren's Method*.—The arsenic and antimony are combined into sulphurets, and to the mixture is added, while still moist, an equal volume of neutral *nitrate of lead*, and about as much water. The mass is boiled in a porcelain dish, being stirred without interruption, and the water which evaporates being renewed until the whole has acquired a dark brown color, it is then filtered. The residue contains the entire amount of antimony, and a portion of the arsenic. The solution contains the arsenic in the state of arsenious acid, nitric acid, and oxide of lead; it is heated with carbonate of ammonia as long as a precipitate is formed. To the liquid filtered from the carbonate of lead some hydrochloric acid is added, until it has an acid reaction; sulphuretted hydrogen gas is then transmitted through the solution, and the sulphuret of arsenic thus obtained has no trace of antimony. To separate the arsenic contained in the state of sulpho-arseniuret of lead, in the mass which remained on the first filtration, *M. Behren* digests it at a gentle heat with caustic ammonia, which converts the sulpho-arseniuret of lead into sulphuret of lead and sulphuret of arsenic, which latter dissolves in ammonia. To the filtered solution hydrochloric acid is added, and the sulphuret of arsenic precipitated is added to that first obtained.

*Fresenius* objects to the precipitation of the lead in the solution containing the arsenic by carbonate of ammonia; he prefers separating the two metals by hydrosulphuret of am-

monia, or by evaporating the solution to dryness, and fusing the residue with carbonate of soda and nitre.

3. *Antimony* and *arsenic* in alloys may, according to *Fresenius*, be separated, though not in a very accurate manner, by heating the mixture covered with common salt and carbonate of soda, in a glass tube, through which a current of dry carbonic acid gas is passing; the tube is heated gently at first, but the heat is gradually increased to the highest degree of intensity; by this means the arsenic is driven off, while the volatilization of the antimony is prevented by the common salt and carbonate of soda.

4. The method proposed by *Fresenius*, to distinguish between the metallic mirrors formed by antimony and arsenic, under similar circumstances, and which has already been described,\* may be employed in the quantitative estimation of these two metals; when carefully performed, it yields results which are tolerably accurate.

*Rose* has recently† described a method of separating the acids of arsenic and antimony, as likewise that of the peroxide of tin from bases by the use of *chloride of ammonium*. Great inconvenience, he observes, are attached to the method generally employed for analyzing these compounds, particularly such as are sparingly soluble in water and in hydrochloric acid; all these difficulties may, however, in many cases, be avoided, by adopting the following process:—Suppose we have a salt of one of these metallic acids, with an alkaline base to examine; after having ignited and weighed it, it is to be mixed in a finely pulverized state with from five to eight times the quantity of finely powdered chloride of ammonium, and heated in a small porcelain crucible, which may be covered with a concave platinum lid, over an argand lamp, until the whole of the chloride of ammonium is volatilized. The alkali is left behind in the state of chloride, the quantity of which may be with great accuracy determined. So long as chloride of ammonium continues to be volatilized, the temperature is so low that none of the alkaline chloride can escape. As soon as the ammoniacal salt is driven off, the temperature is moderated, so that the residue in the porcelain crucible does not fuse. After weighing, it is mixed

\* See Part I., p. 101.

† Chem. Gaz., April 15th, 1848.

with a fresh quantity of chloride of ammonium, and again heated, in order to see whether the weight of the residue remains constant or is diminished; in which latter case, the treatment with chloride of ammonium must be repeated. Sometimes, owing to the access of air, the platinum lid is covered with a film of the metallic acid, especially with peroxide of tin when *stannates* are examined. In this case, the lid, in the subsequent ignition, is covered with a little of the ammoniacal salt. The use of chloride of ammonium in analytical chemistry is not, *Rose* observes, restricted to the compounds here mentioned, but is capable of considerable extension, as he purposes hereafter to point out.

5. Meyer's method of separating arsenic from antimony is founded on the insolubility of antimoniate of soda and the conversion of arseniferous antimony into arseniate and antimoniate of soda. *Chem. Gaz.*, 6, 375.

### *Tin.*

This metal is weighed as *peroxide*: it has also been attempted to estimate it by a *normal solution of iodine*.

*Quantitative estimation as Peroxide.*—The compound under examination is evaporated nearly to dryness, at a boiling heat, with strong nitric acid to insure the whole of the metal being in the state of peroxide; if any hydrochloric acid be present, it must be completely decomposed and expelled. The peroxide of tin, which by the action of the nitric acid has become converted into the insoluble modification, is filtered, washed, ignited, and weighed. Its composition is

|                             |     |       |     |       |
|-----------------------------|-----|-------|-----|-------|
| One equivalent of Sn        | ... | 58.82 | ... | 78.61 |
| Two do. of O                | ... | 16    | ... | 21.39 |
| <hr/>                       |     |       |     |       |
| One do. of SnO <sub>2</sub> | ..  | 74.82 |     | 100   |

Tin may also be precipitated from its acid solution, whether in the state of a proto-salt or of a persalt, by sulphuretted hydrogen; in the former case the resulting sulphuret is brown, in the latter case it is yellow; the gas must be passed through the solution till it smells strongly of it, and a gentle heat must afterwards be applied, by which a small quantity of sulphuret, which is dissolved in the saturated liquor, becomes again deposited; the sulphuret of tin must not be weighed as such, but converted into peroxide, which may be done by heat-



ing it, first gently and then intensely, in a porcelain crucible, till all the sulphur is removed in the form of sulphurous acid, the expulsion of which is facilitated by adding a small fragment of carbonate of ammonia. *Rose* recommends to convert the sulphuret of tin into peroxide by nitric acid, observing that, when the quantity of sulphuret is at all considerable, its conversion into peroxide takes place by heat alone with extreme slowness.

*Quantitative estimation of Tin by Volume.*—This method was proposed by *M. Gaultier de Claubry*.<sup>\*</sup> As a normal solution, he employs 1 grm. (about 15 grs.) of iodine dissolved in a *decilitre* (about 6 cubic inches) of alcohol, sp. gr. 0.932, and the solution of tin is prepared with one gramme of this metal dissolved in hydrochloric acid, and diluted with water freed from air, so as to form a litre (61 cubic inches). By means of a graduated pipette, a demi-decilitre (about 3 cubic inches) of the tin solution is measured off, and the burette, divided into tenths of a cubic centimetre, is filled with the normal solution; the latter is poured into the first until it is no longer decolorized; half a decilitre of the tin solution, containing 5 decigrammes (about 7.5 grs.) of tin, decolorizes 100°, or 10 cubic centimetres of the normal solution. If the tin ore under examination is soluble in hydrochloric acid, the operation is perfectly simple; if it does not dissolve in it, it is acted on with aqua regia, containing much hydrochloric acid; and, when the tin is become converted into perchloride, an excess of hydrochloric acid is added, and it is then boiled with some *iron*, by which it becomes reduced to protochloride; the process is now conducted in the same manner as in the preceding case. If it happens to be an alloy containing only 20 per cent. of lead, hydrochloric acid will dissolve it; beyond that, however, only imperfectly; but, as *aqua regia* scarcely acts on the compounds of lead, the alloy must be dissolved in nitric acid, evaporated to expel the excess of acid, and then treated with hydrochloric acid and iron. *Stannic acid*, especially when it has not been dissolved, is readily converted into protochloride in the presence of an excess of hydrochloric acid and protochloride of iron, so that the assay is brought to the same state as when the product could be acted upon immediately with hydrochloric acid. When the compound to

\* *Comptes Rendus*, July 13, 1846; and *Chem. Gaz.*, vol. iv. p. 455.

be analyzed contains *arsenic, antimony, bismuth, copper, or lead*, the iron precipitates it, and again reduces the assay to the state of a tin solution. To precipitate the whole of the copper, and not to leave any of the protochloride of that metal in solution, a considerable excess of hydrochloric acid must be employed, and the boiling with iron continued for some length of time. The analysis of a salt of tin can be made with the same ease, and if a mixture of a per and proto-salt is examined, or any of the corresponding haloid compounds, the relative proportions can be determined by analyzing the substance itself, and then making a second analysis of the product boiled with hydrochloric acid and iron. *Zinc and iron* do not interfere with the analysis by iodine, while the protosalts of iron and the corresponding haloid compounds decolorize the sulphate of indigo, which *M. Pelouze* had attempted to employ for the estimation of tin, and renders this process impracticable.

Iodine may, according to the author, be used to determine the quantity of tin in a solution containing various metals; but if there be present an *arsenite, sulphite, or hyposulphite, phosphite, or hypophosphite*, the normal solution will be decolorized as with protochloride of tin. It will be requisite, therefore, to oxidize these salts by nitric acid or by chlorine, and to reduce the tin to protochloride by means of iron.

*Separation of protoxide of tin from peroxide of tin.*—*Rose's* method is the following:—The solution is divided into two portions; in one the amount of the metal is determined by precipitating it by sulphuretted hydrogen, and then converting it into peroxide in the manner described above. The other portion is dropped into solution of chloride of mercury, and the subchloride of mercury precipitated is filtered, washed, dried at a gentle heat, and weighed. From this weight it is easy to calculate how much protoxide or protochloride of tin was contained in the solution, since the quantity of chlorine contained in the subchloride of mercury is the same as that contained in the protochloride of tin, by which it was precipitated; or, on the other hand, the quantity of chlorine in the subchloride of mercury is equivalent to the quantity of oxygen in the protoxide of tin, which acted as a precipitant.

*Separation of Oxides of Tin from the Members of the Fifth Group.*—This may be effected by supersaturating the concentrated solution with ammonia, and then precipitating by

hydrosulphuret of ammonia the sulphuret of tin retained in solution, while the sulphurets of the other metals remain undissolved. From most other metals tin may also be separated by nitric acid; the alloy is boiled with the acid, which oxidizes all the metals, and dissolves everything but tin, which remains in the form of insoluble peroxide.

To separate *tin* from *iron*, *Berthier* employs *sulphite of ammonia*, which he adds to the hydrochloric solution; having previously diluted it with water, and neutralized with ammonia, the whole of the tin is precipitated, while the iron remains in the liquid.

*Analysis of Alloys of Tin and Copper.*—The process of *M. Cottereau*\* is founded on the principle that copper is precipitated from its solutions by *zinc* before *tin*. The alloy is reduced to a fine powder, a certain quantity weighed off and digested with boiling hydrochloric acid. Into the resulting solution of the protochlorides of copper and tin a plate of zinc is introduced. By a previous assay of the copper contained in the alloy by the cuprometric process of *M. Pelouze* (p. 328), the quantity of copper is determined, and consequently an equivalent amount of zinc may be added to the solution; or the plate of zinc may be immediately introduced into the solution, and left there until a bright iron blade does not acquire a red tint on being immersed in the liquor. The strip of zinc is then removed, and the precipitate collected on a filter. Whichever plan be adopted, the filtered liquor is acted on just as if it were pure protochloride of tin. The protochloride of zinc formed does not in the least interfere with the reaction.

*Separation of Tin from Antimony.*—This is attended with very great difficulties. The following methods have been proposed:—

1st. *Berthier's Method.*—The two metals being dissolved in concentrated hydrochloric acid, tartaric acid is added to the solution, which is then diluted with water, *sulphite of ammonia* added, and the whole boiled. The tin is precipitated while the antimony remains dissolved.

2d. *Levol's Process.*†—The alloy being reduced to a thin plate is heated with hydrochloric acid; after some minutes'

\* Comptes Rendus, June 29th, 1846; and Chem. Gaz., vol. iv. p. 348.

† Ann. de Chim. et Phys., Jan. 1845; and Chem. Gaz., vol. iii. p. 52.

boiling a saturated aqueous solution of chlorate of potassa is added in small quantities at a time, until the alloy entirely disappears. The two metals are then thrown down together by means of a bar of distilled zinc; the precipitate is removed from the zinc with the greatest care, a quantity of concentrated hydrochloric acid, about equal to what was employed at first, is added, and the whole is boiled so as to redissolve the tin without previously removing the chloride of zinc; when the action has terminated, that is, when nothing remains but the antimony, which is always the case after an hour's boiling, this metal then forms a very fine blackish powder: it is collected on a weighed filter, and the tin may now be immediately obtained from the liquors by sulphuretted hydrogen.

According to *Dr. L. Elsner*\* the above process has no claim to accuracy. He found, on repeating the experiment with a mixture of  $7\frac{1}{2}$  grains of tin and as much antimony, exactly according to the directions given by *Levol*, that the acid liquid filtered from the black powder, on being treated with sulphuretted hydrogen, yielded a precipitate which consisted evidently of two differently colored layers; the inferior layer was clearly the orange-red precipitate of sulphuret of antimony, above which was the chocolate-brown protosulphuret of tin. It is certain, therefore, that some antimony had dissolved with the tin. *Dr. Elsner* convinced himself that antimony is partly dissolved on being boiled with hydrochloric acid, and that, consequently, no quantitative method of separating it from tin can be founded on its insolubility in that acid.

*Rose's Method.*†—Strong nitric acid is cautiously poured upon the metals, and when the violent oxidation has ceased the whole is evaporated at a gentle heat, and the dry powder of the oxides fused in a silver crucible over an argand lamp with an excess of hydrate of soda. The fused mass is softened with a large quantity of water, gently warmed, and the antimoniate of soda allowed to subside. When perfectly cold, the clear solution is passed through a filter: if this is done while it is still warm, the solution will contain some antimoniate of soda. The insoluble salt is again treated once or

\* Journ. für Prakt. Chem., vol. xxxv. p. 313.

† Chem. Gaz., vol. v. p. 313.



twice with water, allowed to settle and cool, and the liquid, when perfectly clear, passed through the filter. When the whole of the stannate of soda has been dissolved in this manner, the liquid which has been warmed with the antimoniate of soda remains opalescent; it must not be poured on the filter, as it would pass through turbid. A small quantity of a dilute solution of carbonate of soda may be added to it, which renders it clear; but the edulcoration must not be continued for any length of time, as otherwise some antimoniate would be dissolved.

The moist antimoniate of soda is now treated in a beaker with a mixture of hydrochloric and tartaric acids, in which it readily dissolves; and the filter, upon which mere traces of the salt should have collected, washed with the same mixture. The antimony is then precipitated from the solution by sulphuretted hydrogen, and the amount of antimony estimated from the quantity of sulphuret obtained. *Rose* reduces the sulphuret of antimony by hydrogen in a porcelain crucible, through the lid of which a thin porcelain tube passes. A gentle heat is carefully applied, until the crucible no longer decreases in weight. After the reduction the inner side of the lid is coated with metallic antimony, which, however, in no way interferes with the accuracy of the experiment.

The solution of stannate of soda is acidified with hydrochloric acid. It is not necessary to add so much acid that the whole of the eliminated oxide of tin is again redissolved. It is merely necessary that the solution should strongly red-dened blue litmus paper. Upon this, sulphuretted hydrogen is passed into it. The sulphuret of tin is converted by roasting into oxide. When it has been dried, it frequently decrepitate, which, by want of care, may occasion a very considerable loss. It is, on this account, preferable to place it with the filter, while still moist, in a porcelain crucible, and to heat it for a long time very gently, and with access of air, in order to expel the sulphur at the lowest possible temperature. If a strong heat be given at the commencement, white fumes of oxide escape, especially when the air has free access. The higher sulphuret of tin has the property of subliming somewhat at certain temperatures; the vapors are oxidized by contact with the air, and form oxide of tin. This is also the cause of a white sediment of oxide of tin being formed upon the charcoal, when sulphuret of tin is heated on charcoal


before the blowpipe. A strong heat should not be applied until there is no longer any perceptible odor of sulphurous acid. After being strongly ignited, a piece of carbonate of ammonia is placed in the crucible, and, after its volatilization, a strong heat applied, with access of air, in order to expel the whole of the sulphuric acid formed; a small decrease of weight will be perceived.

The oxide of tin thus obtained never appears perfectly white: and the sulphuret of tin, precipitated by sulphuretted hydrogen, does not possess a purely yellow color, which *Rose* attributes to melting the metallic oxides with hydrate of soda in the silver crucible, traces of oxide of silver being removed by the alkaline solution. The results do not attain the highest degree of accuracy. Although stannate of soda containing an excess of hydrate of soda does not become turbid by boiling, as stated by *Fremy*, and the solution may even be evaporated until crystals separate, which, on the addition of water, entirely dissolve, yet the antimoniate of soda contains a small quantity of oxide of tin. Consequently the sulphuret precipitated by sulphuretted hydrogen from the acid solution of the antimoniate of soda contains a small amount of sulphuret of tin, which does not part with the whole of its sulphur at the temperature at which the sulphuret of antimony is reduced by hydrogen. For this reason a somewhat smaller amount of tin, a larger quantity of antimony, and a slight excess, is found in the analysis.



*Separation of Tin from Arsenic.*—The following process is given by *Fresenius*.<sup>\*</sup> The solution is perfectly freed from nitric acid by evaporating it to dryness at a gentle heat, with the addition of hydrochloric acid. A weighed portion of the dry mass is digested with hydrochloric acid, and solution of chlorate of potassa added until it is completely dissolved. The solution is introduced into a flask, together with a strip of clean zinc; the flask is provided with a bent tube, through which the disengaged hydrogen is conveyed, first through a bottle half full of water, and then into a Liebig's potash apparatus filled with a solution of neutral nitrate of silver. As soon as the evolution of gas has ceased, the apparatus is taken asunder, the zinc is removed from the flask and carefully washed, the washings being added to the contents of the

<sup>\*</sup> Instruction in Quantitative Analysis, p. 341. See also Appendix.

flask, the precipitate in which is allowed to subside, and the clear supernatant fluid cautiously decanted. The flask contains the whole of the tin, it may also contain a portion of the arsenic, but the greater part of the latter metal will have been volatilized in the form of arseniuretted hydrogen, and have become condensed in the solution of nitrate of silver in the state of *arsenious acid*. The precipitated metal in the flask is treated with hydrochloric acid; if it completely dissolves, it is free from arsenic, and may at once be precipitated as sulphuret of tin by sulphuretted hydrogen, but, if a black powder remains, it consists of metallic arsenic, and must be separated, washed, dried, and weighed, and the weight added to that of the arsenic found in the silver solution. This method is troublesome, but it appears to be the best known of separating these two metals.



When *antimony*, *tin*, and *arsenic* have to be separated from one another, the process just described is adopted; the greater portion of the antimony and arsenic is transferred to the silver solution, and, if the metal precipitated by the zinc does not completely redissolve in hydrochloric acid, the insoluble residue may contain both antimony and arsenic: it is separated by filtration from the tin solution, and after having been well washed, first with dilute hydrochloric acid and then with pure water, it is submitted to one of the processes already described for the separation of antimony from arsenic. The tin in the filtrate is precipitated by sulphuretted hydrogen. The contents of the potash apparatus are filtered, the insoluble antimoniuiret of silver is collected upon a filter, washed, and the antimony determined by nitric acid. The weight found is added to that obtained from the insoluble black powder. The arsenic which remains in the solution, filtered from the antimoniuiret of silver, is separated from the silver by hydrochloric acid, and finally precipitated, with the proper precautions, by sulphuretted hydrogen. The following equations, given by *Fresenius*, illustrate the nature of the decompositions and transpositions in this process:



Six equivalents of nitrate of silver and one of terhydride of

arsenic react in such a manner as to produce six equivalents of silver, one of arsenious acid, three of water, and six of nitric acid; again, three equivalents of nitrate of silver and one of terhydride of antimony, give rise to one equivalent of antimoniuuret of silver, three of water, and three of nitric acid.

### *Platinum.*

In whatever form this metal may be precipitated, it is invariably weighed in the reguline state. It may be precipitated from its solution as *ammonio-chloride of platinum*, as *potassio-chloride of platinum*, and as *sulphuret of platinum*.

1. *Precipitation as Ammonio-Chloride of Platinum.*—The acid solution is concentrated; it is then mixed with a concentrated solution of muriate of ammonia, and a sufficient quantity of spirits of wine added to effect the complete precipitation of the double salt: the precipitate is allowed to subside perfectly,\* it is then collected on a filter and washed with spirits of wine till the fluid passes through quite colourless, dried, and ignited, by which it is completely decomposed, metallic platinum in the form of a gray spongy powder, remaining in the crucible. The ignition requires to be performed with great care; the dried double salt is transferred, filter and all, into a weighed platinum crucible, and is heated gently, the cover of the crucible being laid loosely on, as long as fumes of sal-ammoniac are seen to escape; the cover is then removed, and a stronger heat applied till the organic matter of the filter is consumed; the crucible is finally exposed to an intense heat. The reason why a gentle heat must be applied at first is, because a portion of the undecomposed double salt might otherwise be carried off with the fumes of the sal-ammoniac.

*Precipitation as Potassio-Chloride of Platinum.*—The solution is mixed with chloride of potassium in excess, and alcohol added; the precipitated double salt is collected on a filter, dried at  $212^{\circ}$ , and weighed. It would not be safe, however, to estimate the platinum from the weight of the double salt, and, indeed, after ignition, it is not completely decomposed

\* If the solution is very acid, it should be *nearly* neutralized with ammonia previous to the addition of the sal-ammoniac; and, to ensure entire deposition of the precipitate, a repose of twenty-four hours is required before filtering.



into metallic platinum and chloride of potassium; where accuracy is required, therefore, a known portion of the double salt dried at  $212^{\circ}$  must be introduced into a weighed bulbed tube, and heated to redness, while a stream of dry hydrogen gas passes through it. It thus becomes completely reduced, hydrochloric gas being evolved; when this has ceased, which is known by white fumes ceasing to be formed on bringing a glass rod or a feather dipped in ammonia water near the end of the tube, the apparatus is allowed to cool, the chloride of potassium is then dissolved out with water, and the reduced platinum well washed. It is then again heated to low redness in a stream of hydrogen gas, and weighed; the weight obtained calculated upon the whole precipitate on the filter gives the result.

*Precipitation as Sulphuret.*—This is sometimes practiced to separate platinum from such metals as are not precipitated from their acid solutions by sulphuretted hydrogen, as well as from others whose sulphurets are insoluble in alkaline sulphurets; in the former case, the gas is passed into the acid solution. No precipitation frequently takes place till heat is applied, when the solution turns brown, and sulphuret of platinum is precipitated; it is not weighed as such, but after being washed is ignited, by which it becomes reduced, and is then estimated in its metallic state: in the latter case, the solution is rendered either neutral or alkaline, and hydro-sulphuret of ammonia added in excess, in which the sulphuret of platinum dissolves.

*Separation of Platinum from Antimony, Arsenic, and Tin.*—This is readily effected by taking advantage of the volatility of the chlorides of the three last metals; all four are first precipitated together by sulphuretted hydrogen; the mixed sulphurets are introduced into a bulbed tube, and heated in a stream of chlorine gas. Platinum alone remains.

*Separation of Platinum from the metals which accompany it in its Ores, namely, Iridium, Osmium, Rhodium, and Palladium.*—Berzelius directs to proceed as follows:—The mineral is introduced into a tubulated retort connected with a receiver, and gently heated with hydrochloric acid, to which a little nitric acid has been added; as the action slackens, fresh portions of nitric acid are added. When the acid is

\* *Traité de Chimie*, vol. ii. p. 429, *et seq.*

saturated, the liquor is evaporated to the consistence of syrup. It is then allowed to cool, diluted with a little water, and decanted from the undissolved residue. The product of the distillation contained in the receiver has generally a yellow colour, in consequence of the spirting over of a portion of the contents of the retort. Spangles of osmium-iridium are also sometimes found there. The distillate is returned to the retort, and the greater portion redistilled. If the mineral is not now decomposed, a fresh quantity of aqua regia must be added. It frequently happens that a residue still remains, which, on examination, is found to consist of grains of osmium and iridium, which had escaped detection before submitting the ore to the action of the acid, or of brilliant plates of the same alloy, or of iridium itself in a black and pulverulent state; fragments of hyacinth, quartz, chrome iron, titanium, iron, &c. &c., are also frequently formed in the insoluble residue. The acid from the second distillation should be colorless. Should it not be so, it must be a third time distilled. This distillate contains *osmic acid*, the method of separating which has been already described. The solution in the retort has usually a deep red color; if it disengages an odor of chlorine, it is a proof of the presence of *bichloride of palladium*, which must be decomposed into chloride by boiling. Into the clear liquor, a saturated solution of chloride of potassium is poured, as long as a precipitation takes place. This precipitate, the color of which varies from a clear yellow to a cinnabar red, consists of the double chloride of platinum and potassium, mixed with a greater or less quantity of the double chloride of iridium and potassium, to which it owes its red color. It is received on a filter and washed with a dilute solution of chloride of potassium until the wash liquor ceases to strike blue with ferrocyanide of potassium. The filtrate contains *rhodium*, *palladium*, a little *platinum and iridium*, *iron* and *copper*. The double salt on the filter is dried, intimately mixed with double its weight of carbonate of potassa, and heated gradually till the mass begins to fuse in a platinum crucible. The carbonate of potassa decomposes the double platinum salt, chloride of potassium is formed, the platinum is reduced to the metallic state, while the iridium remains in the state of suboxide. The mass is washed first with water, then with warm hydrochloric acid; the residue is finally digested, first with dilute, and then with concentrated

aqua regia, in which the suboxide of iridium is insoluble. The solution contains the whole of the platinum, still, however, mixed with a certain quantity of iridium. It is, therefore, again precipitated with chloride of potassium, and the precipitate decomposed as before by ignition with carbonate of potassa; should the solution in aqua regia still have a red tinge, it must undergo a third treatment. The solution of platinum, when pure, has a pure golden yellow color. It is necessary to bear in mind, however, that there exists a chloride of platinum the aqueous solution of which has a dark brown color, though this is only formed by evaporating and gently heating the bichloride, during which chlorine is disengaged. It cannot, therefore, be formed by dissolving the chloride of platinum directly. Into the solution of pure chloride of platinum, solution of chloride of ammonia is poured; a clear yellow precipitate is formed, consisting of double chloride of platinum and ammonium; this precipitate furnishes, by gentle ignition, pure metallic platinum. For details of the processes for converting the metal as thus obtained, in what is termed its *spongy form*, into a malleable state, works on general chemistry must be consulted.

### Gold.


This metal, like the preceding, is always weighed in the metallic state, in which it is precipitated from its solutions by *protosulphate of iron* or by *oxalic acid*. A method of estimating the metal indirectly by means of standard solutions has also been published by *O. Henry*. Gold may also be precipitated from its acid solution by sulphuretted hydrogen. The sulphuret is readily reduced by heat alone.

*Precipitation by Protosulphate of Iron.*—If the solution contains nitric acid, it must be evaporated nearly to dryness, with the addition of successive portions of hydrochloric acid, the residue is dissolved in water, acidulated with hydrochloric acid, and mixed with an excess of a clear solution of protosulphate of iron. It is set aside for some time in a warm place till the reduced gold has completely subsided in the form of a fine brown powder, which is then filtered, gently ignited, and weighed. The object in expelling the nitric acid is to prevent the formation of aqua regia, which might redissolve a portion of the precipitated gold. Solution of *proto-nitrate of mercury* may be employed in the place of proto-

sulphate of iron; the latter, however, is preferable as the reducing agent.


*Reduction by Oxalic Acid.*—In certain cases it is not convenient to introduce another metal into the solution from which gold is to be precipitated, *oxalic acid* is then employed as the reducing agent. The solution, as before, is freed from nitric acid, and oxalate of ammonia added; if the solution does not already contain free hydrochloric acid, a quantity is next added, and the mixture set aside in a warm place; the whole of the gold is deposited in the form of yellow scales, which are collected on a filter, washed, gently ignited, and weighed. In cases where gold is the only fixed substance present, its quantity may be estimated by simply evaporating the solution to dryness and igniting the residue, and, when in combination with other substances which are incapable of precipitating from acid solutions by sulphuretted hydrogen, gold may be separated by that reagent, and the resulting sulphuret decomposed by ignition in a platinum crucible.

The rationale of the reduction of terehloride of gold by protosulphate of iron is this:



One equivalent of terehloride of gold and six of protosulphate of iron give rise to two equivalents of persulphate of iron, one of sesquichloride of iron and one of gold.

The rationale of the reduction by oxalic acid is as follows:



One equivalent of terehloride of gold and three of oxalic acid give rise to one equivalent of gold, three of hydrochloric acid, and six of carbonic acid.

*M. Henry's method of estimating Gold by Standard Solutions.\**—This process, which was devised by the author in consequence of the difficulty which he experienced in appreciating very minute quantities of gold, either by weighing or by cupellation, in certain investigations, in which he was engaged relative to the new processes, of gilding and silvering, of *Elkington* and *Ruolz*, is founded on the principle, that in a mixture of terehloride of gold, a basic salt, and copper, a quantity of the latter metal, equivalent to that of the gold, separated either in powder or upon the object to be gilt, is dissolved. When the amount of gold upon a gilt object, or

\* Journ. de Pharm., Jan. 1847; and Chem. Gaz., May 15th, 1847.



in a bath which has been, or is to be employed in gilding has to be ascertained, the following plan may be adopted. The objects, weighed with care, are digested with hot pure nitric acid; as soon as the copper forming the basis is dissolved, the solution is diluted with distilled water, and the gold is soon seen to settle at the bottom of the vessel in small brilliant scales. These are collected, and, after washing, dissolved in aqua regia, the solution evaporated with great precaution nearly to dryness, so as to obtain a ruby red product, soluble in water; this is terchloride of gold with a little acid. This product is now dissolved in distilled water, and mixed with five or six times its weight of pure bicarbonate of potash or soda, dissolved in distilled water; the mixture is heated, conveyed into a ground-stoppered flask, and a somewhat large amount of finely divided copper, which has been previously heated in a current of hydrogen, added to it; the mixture is now and then shaken, and after about an hour the liquid assayed. A very minute quantity of the liquid is poured upon a watch glass and treated with protosulphate of iron; if the liquid does not yield a black or gray precipitate, it is a sign that it contains no gold in solution; should the contrary occur, more copper must be added and again agitated. When the whole of the gold has been precipitated upon the copper, the liquid is carefully saturated with pure sulphuric acid so as to be *slightly acid*. By this means all the copper precipitated in the state of *carbonate* is dissolved without the gold or *metallic copper* being at all acted upon. It is filtered, and a solution of pure *ferrocyanide of potassium* of known strength carefully added by means of a graduated burette, until a precipitate ceases to be formed; the number of divisions of the instrument employed to precipitate the copper is noted, and in this manner the quantity of the metal dissolved in the liquid is ascertained.

When it is a solution which is to be, or has been, used for gilding, the author advises to precipitate the diluted acid solution by a current of sulphuretted hydrogen, to collect the precipitate and strongly calcine it after washing. The sulphuret of gold being reduced to the metallic state, the calcined residue is redissolved in nitric acid, and the gold which has remained unattacked, dissolved in aqua regia, and treated as above described.

The use of the ferrocyanide of potassium, to determine the

amount of copper which represents the gold in a compound, is founded on the fact, that this reagent is still very sensitive when sulphuret of sodium has no longer any perceptible action. The conditions requisite for the success of the operation are: 1st, to take care that the copper employed is perfectly *free* from oxide; 2d, to be certain that, after contact with the copper, no gold remains in solution; 3d, to saturate the mixture exactly with pure sulphuric acid after the reaction; 4th, to mix as quickly as possible, at a gentle heat, the copper and the bicarbonate with the solutions of the terchloride of gold; 5th, to add to the test liquid, which has been made shortly before use with precaution, and only by drops, when but a slight chestnut or dark red precipitate is produced.

*M. Henry* quotes a number of experiments, the results of which prove the exactness of the process, as well as the ease and quickness with which it may be performed.

*Separation of Gold from Platinum.*—The alloy is boiled in aqua regia, and the gold reduced by oxalic acid; from the filtered solution the platinum may be thrown down in the metallic state by formic acid; or the platinum may first be precipitated from the concentrated hydrochloric solution (diluted with 60 per cent. its bulk of alcohol) by chloride of potassium, and the gold in the filtrate may then be reduced by protosulphate of iron.

*Separation of Gold from Antimony, Tin, and Arsenic.*—This may be effected in the same manner as the separation of platinum from these metals, viz., by heating the mixed sulphurets in a stream of chlorine gas. The chlorides of tin, antimony, and arsenic distil over, while the gold remains behind. *Dr. Elsner* employs metallic zinc as the precipitant for gold, which he finds to remove the metal from a solution of its chloride more effectually than protosulphate of iron. For the quantitative determination of gold, however, in a mixture of platinum, gold, and tin, he prefers protosulphate of iron, on account of the greater simplicity of the operation. He first precipitates the platinum by a concentrated solution of chloride of ammonium, and afterwards the gold from the filtrate by a recently prepared solution of protosulphate of iron. He found that, when an excess of this reagent was employed, the filtrate from the precipitate still gave a beautiful dark red coloring with protochloride of tin, though no precipitate was observed.

*Analysis of Alloys of Gold.*—Several methods are employed. In the first place, an approximation to the relative proportions of the constituents is obtained by the touch-stone and the assay-needle: the former is a black and polished basalt; black flint and pottery will serve the same purpose. The assay-needles are small fillets of gold, alloyed with different and known quantities of silver or copper: the sets may consist of pure gold; pure gold,  $23\frac{1}{2}$  carats, with half a carat of silver;\* 23 carats of gold, with one carat of silver;  $22\frac{1}{2}$  carats of gold, with  $1\frac{1}{2}$  carat of silver, and so on till the silver amounts to four carats, after which the additions may proceed by whole carats. Other needles may be made in the same manner, with copper instead of silver, and other sets may have the addition, consisting either of equal parts of silver and copper, or such proportions as the occasions of business require. When a specimen of gold is about to be examined, it is rubbed on the touch-stone, and the color which it leaves is compared with that communicated to the stone by the assay-needles taken successively; that which leaves a mark most nearly resembling that produced by the specimen is in composition most nearly allied to it, and, as the composition of the needle is known, so the operator is enabled to judge of the quantity of silver necessary to be added for the *quartation* proof. The alloy is next cut into small thin plates, and fused in the cupel (see *Silver*), with  $3\frac{1}{2}$  times as much pure silver as it contains gold, and with three or four times its weight of lead. After the operation, the gold and the silver remain, the oxide of copper being absorbed with the oxide of lead by the cupel. This process is termed *quartation*, because the gold forms one-fourth part of the cupelled alloy, a proportion which admits of the complete subsequent extraction of the silver by the action of nitric acid. The alloy of gold and silver is next reduced to thin plates, weighed, and gently heated with nitric acid, diluted, and quite free from nitrous and hydrochloric acids; the silver dissolves, the gold remaining untouched. The acid being saturated, a stronger acid is

\* In estimating or expressing the fineness of gold, the whole mass spoken of is supposed to weigh twenty-four carats of twelve grains each, either real or merely proportional like the assayer's weights; and the pure gold is called fine. Thus, if gold is said to be twenty-three carats fine, it is to be understood that, in a heap weighing twenty-four carats, the quantity of pure gold amounts to twenty-three carats.—*Dr. Ure's Chemical Dictionary.*

added, and the solution is gradually brought to boil, by which the perfect separation of the silver is accomplished, the gold retaining still the form of the original plate. It is, therefore, easily weighed; previous to which, however, it must be washed with distilled water, as long as any traces of silver appear, by the test of common salt, and then heated to redness. The loss which the mass experiences by the process of cupellation indicates the quantity of copper contained in the alloy, and the proportion of silver is afterwards found by the action of the nitric acid. It must particularly be borne in mind, that if the nitric acid be not free from nitrous acid, and especially from hydrochloric acid, a portion of the gold, sufficient to affect seriously the result of the assay, may be dissolved.

*Purification of Gold by Cementation.*—The alloy is reduced to a thin plate, and surrounded in a crucible with a pulverulent mixture of four parts of brick-dust, one of calcined vitriol, and one of common salt. It is then exposed for 16 or 18 hours to a strong red heat. The vapors of hydrochloric and sulphuric acids which are formed attack the metals mixed with the gold, and the mass is prevented from fusing by the brick-dust. If the first cementation has not been found sufficient to purify the gold, the operation is repeated, but, in the place of common salt, nitre is used. The same method is employed to refine the surface of gold articles after they are polished. The cementation here produces the same effect as tartar and salt, in which silver goods are boiled to give them a white color.

*Purification by Fusion with Sulphuret of Antimony.*—Some borax is fused in a crucible, so that the walls become lined with the vitrified flux; a mixture of two parts of sulphuret of antimony and one of the gold to be assayed is then introduced. The sulphur combines with the foreign metals, and the antimony unites with the gold; the alloy being removed, the scoriæ are a second time fused, with the addition of two parts more of sulphuret of antimony, and, when the whole of the gold is extracted, the various alloys are mixed together and heated in an open vessel, with two parts of sulphur. The sulphuret of antimony volatilizes, leaving the gold pure; to increase the action, a current of air from a pair of bellows may be directed on the surface of the melted mass, or, what is perhaps still better, the mixture of the two metals



may be fused in a large crucible, with three times its weight of nitre, by which the antimony becomes oxidized and dispersed, the gold remaining untouched. Another method is to fuse the gold alloy with a mixture of *oxide of lead* and *sulphur*, and to add to the fused mass charcoal in the state of fine powder; the gold is thus obtained alloyed with the lead only, from which it may be separated by cupellation.

### *Selenium.*

When existing in solution in the form of *selenious acid*, it is reduced by sulphite of ammonia, which separates selenium in the form of a cinnabar red powder, which, if boiled, becomes black; it is collected on a filter, and dried at a very gentle heat: nitric acid, if present in the solution, must be decomposed and expelled by hydrochloric acid, previous to the addition of the sulphite of ammonia. When, however, selenium is contained in a solution, as *selenic acid*, it must first be reduced to selenious acid by boiling with hydrochloric acid, if it be intended to precipitate it by sulphite of ammonia. As, however, it is difficult entirely to convert *selenic* into *selenious acid* by hydrochloric acid, *Rose* recommends that the estimation of selenic acid be effected by precipitating it in the form of seleniate of baryta, by nitrate of baryta, which, when washed, dried, and ignited, has the following composition:

|                                       |     |        |     |       |
|---------------------------------------|-----|--------|-----|-------|
| One equivalent of $\text{SeO}_3$      | ... | 63.57  | ... | 45.34 |
| One do. of $\text{BaO}$               | ... | 76.64  | ... | 54.66 |
| <hr/>                                 |     |        |     |       |
| One do. of $\text{BaO}, \text{SeO}_3$ |     | 140.21 |     | 100   |

As selenium is precipitated from its solution when in the form of selenious acid by sulphuretted hydrogen, it may thus be separated from all those substances which are not precipitated by that reagent. *Selenic acid* does not, however, possess the property of being precipitated by sulphuretted hydrogen; when selenium, therefore, exists in this state, and has to be separated from other substances, it must either be precipitated as seleniate of baryta, or reduced to selenious acid. From the metals of the Fifth Group selenious acid may be separated by hydrosulphuret of ammonia, in which sulphuret of selenium is soluble; and from the other metals of

the Sixth Group it may be separated by converting it into selenic acid, which remains, as before observed, unaltered by sulphuretted hydrogen gas.

*Analysis of Seleniate of Lead.*—It is reduced to a fine state of division, and diffused in water, through which a current of sulphuretted hydrogen is passed; the liquor filtered from the sulphuret of lead is boiled, to expel the excess of sulphuretted hydrogen, and the selenic acid precipitated as seleniate of baryta; in this way selenic acid may be separated from other metals which are capable of precipitation by sulphuretted hydrogen.

### *Tellurium.*

Like *selenium*, this metal is best precipitated from its solution when in the state of oxide, by sulphite of ammonia; the precipitation must be effected at a boiling temperature, and the solutions should contain free hydrochloric, but not nitric acid. From these oxides which are not precipitated by sulphuretted hydrogen, it may be separated by that reagent. The sulphuret of tellurium is decomposed by digestion with aqua regia, and subsequently reduced by sulphite of ammonia. From the metals of the Fifth Group, tellurium is separated by hydrosulphuret of ammonia. From gold and platinum it may be separated by ignition in a glass tube through which a stream of chlorine is passing. Chloride of tellurium is volatilized, and may be received into a vessel containing very dilute hydrochloric acid, in which it dissolves, and out of which it may be precipitated by sulphite of ammonia. From arsenic, tellurium may, according to *Berzelius*, be separated by distillation, reguline tellurium remaining behind.

### *Tungsten.*

The method proposed by *Berzelius* for quantitatively estimating tungstic acid, was to precipitate it from its neutral or alkaline solution in the form of sulphuret of tungsten by hydrosulphuret of ammonia, and then to add excess of the reagent, by which the sulphuret is dissolved; from this solution it is reprecipitated by nitric acid, and, having been washed and dried, it is roasted by a gentle heat, whereby it becomes converted into tungstic acid, in which state it is weighed. The composition of tungstic acid is

|                               |     |        |     |       |
|-------------------------------|-----|--------|-----|-------|
| One equivalent of W (Wolfram) | ... | 94.64  | ... | 79.77 |
| Three do. of O                | ... | 24.00  | ... | 20.23 |
| <hr/>                         |     |        |     |       |
| One do. of $\text{WO}_3$      | ... | 118.64 | ... | 100   |

A method of determining the quantity of tungstic acid in neutral salts, by nitrate of mercury, has also been described by *Berzelius*. The following is the plan proposed by *M. Marguerite*.<sup>\*</sup> He recommends it as being very simple and perfectly exact.

The salt to be analyzed is placed in a small platinum crucible, and several times its weight of pure concentrated sulphuric acid added. At first a gentle heat is employed, and then the temperature is gradually raised to a red heat. After calcination, the residue is composed of an acid sulphate and of free tungstic acid. It is thrown on a filter, washed with water, charged with sal-ammoniac, which prevents the tungstic acid from combining with water, and from passing through the filter, which frequently happens, even when it has been ignited. When the last washings no longer precipitate chloride of barium, the residue is ignited to drive away the sal-ammoniac, and a few drops of nitric acid added to obviate any error that might arise from a slight reduction which the tungstic acid may have undergone, and to insure the perfect combustion of the last traces of charcoal of the filter. In this way the tungstic acid may be directly determined.

*Analysis of Insoluble Tungstates.*—They are fused with carbonate of potassa† in a platinum crucible, by which operation tungstate of potassa is formed, which salt, being soluble in water, may be treated with hydrosulphuret of ammonia as above directed.

*Analysis of Wolfram.*—This mineral, which is a double tungstate of iron and manganese, is best analyzed, according to *Wöhler*, by mixing it in a finely divided state with two parts of dry chloride of calcium and fusing in a platinum crucible. The melted mass is treated with water, which dissolves out the chlorides of manganese and iron, and leaves the tungsten in the form of insoluble tungstate of lime.

<sup>\*</sup> Comptes Rendus, Feb. 3, 1845; and Chem. Gaz., vol. iii. p. 183.

† Bisulphate of potassa is an excellent substitute.

*Molybdenum.*

This metal is weighed in the form of the gray bisulphuret. It is precipitated from its solution in hydrosulphuret of ammonia by hydrochloric or acetic acid. The compound thus precipitated is the tersulphuret, which may, indeed, be converted by ignition into molybdic acid ( $\text{MO}_3$ ); but it would not be safe to estimate the metal in this form, because, at the temperature necessary to decompose the tersulphuret, a portion of molybdic acid would be volatilized.\* *Rose*, therefore,

\* As molybdic acid is volatilized at a high temperature, especially with access of air, in considerable quantity, its estimation is rather a difficult matter. Molybdic acid may, it is true, be precipitated from dilute acid solutions by a current of sulphuretted hydrogen in the state of brown sulphuret. However, this precipitation is accompanied with great inconvenience, as it is excessively difficult to convert the molybdic acid wholly into the state of sulphuret.

The author found the best method of determining molybdic acid quantitatively was to convert it into molybdic oxide, which is most readily effected by heating it in an atmosphere of hydrogen. On heating it over a spirit-lamp at not too high a temperature, there need be no fear of small quantities of metallic molybdenum being formed with the oxide. The heating may be effected in a platinum crucible with a perforated lid, through which the hydrogen is conveyed into the crucible. Heat is applied until the weight of the oxide of molybdenum remains constant.

If a liquid contain molybdic acid dissolved in ammonia, it is carefully evaporated to dryness, and the dry mass heated in the same manner as pure molybdic acid in an atmosphere of hydrogen, to convert it into oxide. This operation may also be carried out in a platinum crucible.

When the molybdic acid is contained in an alkaline solution, it may be entirely precipitated by a solution of protonitrate of mercury after the liquid has been neutralized with nitric acid. If any alkaline carbonate were present, the solution, after saturation with nitric acid, is kept from twelve to twenty-four hours in a moderately warm place, in order to expel the whole of the carbonic acid. The precipitate of the protomolybdate of mercury is of a yellow color and very bulky, but after standing for some hours sinks very much together. It is collected on a weighed filter, and washed with a very dilute solution of the protonitrate of mercury, as it is somewhat soluble in pure water. After being perfectly dried at  $212^\circ$  and accurately weighed, the precipitate is removed from the filter, and treated in a platinum or porcelain crucible with hydrogen, in the same manner as molybdic acid or the molybdate of ammonia; oxide of molybdenum is obtained; that which remains adherent to the filter is weighed with it, and the quantity of molybdic oxide contained in it calculated.

By this method it is possible to determine accurately at the same time the amount of fixed alkali which was combined with it. Sulphuric acid is added to the liquid filtered from the protomolybdate of mercury, and the whole concentrated by evaporation. Protosulphate of mercury separates, which is converted, on the evaporation of the liquid, into yellow basic sulphate of mercury. The dry mass is exhausted with hot water, the yellow residue separated by filtration, and the filtered liquid evaporated to dryness. The dry mass may be



directs the precipitate occasioned by adding hydrochloric or acetic acid to the solution of tersulphuret of molybdenum in hydrosulphuret of ammonia to be gently ignited in a small weighed retort, by which it loses one of its atoms of sulphur, leaving the bisulphuret, which has the following composition :

|                             |     |       |     |       |
|-----------------------------|-----|-------|-----|-------|
| One equivalent of MO        | ... | 47.88 | ... | 59.94 |
| Two do. of S                | ... | 32    | ... | 40.06 |
| <hr/>                       |     |       |     |       |
| One do. of MOS <sub>2</sub> | ... | 79.88 | ... | 100   |

From all the metallic oxides, the sulphurets corresponding to which are not soluble in hydrosulphuret of ammonia, *molybdenum*, like *tungsten*, may be separated by that reagent. For this purpose, the compound is dissolved in excess of hydrochloric acid; should *lead* or *silver* be present, the chlorides thus formed are removed by filtration, excess of hydrosulphuret of ammonia containing excess of sulphur is added, and the mixture digested for an hour. It is then filtered, the filtrate containing the tersulphuret of molybdenum is supersaturated and digested with acetic or hydrochloric acid, and the precipitate treated as above directed.

## ACIDS.

### 1. *Acids of Sulphur.*

*Quantitative estimation of Sulphuric Acid.*—This is always effected by converting it into *sulphate of baryta*. If the substance to be examined be dissolved in water, it must be acidified with pure hydrochloric acid heated nearly to ebullition,

converted in the usual manner, by treatment with carbonate of ammonia, into neutral alkaline sulphate.

The combinations of molybdic acid with the fixed alkalies may also be decomposed by chloride of ammonium. They are mixed in the dry state with an excess of an ammoniacal salt, and calcined with it. When the acid exists in the state of an acid salt, the mass does not fuse, but the acid is converted into molybdic oxide. It is mixed with fresh quantities of chloride of ammonium, and again calcined until no further increase in weight results. The ignited mass is treated with water, which leaves the molybdic oxide undissolved. It is collected on a weighed filter, and dried at 212°. The liquid separated from the molybdic oxide contains the alkali in the state of chloride.

This method does not afford such accurate results as the determination of molybdic acid by means of the protonitrate of mercury, a small portion of the acid being reduced by the chloride of ammonium to the state of metal. It may, however, be employed for those molybdates which are very sparingly soluble in water.—*ROSE. Proceedings of the Berlin Academy, July 1848.*

and chloride of barium or nitrate of baryta gradually added till no further precipitation occurs. The sulphate of baryta formed usually subsides quickly and completely, but it must be allowed to settle thoroughly before it is filtered; it is washed on the filter repeatedly with boiling distilled water, dried and ignited, the weight of the ash left by the filter, which has been determined by a previous experiment, being deducted: for the composition of sulphate of baryta, see page 253. If the substance analyzed be dissolved in nitric acid, it must be well diluted with distilled water before it is precipitated by a baryta salt, otherwise nitrate of baryta may be thrown down, which would afterwards require long-continued washing to remove; in all cases, the operator must be careful to wash the precipitate on the filter till the washings no longer give any cloudiness when dropped into dilute sulphuric acid. Should the substance under examination be insoluble in water and in hydrochloric acid (sulphates of baryta, strontia, lime, or lead, for example), it must be fused in a platinum crucible (porcelain in the case of lead) with about four times its weight of a mixture of carbonate of soda and carbonate of potassa, the whole having been previously well mixed by trituration in a mortar; the mass should be kept in a state of fusion for some time, to insure complete decomposition, and, when cool, transferred to a dish, and digested with distilled water repeatedly, till all the soluble matter is removed; this consists of the whole of the sulphuric acid of the compound analyzed, in combination with soda and potassa, together with the excess of the alkaline carbonates; the base or bases with which the acid had been previously in combination remain in the form of insoluble carbonates, and are to be determined in the manner directed in the preceding pages. The sulphuric acid is precipitated from the solution by nitrate of baryta or chloride of barium, having previously supersaturated the liquid with hydrochloric acid, or with nitric acid if lead be present; the precipitant in that case being nitrate of baryta.

*Estimation of Sulphurous Acid.*—The precipitate which this acid forms with barytic salts is soluble in hydrochloric acid, by which it is at once distinguished from sulphate of baryta; when a soluble sulphite, or a salt of any of the other lower acids of sulphur is presented for analysis, it is converted into sulphate by careful and protracted digestion with nitric acid, or with aqua regia: dry *sulphites*, *hyposulphites*, and

*hyposulphates*, may also be converted into sulphates by fuming nitric acid. When a mixture of a sulphate and a sulphite has to be examined, two different portions of the compound are analyzed; in one the quantity of *sulphuric acid* is determined in the ordinary manner, namely, by precipitating it from its hydrochloric solution by chloride of barium or nitrate of baryta; the other portion is digested with nitric acid or with aqua regia, and, the sulphite being thus converted into sulphate, the solution is also precipitated by a barytic salt. The difference in the two quantities of sulphuric acid found furnishes the data for calculating the proportion of *sulphite* in the compound. The same method may be adopted for analyzing mixtures of sulphates with salts of any of the other lower acids of sulphur.

*MM. Fordos and Gelis' method of analyzing a mixture of the different compounds of Sulphur with Oxygen.\**—The process is founded on the different action which chlorine and iodine exert on the acids of sulphur.† Thus, neither of these bodies exerts any action on sulphuric or hyposulphuric acids, while they rapidly convert sulphurous into sulphuric acid. On passing a current of chlorine into a dilute solution of a hyposulphite, sulphur is precipitated, and sulphurous acid disengaged; and, on passing the gas into a solution of the sulphypo-sulphuric acid of *Langlois*, or the bisulphypo-sulphuric acid of *Fordos and Gelis*, the whole of the sulphur becomes converted into sulphuric acid; again, iodine, though without any action on the sulphohyposulphates, exerts an action of a peculiar nature on solutions of the hyposulphites. *MM. Fordos and Gelis* apply these facts to the analysis of mixtures of salts of the different acids of sulphur. Thus, suppose the

\* Journ. de Pharm., June 1843; and Chem. Gaz., July 15th, 1843.

† Six of these compounds have been well made out, and the existence of several others is probable; the six well defined acids have the following composition:— $\text{SO}_3$ ,  $\text{SO}_2$ ,  $\text{S}_2\text{O}_2$ ,  $\text{S}_2\text{O}_5$ ,  $\text{S}_3\text{O}_5$ ,  $\text{S}_4\text{O}_5$ , and they have been thus classified by Berzelius:—

|              |                                                   |                                                          |
|--------------|---------------------------------------------------|----------------------------------------------------------|
| Monothionic  | $\text{SO}_3$ , $\text{SO}_2$ ,                   | Sulphuric and sulphurous acids.                          |
| Dithionic    | $\text{S}_2\text{O}_3$ , $\text{S}_2\text{O}_5$ , | Hyposulphurous and hyposulphuric acids.                  |
| Trithionic   | $\text{S}_3\text{O}_5$ ,                          | Sulphypo-sulphuric acid of <i>Langlois</i> .             |
| Tetrathionic | $\text{S}_4\text{O}_5$ ,                          | Bisulpho-hyposulphuric acid of <i>Fordos and Gelis</i> . |

Besides these, a new series of acids of sulphur has been announced by Plessy (Comptes Rendus, Aug. 1845), to which he assigns the following composition:— $\text{S}_5\text{O}_6$ ,  $\text{S}_5\text{O}_7$ ,  $\text{S}_6\text{O}_7$ ,  $\text{S}_8\text{O}_{10}$ ; and M. Wackenroder, and MM. Fordos and Gelis, have each described an acid having the composition  $\text{S}_5\text{O}_5$ .

solution to contain a sulphate, a sulphite, a hyposulphite, a hyposulphate, and a bisulpho-hyposulphate. The liquid is divided into two equal portions.

1. The sulphuric acid is determined by chloride of barium, the precipitated sulphate of baryta being washed first for some time with boiling distilled water, and then with water rendered slightly acid with hydrochloric acid; the solution must not be acid previous to adding the chloride of barium, or a partial oxidation of the sulphurous acid may take place, thus occasioning too large an amount of sulphate of baryta.

2. Another portion is mixed with a considerable quantity of carbonate of magnesia, and saturated with iodine, the quantity required being carefully noted; the amount of sulphuric acid contained in the liquid is again determined by chloride of barium; the quantity of sulphate of baryta obtained will be greater than in the first experiment, and the increase will indicate the quantity of sulphurous acid and the weight of iodine which it was necessary to employ in order to convert it into sulphuric acid; when this point is attained, it is easy, without having recourse to any other experiment, and by a simple subtraction, to procure all the elements necessary for the determination of the amount of hyposulphurous acid. The quantity of iodine which had been required to convert the sulphurous acid into sulphuric is subtracted from the total amount employed; the difference will have been absorbed by the hyposulphurous acid: *two* equivalents of this acid absorb *one* of iodine. In treating the liquid with iodine, an alcoholic solution of known strength is employed, or small fragments of iodine are added by degrees to the liquid from a flask, the weight of which has been previously determined. The solution is very rapid, and the point of saturation is easily ascertained. As soon as the liquor acquires a yellow colour, no more should be added. The change of colour is very striking, and it is quite useless to add starch or any other foreign body to the solution. The necessity of adding carbonate of magnesia to the liquid previous to the addition of the iodine arises from the fact, that water is decomposed by the *sulphite*, which is also in solution; it becomes sulphate, taking oxygen from the water; at the same time the iodine takes the hydrogen, and hydriodic acid is formed; but this acid would, if at the moment of its production it did not find



a base to saturate it, act on the undecomposed portion of the sulphite or on the hyposulphite, which the liquid likewise contains, and there would be a loss of sulphurous acid and a deposit of sulphur.

3. This portion of the liquid is employed to determine the amount of bisulpho-hyposulphuric acid. It is saturated with iodine, without, however, keeping any account of the quantity employed. The iodine forms as before a sulphate at the expense of the sulphite, and a bisulpho-hyposulphate at the expense of the hyposulphite. This quantity will go to increase that already contained in the solution. This being done, about 100 parts of water are added to the liquid under examination, through which a current of chlorine is then passed. This gas will bring to the state of sulphate the whole of the sulphur of the bisulpho-hyposulphate, without attacking that of the ordinary hyposulphite. When the saturation is complete, chloride of barium is added to the solution; the weight of the sulphate of baryta obtained will represent the sulphur of the sulphate, of the sulphite, of the hyposulphite, and of the bisulpho-hyposulphite. As the operations made with the first and second portions of the liquid will have indicated the quantity of sulphur contained in the three first, the difference between the two weights will serve to determine the amount of sulphur contained in the latter, and consequently its entire amount.

4. There will now only remain the hyposulphuric acid. To determine this it will suffice to know the total amount of sulphur in the mixture analyzed; for then, after having assigned to the four other acids the amount pertaining to them, the difference must of course belong to the hyposulphuric acid. The solution is evaporated to dryness, a small quantity of caustic soda being added, to retain the sulphurous gases; the solid residue is treated in the usual manner with fuming nitric acid, and the amount of sulphur determined by chloride of barium.

*Quantitative estimation of Hydrosulphuric Acid (Sulphuretted Hydrogen).*—The best precipitant is *arsenious acid*; if the acid be in solution in water, as, for example, in certain mineral springs, the water is mixed with a clear solution of arsenious acid in hydrochloric acid, and the precipitate which forms allowed to subside; it is then collected on a filter, washed with cold water, dried at  $212^{\circ}$ , and weighed: for the

composition of sulphuret of arsenic see page 345. If the hydrosulphuric acid is evolved in the gaseous form, the substance from which it is expelled is heated in a flask, and the gas received into a vessel containing a solution of arsenious acid in caustic potassa: the last traces of the gas are removed from the flask by pouring into it solution of bicarbonate of potassa. The operation being completed, the alkaline ley is supersaturated with hydrochloric acid, and the sulphuret of arsenic thereby precipitated collected, dried, and weighed.

*Analysis of Compounds of Sulphur with Bases.*—Sulphur is readily detected in sulphurets and in sulphates by fusing the sample with soda upon charcoal before the blowpipe; a hepar is thus obtained, which, on being moistened, is easily recognized by means of silver; as, however, it may still be uncertain whether the sulphur existed in the compound in the form of a sulphate or of a sulphuret, *Von Kobell* has suggested the following simple method of solving the question: The finely pulverized sample is boiled with caustic potassa in a porcelain crucible, and heated till the potash begins to melt, or the sample is fused with hydrate of potassa in a platinum spoon before the blowpipe. The mass is then dissolved in a little water, and filtered; a bright strip of silver is placed in the solution; and, if the sample contains a sulphuret, the hepatic reaction is frequently immediately perceptible, but sometimes only after a few hours. With very small quantities the platinum spoon, with the flux, may be placed in a small glass with some water, and the silver introduced. The silver is easily restored to brightness by rubbing it with leather and a little caustic lime: sulphates after such treatment have no reaction on the silver.

*Separation of Sulphur from the Alkalies and Alkaline Earths.*—If the compound be soluble in water, its solution may be mixed with a solution of *chloride of copper* upon which sulphuret of the latter metal is precipitated. The precipitate is collected on a filter as quickly as possible, to prevent the oxidation of a portion of the sulphuret, and then treated with red fuming nitric acid, by which the sulphur is brought into the state of sulphuric acid, and may then be precipitated with the proper precautions by a soluble salt of baryta. The weight of the sulphate of baryta obtained, furnishes data for calculating the amount of sulphur present in the substance analyzed. If the sulphuret to be examined be not readily soluble

in water, it may be decomposed in a flask by dilute sulphuric or hydrochloric acid, the hydrosulphuric acid evolved being conducted through a series of Wolfe's bottles, about two-thirds filled with a neutral solution of chloride of copper; three bottles may be employed, the latter containing, in addition to the metallic chloride, a little caustic ammonia, to insure the complete absorption of the hydrosulphuric acid gas. The gas remaining in the flask at the end of the operation must be driven forward into the bottles by a current of carbonic acid gas. This is effected by pouring into the flask through its funnel a solution of carbonate of ammonia, not, however, sufficient to neutralize the acid, because it may happen that a portion of sulphur has been deposited in the generating flask during the decomposition, which it would of course be necessary to collect on a tared filter, wash, dry, and weigh; but if the liquor were rendered alkaline, supposing the sulphuret of an alkaline earth to have been under an examination, an insoluble carbonate would be precipitated, which would render the collection of the sulphur difficult.

Metallic sulphurets\* may be analyzed in the dry way by mixing them with thrice their weight of dry carbonate of soda and an equal quantity of nitre, to which must be added a considerable quantity of pure and dry common salt; if the sulphuret loses sulphur by heat, the mixture is kept for some time in fusion in a porcelain crucible; by this operation the sulphur is separated from the metal with which it was originally combined, and is transferred in the form of sulphuric acid to the alkali; a soluble sulphate is thus produced, which may be precipitated by nitrate of baryta, and the quantity of sulphur calculated from the weight of the sulphate of baryta formed.

*Dr. Geo. Kemp†* applies this method to the analysis of copper ores in the following manner:—A portion of the ore is carefully mixed with about three times its weight of pure *chlorate of potassa*, previously fused, and the mixture is introduced into a Bohemian glass tube about six inches in length; another portion of chlorate is used to remove the last portion of the mixture from the mortar, finishing the contents of the

\* According to Millar, a mixture of nitric acid and of chlorate of potassa with the aid of heat, rapidly converts the sulphur of metallic sulphurets into sulphuric acid.

† Chem. Gaz., vol. ii. p. 215.

tube by adding another small quantity of perfectly pure chlorate in powder. The tube is thus nearly one-third filled. Having provided a passage for the gas given off in the usual way,\* the tube is exposed to the heat of a Berzelius' spirit lamp, commencing at the upper part of the mixture and proceeding downwards: in the course of a few seconds the oxidation is complete, and the contents of the tube, when cold, carefully washed out with nitro-hydrochloric acid into a small digesting flask, and placed on the sand bath; after a few minutes' digestion a clear solution is obtained, containing all the copper, iron, and sulphate of potassa, while the silica remains as a precipitate. Having diluted the solution, the metals and the sulphur are precipitated and estimated in the usual way.

*Determination of Sulphur in Iron.*—Dr. Bromeis† passes the gas obtained by acting on the iron, with dilute sulphuric acid, through an ammonical solution of silver, contained in an apparatus similar to that employed by Will and Varrentrap for nitrogen analyses; the whole of the hydrosulphuric acid is absorbed, and is determined as sulphuret of silver.

*Determination of Sulphur in Sulphuret of Lead.*—The sulphur is converted into sulphuric acid by digesting the ore in fuming nitric acid; the sulphate of lead produced is dissolved in hot caustic potassa, the alkaline solution is filtered from the insoluble matters, and the lead again precipitated as sulphuret by sulphuretted hydrogen; it is received on a filter, washed, dried, and digested in a weighed platinum capsule with fuming red nitric acid; it is thus again converted into sulphate, in the form of which salt it is weighed.

*Sulphuret of silver and sulphuret of bismuth* must be decomposed by pure nitric acid; the substances should be reduced to as fine a state of division as possible, and projected into a flask capable of being closed with a stopper, and containing the very strongest fuming nitric acid; the bottle must be closed the moment the sulphuret is introduced, and occasionally agitated; when the action slackens, a gentle heat may be applied. In the case of *sulphuret of silver*, should any of the sulphur have escaped oxidation, it may be dissolved by adding in small portions, chlorate of potassa; but, in the case of *sulphuret of bismuth*, the unoxidized sulphur must be collected

\* This operation will be minutely described further on.


† Ann. der Chem. und Pharm., Sept. 1842; and Chem. Gaz., vol. i. p. 160.



on a tared filter, washed with acetic acid, dried, and weighed; from the clear filtrate the bismuth is precipitated by sulphuretted hydrogen, and from the filtrate from the precipitated sulphuret of bismuth, the sulphuric acid is precipitated by a salt of baryta, having first acidified it with hydrochloric acid.

*Separation of Sulphur from Metals by Chlorine Gas.*—This method is applicable to the analysis of compound sulphurets of those metals, the chlorides of which are not volatile at a low red heat. The substance is introduced into a bulbed tube connected with an apparatus by means of which a stream of dry chlorine gas may be passed through it. The disposition of the apparatus is seen in Fig. 12; *a* is the flask containing the materials for generating chlorine gas, which is dried by passing first through the Wolfe's bottle *b*, containing concentrated sulphuric acid, and then through the siphon-shaped tube *c*, containing chloride of calcium; the sulphuret to be analyzed is weighed, and carefully introduced into the bulbed tube *d*, bent at right angles, and dipping into water contained in the bottle *e*. If the process cannot be conducted under a flue, it may be advisable to close the mouth of the bottle *e*

Fig. 12.



with a cork, through which a tube is inserted which may convey the excess of chlorine into another bottle, containing milk of lime or potash, thus preventing annoyance to the operator by the escape of the irritating gas into the apartment. The whole apparatus is first filled with chlorine, which is made evident by the yellow green color of the space above the water

in the bottle *c*, a very gentle heat is then applied to the bulb, the sulphuret is decomposed, its metallic base or bases combining with the chlorine, while the sulphur is driven forward into the bottle *e* in the form of *chloride of sulphur*, which is immediately decomposed by the water into hyposulphurous acid, hydrochloric acid, and sulphur; the former, by the action of the chlorine, passes into sulphurous acid, and finally into sulphuric acid, so that the last result of decomposition is sulphuric acid, hydrochloric acid, and a greater or less quantity of free sulphur. When the action is over, the bulb is heated towards the bend, so as to force the whole of the chloride of sulphur into the bottle *e*; the tube is then cut off under the bend, and the separated end thrown into the bottle. The excess of chlorine is expelled from *e* by the application of a gentle heat, it is allowed to remain at rest for some hours till the sulphur has completely solidified, it is then collected on a tared filter, washed, dried, and weighed, and the sulphuric acid is lastly precipitated by nitrate of baryta or chloride of barium.

*Rose* applies the above method to the analysis of mixed sulphurets of those metals the chlorides of which are either partly or wholly volatile at the temperature employed. For example, in the analysis of the mixed sulphurets of *antimony*, *iron*, and *zinc*; in such a case, the water in the bottle *e* must be mixed with tartaric acid and a small quantity of hydrochloric acid; and the chloride of antimony which distils over into the bottle *e* is precipitated by sulphuretted hydrogen, after the free sulphur has been removed by filtration, and the sulphuric acid by a soluble salt of baryta. If the heat employed has not been too great, the whole of the chloride of zinc, and the greater part of the perchloride of iron, will be retained in the bulb; a certain portion of the latter, however, will have been volatilized, and will have found its way into the liquid in the bottle *e*, from which, together with any chloride of zinc which may also have distilled over, it must be precipitated after the removal of the antimony, by hydrosulphuret of ammonia.

The methods of separating sulphur from organic substances will be described further on.

## 2. *Acids of Phosphorus.*

1. *Phosphoric Acid*.—In a solution which contains nothing but phosphoric acid, the amount of that acid may be estimated

by evaporating to dryness with the addition of a known weight of recently ignited protoxide of lead; the residue, after being heated to redness, is weighed, the increase of weight indicates the amount of phosphoric acid. The presence of nitric acid does not interfere with the accuracy of this method.

The quantitative determination of phosphoric acid, when in combination with bases and in the presence of other acids, is frequently attended with considerable difficulties, especially when it exists in small quantities only. The following are the principal methods at present in use.

*Estimation as Pyrophosphate of Magnesia.*—Chloride of ammonium, ammonia, and sulphate of magnesia are added to the solution, which is then well agitated, or stirred with a feather; a glass rod should not be used for the purpose, as the crystalline double salt which is precipitated adheres so firmly to those parts of the sides of the beaker which have been touched by the glass rod that it cannot afterwards be readily removed. The mixture is allowed to remain at rest for several hours; it is then filtered, and the precipitate washed with water containing a little ammonia, in which it is almost insoluble; the washing must not be continued too long, but stopped immediately it is found that a few drops of the filtrate, when evaporated on platinum foil, leave no residue; it is then ignited, first gently and afterwards strongly: for the composition of the ignited salt, see p. 258. This method does not apply to the analysis of phosphates after they have been ignited, without a previous preparation, as has been shown by *Weber*;<sup>\*</sup> the reason is, that they are converted by heat from tribasic into bibasic salts, and bibasic or pyrophosphoric acid forms with magnesia a salt which is much more soluble in water than tribasic or common phosphoric acid. By the action of acids it is true that pyrophosphoric acid is converted into the tribasic acid, but *Weber* found that the transformation was not perfect, even when the compound was treated for a considerable time with concentrated sulphuric acid. In order to ascertain which of these two phosphoric acids we have under examination, the following test may be applied. The compound is dissolved in nitric acid and reprecipitated by ammonia; the precipitate, after long standing, is collected on a filter; to the filtrate, nitrate of silver is added, and the am-

\* *Chem. Gaz.*, vol. v. p. 450.

moniacal liquid is then carefully neutralized with nitric acid; the appearance of a white turbidness, or the formation of white flakes, indicates the presence of pyrophosphoric acid. When the phosphoric acid in a phosphate is to be separated and determined by magnesia, and is not contained in the solution as the tribasic compound, the phosphate must be fused with excess of carbonate of soda. This can be done in all cases when the phosphoric acid is combined with the alkalis or those metals which are completely decomposed by fusion with carbonate of soda; but it does not succeed in converting the phosphoric acid into the tribasic compound in its combinations with the alkaline earths, as these are only imperfectly decomposed. The only way to reprecipitate entirely the pyrophosphate of magnesia from its solutions by ammonia is to heat it for some time with concentrated sulphuric acid, when, on solution, it can be almost entirely precipitated by ammonia.

The precipitates which the tribasic and bibasic phosphoric acids produce with magnesia differ essentially from each other in their external properties. The first is granular, crystalline, and soon subsides, especially when warmed; the latter is voluminous and flocculent, and remains long suspended in the liquid. Small quantities of pyrophosphoric acid cannot be separated or even detected by magnesia.

*Estimation by a Standard Solution of Permanganate of Potash.—Raewsky's Method.*—This process consists in bringing the acid to the state of pure perphosphate of iron, which is collected, and the amount of iron in it determined. The author has ascertained, by numerous experiments, that the perphosphate of iron in the state in which it is obtained in this experiment has a uniform composition, viz:  $\text{Fe}_2\text{O}_3\text{PO}_5$ , the relation of the oxygen of the base to the oxygen of the acid being as 3 to 5. The process is conducted as follows. The phosphoric acid compound is dissolved in acetic acid: should it be in combination with bases which yield salts insoluble in acetic acid, it must be separated from them; to the solution is added an excess of a solution of peracetate of iron, or, as this salt is not permanent, it may be made by double decomposition at the very moment it is called into action, with which view 1500 grains of iron alum are dissolved in about a quart of water, and an equal quantity (or rather less) of acetate of soda in another quart of water, equal quantities of each are added to the solution. The phosphate of iron im-



mediately separates in the form of slightly yellowish light flakes, the precipitate is collected and carefully washed. The excess of iron passes off in the washing, and the pure phosphate is left on the filter. Hydrochloric acid is then dropped on the filter so as to dissolve the whole; the salt of iron is reduced by means of sulphite of soda, and the amount of iron determined by converting it into peroxide with a solution of mineral chameleon of known strength, according to the method of, and following the precautions indicated by *M. Marguerite*, see page 297. Having determined the quantity of iron by a simple calculation, and knowing the composition of the per-phosphate, the proportion of phosphoric acid is readily found. Thus, supposing phosphate of soda to be the subject of analysis, and that having operated on 0.466 gramme (7.2 grains), 15 divisions of the normal solution have been employed, the strength of which is 54.4 divisions for every 0.250 gramme (3.86 grains) of iron, the iron is then found by the proportion:—

$$\text{As } 54.4 : 0.250 :: 15 : X = 0.069 \text{ of iron.}$$

On the other hand, the composition of the phosphate of iron being known, we have the proportion:—

As  $56 (\text{Fe}_2) : 72 (\text{PO}_5) :: 0.069 (\text{Fe}) : X = 0.0887$  phosphoric acid. Now, in 1 of phosphate of soda there is 0.191 phosphoric acid; consequently we have the proportion:—

As  $0.191 (\text{PO}_5) : 1 (2\text{NaO}, \text{HO}, \text{PO}_5) :: 0.0887 : X$   
 $X = 0.464$  phosphate of soda, the quantity submitted to analysis was 0.466 gramme.

*M. Raewsky* found that the same process was applicable to the determination of pyrophosphoric acid, with this difference, that, instead of using the neutral acetate of iron, the solution must be precipitated by a solution of ammoniacal iron alum.

*Separation of Phosphoric Acid from Sulphuric Acid.*—This is very easily effected by means of chloride of barium, the solution being dilute and acidified with hydrochloric acid.

*Separation of Phosphoric Acid from Bases.*—This is frequently attended with very great difficulties; wherever it is admissible the quantity of the base is determined, the amount of phosphoric acid in combination therewith being calculated from the loss. When it is necessary to make a direct determination of the acid, it may be done in the following manner.

*Separation of Phosphoric Acid from the Alkalies.*—A very accurate method is to add to the solution of the alkaline phosphate a known quantity of solution of pure iron, and then to precipitate with ammonia; the quantity of phosphoric acid present is ascertained by the increase of weight in the precipitate above that which the known quantity of iron should yield. A certain weighed quantity of pure iron (harpsichord wire) is dissolved in nitric acid, and added to the solution under examination; ammonia in excess is then added, which should produce a voluminous red brown precipitate; if it has a white tinge, it is a proof that sufficient iron has not been added: this precipitate is collected on a filter well washed with hot water, dried, ignited, and weighed. It consists of peroxide of iron *plus* a certain quantity of basic perphosphate of iron; suppose, for example, that 10 grains of iron dissolved in nitric acid had been added, and that the ignited precipitate weighed 20.36 grains, we obtain the amount of phosphoric acid by simply subtracting 14.286, the amount of sesquioxide of iron, which 10 grains of metallic iron yield from 20.36, and we find that the phosphate under analysis contains 6.074 grains of phosphoric acid. The alkalies in the filtrate from the precipitate are determined as directed in page 236.

Tribasic alkaline phosphates are very conveniently analyzed by precipitating their aqueous solutions with neutral nitrate of silver. The composition of the ignited precipitate, which is yellow, is

|                                  |     |       |     |       |
|----------------------------------|-----|-------|-----|-------|
| Three equivalents of AgO         | ... | 348   | ... | 82.85 |
| One do. of PO <sub>5</sub>       | ... | 72    | ... | 17.15 |
|                                  |     | <hr/> |     |       |
| One do. of 3AgO, PO <sub>5</sub> |     | 420   |     | 100   |

Alkaline phosphates containing one equivalent of basic water give, after ignition, when dissolved in water, a white precipitate with neutral nitrate of silver, the composition of which after ignition is

|                                  |     |       |     |       |
|----------------------------------|-----|-------|-----|-------|
| Two equivalents of AgO           | ... | 232   | ... | 76.31 |
| One do. of PO <sub>5</sub>       | ... | 72    | ... | 23.69 |
|                                  |     | <hr/> |     |       |
| One do. of 2AgO, PO <sub>5</sub> |     | 304   |     | 100   |

*Indirect Determination of Phosphoric Acid by Oxide of Lead.*—Acetate of lead is added in slight excess to an aqueous

solution of the substance under examination; a precipitate is produced containing all the phosphoric acid in combination with oxide of lead; but, as this compound is not of invariable composition, it must be analyzed in order to ascertain the amount of phosphoric acid which it contains: with this view it is collected on a filter, washed, dried, ignited, and weighed, it is then dissolved in as small a quantity of nitric acid as possible, and sulphuric acid and alcohol added; the latter for the purpose of preventing the solution of any trace of the sulphate of lead; the sulphate is collected on a filter, washed with dilute alcohol, ignited and weighed; from the weight obtained the equivalent of oxide of lead is calculated, and, this being deducted from the weight of the mixture analyzed, the amount of phosphoric acid is obtained.

*Separation of Phosphoric Acid from the Alkaline Earths.*

—The compound is dissolved in a small quantity of hydrochloric acid, perchloride of iron is next added, and then acetate of soda in excess, the precipitate must have a reddish brown color; if it has a white tinge, more perchloride of iron must be added; the whole is now heated to ebullition for ten minutes in an evaporating basin, a bulky precipitate subsides, provided a sufficient quantity of alkaline acetate has been added: this is basic phosphate and basic peracetate of iron. It is collected on a filter, and well washed with boiling water. The amount of phosphoric acid which it contains may be determined in two ways.

a. It is dissolved in hydrochloric acid, and, tartaric acid having been added (to prevent the precipitation of peroxide of iron), it is treated with excess of ammonia; a clear transparent yellow liquid is obtained, in which the phosphoric acid is determined as pyrophosphate of magnesia, in the manner already directed.

b. The mixture of basic phosphate and basic peracetate of iron, after being well washed, is ignited with free access of air. To insure the whole of the iron being in the maximum state of oxidation, a few drops of nitric acid are added to the residue in the crucible, which is again ignited, and this is repeated as long as the least increase of weight is observed. It is now digested, crucible and all, with strong hydrochloric acid, and, a perfect solution having been obtained, water is added, then tartaric acid, ammonia in excess, and finally hydrosulphuret of ammonia; a gentle heat is applied, and the

mixture is allowed to remain at rest in a warm situation, covered with a glass plate, until the sulphuret of iron has completely subsided, the supernatant liquor having a clear yellow color; the sulphuret is transferred to a filter, and washed uninterruptedly with as little access of air as possible, with water, to which a few drops of hydrosulphuret of ammonia have been added. The object in keeping the funnel covered with a glass plate during the filtration is, to prevent a portion of the sulphuret of iron from being oxidized into sulphate, which, being soluble, would pass through the filter, thus occasioning a serious loss. The sulphuret of iron, having been washed, is dissolved in hydrochloric acid; the solution is peroxidized by the addition of nitric acid, and finally precipitated by ammonia; the weight of the ignited oxide obtained subtracted from that of the original mixture of perphosphate and peroxide, gives the amount of phosphoric acid.

This method, which gives very accurate results, is adopted by *Will* and *Fresenius* in the analysis of soils and ashes.

*Separation of Phosphoric Acid from Alumina.\**—This may be effected in two ways: First, the compound is dissolved in nitric or hydrochloric acid, and having added tartaric acid and ammonia, the phosphoric acid is estimated as pyrophosphate of magnesia: in this case the filtrate from the precipitate by sulphate of magnesia will contain magnesia and alumina, which must be separated from each other as directed page 260. Secondly, the phosphate of alumina is heated to intense ignition for half an hour in a platinum crucible, with a mixture of one and a half parts of artificially prepared silicic acid and six parts of carbonate of soda. The ignited mass is digested with bicarbonate of ammonia in excess, and the solution filtered from the insoluble silicate of soda and alumina: the phosphoric acid in the filtrate is determined by adding a known quantity of iron dissolved in nitric acid, and precipitating by ammonia in the manner already described.

Another method of separating alumina from phosphoric acid, recommended by *Fuch*, is to dissolve a known weight of the compound in caustic potassa, and to precipitate the alumina in the form of double silicate of alumina and potassa by a solution of silicate of potassa. The solution filtered from this precipitate contains all the phosphoric acid; it is super-

\* See Chapter VI.



saturated with hydrochloric acid and evaporated to dryness: the residue is dissolved in water, the solution rendered alkaline by ammonia, and the phosphoric acid determined as pyrophosphate of magnesia. The precipitate, consisting of double silicate of potassa and alumina, having been washed, is digested in hydrochloric acid and evaporated to dryness, the residue is moistened with hydrochloric acid, allowed to stand for half an hour, and then treated with water, whereupon the chloride of aluminum dissolves; leaving the silicic acid in its insoluble form; the alumina is finally precipitated from the filtered liquid by carbonate of ammonia.

*Separation of Phosphoric Acid from Magnesia, Oxide of Cobalt, and Oxide of Nickel. Von Kobell's Method.*—To the nitric or hydrochloric solution of the compound, perchloride of iron is added; it is then precipitated with carbonate of lime; the whole of the phosphoric acid is found in the precipitate, the supernatant liquid containing no traces of it.

*Separation of Phosphoric Acid from Oxide of Uranium. Ebelmen's Method.*—The phosphate, as precipitated from its solution by ammonia, is dissolved in a solution of bicarbonate of potash; on the addition of caustic potash the oxide of uranium is precipitated in the form of uranate of potash, while the phosphoric acid remains in the alkaline solution. Or the phosphoric acid may be first separated from the solution by the addition of a known quantity of peroxide of iron dissolved in nitric acid, the bicarbonate being in excess; a precipitate falls consisting of the whole of the peroxide of iron and phosphoric acid, the increase of weight of which represents the amount of phosphoric acid. The peroxide of uranium is afterwards estimated in the usual manner.

*Analysis of Phosphites and Hypophosphites.*—They are converted into phosphates by evaporating to dryness with nitric acid, and igniting the remainder. When treated in this manner, the neutral phosphites yield neutral phosphates, while the neutral hypophosphites yield acid phosphates (*Rose*).

The following method of separating phosphoric acid from phosphorous and hypophosphorous acids is likewise given by *Rose*: The solution is poured gradually and in small quantities into a solution of chloride of mercury which must be fully saturated; a precipitate of subchloride of mercury, exhibiting the splendor of mother-of-pearl, is determined, but

its complete separation requires gentle digestion for several days: the subchloride of mercury is collected on a filter, dried by exposure to a gentle heat, and weighed. From its weight it is easy to calculate how much oxygen has been taken up by the phosphorous or hypophosphorous acid to effect its conversion into phosphoric acid: hence the quantity of either of these acids is readily inferred. This quantity of oxygen is equivalent to the quantity of chlorine contained in the subchloride of mercury, since the chloride of that metal, on being converted into subchloride, loses exactly one-half of its chlorine. Another quantity of the solution to be analyzed is treated with nitric acid, and a weighed quantity of oxide of lead in the manner already described, the object being to determine the whole quantity of phosphoric acid, both that originally contained in the solution and that formed from the phosphorous or hypophosphorous acid, at the expense of the oxygen of the nitric acid. Now, it is learnt by the first operation how much phosphoric acid is produced by the phosphorous or hypophosphorous acid of the solution, and, by deducting this from the whole quantity obtained by the second operation, the actual proportion of phosphoric acid in the solution analyzed is known.

According to *Wohler*,\* phosphorous acid is converted into phosphoric acid by being heated with sulphurous acid, sulphuretted hydrogen being formed and sulphur separated. In this manner, he states that phosphorous acid may easily be detected in phosphoric acid: when arsenious acid is present at the same time, the sulphuret of arsenic is immediately formed on treatment with sulphurous acid. Phosphorous acid in phosphoric acid may also be detected by Marsh's apparatus, from the phosphuretted hydrogen which is disengaged. The gas burns with a whitish flame, and when held close to a surface of porcelain a ring of green light is observed in the expanded flame, similar to that afforded by phosphorus when burnt in chlorine gas, or with an insufficient access of atmospheric air.

### *Boracic Acid.*

*Quantitative estimation of Boracic Acid.*—As this acid does not form with any base a compound perfectly insoluble in

\* *Ann. der Chem. und Pharm.*, xxix. 252; and *Chem. Gaz.*, vol. i. p. 127.

water, it cannot be determined by direct precipitation, neither can it be estimated even when existing alone in solution by evaporating to dryness, because, although it is one of the most fixed of all substances at an intense heat, it possesses the property of volatilizing with the vapor of water or of alcohol. Boracic acid may be determined by adding to the solution an accurately weighed quantity of pure oxide of lead, evaporating to dryness, igniting, and weighing the residue, and calculating the amount of boracic acid from the increase of weight. The quantity of this acid, in its salts, is best found by determining the quantity of the base accurately and subtracting the amount from the weight of the substance analyzed.

*Separation of Boracic Acid from Phosphoric Acid.*—The phosphoric acid may be precipitated by sulphate of magnesia, and determined as pyrophosphate, or by *Von Kobel's* method, by the addition, first, of perchloride of iron, and then of carbonate of lime; not a particle of boracic acid is precipitated, but the separation of the phosphoric acid is complete.

*Separation of Boracic Acid from the Alkalies.*—The alkalies are converted into sulphates by heating for some time with excess of sulphuric acid; the boracic acid is removed by agitating the evaporated mass repeatedly during a considerable time with absolute alcohol, the flask being kept closed.

*Separation of Boracic Acid from those fixed Bases with which it forms Compounds decomposable by Sulphuric Acid.*—The following method was proposed by *Arfwedson*. A known weight of the compound is reduced to a fine powder, and mixed in a platinum crucible with four parts of pure pulverized fluor spar. It is then moistened with sulphuric acid and heated, first gently, and gradually to redness, at which temperature it is maintained as long as fumes continue to be evolved. The whole of the boracic acid is thus driven off in the form of fluoride of boron ( $\text{BO}_3 + 3\text{FlH} = \text{BF}_3 + 3\text{HO}$ ). The bases, together with gypsum, remain behind in combination with sulphuric acid; they are separated from each other according to the directions which have been given in the preceding pages, and the amount of boracic acid is calculated from the loss sustained by the original substance after deducting from it the quantities of the different bases found; these determinations must, therefore, be made with great care, since the whole loss falls on the boracic acid.

When the bases with which boracic acid is combined are

precipitable by sulphuretted hydrogen or by hydrosulphuret of ammonia, these reagents are employed to separate them; their quantities must be accurately determined and deducted from the weight of the compound submitted to analysis; the difference of weight is the quantity of boracic acid.

From the alkaline earths boracic acid is separated in the same manner as phosphoric acid, the amount of acid being calculated from the loss.

*Determination of Boracic Acid in Silicates undecomposable by Acids (Axinite, Tourmalines).*—No methods leading to accurate results are at present known; the following process adopted by *Gmelin*, and given by *Rose*, is the best. The mineral is finely levigated, and heated strongly with carbonate of baryta. The ignited mass is treated with a sufficient quantity of hydrochloric acid to decompose it, and evaporated to dryness on the water bath. The silica is separated from the residual mass in the usual manner, and the baryta precipitated from the filtered solution by carbonate of ammonia. The clear liquid is again evaporated to dryness and gently ignited; it is then weighed and treated with alcohol and hydrochloric acid. The alcohol is inflamed, and in this way the boracic acid is got rid of; the residue is once more ignited and weighed, and the quantity of boracic acid is indicated by the loss of weight. Another method, recommended by the same chemist, is to ignite the pulverized mineral with carbonate of soda, and to treat the ignited mass with water. The solution having been digested with carbonate of ammonia, to remove the small portions of silica and alumina which the water had dissolved, is evaporated to dryness, the dry mass treated with sulphuric acid, and the boracic acid dissolved by digestion with alcohol. The solution is finally saturated with ammonia, and the residue, which consists of boracic acid, is ignited and weighed.

### *Silicic Acid.*

This acid is always converted from its soluble to its insoluble condition, for the purpose of estimation. The conversion is effected by evaporating the solution to dryness with hydrochloric acid, or any other volatile acid. The silicic acid is, generally, first obtained in a gelatinous state; but, by continuing the heat, it loses the whole of its water, and is brought to the condition of a dry powder. The evaporating mass must



be constantly stirred with a glass rod during its exsiccation, to prevent spurting. The bases with which the silicic acid was combined are separated by dilute acid, and the silicic acid, having been thoroughly washed and dried, is ignited in a platinum crucible and weighed, when cold, with the cover on, the dry powder absorbing moisture rapidly from the air. For the properties of silicic acid, see Part I., p. 130. Its composition is:—

|                             |     |       |     |       |
|-----------------------------|-----|-------|-----|-------|
| One equivalent of Si        | ... | 21.35 | ... | 47.08 |
| Three do. of O              | ... | 24.00 | ... | 52.92 |
| <hr/>                       |     |       |     |       |
| One do. of SiO <sub>3</sub> | ... | 45.35 |     | 100   |

*Separation of Silicic Acid from Bases.*—*Quantitative Analysis of Natural Silicates.*—In the first part of this Treatise\* it was remarked that the great natural family of silicates may be arranged in three classes:—1st. Those easily decomposable by hydrochloric acid; 2d, those only decomposable by prolonged digestion with concentrated acid; and, 3d, those which absolutely resist the action of acids, even after prolonged digestion. We now extract from Rose's Treatise on Analysis† a list of the names and composition of a series of interesting minerals belonging to each of these classes:—

1. *Silicates decomposable by Hydrochloric Acid in the Cold.*

|                     |       | Combination of |            |                                           |
|---------------------|-------|----------------|------------|-------------------------------------------|
| 1. Apophyllite      | . . . | Potassa,       | silica,    | lime and water.                           |
| 2. Natrolite        | . . . | Silica,        | soda and   | water.                                    |
| 3. Scolezite        | . . . | Silica,        | alumina,   | lime, soda and water.                     |
| 4. Mesolite         | . . . | ditto          | ditto      | ditto.                                    |
| 5. Mesole           | . . . | ditto          | ditto      | ditto.                                    |
| 6. Analcime         | . . . | Silica,        | alumina,   | soda and water.                           |
| 7. Laumonite        | . . . | Silica,        | alumina,   | lime and water.                           |
| 8. Potash harmotome |       | Silica,        | alumina,   | baryta, potash and water; sometimes lime. |
| 9. Leucite          | . . . | Potassa,       | silica and | alumina.                                  |
| 10. Eleolite        | . . . | Silica,        | alumina,   | lime, potassa, soda and water.            |
| 11. Brewsterite     | . . . | Silica,        | alumina,   | strontia, baryta, lime and water.         |

\* Page 188, "Qualitative Analysis of Natural Silicates."

† Translated, with Notes and Additions, by A. Normandy.

- |                       |                                                                                                                          |
|-----------------------|--------------------------------------------------------------------------------------------------------------------------|
|                       | Combination of                                                                                                           |
| 12. Sodalite . . .    | Soda, silica and alumina, with a small quantity of hydrochloric acid.                                                    |
| 13. Cronstedtite . .  | Silica, oxide of iron and water.                                                                                         |
| 14. Ilvaite . . . .   | Silica, protoxide of iron and lime.                                                                                      |
| 15. Gehlenite . . .   | Silica, alumina, lime and oxide of iron.                                                                                 |
| 16. Wernerite . . .   | Silica, alumina, lime and soda.                                                                                          |
| 17. Tabular spar . .  | Silica and lime.                                                                                                         |
| 18. Nepheline . . .   | Soda, silica and alumina.                                                                                                |
| 19. Cancrinite . . .  | Soda, silica and lime.                                                                                                   |
| 20. Mellinite . . .   | Silica, magnesia, lime and oxide of iron.                                                                                |
| 21. Chabasite . . .   | Silica, alumina, lime and water, with a little potassa.                                                                  |
| 22. Pectolite . . .   | Silica, lime, soda, potash, oxide of iron and water.                                                                     |
| 23. Okenite . . . .   | Silica, lime, soda, potash, oxide of iron, oxide of manganese and water.                                                 |
| 24. Davyne . . . .    | Silica, alumina, lime, iron and water.                                                                                   |
| 25. Sodolenite . . .  | Yttria, silica, glucina, oxides of cerium and iron.                                                                      |
| 26. Allophane . . .   | Alumina, silica and water.                                                                                               |
| 27. Helvine . . . .   | Silica, glucina, alumina, protoxide of iron and of manganese.                                                            |
| 28. Datholite . . .   | Silica, boracic acid, lime and water.                                                                                    |
| 29. Botryolite . . .  | Differs from the preceding in containing one atom more water.                                                            |
| 30. Häüyne . . . .    | Potash or soda, silica, alumina, lime and sulphuric acid.                                                                |
| 31. Nosian . . . .    | Sesquisilicate of alumina and soda (Klaproth).                                                                           |
| 32. Lazulite . . . .  | Silica, alumina, lime, oxide of iron, magnesia, soda and sulphuric acid.                                                 |
| 33. Eudialite . . .   | Silica, soda, zirconia, lime, oxides of iron and manganese, hydrochloric acid and water.                                 |
| 34. Orthite . . . .   | Silica, alumina, oxides of iron, cerium, lanthanum and manganese; lime, yttria, magnesia, and a small quantity of water. |
| 35. Electric Calamine | Oxide of zinc, silica and water.                                                                                         |

- |                        |                                                                                             |
|------------------------|---------------------------------------------------------------------------------------------|
|                        | Combination of                                                                              |
| 36. Sidéroschisolite . | Protoxide of iron, silica, alumina and water.                                               |
| 37. Hisingerite . .    | Silicate of protoxide and sesquioxide of iron + six atoms of water.                         |
| 38. Diopase . . .      | Silicate of copper and water.                                                               |
| 39. Meerschäum . .     | Magnesia, carbonic acid, silica, water, a little alumina, and traces of manganese and lime. |
| 40. Copper, Malachite  | Carbonate and silicate of copper and water.                                                 |

The above minerals, when finely pulverized, form a jelly when hydrochloric acid is poured upon them. The next nine do not form a jelly, and some of them are only decomposed by protracted digestion with hot hydrochloric acid. Nearly all of these minerals resist altogether the action of acids after being ignited.

- |                       |                                                                                                                             |
|-----------------------|-----------------------------------------------------------------------------------------------------------------------------|
| 1. Stilbite . . . .   | Silicate of alumina, lime and water.                                                                                        |
| 2. Epistilbite . . .  | ditto ditto.                                                                                                                |
| 3. Heulandite . . .   | Tersilicate of alumina and lime.                                                                                            |
| 4. Anorthite . . .    | Silica, alumina, lime and magnesia.                                                                                         |
| 5. Spheue or Pitanite | Tersilicate of lime and titanate of lime.                                                                                   |
| 6. Pyrosmalite . .    | Lime, tersilicate of oxide of iron and of manganese.                                                                        |
| 7. Cerite . . . .     | Hydrated silicate of peroxide of cerium.                                                                                    |
| 8. Cerine or Allanite | Silicate of alumina and of cerium, of iron and of lime.                                                                     |
| 9. Pitchblende . .    | Uranium ore, containing from two to five per cent. of silica, probably in a state of mechanical, not chemical, combination. |

*Silicates only decomposable by fusion with Carbonate of Potassa or Soda.*

- |                                |                           |
|--------------------------------|---------------------------|
| 1. Felspar.                    | 6. Oligoclase.            |
| 2. Albite.                     | 7. Labradorite.           |
| 3. Rhiacolite.                 | 8. Barytic harmotone.     |
| 4. Petalite.                   | 9. Olivine.               |
| 5. Spodumene (Soda Spodumene.) | 10. Prehnite.             |
|                                | 11. Carbonated Manganese. |

- |                                    |                   |
|------------------------------------|-------------------|
| 12. Mica.                          | 26. Dichroite.    |
| 13. Lepidolite.                    | 27. Emerald.      |
| 14. Talc.                          | 28. Euclase.      |
| 15. Chlorite.                      | 29. Phenakite.    |
| 16. Pinite.                        | 30. Tourmaline.   |
| 17. Achmite.                       | 31. Axinite.      |
| 18. Amphibole.                     | 32. Topaz.        |
| 19. Anthrophyllite.                | 33. Chondrodite.  |
| 20. Pyroxene.                      | 34. Picrosmine.   |
| 21. Diallage.                      | 35. Carpholite.   |
| 22. Chaloyant or Schiller<br>Spar. | 36. Steatite.     |
| 23. Epidote.                       | 37. Serpentina.   |
| 24. Idocrase.                      | 38. Pumice stone. |
| 25. Garnet.                        | 39. Obsidian.     |
|                                    | 40. Pitch stone.  |

To this class belong also the different species of false gems and artificial glass.

*Silicates which resist the action of Acids and fusion with Alkaline Carbonates, but which are decomposed by ignition with pure Potash.*

- |               |                |
|---------------|----------------|
| 1. Zircon.    | 4. Staurolite. |
| 2. Cyanite.   | 5. Andalusite. |
| 3. Cymophane. |                |

*Decomposition of Silicates by Acids*—The mineral is reduced to the finest possible powder, according to the instructions given, page 188, Part I., without, however, employing the elutriating process. It is dried at  $212^{\circ}$ , avoiding a higher temperature, because many of these compounds contain water and other volatile matters, which must not be expelled; and because, moreover, an elevated temperature might interfere with the readiness with which the silicate is decomposed by acids. The pulverized mineral, having been deprived of its hygrometric water, is weighed in a platinum or porcelain dish, and digested at a gentle heat, until complete decomposition has taken place, which is known by rubbing a glass rod against the bottom and sides of the vessel; if it produce a grating noise, it shows that the decomposition is not complete, and the digestion must be continued till the end of the rod glides smoothly over the bottom of the dish. The separated silicic acid does not, in all cases, assume the



same appearance, as was remarked above: sometimes it separates in a bulky gelatinous state, in other cases no jelly is formed, the acid being liberated in the form of a fine powder: some silicates, again, are decomposed almost instantaneously, while others require long-continued digestion. The operator must bear all these facts in mind; and, above all, he must assure himself of the complete decomposition of the mineral, or all his time and labor will have been expended in vain. The decomposition being complete, the mass is evaporated to dryness on the water bath, and the residue heated until all moisture is expelled; the dry mass is then digested with hydrochloric acid, which dissolves out all the bases, leaving the silicic acid in its insoluble modification: it is collected on a filter, washed with boiling distilled water, dried, ignited, and weighed. The filtrate and the washings are quantitatively examined for bases, according to the instructions given in the last chapter. *Rose* objects to the evaporation of the silicate to dryness after its decomposition by hydrochloric acid, partly on the grounds that the whole of the silica is not thereby rendered insoluble, and that portions have still to be separated in the course of the analysis, but chiefly because it is possible that during the evaporation certain volatile constituents of the compound may be expelled, and thus escape detection, which, he says, has happened with many chemists who have pursued this method. Compounds which are easily decomposed by hydrochloric acid should never, according to this eminent chemist, be exposed to heat, but digested with cold acid, only employing heat when the decomposition will not proceed without it. In cases where the silicic acid is separated in the gelatinous form, *Rose* treats the mass with water, and thus separates the silicic acids in light flocks. Most chemists, however, prefer the method of evaporating the whole mass at once to dryness: it is the simplest, and, on the whole, the least troublesome; and, if the mass has been thoroughly exsiccated, there is very little fear of any of the silicic acid finding its way again into the solution. In the case of those minerals which contain volatile constituents, their nature will generally be made known by the preliminary examination, and the course of analysis will be shaped accordingly: it is evident, however, that these particular cases cannot come within the limits of a description of a general method, to which the above instructions must be understood to apply.


*Decomposition of Silicates by Fusion with Alkaline Carbonate.*—The mineral reduced to the finest possible state of division, by elutriation, if necessary, is mixed in a platinum crucible with from three to four times its weight of pure anhydrous carbonate of soda, or with an equal quantity of well-dried and previously pulverized carbonate of potash, or, which perhaps is still better, with a mixture of the two carbonates in the proportion of single equivalents, such as is obtained by calcining Rochelle salt, (tartrate of potash and soda,) lixiviating the calcined mass in water, and evaporating the solution to dryness. The mixing of the pulverized mineral with the alkaline carbonate is made by a rounded glass rod: it must be very intimate, and all portions adhering to the rod must be carefully wiped off into the crucible. The cover is placed on the crucible, and it is buried in calcined magnesia contained in a good Hessian crucible, which is then placed in the furnace. The heat must be gentle at first, but gradually raised to intense ignition, at which it must be maintained from thirty minutes to an hour; at the end of this time the mass will be either completely fused or in a state of semifusion, according as the mineral contains more or less silicic acid. The crucible is removed from its bed of magnesia when cold, and its contents transferred to a beaker, which can be covered with a glass plate. When the mass has only been in a state of semifusion, it is generally easily removed by bending and pressing the sides of the crucible; but, when the fusion has been complete, it is sometimes not very easy to remove it without having recourse to hydrochloric acid: in the event of this being necessary, the crucible should be placed in a large beaker before the acid is poured on it, in order to avoid loss by the sudden evolution of carbonic acid. The contents of the crucible being safely lodged in the beaker, the mass is drenched with water, and hydrochloric acid added cautiously, to prevent too violent an effervescence; it is then covered with its plate and exposed to a gentle heat, until perfect solution has taken place, or until only slight flakes of silica are seen floating in it, by which it is known that the decomposition of the mineral has been complete. If, on the other hand, a heavy gritty powder should subside to the bottom of the vessel, the operator hereby learns that, either from the mineral not having been in a sufficiently fine state of division, or from the heat not having been sufficiently intense or long continued,

or from some other cause, the mineral has not been entirely decomposed; and the powder must be carefully collected, washed, dried, and weighed, and the weight deducted from the quantity originally taken; or, which is always best, the whole experiment must be recommenced with a fresh portion of substance. Supposing, however, the decomposition to have been successfully performed, the silica is separated by evaporation to dryness on the water bath, and the analysis proceeded with precisely in the same manner as in the case of a silicate, decomposable by simple digestion with hydrochloric acid.

*Decomposition of Silicates by Fusion with Caustic Potash.*

—The finely pulverized mineral is mixed in a silver crucible, with four or five times its weight of caustic potash; the cover is placed on the crucible, and it is carefully heated over a lamp to dryness, and the dry mass is subsequently heated to redness; a far better method, however, of decomposing these silicates, which refuse to yield to alkaline carbonate, is to subject them to the action of hydrofluoric acid, as first recommended by *Berzelius*, and afterwards adopted by *Brunner*. With this view, the finely powdered mineral is placed in a shallow platina dish *b*, supported on a leaden tripod, standing in the centre of a leaden dish *a*,  $2\frac{1}{2}$  inches high (Fig. 13), about six inches in diameter. The bottom of this leaden vessel is covered to the depth

Fig. 13.



of from one-eighth to one-fourth of an inch, with a mixture made to the consistence of paste of powdered fluor spar and sulphuric acid. The dish is provided with a flat cover, made of the same metal. The mineral to be decomposed is moistened with a little water, and, the cover having been placed on the dish, the latter is gently heated over the sand bath underneath a flue; hydrofluoric acid gas is liberated, by means of which from twenty to thirty grains of silicious mineral may be completely decomposed in the course of an hour and a half. During the process the powder must be twice moistened with a few drops of water; if it is well spread out on the platina dish, it is unnecessary to stir it. When the operation is finished, concentrated sulphuric acid is added, drop by drop, to the powder, as long as hydrofluosilicic acid is given off; a

gentle heat is at the same time applied, and finally the excess of sulphuric acid is driven off by continued heat and evaporation to dryness. The dry residue, after being moistened with hydrochloric acid, is boiled in water, and further examined in the usual way. This method is particularly applicable to the examination of such minerals as contain alkalis; another method of analyzing such silicates, proposed by *Abich*, is to fuse them with hydrate of baryta or with carbonate of baryta, using from four to six parts of the carbonate to one of the mineral; the most intense heat is required, no action taking place till a state of fusion has been induced; but, when once the action has commenced, it goes on rapidly and energetically, and the operation is finished in a quarter of an hour; no silicate has yet been found to withstand the action of this agent, but the most powerful heat, attainable in a wind furnace of the best construction, is required. When hydrate of baryta is employed, the operation may be conducted in a silver crucible over a good spirit lamp; from four to five parts of the hydrate, deprived of its water of crystalization, are mixed intimately with one of the powdered mineral, and the mixture is then covered with a layer of carbonate of baryta. The decomposition being complete, the analysis is proceeded with in the usual manner.

It must be observed that the silicic acid, as separated from minerals of difficult decomposition, may contain a considerable quantity, 12 or 15 per cent., of *alumina*, and still form a transparent glass when fused with soda. It is always necessary, therefore, to examine the silica obtained from such minerals very carefully for that earth; with which view it is fused with carbonate of potash, the melted mass treated with hydrochloric acid, and the solution evaporated to dryness. The dry mass is moistened with hydrochloric acid, and afterwards treated with water. The acid solution, filtered from the undissolved silicic acid, is now super-saturated with ammonia. If the solution give no precipitate, the silicic acid may be considered to have been pure; but if a precipitate is formed, this can only arise from an impurity, which, in most cases, will prove to be alumina.

#### *Carbonic Acid.*

*Determination of Carbonic Acid in a free state in Aqueous Solution.*—This is very conveniently effected by adding to a



weighed or measured quantity of the solution a clear mixture of chloride of calcium and excess of ammonia; the latter absorbs the carbonic acid, and carbonate of ammonia is formed, which, reacting with the chloride of calcium, gives rise to chloride of ammonium and carbonate of lime: the latter is precipitated. It is collected on a filter and washed with water, to which ammonia has been added; the funnel must be carefully protected from the air during filtration, otherwise carbonic acid might be absorbed, which would increase the amount of carbonate of lime. The amount of carbonic acid in the precipitate may be estimated by gently igniting it, and estimating it as carbonate of lime (for the composition of which see page 256), or it may be determined in the apparatus of *Fresenius* and *Will*, Fig. 7, using that modification of the apparatus recommended for the analysis of carbonates, the bases of which form insoluble compounds with sulphuric acid, and described page 245.

*Estimation of Carbonic Acid in the gaseous state.*—The volume of gas is first accurately measured in a graduated tube standing over mercury; a small piece of moistened caustic potassa, attached to a piece of ignited harpsichord wire, is then passed through the mercury into the tube; when the absorption has ceased, the potassa is withdrawn, and the volume of the unabsorbed gas accurately determined: the difference in the two measurements indicates the quantity of carbonic acid. When the volume of the gas is large, and contained in a receiver which is not graduated, it is sometimes determined by the increase in weight of a piece of caustic potash passed into the receiver, and allowed to remain for some time in contact with the gas.

*Analysis of Carbonates.*—We have already described at some length the method which is easiest of execution, and which, on the whole, gives the most satisfactory results, viz: that of *Fresenius* and *Will* (page 245). Fig. 14 shows a little apparatus that may sometimes be conveniently employed. It consists of a small thin-bottomed flask, capable of containing about four ounces of water. It is fitted with a cork, through



Fig. 15.

which is inserted a bent tube adapted to another wide tube, containing fragments of dried chloride of calcium; the extremity of this tube is drawn out to a capillary orifice. The small tube seen inside the flask is intended to hold the sulphuric or hydrochloric acid, with which it is proposed to decompose the carbonate. It is made somewhat too long in the figure; it should rest against the side of the flask at an angle of about  $45^{\circ}$  from the bottom, so that by inclining the flask the whole of the acid can be made to flow out. The carbonate to be analyzed is accurately weighed and projected into the flask, which should contain about an ounce of water; and, the chloride of calcium tube having been fixed air-tight into its place, the whole apparatus is accurately weighed. Great care must be taken that none of the acid in the tube runs in contact with the carbonate before the operation is commenced. Everything being ready, the flask is inclined so as to allow a portion of the acid to flow out of the tube; effervescence immediately takes place, carbonic acid is expelled, and escapes through the orifice of the chloride of calcium tube, being thoroughly dried during its passage through the lime salt. As soon as the effervescence has ceased, a fresh portion of acid is caused to flow out of the tube, and the operation is repeated until no farther escape of carbonic acid gas is perceived.

The flask is now placed in a vessel of boiling water, where it is allowed to remain for some time in order to expel all the carbonic acid in the liquor, and in the upper part of the flask aqueous vapor is prevented from escaping by the chloride of calcium. On cooling, atmospheric air finds its way into the flask, which is thus brought to the same condition it was in previous to commencing the experiment. It is now weighed; the loss of weight indicates the amount of carbonic acid. This is a very convenient little apparatus for the analysis of limestones and marls.

In *Silliman's Journal* for April 1844, *Professor Rogers*, of the University of Virginia, having given an account of some new instruments and processes for the analysis of carbonates;\* their object being to attain a higher degree of accuracy than they found possible by any of the methods in ordinary use, which, though fitted for ordinary analysis, were not, as they considered, adapted for that higher description of

\* See Chem. Gaz., vol. ii. page 305, *et seq.*

research involved in the investigation of the atomic weights of lime, magnesia, potash, &c. &c.


The method of the American chemists is, like those already described, the *indirect* method, the amount of carbonic acid being calculated from the loss of weight after the operation is concluded. They also take account of the amount of carbonic acid contained in the liquid, which they found too considerable to be overlooked. They separate and measure this portion of absorbed carbonic acid in the following manner. A tube of thin glass twenty-four inches long and one-fourth of an inch in diameter, is graduated at its closed extremity to fiftieths of a cubic inch. Mercury is poured into the tube until the vacant space above is not much more than sufficient to contain all the liquid in the bottle in which the analysis has been made; this liquid is then poured on the mercury gently, so as to produce as little agitation as possible, and the tube is then completely filled with mercury. The tube thus filled is inverted in a bowl of mercury, and supported in an inclined position; the part containing the solution is then heated to the boiling point by the flame of a spirit lamp. Bubbles of carbonic acid rapidly ascend, and the gas continues to be disengaged, even after the commencement of ebullition, so that, to ensure its entire separation, this temperature should be maintained for two or three minutes. The tube placed in an erect position may now be brought to the temperature of the apartment by a moist cloth.

The mercury in the bowl is now covered with a saturated solution of common salt, and the tube is raised a little, so as to allow this liquid to ascend and take the place of the mercury in the tube; after which the instrument is transferred to a deep narrow jar, filled also with the saturated solution, and is depressed to the proper level for measuring the volume of included gas. As this volume always includes a minute quantity of common air, disengaged from the liquid by boiling, the tube is now transferred to a large cistern of water, when, by continued agitation for a minute or two, all the carbonic acid will be absorbed, and thus its volume made known by subtraction. These processes being conducted at or near the temperature of the room, or the volume being corrected for expansion, should the temperature be much higher, the height of the residuary carbonic acid is given with sufficient

accuracy, by estimating each length of a cubic inch as equivalent to 0.047 gr.

*Direct determination of Carbonic Acid in saline Compounds. Brunner's Method.*—Deeming it advisable to exchange the negative method of determining carbonic acid in saline compounds for a positive method, in which the liberated acid should itself be brought into the balance, *Brunner* invented the apparatus shown in Fig. 16.\* The substance to be examined is placed in the little flask *a*, and a

Fig. 16.



suitable quantity, for instance an ounce of water, poured over it; upon which the flask is closed with a tight-fitting cork provided with three tubes, and when necessary coated with cement. The straight tube terminates above in a small funnel *g*, through which the sulphuric acid is poured. The second, provided with two bulbs, is connected by its rectangular bend with a tube *b c*, from a third to half an inch wide, and in order to gain space, likewise furnished with two expansions, containing asbestos, moistened with sulphuric acid. The third is bent twice, and terminates in the large empty flask *A*. To adapt it more easily, it may be cut anywhere in the middle, and the two parts connected by caoutchouc.

The two tubes dipping in the liquid of the bottle *a* are drawn out at their lower lengths into fine somewhat laterally

\* Poggendorff's *Annalen*, No. 6, 1846; and *Chem. Gaz.*, vol. iv. p. 367.



curved points; the tube *b e* contains, in the expanded portion *b d*, which is from three-quarters to one inch in width, well-burnt lime which may be readily moistened with water; from *d* to *e* asbestos or fragments of pumice stones, drenched with sulphuric acid, and separated from the lime by a tight stopper of asbestos; the small Wolfe's flask contains lime water.

The analysis is now performed in the following manner. A small quantity of sulphuric acid is poured into the flask *a* through the funnel tube, the stopcock of *f* being closed; as this will not descend of itself, it is made to do so by drawing gently with the mouth at *h*. The evolution of gas, which is made perceptible by the ascending bubbles, and by the air passing through the lime water in *i* is now waited for; another portion of acid is then added, and this continued until it may be assumed that a tolerable excess of acid has been introduced. This being done, some water containing a little caustic potash in solution is allowed to flow into the flask *A* by opening the stopcock of *f*, whereby a current of air is passed through the vessel *a*, which carries the carbonic acid contained partly in the liquid, partly in the upper space of the vessel, into the tube *b e*; but, since this would never be completely effected without the application of heat, the vessel *a*, towards the end of the experiment, is immersed in a small dish filled with water, which is kept warm over a small lamp as long as is found requisite.

It is best to regulate the current of air, so that about two bubbles of gas pass through the lime water in a second. It will, however, never be found to become in the least degree turbid. It is scarcely necessary to observe that the object of the sulphuric acid in *b e* is to retain the moisture carried by the gas from *a*; also that the potash added to the water which flows into the large flask is to absorb the carbonic acid of the atmospheric air; and lastly, that the increase in the weight of *b e* yields the result sought for. Several analyses made by the author according to this method yielded very satisfactory results.

The analysis of a great many solid carbonates may be very simply effected by simply igniting them, and estimating the amount of carbonic acid from the loss of weight; it is, of course, indispensable that the substance shall contain no other volatile constituents, which may be expelled by the ignition, together with the carbonic acid. It is also necessary

that the substance from which the carbonic acid is expelled shall not itself undergo any alteration whereby it may be either increased or diminished in weight. The carbonates of certain metallic oxides are in this condition; as, for example, the carbonates of protoxide of iron and of manganese, and of oxide of cobalt. The analysis of these salts may be performed by igniting them in a bulbed tube of hard glass, through which a stream of dry carbonic acid gas is passing. Carbonates which contain water are analyzed by the same process which is adopted in determining the carbon and hydrogen in organic substances, and which will be fully described hereafter.

The decomposition of carbonates by heat is greatly facilitated by mixing them with about four times their weight of finely powdered borax, as was first pointed out by *Count F. Schaffgotsch*.<sup>\*</sup> He did not find anhydrous boracic acid so convenient for the purpose, since by long melting this acid decreases slowly but constantly in weight. The anhydrous biborate of soda, or glass of borax, is, however, absolutely fixed, and is well adapted for the purpose, from the ease with which it decomposes the carbonates in fusing, and from its causing no ebullition on account of its thick fluidity.

*Separation of Carbonic Acid from Sulphurous Acid.*—For this purpose *Persoz* introduces into a graduated tube containing the mixed gases a glass rod covered with paste, and coated with powdered iodate of potash or soda; the sulphurous acid is hereby converted into sulphuric acid, and as soon as no further decrease in the quantity of the confined gas is perceptible, the glass rod is removed, and the residual gas immediately measured. Before, however, the carbonic acid can be considered as free from sulphurous acid, another glass rod must be introduced, which is also covered with the paste made with starch and a dilute solution of iodate of potash; if the least trace of sulphurous acid exist in the gas, the rod is instantly colored blue. This method is, therefore, well adapted for the detection of minute traces of sulphurous acid.

*Separation of Carbonic Acid from all other Acids.*—As carbonic acid is readily removed from its combinations by heating with stronger acids, its separation from most other electro-negative bodies is attended with but little difficulty. The carbonic acid is determined in one portion of the com-

<sup>\*</sup> Poggendorff's *Annalen*, No. 10, 1842, p. 263.

pound, and the other acids in another portion. If the substance under examination contains fluorides, the carbonic acid is expelled by one of the weak non-volatile acids, such as tartaric or citric acids; since, if sulphuric or hydrochloric acid were employed, hydrofluoric acid would, at the same time, be discharged. When there occurs, in the course of an analysis, a mixed precipitate of fluoride of calcium and carbonate of lime, *Fresenius* directs the separation of the two substances to be effected by pouring acetic acid over the mixed precipitate, adding alcohol, filtering, and, finally, washing the residue with alcohol.

*Separation of Carbon from Nitre and Sulphur. Analysis of Gunpowder.*—The sample intended for analysis (from 20 to 30 grains) is finely pulverized and dried, either in the water bath, or in vacuo over sulphuric acid. It is then digested for some time with boiling distilled water, and the insoluble portion thrown on a filter, the weight of which is known. It is repeatedly washed while on the filter with hot water. The filtrate and the washings are evaporated to dryness, and the dry mass estimated as nitre; or, after having weighed the residue, it may be redissolved in water, and tested for common salt by nitrate of silver, and, if any notable quantity is thereby indicated, the silver salt must be added as long as any precipitation takes place, and the resulting chloride of silver calculated into its equivalent of chloride of sodium, and the amount deducted from the dry salt. The substance remaining on the filter is dried and weighed; it consists of carbon and sulphur.\* To determine the proportion of these two elements, a fresh quantity, from 15 to 20 grains, of the finely powdered sample, is intimately mixed with an equal amount of pure anhydrous carbonate of soda; the mass is thus mixed with about eight parts of nitre and six of common salt. The whole is strongly heated in a platinum crucible: the sulphur becomes hereby oxidized into sulphuric acid at the expense of the oxygen of the nitric acid, and the acid thus formed unites with the potash of the decomposed nitre, forming sulphate of potash. As soon as the mass becomes white, it is dissolved in water, acidified with hydrochloric acid, and the sulphuric acid precipitated by chloride of barium;

\* Carbon and sulphur may be separated from each other by sulphite of potassa, which converts the sulphur into soluble hyposulphite and leaves the carbon unaltered.

from the weight of sulphate of baryta obtained, the amount of sulphur is calculated.

*Marchand* modifies the above (*Gay Lussac's*) method of estimating the sulphur in gunpowder in the following manner. A mixture of 1 part of nitrate and 3 parts of carbonate of baryta is intimately mixed with a twelfth part of the powder, and heated in a tube closed at one end. A layer from 3 to 4 inches in length of baryta salt is inserted in front of the mixture, and the whole is heated in the combustion furnace, beginning at the anterior portion. The mixture which does not fuse is easily removed from the tube, which is rinsed with dilute hydrochloric acid, in which the ignited mass is then dissolved. The liquid is retained in a beaker for several hours near  $212^{\circ}$ , and the sulphate of baryta is then collected on a filter. The amount of sulphur may likewise be determined accurately in the moist way. From 30 to 40 grains of the powder are treated in a flask with concentrated nitric acid, with the addition of a few grains of chlorate of potassa; the mass is kept gently boiling, until at last a colorless liquid is obtained, which is diluted with a large quantity of water, and precipitated while hot with chloride of barium.

The charcoal is estimated indirectly by deducting the weights of the moisture, nitre, and sulphur from the original weight of the powder analyzed.

The amount of nitre in gunpowder may, according to *Marchand*, be ascertained with great precision by determining the quantity of nitrogen in the powder. For this purpose a portion of the sample is weighed off, reduced to a fine powder, and intimately mixed with oxide of copper; the mixture is transferred to a combustion tube, the sealed end of which is charged with carbonate of lead, and then with oxide of copper; oxide of copper and metallic copper are placed in front. The details of the process will be given hereafter.

*Separation of the Sulphur from the Charcoal.\**—For this purpose *Marchand* adopts *Wöhler's* method, which is as follows. An indefinite quantity of the mixture as dry as possible is brought into the bulb of a weighed reduction tube; the tube is filled with metallic copper, it is heated in a current of dry hydrogen gas, which drives the sulphur into the copper; the tube is then weighed, and likewise after shaking out the resi-

\* See note on page 405.



duary charcoal. In this way the relative quantity of sulphur and charcoal is obtained. The heat which must be applied to remove the whole of the sulphur from the charcoal is, in general, greater than that at which the charcoal had been prepared, and there is generally observed during the expulsion of the sulphur a strong odor of humic acid, carbonic acid, carbonic oxide, and water. Instead of distilling the sulphur from the charcoal, it may be removed by solvents. *Marchand* employs for this purpose *sulphuret of carbon*. After exhausting the gunpowder with water, which he effects in a displacement apparatus of the form of an ordinary chloride of calcium tube, from 7 to 8 inches long, the bulb being stopped with asbestos, he treats it with absolute alcohol, which displaces the water, upon which sulphuret of carbon, which has been rectified over oxide of lead, is poured over it until what passes through leaves no sulphur on evaporation; the powder is then finally treated with alcohol. It is still better to use the sulphuret of carbon mixed with absolute alcohol. As soon as the charcoal is washed, a current of dry air is drawn through the tube by means of an aspirator, the tube itself being confined in an air bath at  $248^{\circ}$ . The dry charcoal is weighed accurately in the tube.

The sand, &c., contained in the powder may be determined with tolerable accuracy by trituration and suspension. *Marchand* gives the following as the composition of the so-called *Bernese sporting powder*:—

|          |   |   |   |   |   |   |       |
|----------|---|---|---|---|---|---|-------|
| Nitre    | . | . | . | . | . | . | 79.16 |
| Sulphur  | . | . | . | . | . | . | 9.72  |
| Charcoal | . | . | . | . | . | . | 10.99 |
|          |   |   |   |   |   |   | <hr/> |
|          |   |   |   |   |   |   | 99.87 |


### *Oxalic Acid.*

The quantitative estimation of this acid may be effected by precipitating it from its solutions in the form of oxalate of lime, and determining the latter as carbonate, or by ascertaining the amount of carbonic acid yielded by its decomposition.

#### *Quantitative Estimation of Oxalic Acid by Precipitation.*

—The acid, if in a free state, is neutralized as exactly as possible with ammonia diluted with water, and chloride of calcium

mixed with acetate of soda added; the precipitated oxalate is well washed, dried, and ignited, with the precautions prescribed page 255, by which it is converted into carbonate; and the quantity of oxalic acid is calculated from the weight of the latter, every equivalent of oxalic acid yielding two of carbonic acid, thus



There are two ways of estimating the amount of carbonic acid yielded by the decomposition of oxalic acid; one is by burning it with oxide of copper, according to the ordinary method of organic analyses; and the other, which is by far the most convenient and expeditious, is by neutralizing it with ammonia, and bringing it into contact with peroxide of manganese and sulphuric acid, in the manner fully described under the head of MANGANESE, page 284. 9 parts of oxalic acid require theoretically 11 parts of manganese, but an excess of the latter does no harm. Both of these latter methods are applicable to the determination of oxalic acid in the oxalates. When the oxalate is soluble in water, the amount of oxalic acid may be determined by precipitation, as carbonate of lime, and the base or bases with which it was combined determined in the filtrate by appropriate methods. Many of the insoluble oxalates may be analyzed by simple ignition, the bases being left either as pure metals, or as oxides or as carbonates. Oxalates, the bases of which are precipitated by carbonate of potash, may be decomposed by boiling for some time with that alkali; oxalic acid is thus brought into a soluble state in the form of oxalate of potash, and may be precipitated by a neutral solution of lime.

Oxalic acid, as met with in commerce, frequently contains *tartaric acid* and *sulphate of potash*. The former is detected by digesting a portion of the acid in a test tube with concentrated sulphuric acid; it should remain colorless; but if tartaric acid is present, it turns black, that acid being decomposed. The presence of sulphate of potash is indicated by a precipitate insoluble in nitric acid, produced on adding to a solution of the suspected acid a few drops of chloride of barium.

### *Hydrofluoric Acid.*

When this acid exists in aqueous solution, it is quantitatively estimated, by rendering the liquid alkaline by ammonia, and precipitating the hydrofluoric acid in the form of fluoride

of calcium by the addition of chloride of calcium: the precipitate, which is gelatinous, is washed on the filter with hot distilled water, and then with acetic acid, to remove any carbonate of lime which may have formed during the process of filtration. The composition of the ignited salt is

|                      |     |      |     |       |
|----------------------|-----|------|-----|-------|
| One equivalent of Ca | ... | 20.0 | ... | 51.68 |
| One do. of Fl        | ... | 18.7 | ... | 48.32 |
| <hr/>                |     |      |     |       |
| One do. of CaFl      | ... | 38.7 |     | 100   |

The fluorine in soluble fluorides may be determined in the same manner, the bases being estimated in the filtrate according to the usual rules. Insoluble fluorides may be analyzed in two ways.

1. *Decomposition by Sulphuric Acid.*—The fluorine in this process is estimated *indirectly*. A weighed quantity of the fluoride, finely pulverized, is heated in a platinum capsule with concentrated sulphuric acid; the fluorine escapes in the form of hydrofluoric acid gas, and the excess of sulphuric acid is finally expelled by raising the heat to ignition. From the weight of the resulting sulphate the quantity of metal in the base is calculated; that of the fluorine is indicated by the loss of weight. Should the substance analyzed contain more than one base, the resulting sulphates must be submitted to further analysis, before a calculation can be made of the amount of fluorine present in the substance.

2. *Conversion of the Fluorine into Fluoride of Silicium.* *Wöhler's process.*\*—The weighed substance is intimately mixed with pure silica, unless it already contains some; the mixture is placed in a small flask, which can be weighed on the balance; very concentrated sulphuric acid, which has been boiled, is added, and the flask quickly closed with a cork, through which a small tube, filled with fused chloride of calcium, and drawn out to a fine point, passes. The whole apparatus is now weighed, and then exposed to a proper heat, as long as gaseous fluoride of silicium is evolved. The last portions are removed by exhaustion under the air-pump. The loss of weight which it experiences is fluoride of silicium, from which the amount of fluorine is calculated. 1.395 parts of fluoride of silicium are formed for each part of fluorine. To

\* Poggendorff's Annalen, vol. xlviii.; and Chem. Gaz., vol. iii. p. 504.

test this method, the author estimated the amount of fluorine in fluor spar, and the results were accurate to the first decimal place. To avoid the use of the air-pump, *Fresenius* modifies the apparatus by adding a second tube, closed with a waxed stopper, the lower end reaching nearly to the bottom of the flask; the last traces of gas may, with this arrangement, be removed from the flask by simple suction: for which purpose a suction tube is applied, filled with dry cotton at the lower end, and with moist cotton in the centre. Fig. 17 shows the apparatus arranged for this purpose. The above

Fig. 17.



process is well adapted for the separation of fluorine from the silicates.

Another method, proposed by *Berzelius* and modified by *Regnault*, is the following: the finely levigated powder is kept for some time in a state of fusion, with four times its weight of carbonate of soda: it is then extracted with boiling water, and the filtered solution is mixed with a solution of carbonate of zinc in ammonia, and evaporated to dryness. By digesting the dry residue with boiling water, a solution is obtained which contains the whole of the fluorine in the form of fluoride of sodium, in conjunction with carbon-

bonate of soda. It is carefully neutralized with hydrochloric acid, and the carbonic acid completely removed by allowing to stand for some hours under a bell jar by the side of a vessel containing solution of caustic potassa. The hydrofluoric acid is finally precipitated and estimated in the form of fluoride of calcium.

Where the fluoride to be analyzed contains water, the amount of that substance cannot be estimated by simply heating the fluoride, since the simultaneous action of the air and the water sometimes effects a partial decomposition of the fluoride, and a portion of hydrofluoric gas escapes along with the vapor of water. In such cases the analysis is performed as follows. The joint amount of water and fluoride is first determined by heating a known weight of the substance with concentrated sulphuric acid in the manner above described; a



fresh portion of the compound is then mixed in a little glass retort with about six times its weight of finely pulverized and recently ignited protoxide of lead; the mixture is covered with a layer of oxide of lead; the retort is weighed, and heat is then applied, gentle at first, but gradually increasing to redness; aqueous vapor, unaccompanied with the slightest trace of hydrofluoric acid gas, escapes. The retort is allowed to cool; it is then weighed again, and the amount of water calculated from the loss which it has sustained. By the first operation the joint amount of water and fluorine has been learnt; and we have only now to deduct from that amount the quantity of water, indicated by the second experiment, to find the quantity of fluorine in the substance under examination.

*Separation of Fluorides from Phosphates.*—The process of *Berzelius* as modified by *Regnault*, which we have described above, for separating fluorides from silicates, may also be employed when phosphates also are present. In this case the solution filtered from the silicic acid will contain phosphate of soda in addition to fluoride of sodium and carbonate of soda. It is analyzed as follows: it is rendered ammoniacal, and mixed in a glass flask which can be closed air-tight with a solution of chloride of calcium; the precipitate which is produced consists of fluoride of calcium and phosphate of lime. It is washed with the proper precautions, dried, ignited, and weighed; it is then treated in a platinum crucible with concentrated sulphuric acid, and heated until the whole of the hydrofluoric acid is expelled. The residue is treated with alcohol in which sulphate of lime is insoluble, and the phosphoric acid dissolved in the alcohol is precipitated and estimated as pyrophosphate of magnesia. The amount of fluorine originally present in the mixed precipitate of fluoride of calcium and phosphate of soda is learnt by the loss of weight sustained by the action of the sulphuric acid.

### *Hydrochloric Acid.*

The quantitative determination of this acid is effected by precipitating its chlorine in the form of chloride of silver; for the composition of this salt, and for the precautions to be observed in its precipitation, the student is referred to p. 306. If hydrochloric acid alone is present in aqueous solution, it may be estimated in the form of sal ammoniac by adding ammonia

in excess, evaporating the solution to dryness, and performing the exsiccation of the residue in the water bath.

Soluble chlorides are analyzed by first precipitating the chlorine by nitrate of silver, and then, after removing the excess of the silver salt from the filtrate by hydrochloric acid, estimating the amount of base or bases by the ordinary processes.

The analysis of the compounds of chlorine with *tin* and *antimony* is performed in a somewhat different manner. If a solution of nitrate of silver were added to a solution of perchloride of tin, there would be precipitated, besides chloride of silver, a compound of peroxide of tin with oxide of silver, which would vitiate the result. It is necessary, therefore, to remove the base from the solution before attempting to precipitate the electro-negative element; this is done by passing through the solution, contained in a flask which can be corked, a stream of sulphuretted hydrogen, and, when it is saturated, allowing it to repose for a considerable time; the sulphuret of tin is filtered off as soon as it is completely subsided, and the excess of sulphuretted hydrogen removed from the filtrate by mixing it with a solution of sulphate of copper;—this is indispensable; otherwise, on the addition of nitrate of silver, a precipitate both of chloride and of sulphuret of silver would take place. The excess of sulphuretted hydrogen being removed, the solution is precipitated by nitrate of silver in the usual manner. In the case of chloride of antimony, it is unnecessary to remove the base previous to determining the chlorine; but the precaution must be taken of mixing the solution with a sufficient quantity of tartaric acid to prevent the formation and precipitation of a basic salt.

Such chlorides as are insoluble, or only sparingly soluble, in water, but soluble in nitric acid, are dissolved in the latter menstruum, the solution diluted with water, and precipitated by nitrate of silver in the usual manner.

*Analysis of Chlorides insoluble in Water and in Nitric Acid.*—This may be performed in three ways:—1st, by reducing them to the metallic state by ignition in a stream of dry hydrogen gas; 2d, by fusion with alkalies; and 3d, by digestion with caustic potash.

1st. *By Reduction.*—The apparatus, Fig. 9, p. 272, may be employed. The chloride to be analyzed (chloride of lead for instance) is accurately weighed in the little porcelain cru-

cible *d*, a stream of dry hydrogen gas from the bottle *a* is conducted over it, and the crucible is then heated to redness by means of a spirit lamp, the heat required being somewhat greater than in the reduction of oxides. When hydrochloric acid gas ceases to be disengaged, which is known by fumes ceasing to be produced when a feather or glass rod moistened with ammonia is held near the tube of the crucible cover, the crucible is allowed to cool and again weighed; the loss of course indicates the amount of chlorine.

2d. *By Fusion with Alkalies*.—The chloride to be analyzed (chloride of silver, for instance) is mixed in a porcelain crucible with three parts of a mixture of carbonates of potash and soda, and heated till the mass enters into fusion, and effervescence ceases; it is then allowed to cool, and the mass treated with water. The silver remains undissolved in a state of very fine division. It is filtered, washed, ignited, and weighed. The chlorine in the filtrate, representing that in the compound analyzed, is determined as chloride of silver. *Gmelin* decomposes chloride of silver in the following manner:—He fills a crucible almost to the top with an intimate mixture of three parts of the chloride and seven of *colophony*; he then exposes it to a gentle heat, when the resin burns with a green flame, owing to the hydrochloric acid generated from the chlorine of the chloride and the hydrogen of the resin; a stronger heat is then given to fuse the silver, a little borax is added, and the crucible tapped gently once or twice to facilitate the union of the silver. This process was first proposed by *Mohr*.

3d. *By Digestion with Caustic Potash*.—This method is particularly applicable to the analysis of *protochloride of mercury*. The solution filtered from the metallic protoxide is acidulated with nitric acid, and precipitated with nitrate of silver. The protoxide of mercury may be dissolved in aqua regia, and determined by one of the methods described page 330; or a fresh portion of the protochloride may be taken and treated with hydrochloric acid and protochloride of tin, as directed page 315. *Dr. Gregory*\* decomposes chloride of silver by digestion with caustic potassa, and has recommended it as a convenient method of preparing pure oxide of that metal. His method is to mix well the moist chloride with a

\* Proceedings of the Chemical Society, No. 4.

sufficient quantity of caustic potash, specific gravity 1.25, and to boil for about ten minutes, or until the chloride has become converted into a jet black powder. If any white specks are observed, the mixture must be rubbed in a mortar, and again boiled. When the decomposition appears complete, the oxide is to be carefully washed by decantation with hot water until all the saline matter has been removed; it is thus obtained as a heavy black powder. It is worthy of remark that, if the chloride of silver has once been dried, it is only decomposed by boiling for a long time with caustic potash, and then with great difficulty. According to *Dr. Meurer*,\* the above process does not succeed when the experiment is made on several ounces.

*Levol* modifies the process thus:—He places the chloride in a solution of caustic potassa, in which some *sugar* is dissolved, and then boils. The silver is quickly reduced by the sugar, carbonic acid being evolved, and is brought to the state of fine powder, which is easily washed.

The amount of chlorine in many metallic chlorides may be determined *indirectly* by converting them into sulphates, for which purpose the compound is treated with concentrated sulphuric acid and heated till all the hydrochloric acid gas and the excess of sulphuric acid are expelled; the amount of chlorine is inferred from the loss of weight.


*Quantitative Estimation of Free Chlorine.*—Since chlorine gas is absorbed both by water and mercury, it cannot be estimated by the ordinary methods of measuring gases without very great difficulty. The determination of the gas is best effected by leading it into ammonia, a portion of which it decomposes, muriate of ammonia being formed, and nitrogen gas set free. The operation is conducted as follows:—The substance from which the gas is to be liberated is introduced into the flask A, Fig. 18. This flask is provided with a well-fitting cork, through which two tubes are inserted, one of which, *b*, communicates with a Wolfe's bottle, B, containing a sufficient quantity of ammonia to absorb all the chlorine that can be evolved; the other tube, *d*, is a safety tube, and is surmounted by a funnel, through which any required liquid may be poured into the flask. The Wolfe's bottle, B, is connected with a second bottle, C, also containing ammonia,

\* *Archiv. de Pharmacie.*



further to prevent the possibility of any chlorine escaping absorption. This second bottle is provided with a long tube, surmounted by a funnel, in which, during the operation, there

Fig. 18.



is placed some cotton moistened with ammonia. Heat is applied to the flask A, and, when the disengagement of chlorine has ceased, all the gas with which the flask is filled, as well as that in the connecting tubes, is expelled, and conducted into the ammonia, by pouring through the funnel of the safety tube (which during the experiment is filled with a strong solution of common salt) a concentrated solution of bicarbonate of potash until it is filled. The extremity of the tubes leading from the flask to the first Wolfe's bottle, and from the first Wolfe's bottle to the second, must not quite reach the surface of the ammonia, to avoid the danger of a sudden absorption, and the consequent rushing of the ammonia into the evolution flask. The operation being ended, the ammonia and the moistened cotton are transferred to a beaker acidulated with nitric acid, and the amount of chlorine condensed determined by the nitrate of silver. The disengagement of the chlorine throughout the experiment must be very slow, otherwise a complete decomposition of the ammonia might not take place, and a portion of chlorine may be liberated in company with the nitrogen. If the chlorine is in aqueous solution, it may be determined by the same decomposition, for which purpose it is only necessary to add excess of ammonia, and proceed with the solution in the usual manner.

According to *Buchner*,\* the amount of chlorine in chlorine water may be determined by agitating it with a weighed amount of metallic mercury, taking care to use such an excess, that a portion of the fluid metal separates in the free state, in order that the whole of the chlorine shall be in the form of the insoluble subchloride; the quantity of chlorine is found by collecting, drying, and weighing the calomel and unaltered mercury, and comparing the weight with that of the metal when introduced into the solution. The same method may be employed to test a solution of chlorine for hydrochloric acid, the chlorine being so entirely removed, that the presence of hydrochloric acid may be ascertained by the acid reaction of the liquid, and its amount determined in the usual manner.

*Chlorimetry, or Determination of the Value of Chloride of Lime.*

1. *Modification of the Method of Gay-Lussac.*—This is founded on the conversion of calomel into chloride of mercury by the chlorine set free from the bleaching powder. A fluid is prepared holding in suspension a known quantity of subchloride of mercury; into this a measured quantity of the solution of chloride of lime to be tested is poured until the liquid becomes perfectly clear, the quantity of chlorine consumed, and, consequently, the value of the bleaching powder is calculated from the number of divisions of the burette which have been required to render the turbid mixture clear.

*Preparation of the Standard Mercurial Test Liquor.*—It is based on the following considerations:—

Every 236.64 grains of subchloride of mercury require 35.5 grains of chlorine to convert them into chloride; every 58.47 grains of common salt (which is the chloride most convenient for the purpose) contain 35.5 grains of chlorine, or 164.7 grains contain 100 grains of chlorine.

Let 50 measures of a solution of a protosalt of mercury, the proto-nitrate, for example, be introduced into the graduated burette, Fig. 6, and then poured off into a beaker and diluted with 4 or 5 ounces of water; then let 82.35 grains of common salt be dissolved in water and introduced into the burette so as to fill exactly 100 measures. Let this solution be poured

\* *Buchner's Report*, xxxi. p. 164.

gradually into the solution of the protonitrate, which during the time should be kept warm by immersion in a basin of hot water, until the last drop added no longer produces a precipitate. Let us suppose that 20 measures have been required; now, as 100 measures of the saline solution contain 82.35 grains of chloride of sodium = 50 grains of chlorine; the 20 measures must contain 16.47 grains = 10 of chlorine. We consequently arrive at the conclusion that 50 measures of the protonitrate of mercury require 10 grains of chlorine to convert the salt into subchloride, and if the 50 measures are increased to 100 by dilution with water a solution is obtained, every 10 divisions of which are equivalent to 1 grain of chlorine, and every single division of which represents one-tenth of a grain; any quantity of the test liquor may thus be easily prepared.


*Method of testing the Bleaching Powder.*—100 grains of the specimen, selected from different parts of the sample, and well mixed together, are rubbed in a mortar with a little water, and transferred to a tube graduated into 200 equal parts, each part corresponding with a division of the burette; the mortar is rinsed out with a little more water, the washings transferred to the graduated tube, the whole well agitated, and the mark at which the solution stands in the tube is accurately noted. Suppose the whole to occupy 150 measures. The burette is now filled to 100 with the mixture. Next, 100 measures of the standard protonitrate of mercury are poured into a beaker and diluted with water, excess of common salt is added to the solution, which is then acidified with pure hydrochloric acid. The well-agitated solution of chloride of lime is then dropped gradually into the newly formed calomel in the beaker, until it is perfectly clear, by which it is known that the whole of the calomel has been converted into corrosive sublimate. It must be constantly stirred while the bleaching solution is being added, and it is essential that it should remain acid during the whole time. Now, from what has been explained above, it is evident that the number of divisions of the bleaching solution that have been consumed in rendering the turbid mercurial salt clear, must correspond with 10 grains of chlorine. Suppose 65 measures were required, then the value of the specimen is found very simply by the following proportion:—

$$\text{As } 65 : 10 :: 150 : x$$

$x = 23.07$  = the quantity of chlorine in 100 grains of the bleaching powder.

It is evident that any other proportions than those here given may be employed, both in making the standard mercurial solution and in performing the analytical process. The above must be regarded as merely an illustration of the principles of the operation. This method is found to yield very accurate results: there is, perhaps, one disadvantage attending it, which is, that the solution of protonitrate of mercury is somewhat liable to change, and give rise to the formation of an insoluble basic salt, which would, of course, interfere with its accuracy as a test. From this objection the methods next to be described are free.

2. *Gay Lussac's Method by Arsenious Acid.*—When arsenious acid, water, and chlorine are brought into contact with each other, a reaction takes place, the result being the formation of hydrochloric and arsenic acids, thus:—



every equivalent (or 99 parts) of arsenious acid requires two equivalents (or 71 parts) of chlorine; 100 parts of chlorine are therefore required to peroxidize 140 parts of arsenious acid. To prepare a standard solution of this acid 280 grains are dissolved in hydrochloric acid, the quantity employed being exactly 20 times the capacity of a large dropping tube; which, therefore, when immersed into the bottle containing the solution, as shown in Fig. 19, will remove just 14 grains



Fig. 19.

of arsenious acid = 10 grains of chlorine; a mark is made in the neck of the dropping tube to regulate the quantity of solution admitted. When the chlorimetric assay is about to be made, 50 grains of the bleaching powder are prepared in the manner already described, and the burette is filled to the 100th division with the solution. A measure of the arsenious solution is then taken from the bottle with the dropping tube, transferred to a beaker diluted with water, and colored blue by the addition of a few drops of solution of indigo. The bleaching liquid is then gradually and carefully dropped into the arsenical solution, which is all the time well stirred, until the blue tinge is entirely




destroyed. This shows that the conversion of the arsenious into arsenic acid is complete, and, consequently, that 10 grains of chlorine have been consumed, and, as before, the value of the bleaching powder is ascertained by the rule of simple proportion; thus, suppose 90 measures have been consumed, then

$$\text{As } 90 : 10 :: 100 : x$$

$x = 11.11$  = the quantity of chlorine in 50 grains of the bleaching powder, or 22.22 per cent.; or still more simply, as each measure of the burette corresponds with half a grain of bleaching powder, and as the number of measures consumed contain ten grains of chlorine, we find at once the percentage amount of chlorine in the example by dividing 2000

by the number of measures required; thus  $\frac{2000}{90} = 22.22$ .


3. *Otto's Method by Protosulphate of Iron*.—When protosulphate of iron, water, chlorine, and free sulphuric acid are brought into contact, a reaction takes place, resulting in the formation of hydrochloric acid and persulphate of iron; thus



every two equivalents, or 152 parts of anhydrous, or 278 parts of crystalized protosulphate of iron, require one equivalent, or 35.5 parts of chlorine; 100 grains of chlorine are therefore required to convert 783.1 grains of crystalized protosulphate of iron into persulphate. To prepare the iron salt for these experiments, *Fresenius* directs that iron nails free from rust be dissolved in dilute sulphuric acid, finally with the application of heat; the solution is filtered while still warm, into about twice its volume of spirits of wine; the precipitate which is produced consists of protosulphate of iron with 7 equivalents of water. It is collected on a filter,edulcorated with spirits of wine, spread upon a sheet of blotting paper, and allowed to dry in the air until it has completely lost the smell of spirits of wine: the dry salt must be kept in a well-closed bottle. To perform the chlorimetric assay, 78.3 grains of the proto-sulphate are dissolved in about two ounces of water, and the solution strongly acidulated with sulphuric acid; 50 grains of the bleaching powder are then prepared as before directed, and the burette filled with the solution, which, after being well agitated, is added drop by drop to the solution of the iron salt until complete

peroxidation has taken place; this is known by solution of red prussiate of potash no longer striking a blue precipitate. The best way of testing the solution from time to time, is to cover a large white plate with drops of the red precipitate, and, as the operation draws towards an end, to convey a minute drop from the solution, at the end of a small stirring rod, to one of the drops; the process is complete when prussian blue ceases to be formed, a green color being produced in its stead. The number of divisions of the burette which have been consumed is now noted; this corresponds with ten grains of chlorine, that being the quantity required for the peroxidation of 78.3 grains of crystalized protosulphate of iron. The calculation is precisely the same as in the last method.

4. *By Yellow Prussiate of Potash.*—When ferrocyanide of potassium is brought into contact with free chlorine, a reaction takes place, resulting in the production of *ferricyanide* of potassium and chloride of potassium. Thus



every two equivalents, or 368 parts of anhydrous, or 422 parts of crystalized ferrocyanide of potassium require one equivalent, or 35.5 parts of chlorine; 100 grains of chlorine, therefore, are required to convert 1188.7 grains of crystalized yellow prussiate of potash into red prussiate, or 118.87 grains correspond to 10 grains of chlorine. The experiment is conducted in precisely the same manner as before, and as soon as the whole of the ferrocyanide is converted into ferricyanide, the mixture ceases to give prussian blue with a solution of peroxide of iron.\*

\* This method, which is given by Mr. Parnell, see "Elements of Chemical Analysis," p. 416, is ascribed to Mr. J. Mercer, of Oakenshaw. This gentleman also avails himself of the oxidizing powers of a mixture of ferricyanide of potassium and caustic potash, in effecting the bleaching of indigo. The manner of applying the discharge may be arranged to suit the conditions of the calico-printer; but the experiment for illustration may conveniently be made by impregnating indigo blue calico with a solution of the red prussiate, and dipping it into a weak solution of the alkali. The nature of the reaction is as follows:—

One equivalent of *Ferricyanide* of Potassium,  $\text{K}_3\text{Cfy}_2$ , differs from two equivalents of *Ferrocyanide*  $2(\text{K}_2\text{Cfy})$ , by containing one atom less potassium. When potash is presented to the former, this deficient atom of potassium is supplied; but the affinity is not strong enough to liberate the oxygen. When, however, a second body, having an affinity for oxygen, such as litharge or indigo, is presented to the potash and ferricyanide, this second affinity, acting in a


5. *By a Standard Solution of Sulphate of Indigo.*—This method is now very rarely employed, in consequence of the alteration which the indigo solution undergoes by keeping, and of the complex nature of the action which chlorine exerts on the coloring principle. The indigo solution was prepared by dissolving indigo of commerce in Nordhausen sulphuric acid, and diluting the deep blue compound formed until a certain volume was exactly decolorized by an equal volume of dry chlorine. This was effected by filling a bottle with dry gas, perfectly pure, and causing it to be absorbed by a dilute solution of caustic potassa; the indigo solution was then diluted till 100 measures were exactly decolorized by 100 measures of the chlorinated potash. The method being now but little used, further details may be dispensed with. From all the acids which have hitherto been treated of, hydrochloric acid is easily separated by nitrate of silver; the compound to be examined should be dissolved in nitric acid, the whole of the chlorine is thus obtained in the form of chloride of silver, and the other acids may, generally speaking, be determined in the filtrate by the usual methods.

### *Hydrobromic Acid.*

When present in a solution in the form of hydrobromic acid, bromine is determined by precipitating it in the form of bromide of silver, precisely in the same manner as chlorine. Like the chloride, the bromide of silver is insoluble in water and in nitric acid; it is yellowish white when precipitated, but it changes color when exposed to the light. It is decomposed by chlorine, bromine being separated. When heated it fuses, solidifying, on cooling, into a yellow horny mass. Its composition is

|                      |     |        |     |       |
|----------------------|-----|--------|-----|-------|
| One equivalent of Br | ... | 78.26  | ... | 42.01 |
| One do. of Ag        | ... | 108.00 | ... | 57.99 |
| <hr/>                |     |        |     |       |
| One do. of AgBr      | ... | 186.26 |     | 100   |

different direction, withdraws the oxygen, and allows the potassium to unite with the compound radical ferrocyanogen, thus



the decomposition being of the same kind when any organic matter is substituted for the oxide capable of further oxidation, soda and ammonia may be substituted for potash in the above decomposition, producing the oxidation, or discharging the indigo. *Mem. Chem. Soc., Part 21.*

The analysis of bromides may be effected in the same manner as that of the corresponding chlorides. The indirect method is, in many cases, the most convenient; a weighed quantity of the compound is decomposed by heating it in a porcelain capsule, with concentrated sulphuric acid; the amount of metal is calculated from the weight of the resulting sulphate, and that of the bromine from the loss sustained. The analysis of those bromides, the bases of which are capable of being precipitated by sulphuretted hydrogen, may be performed by that reagent. Free bromine, in aqueous solution, is determined in exactly the same manner as free chlorine.

*Separation of Bromine from Chlorine.*—Two methods of performing this analysis are known, a *direct* and an *indirect* method. The former is based on the solubility of bromide of barium in absolute alcohol, and the insolubility of chloride of barium in the same menstruum. The two substances are precipitated together out of their solution, by nitrate of silver; the precipitates, after having been washed and dried, are reduced by being brought into contact with zinc and dilute sulphuric acid, there are thus formed bromide and chloride of zinc, which are dissolved in the acid liquor; on the addition of excess of baryta water the zinc is precipitated, together with sulphate of baryta in the form of hydrated oxide; the filtered solution contains bromide and chloride of barium, it is evaporated to dryness, and the dry mass treated with absolute alcohol, which, as above stated, dissolves only the bromide of barium. The bromine is separated from the barium in the alcoholic solution, and the chlorine from the barium in the solution obtained on treating the residual mass with water, by one of the methods already given.

This method does not give absolutely accurate results. The *indirect* method is based on the decomposition of bromide of silver by chlorine gas. The bromine and chlorine are, as before, precipitated together by a solution of nitrate of silver, and the precipitate having been washed, dried, fused, and very accurately weighed, is introduced into a bulbed tube of hard glass, the exact weight of which has also been noted. The tube is connected with an apparatus for evolving chlorine, and a current of that gas dried by passing through chloride of calcium is caused to traverse the tube, to which heat is at the same time applied sufficient to keep the mixed silver salts in a state of fusion. After the operation has been continued



for about half an hour, the tube is allowed to cool, and the chlorine in its interior having been replaced by atmospheric air it is again weighed; the process is again repeated, and the tube a second time weighed; should the second weight correspond with the first, the analysis is complete; if not, the process must be again repeated till the two last weighings are absolutely alike.

The amount of bromine originally present is calculated from the diminution in the weight of the mixture, the bromide of silver being now replaced by chloride of silver. The calculation is made thus:—Suppose the weight of the mixed chloride and bromide to have been 100 grains, and, after the experiment, suppose the weight to have decreased 5 grains. The equivalent of bromide of silver is 186.26, that of chloride of silver 143.5; then, as 42.76 (the difference between the respective equivalents of bromide and chloride of silver) : 186.26 (the equivalent of bromide of silver) :: 5 (the difference in weight found in the experiment) :  $x$ ;  $x=21.78$  = the quantity of bromide of silver in the mixture analyzed.

### *Hydriodic Acid.*

Iodine, when present in a solution in the form of hydriodic acid, and in the absence of bromine and chlorine, is best precipitated in the form of iodide of silver by solution of nitrate of silver. This salt, which when newly precipitated is of a bright yellow color, has many properties in common with the corresponding chlorine and bromine compounds. Thus, it is insoluble in water and in dilute nitric acid, and soluble, though with great difficulty, in ammonia; like bromide of silver, it is decomposed by chlorine; it also blackens when exposed to the light, and, when heated, it fuses into a horny mass, without undergoing decomposition. Its composition is

|                     |     |        |     |       |
|---------------------|-----|--------|-----|-------|
| One equivalent of I | ... | 126.36 | ... | 53.91 |
| One do. of Ag       | ... | 108.00 | ... | 46.09 |
| <hr/>               |     |        |     |       |
| One do. of AgI      | ... | 234.36 |     | 100   |

In the presence of hydrobromic and hydrochloric acids, iodine may be very accurately estimated in the form of *protiodide of palladium*, by means of protochloride of palladium. The precipitate, which is of a deep brown-black color, is allowed to settle for some hours; it is then collected in a tared

filter, dried at a temperature below the boiling point of water, or, what is still better, in vacuo, over sulphuric acid and weighed. Its composition is

|                     |     |        |     |       |
|---------------------|-----|--------|-----|-------|
| One equivalent of I | ... | 126.36 | ... | 70.84 |
| One do. of Pd       | ... | 53.27  | ... | 29.66 |
|                     |     |        |     | <hr/> |
| One do. of PdI      | ... | 179.63 |     | 100   |

Iodine may also be estimated by the process recommended by *M. Duflos*, viz: by precipitating it in the form of protiodide of copper by a solution of sulphate of copper in concentrated sulphurous acid; the precipitate may either be collected on a filter, washed, and determined as protiodide of copper, or it may be dissolved in dilute nitric acid, precipitated by nitrate of silver, and weighed as iodide of silver. This method is well adapted to the separation of iodine from chlorine, in cases where the presence of chlorine is immaterial. *M. Sarphati*\* recommends a solution of perchloride of copper in dilute hydrochloric acid; a solution composed of 1 part of crystalized sulphate of copper, and  $2\frac{1}{2}$  of crystalized sulphate of iron.

Iodine is sometimes determined by the *indirect* method, viz: by converting the base or bases with which it is combined into sulphates, by digestion with sulphuric acid in a porcelain capsule, and calculating the quantity of iodine from the loss. Metallic iodides, which are insoluble in water, may be decomposed by ignition with carbonates of soda, iodide of sodium is obtained on treating the fused mass with water, from which the iodine may subsequently be precipitated by nitrate of silver. The base or bases are found in the insoluble residue either as carbonates or oxides. Metallic iodides may also be decomposed by boiling with caustic potash.

Iodine in a free state, in aqueous solution, cannot be determined in the same manner as chlorine and bromine, viz: by the decomposition of ammonia, since the contact of iodine with ammonia gives rise to the formation of iodide of nitrogen, which is not decomposed by excess of ammonia. In order to estimate the iodine under these circumstances, it is dissolved in excess of caustic potash, the solution, which must be colorless, treated with nitric acid, and precipitated by

\* Ann. der Chem. und Pharm., xxxix. p. 254.

nitrate of silver; the washed and dried precipitate is ignited, by which the small quantity of iodate of silver formed, is converted into iodide.

*Separation of Iodine from Chlorine.*—Of all the methods which have been proposed, none are so convenient or easy of execution as that of precipitating the iodine in the form of protiodide of palladium. The separation is complete, and the chlorine in the filtrate may be precipitated by nitrate of silver. Should bromine likewise be present, it is precipitated with the chlorine in the form of bromide of silver; the mixed silver salts are analyzed by the method described in the last section, viz: by converting the bromide of silver into chloride by heat, in a current of dry chlorine gas.

### *Hydrocyanic Acid.*

This acid, when in a free state, is best estimated by precipitating it in the form of cyanide of silver. It falls as a white curdy mass, which is insoluble in water, and in dilute nitric acid, but soluble in ammonia. Unlike the chloride, bromide and iodide of silver, it does not change color when exposed to light, neither will it bear ignition without being decomposed. It may, however, be dried at  $212^{\circ}$ , without alteration. For its composition, see page 307. Soluble cyanides may also be precipitated by nitrate of silver; insoluble cyanides, which do not readily dissolve in dilute nitric acid, may be analyzed by determining the amount of carbon and nitrogen which they contain by the methods of organic elementary analysis; or the amount of cyanogen may be determined in the indirect manner, by igniting the compound, and weighing the residue. *Smith*\* proposes to decompose and estimate hydrocyanic acid by means of chloride of lime, a process which occupies but a few seconds; the products are nitrogen gas and carbonate of lime. In some cases he prefers the employment of chloride of soda to chloride of lime, on account of the solubility of the compounds that are formed. The same method is applicable to the analysis of the salt of cyanogen, and also to that of the ferrocyanides.

The usual method of analyzing the latter, when free from alkali, is to fuse them, in small portions at a time, at an intense heat, in a porcelain crucible, with nitre. The bases

\* In a paper read before the Royal Society, Jan. 29th, 1846.

which remain are separated from each other by the ordinary processes, and the cyanogen is estimated in a fresh portion by the direct determination of the carbon and nitrogen. Alkaline ferrocyanides are decomposed by boiling sulphuric acid, nitric acid, or aqua regia, and the evaporated mass treated as usual for the bases. The reason why it is inadmissible to decompose them by fusion with nitre is, that an explosion would certainly result from the contact of the nitre with the fused salt. Those alkaline double cyanides, which resist decomposition by boiling concentrated acids, are kept for a long time ignited in the air, or in contact with oxide of copper; and, should the ferrocyanide under examination contain a volatile metal, the latter must be determined by dissolving a separate portion of the compound in caustic potassa, or in hydrochloric acid, and precipitating the metal with sulphuretted hydrogen.

A method of analyzing compounds of cyanogen, founded on the action of *iodine*, has been proposed by *M. V. Gerdy*.<sup>\*</sup> It was found by this chemist, that, in many of the soluble combinations of cyanides, the cyanogen may be substituted, atom for atom, by iodine; so that from the amount of solution of iodine employed and decolorized before its action on starch becomes evident, it is possible to calculate with the greatest ease, and in a few moments, the amount of the cyanogen contained in the liquid, and the quantity of metal with which it was combined. *Gerdy* has thus analyzed cyanide of potassium with great accuracy. He states, also, that the method is equally applicable to the analysis of cyanide of mercury; of the double compound of cyanide of potassium and cyanide of silver, which contains eight atoms of cyanogen to one of silver; of cyanide of silver, dissolved in ferrocyanide of potassium; of cyanide of potassium and copper; of cyanide of gold dissolved in cyanide of potassium, &c. The analysis of cyanide of gold is, he says, not so easy of execution, according to this method, as is the case with the other compounds above mentioned, and requires some care. The reaction is here of a different description; for, while eight atoms of cyanogen are required to dissolve one atom of gold, viz: four atoms combined with the gold, and four with the potassium, four atoms of iodine alone suffice to effect the decomposition. This peculiarity he considers to be owing to the

\* Comptes Rendus, Jan. 2, 1843.



cyanide of gold not being acted on by the iodine, and being only precipitated entirely when the iodine has decomposed the whole of the cyanide of potassium.

*Separation of Cyanogen from Chlorine, Bromine, and Iodine.*

The best method is to precipitate all three of the electro-negative elements with nitrate of silver, and, having carefully collected, washed, and dried the precipitate in the water bath, to determine the amount of carbon and nitrogen yielded by the mixture by the ordinary methods of organic analysis. From the numbers obtained, the amount of cyanide of silver is calculated, and the proportion of iodine, bromine, and chlorine is inferred from the difference.

*Fresenius* gives the following method of determining the relative proportions of hydrocyanic and hydrochloric acids, when together present in a solution. It is founded on the circumstance, that percyanide of mercury is not decomposed by nitrate of silver. The solution is divided into two equal parts. One portion is precipitated with nitrate of silver, and the mixed precipitate of chloride and cyanide of silver weighed; the other portion is mixed with peroxide of mercury, and the mixture agitated until perfectly inodorous. The fluid is then filtered off, the filtrate subsequently precipitated with nitrate of silver, and the precipitate weighed. The difference between the respective weights of the two precipitates indicates the amount of cyanide of silver contained in the precipitate in the first portion.

*Nitric Acid.*


This acid is best estimated by the *indirect* method.

1. *Estimation of by Hydrate of Baryta.*—To the solutions containing the acid in a free state, water of barytes is added, until it begins to acquire an alkaline reaction; the whole is then evaporated to dryness. The dry mass is redissolved in water, and the solution being filtered off from the carbonate of baryta, which may have formed during the evaporation, is precipitated by the addition of dilute sulphuric acid. The quantity of nitrate of baryta is calculated from the weight of the sulphate precipitated, and from this is deduced the weight of the nitric acid originally present in the solution.

2. *By the Process of Acidimetry.*—This method, which is based on the determination of the amount of carbonic acid

expelled by a weighed quantity of the acid under examination, is best performed with the alkalimetric apparatus of *Fresenius* and *Will*, see annexed figure. It being indispensable

Fig. 20.



that the bicarbonate employed for this experiment should be entirely free from neutral or sesquicarbonate (though its perfect freedom from any admixture of sulphate and chloride is not of consequence). *Fresenius* and *Will* recommend to purify the bicarbonate of soda of commerce in the following manner.\* Half a pound or a pound is reduced to a uniform powder, and a portion of it first tested with chloride of mercury; if the solution becomes merely turbid or milky at first, it is tolerably free from carbonates, the powder is then put into a glass jar and covered with the same amount of cold rain water; it is al-

lowed to stand for 24 hours, with frequent stirring. The salt is then placed upon a funnel, the tube of which is stopped with loose cotton, so as to allow the ley to drop off. The salt is then washed several times with small quantities of cold rain water; what remains is generally pure, and adapted for acidimetric purposes. It is dried between some sheets of blotting paper, without the aid of heat, and kept for use in a well-closed glass jar. The operation is conducted as follows:—A portion of the fluid to be examined is carefully weighed into *b*; if the acid be concentrated, from four to eight times its amount of water should be added. A little glass tube is provided, capable of holding about 75 grains of bicarbonate of soda; it is filled nearly to the brim with the alkali, and, a silk thread being tied round its upper end, it is lowered down into *b*, so as to remain suspended perpendicularly when the flask is closed, the silk thread becoming fixed between the cork and the glass. The apparatus is then arranged as described page 245, and accurately weighed. When the operation is about to be commenced, the cork of the flask *b* is slightly loosened, so as to allow the little tube, together with

\* New Method of Alkalimetry and Acidimetry, p. 89. Edited by J. L. Bullock.

its silk thread, to fall into the acid, and immediately fixed again air tight. The evolution of carbonic acid commences instantaneously, and continues in a uniform and uninterrupted manner till the acid is completely neutralized. The operation may be accelerated by repeatedly shaking the apparatus. When no more bubbles of gas appear upon agitation, the flask *b* is placed up to its neck in hot water, and there left until the renewed evolution of gas has completely ceased; this is also promoted by agitating the apparatus. The wax stopper is then removed from *d*; the flask removed from the hot water, wiped dry, and suction applied to *e* until the carbonic acid is completely removed. The apparatus is allowed to cool, and again weighed; the amount of anhydrous acid in the sample examined is determined from the amount of carbonic acid evolved; every two equivalents of the latter indicate one equivalent of nitric acid. It is evident that this method applies to all acids capable of decomposing bicarbonate of soda, and, consequently, that it cannot be employed to determine nitric acid in the presence of any other free acid.

*Analysis of Nitrates.*—Those nitrates whose bases form with sulphuric acid compounds which are not decomposed by mere ignition, may be analyzed by heating them in a platinum crucible, with sulphuric acid, and, having expelled the excess of acid by feeble ignition, determining the quantity of nitric acid expelled by calculation from the weight of the sulphate obtained. Nitrates which contain no water of crystalization may also be analyzed by simple ignition, nothing but pure metallic oxide being in most cases left; the amount of nitric acid is inferred from the loss of weight. If the salt to be examined be mixed with two or three times its weight of perfectly anhydrous borax, the decomposition is effected at a lower temperature, and without danger of deflagration. Hydrated nitrates are analyzed by determining the base in one portion, and the water and nitric acid in another, by the method of organic elementary analysis. Nitrates, the bases of which are precipitable by sulphuretted hydrogen, may be analyzed by removing the base by that reagent, excess of which should be avoided, and determining the amount of nitric acid in the filtrate by hydrate of baryta, in the manner described at the beginning of this section.

The analysis of those nitrates which are insoluble in water may be effected also by sulphuretted hydrogen. They should

be reduced to a state of minute division, and kept suspended in water while a stream of sulphuretted hydrogen is passed through the liquid.

From *baryta*, *strontia* and *lime*, nitric acid may be separated by mixing the solution with slight excess of sulphuric acid; and, in the case of lime and strontia, adding also alcohol, to render the precipitation more complete. Water of baryta is added to the fluid filtered off from the precipitate, until it is slightly alkaline; it is then evaporated to dryness on the water bath, redissolved in water, filtered, and the filtrate treated as above directed. Another method, which may be adopted for determining the amount of nitric acid in the nitrates, is to distil them in a retort, with sulphuric acid, and to collect the products in a receiver containing baryta water. The distillation is continued until fumes of sulphuric acid begin to make their appearance. Should the nitrate under examination contain an *iodide*, or *bromide*, or a *chloride*, the solution should be treated with sulphate of silver, previous to commencing the distillation, the precipitated iodide, bromide, or chloride of silver being removed by filtration, the solution should be mixed with a slight excess of carbonate of soda, and then the distillation with excess of sulphuric acid proceeded with.

*New Methods of estimating Nitric Acid. 1st. Method of Gossart.\**—This is founded on the oxidizing action of nitre under the influence of sulphuric acid. The reagents employed in analyzing crude nitre are—1st, an acid solution of proto-sulphate of iron; and, 2d, a very dilute solution of the ferricyanide of potassium. The analysis is performed as follows:—Into a flask with a long neck is poured a certain measured quantity of sulphuric acid, sp. gr. 1.704, and half that volume of a solution of saltpetre, containing about 150 grains per 30 cubic inches (10 grammes of refined saltpetre in a *demilitre*); a few drops of the solution of protosulphate of iron are then added from a graduated burette, and the mixture gently agitated; it becomes brown, suddenly clears again, and acquires a more or less deep straw color, the normal solution of saltpetre is cautiously added drop by drop, waiting each time till the liquid brightens; when the changes of color become less rapid, a gentle heat is applied, and, when they are no longer

\* Comptes Rendus, Jan. 4th, 1847.



perceptible, it is examined whether on taking out a few drops with a pipette they yield a blue color with the red prussiate of potash. When the blue color appears and no longer disappears on boiling the liquids, the number of divisions of the burette which have been employed is noted. A second examination, in which a great number of the trials may be dispensed with, will give an accurate result.

Let  $N$  be the number of divisions of the normal solution requisite to saturate completely a certain measure of the standard solution of refined nitre, 10 grammes of the saltpetre to be examined are then dissolved in a demilitre of water, and it is ascertained how many divisions of the normal solution of iron are required to saturate an equal quantity of the sample precisely in the same manner as when testing the solution of refined saltpetre; let  $N^1$  be the number of divisions required, then  $\frac{N^1}{N}$  gives the strength of the saltpetre under examination with great accuracy.


This process, which is applicable to the estimation of nitric acid as well as to the nitrates in general, may also, according to the author, be employed for determining the quantity of nitric acid contained in gun cotton.

For this purpose he directs the whole of the cotton to be oxidized with a mixture of sulphuric acid and peroxide of manganese: the liquid is filtered and decolorized with a few drops of solution of protosulphate of iron, which decomposes the whole of the sesquioxide of manganese before acting upon the nitric acid. In this manner a solution is obtained containing the whole of the nitric acid which existed in the pyroxyline, and the amount of which may be readily estimated.

2d. *Method of Pelouze*.\*—This is founded on the peroxidation of a protosalt of iron by the oxygen of the nitric acid, a solution of permanganate of potash being employed, as in *Marguerite's* experiments (see page 297), to indicate the completion of the oxidation. It is particularly adapted to the analysis of nitre. The operation is as follows:—It is first accurately determined how much pure nitrate of potash is requisite to peroxidize a known weight of iron dissolved in excess of hydrochloric acid. *Pelouze* found that 2 grammes

\* Comptes Rendus, Feb. 15th, 1847.

(30.88 grains) of pure iron (pianoforte wire) dissolved in a considerable excess of hydrochloric acid required from 1.212 to 1.220 gramme (from 18.7 to 18.8 grains); on an average, therefore, 1.216 gramme (18.77 grains) of pure nitrate of potash. He examined the nature of the gases given off in this reaction, and found them to consist of hydrochloric acid and deutoxide of nitrogen. Converting these numbers into equivalents, they correspond to 6 equivalents of iron and 1 equivalent of nitrate of potash: the acid of this last salt is decomposed, therefore, into deutoxide of nitrogen, which is disengaged, and into 3 equivalents of oxygen, which deprive the hydrochloric acid of 3 equivalents of hydrogen to form 3 equivalents of water and liberate 3 equivalents of chlorine, which produce with the 6 equivalents of protochloride of iron 3 equivalents of perchloride. These reactions will be better understood by putting them into an equation, thus:—



It will be observed, by the way, that this decomposition of nitrates by protosalts of iron in the presence of an excess of hydrochloric acid furnishes a good mode of preparing deutoxide of nitrogen. This decomposition being established, it occurred to *Pelouze* that it might be made the basis of a ready and simple method of analyzing the nitrates. He found that the presence of sulphates and chlorides in no way interfered with the decomposition in whatever proportion they were present, and there only, therefore, remained to be found a safe and ready method of determining, in the assay of an impure nitrate, the quantity of iron not peroxidized. Such a method has been described by *Marguerite* (see page 297). Suppose, for instance, that, having operated upon 30.88 grains of iron, and 18.77 grains of impure nitre, the mineral chameleon indicates that 3.088 grains of iron have not been peroxidized: it may be concluded that 30.88 grains minus 3.088 grains or 27.79 grains have been peroxidized: now, if the nitre had been pure, the whole 30.88 grains would have been peroxidized: we, therefore, have the proportion—

As 30.88 : 18.77 : : 27.79 : 16.89;

the 18.77 grains of impure nitre consequently contain 16.89 grains of nitrate of potash, or 90 per cent.

The following example will illustrate the practical details of the method. The specimen may be supposed to be taken

from a sample of the crude nitre of commerce as it is sent to the refiner.

30.88 grains of pianoforte wire are placed in a flask of the capacity of about 10 cubic inches, and on them are poured about 1500 grains of strong hydrochloric acid, the flask is closed with a cork furnished with a drawn out tube, and the iron dissolved at a gentle heat. When the whole is dissolved, 18.52 grains of the nitre under examination are introduced, the flask is immediately closed, and the liquid boiled; it becomes of a brown color; dense vapors of hydrochloric acid, mixed with deutoxide of nitrogen, issue from the orifice of the drawn out tube, and prevent the access of air. As soon as the liquor loses the brown color, it becomes yellow, and gradually brightens: after boiling for 5 or 6 minutes, and when the liquid has become perfectly transparent, the flask is removed from the fire, the liquid which it contains and the wash water are poured into a flask capable of holding about 60 cubic inches, which is then entirely filled with ordinary water: upon this a solution of permanganate of potash of known strength is gradually added from a graduated burette. The operation is then finished, and there remains only to calculate the result.

Let us suppose that the solution of mineral chameleon was of such a strength that 25 divisions of the burette were required to peroxidize 7.72 grains of iron, or 50 divisions for 15.44 grains of that metal; and let us further suppose that to complete the preceding experiment 10 divisions of the same solution were required; now, if 50 divisions of this permanganate suffice to peroxidize 20 of iron, how much ought 10 divisions to peroxidize?

$$\text{As } 50 : 15.44 :: 10 : 3.088$$

3.088 therefore are subtracted from 30.88 grains of iron, and it may be concluded that the remaining 27.888 have been peroxidized by 18.52 grains of crude nitre: but it is known that 30.88 grains of iron represent 18.77 grains of pure nitrate of potash, the quantity of that salt therefore corresponding to 27.888 grains of iron is found by the following proportion:—

$$\text{As } 30.88 : 18.77 :: 27.888 : 16.95$$

In the 18.52 grains of saltpetre submitted to analysis there were, therefore, 16.95 grains of pure nitre = 91.4 per cent. In performing the experiment the operator must be careful in

guarding against access of air: otherwise this would be apt to act upon the deutoxide of nitrogen, and render it capable of peroxidizing a further quantity of iron, so that the amount of nitre would be exaggerated. However, the peroxidation of iron, when the metal is dissolved in a strongly acid liquid, is very slow, as *Marguerite* has shown, and in the manner of conducting the process, as described above, the inconvenience is avoided, for as soon as the iron has disappeared in the acid the flask is filled with hydrogen and hydrochloric acid gases: the nitrate which is introduced carries with it but a mere trace of air, and the liquid kept boiling disengages, by the drawn out tube, acid and aqueous vapors, the issuing forth of which being always visible and readily maintained, does not allow the admission of any air.

The nitrates may be employed either in the solid state or in solution in water. *Pelouze* prefers the former; though in the case of crude nitre, where great differences frequently occur in the same sample, and where the mean composition is the object sought, he recommends to dissolve 120 grammes (1852.8 grains) of the nitre to be examined in a vessel capable of holding two quarts, which is finally filled exactly with ordinary water; twenty cubic centimetres (1.318 cubic inches) of the solution, containing 1.20 gramme (18.52 grains) of the salt, are then poured into the solution of 30.88 grains (two grammes) of iron in about 1500 grains of concentrated hydrochloric acid, just as the metal has disappeared, and the experiment is proceeded with as before.

*Pelouze* states that he has confirmed the accuracy of his method by the analysis of several other nitrates, such as those of soda, ammonia, lead, &c., and he observes, further, that it will enable us to determine the amount of water in certain nitrates, the composition of which is at present doubtful; and that it will prove of great value in analyzing mixtures of nitric and sulphuric acid destined for the preparation of gun cotton, as the sulphuric acid in no way interferes with its accuracy: nitric acid diluted with water only, or mixed with sulphuric acid, may be estimated just as easily as a neutral-nitrate. But it is principally in determining the value of crude saltpetre, that he anticipates that his method will prove of the greatest utility. In most cases the saltpetre of commerce contains only one nitrate, that of potash, which is mixed with earthy matters, sulphates, and alkaline chlorides.



Its analysis may therefore be made with the greatest accuracy and quickness by the above process, as far, that is, as regards the determination of the amount of nitric acid. It scarcely requires twenty minutes, and is accurate to within two or three thousandths.

*Ordinary Methods of testing or "refracting" Saltpetre.*—The methods in general use have no pretensions to scientific accuracy, neither is such necessary for practical purposes. In *Sweden*, a very rough plan is adopted. It consists in casting the melted salt into the form of a cake, one inch in thickness, by means of a small tin box, and then examining its fracture; pure saltpetre has, in the melted state, a coarsely fibrous structure and is very translucent; if it contains  $\frac{1}{40}$ th of common salt, the nucleus is no longer fibrous; and, if it amount to  $\frac{1}{30}$ th, the fibrous texture is perceptible only at the edges of the cake.

In France, saltpetre is tested by a process introduced by *Riffaut*.<sup>\*</sup> A weighed quantity of the dried crude salt is gradually washed, at the temperature of the testing room, with a saturated solution of pure saltpetre in water. When as much of this solution has been used for washing as would be sufficient to dissolve four or five times as much chloride as can possibly be contained in the worst sample of crude saltpetre, it is then quite certain that nothing but pure saltpetre can remain. For a sample consisting of  $12\frac{2}{3}$  ounces,  $18\frac{1}{2}$  ounces of a pure solution of saltpetre are used, which will dissolve  $8\frac{1}{2}$  ounces of common salt, or 66 per cent. of the sample, a quantity which is never actually present. Nothing now remains to be done, but to weigh the saltpetre remaining upon the filter; there is, however, some difficulty attending this, as the solution which clings to it must be first removed. To effect this removal the filter is spread out upon blotting paper, placed upon a porous substance (a slab of gypsum, for instance), that, at the expiration of twenty-four hours, the saltpetre may be taken out and dried. From the weight found, which indicates the amount of saltpetre in the sample, two per cent. must always be deducted, as that quantity has been found by experiment to remain in the wash water, and which it is impossible wholly to remove. It is obvious that this process must be both tedious and inaccurate.

<sup>\*</sup> Knapp's Technology. Edited by Drs. Ronalds and Richardson.

*Gay Lussac's Method.*—He uses his alkalimeter (see page 242); with which view he converts the saltpetre into carbonate of potash, by fusion with charcoal, when all the nitrogen is evolved. That the evolution of gas may not be too violent, and thus a portion of the test ejected, four parts of common salt, which in no way affect the test, are mixed with half of charcoal powder or soot by way of dilution, and the whole is brought into a state of fusion in an iron spoon. The fused saline mass gives a solution of carbonate of potash and chloride of sodium, which must be filtered and treated with test acid in the manner described in page 242. Every per cent. of potash indicated by the alkalimeter proves the presence of 2.14 per cent. of saltpetre; every per cent. of carbonate of potash, 1.46 of saltpetre in the sample tested. The only objection that can be raised against this method is, that it requires as much care and dexterity in its execution as any regular chemical analysis, which rather unfits it for practical use.

*Husz's Method.*—This is a *physical* analysis, and is founded on the fact that, the temperature at which a cooling solution of saltpetre loses the property of dissolving more saltpetre, or, what is the same thing, the temperature at which it begins to deposit crystals is a fixed temperature, and depends solely upon the relative proportion of water to that of the saltpetre dissolved, whether chlorides are present or not. If, therefore, the quantity of water remains the same in different cases, the point of saturation will solely depend upon the quantity of saltpetre, and the temperature at which saturation occurs will be a means of ascertaining the amount of saltpetre in a given specimen. Experiments must have been made previously to determining the point of saturation of solutions containing different quantities of saltpetre in an equal amount of water. This method was introduced by the author into Austria, but we have not heard that it has been ever practiced in this country.

No suitable means have as yet been discovered of ascertaining the amount of nitrate of soda, which frequently accompanies the first crop of crystals obtained in preparing saltpetre from cubic nitrate of potashes. The discovery of a ready method of determining this point is a great desideratum, since the absence of this salt in nitre employed for making gunpowder is indispensable, on account of the facility with

which it absorbs moisture from the atmosphere, a property which would soon render gunpowder, into the composition of which it entered, perfectly useless.

### *Chloric Acid.*

When this acid exists in a free state in aqueous solution, it is most simply estimated, according to *Fresenius*, by converting it into hydrochloric acid by means of sulphurous acid, in the following manner. The solution is mixed with a considerable excess of an aqueous solution of sulphurous acid, and well agitated: the flask is then stopped, and its contents digested for some time. The excess of sulphurous acid is then removed by bichromate of potash, and the liquid, being acidified with nitric acid, is precipitated with nitrate of silver, and the amount of chloric acid originally present calculated from the quantity of chloride of silver obtained.

Chlorates are analyzed either by measuring the volume of oxygen gas which they evolve by their decomposition, or by exposing a known weight to ignition, and calculating the amount of chloric acid from the loss of weight thereby experienced; should the salt under examination contain water of crystalization, it must be ignited in a retort of hard glass, to which there is attached a previously weighed tube containing chloride of calcium.

When a *chloride* and a *chlorate* are contained in the same solution, and are each to be estimated, the amount of chlorine in the chloride is first determined in a weighed quantity of the solution by precipitating it as chloride of silver, another weighed portion of the solution is evaporated to dryness and ignited, by which the chlorate present is converted into chloride; it is then redissolved in water and precipitated by nitrate of silver; from the amount obtained we have merely to deduct that yielded by the first experiment to obtain the requisite data for calculating the quantity of chloric acid.

## CHAPTER III.

## ON THE ELEMENTARY ANALYSIS OF ORGANIC BODIES.

NUMEROUS and diversified as are the forms and properties of vegetable and animal substances, and complex as is in general their composition, they are nevertheless made up of a very few of the so-called elements of the material world. A vast number of organic substances consist but of three of these elements, viz: *carbon*, *hydrogen*, and *oxygen*; and very many contain only two, *carbon* and *hydrogen*. There is, again, a very large class of organic bodies, into the composition of which *nitrogen* enters in conjunction with *carbon*, *hydrogen*, and *oxygen*, and there are a few to which, together with these four principles, *sulphur*, and *phosphorus*, *iron*, *manganese* and a few other elements appear to be essential. Thus, of the 63 substances at present recognized by chemists as simple, not more than ten or a dozen are found in the organic world. It is true that organic compounds may contain other bodies; but such are of artificial production, and do not, therefore militate against the fact we have just stated, viz: that by far the greater number of that almost bewildering variety of substances, which we meet with as the products of animal and vegetable life, and of their reactions on each other, are constituted of three or four only of the at present recognized elements: and that about a dozen of them are the most that are ever found to enter into their composition.

The older chemists, being unacquainted with any methods of resolving organic substances into their ultimate constituents, or of re-arranging their elements into such forms of combination as might enable them to pronounce upon their constitution, were obliged to satisfy themselves with the examination of the results of their destructive distillation; they thus resolved them into a series of products, which, being liable to infinite variation dependent upon the manner in which the distillation was effected and the degree of heat employed, could, it is obvious, throw but little light on the composition or properties of the substance under examination. A vast number of analyses were, however, made in this way by the earlier pneumatic chemists, of whom *Hales* and the celebrated



*Priestley* studied attentively the gaseous products of the operation.

The first chemists who attempted to combat the difficulties which surrounded the original attempts to gain an insight into the composition of organic substances by the examination of the results of their combustion in oxygen, were *Gay Lussac* and *Thenard*. Their method was to mix a certain weight of the substance to be analyzed into one or more pellets with chlorate of potassa, and to drop them, by a suitable contrivance, into an ignited glass tube, receiving the products of the combustion into a jar filled with mercury, and inverted in a mercurio-pneumatic apparatus. It was soon found, however, that a perfect combustion of the substance could not be effected with chlorate of potash, in consequence of the sudden manner in which this salt liberates its oxygen when exposed to heat. *Gay Lussac*, therefore, suggested the employment of oxide of copper, a substance which does not decompose when ignited alone, but which readily yields its oxygen when heated strongly with an organic substance. The idea of using this oxide was a very happy one, and there can be no doubt that we owe to its application, in a great measure, that vast addition which has of late years been made to our knowledge in this department of chemistry.

*Dr. Prout* employed an entirely different method; it was complicated, though exceedingly accurate, as is evident from the fact that the analyses performed by its distinguished inventor are still regarded as models of scientific research, and from the circumstance that *Dumas* has been induced to recur to it, notwithstanding its complexity. *Dr. Prout's* object was to burn the substance effectually in oxygen gas; in which case, supposing it to contain three elements, hydrogen, carbon, and oxygen, one of three things must happen:—1st, the original bulk of the oxygen must remain the same, in which case the hydrogen and oxygen in the substance exist in it in the same proportion in which they exist in water; or, 2d, the original bulk of the oxygen is increased, in which case that element must exist in the compound in a *greater* proportion than it exists in water; or, 3d, the original bulk of the oxygen is *diminished*, in which case the *hydrogen* must predominate. In the first case, the composition of a substance may be known by determining the quantity of carbonic acid gas yielded by a known quantity of it; while in the other two the same can

be readily ascertained by the same data, by noting the excess or diminution of the original bulk of oxygen. For full details respecting the manner of conducting the whole operation, the student is referred to *Dr. Prout's* original paper in the *Philosophical Transactions* for 1827, or to an abstract of the same in *Brande's Manual of Chemistry*, where he will also find wood-cut illustrations of the different parts of the apparatus. We must content ourselves here with a general statement of the advantages of this method of analyzing organic compounds as summed up by the inventor. In the first and chief place there is nothing to be apprehended from moisture. Whether the substance to be analyzed be naturally a hydrate, or in whatever state it may be with respect to water, the results will not be affected; and the great problem whether the hydrogen and oxygen exist in the substance in the proportions in which they form water, or whether the hydrogen or oxygen predominates, will be equally satisfactorily solved, and that (within certain limits) independently of the weight of the substance operated on. When, however, it is the object to ascertain the quantity of carbonic acid gas and water yielded by a substance, it is of course necessary to operate on a known weight; but, this being once determined, there is no fear, as in the common methods, of exposing the substance to the atmosphere as long as may be necessary. The hygrometric properties of the oxide of copper, as well as its property of condensing air, are also completely neutralized; for the whole, at the end of the experiment, being left precisely in the same state as it was at the commencement, the same condensation of course must take place, and any little differences that may exist are rendered quite unimportant from the bulk of oxygen gas operated on, which of course, in all cases, should be considerably greater than that of the carbonic acid gas formed. Another advantage of this method is, that *perfect combustion* is insured by it. There is, also, no trouble of collecting and estimating the quantity of water, a part of the common process attended with much trouble, and liable to innumerable accidental errors; here, on the contrary, the results are obtained in an obvious and permanent form, and, from the ease with which they are thus verified, comparatively very little subject to error.

We shall now proceed to describe, somewhat in detail, the more modern methods of analyzing organic substances, for

the perfection of which the scientific world is indebted to *Baron Liebig*, the renowned chemist of Giessen. This method combines with great exactness such simplicity of execution, that it is frequently resorted to as the easiest method of testing the purity of a substance; and it is generally admitted that to its invention must be ascribed the rapid progress of organic chemistry within the last few years. The process consists in burning the organic substance together with oxide of copper or chromate of lead, by which its carbon is converted into carbonic acid and its hydrogen into water, both of which are collected and weighed; if the body contains nitrogen, it is either collected in a gaseous state or is determined by other methods, and the oxygen is calculated by deducting from the original weight of the substance analyzed, the combined weights of the carbon, hydrogen, and nitrogen formed.

*Preliminary testing of the Organic Substance.*—Before commencing the ultimate analysis of an organic compound, the operator must assure himself of its purity. The presence or absence of inorganic non-volatile matter is easily ascertained by heating the substance on platinum foil over a spirit lamp, and, if necessary, urging the flame with the blowpipe; if it does not wholly disappear, the residue must be minutely examined; and if it has been determined to proceed with the ultimate analysis of the compound, notwithstanding the presence of inorganic matter, the amount of the latter must be accurately ascertained. We will suppose, however, that the substance has been proved to be free from inorganic non-volatile matter; it has next to be tested for nitrogen, sulphur, and phosphorus.

*Testing for Nitrogen.*—If the quantity of this element be large, it is easily detected by simply burning the body, which emits during ignition a smell of singed hair. In smaller quantities it may be detected by mixing the substance with soda lime, and heating it in a test tube; the water of the hydrate is thereby decomposed, its oxygen passing to the carbon and hydrogen of the organic substance, and its hydrogen to the nitrogen (if it contain any), giving rise to the formation of ammonia, which may be detected at the orifice of the tube by holding near it a feather, moistened with strong acetic acid. The following beautiful and delicate test for minute quantities of nitrogen in organic substances has also

been recommended by *Lassaigne*.\* It is based on the facility with which cyanuret of potassium is formed, when an organic substance, containing even very little nitrogen, is calcined at a red heat, and protected from the atmosphere, together with an excess of potassium. A small piece of this metal is placed at the bottom of a tube, and the matter to be tested is then added. The end of the tube is heated to a dark red in the flame of a lamp; then left to cool, and the potash salt, formed by the calcination, dissolved with four or five drops of distilled water. The decanted liquor is tested with a drop of solution of ferrosiferrous oxide (magnetic oxide of iron); a dirty greenish precipitate is immediately formed, which, being brought into contact with a drop of hydrochloric acid, becomes of a beautiful dark blue, if the matter under examination contains a trace of nitrogen. In the contrary case the precipitate of the hydrate of oxide of iron is entirely redissolved, without any blue coloring. *Lassaigne* found that neither potash nor its carbonate could be substituted for potassium in this process, neither is it applicable when the organic substance is accidentally mixed with a nitrate, or with an ammoniacal salt. Of these two methods of testing for nitrogen the latter is in its indications the least liable to misconception.

*Testing for, and Estimation of, Sulphur.*—A variety of methods have been proposed for detecting and estimating the amount of this element in organic substances. The subject is invested with a high degree of interest, in consequence of the sharp discussion which has lately taken place between Professors *Liebig* and *Mulder*, respecting the existence or non-existence of this principle in the so-called *proteine* of the latter chemist. The following are the principal methods which have been published:—

1. *Rüling's Process*.†—The finely pulverized substance is fused in a spacious silver dish, with about twelve times its weight of caustic potash, perfectly free from sulphuric acid; it is then mixed with pure nitre, in weight equal to about half the potash employed, and heated till the fused mass appears perfectly white. The whole is then supersaturated with hydrochloric acid, and a salt of baryta added: the formation of a white precipitate indicates sulphur. It consists of sulphate

\* Bibliothèque Univ., April 1843.

† Chemical Gazette, vol. iv. p. 362.



of baryta, and is collected, washed, dried, and ignited. Its weight furnishes the datum for calculating the amount of sulphur originally present in the substance.

2. *Kemp's Process*.\*—Fine quartz sand, which has been carefully tested for sulphuric acid, is mixed with chlorate of potash, in the proportion of two-thirds of the former to one-third of the latter. The substance to be examined is intimately mixed with the above, introduced into a large platinum crucible, and exposed to a high temperature over a spirit lamp. The process is completed in a few seconds. The contents of the crucible are treated with boiling distilled water, the insoluble portion separated by filtration, and washed till no traces of sulphuric acid remain: the sulphates and phosphates, if any exist, may by this plan be estimated simultaneously by means of a salt of baryta. The object of the sand is to prevent the too rapid oxidation of the organic body, and the risk of a portion being thrown out of the crucible.

3. *Weidenbusch's Process*.†—The substance is mixed with an excess of nitrate of baryta, and stirred in a beaker glass, with the most concentrated fuming nitric acid to a thin paste; the beaker is covered and exposed to the temperature of the sand bath, replacing the evaporated nitric acid until the organic substance is entirely destroyed, which is perceptible from the circumstance that, on evaporating the nitric acid still present, the mass begins to thicken, but no longer ascends in large bubbles in the glass, and dries quietly without frothing. The decomposed mass is now carefully washed into a platinum dish, dried at  $212^{\circ}$ , and then heated gradually until the saline mass is perfectly liquid. If the organic substance had not been completely destroyed by the nitric acid, it frequently happens that the mass takes fire, and a portion is projected from the slight deflagration. This must be avoided, as it occasions a loss of substance; but, even though this were not the case, a smaller quantity of sulphate of baryta would probably be obtained, since it appears that the sulphur still contained in organic combination is not oxidized so readily by the deflagration of the mass as by the slow

\* *Chemical Gazette*, vol. iv. p. 371.

† *Liebig's Annalen*, March 1847.

action of the nitric acid. The fused mass is carefully separated from the platinum dish, and treated in a beaker glass with dilute acetic acid, and heat applied as long as any evolution of gas is perceptible. The carbonate of baryta is decomposed, and the residue (if any) consists of pure sulphate, which is collected on a filter, washed, dried, heated to redness, again digested with acetic acid after ignition, and again heated to redness. After the second ignition it is perfectly pure, and the amount of sulphur may be calculated from it.

4. *Heintz' Process*.<sup>\*</sup>—He converts the sulphur into sulphuric acid by burning the organic substance with oxygen and oxide of copper. For this purpose an ordinary combustion tube, open at both ends, is half filled with copper turnings, and a little vessel containing the dry and pulverized substance placed in the tube, which is then connected with a bulb apparatus, filled with solution of potash, perfectly free from sulphuric acid, and the combustion made in a current of oxygen. The contents of the bulb apparatus are now decanted into a spacious flask, containing a warm solution of chlorate of potash in dilute nitric acid, and closed with a glass stopper. The sulphurous acid absorbed by the potash, and which had formed from the decomposition of a portion of the sulphate of copper, is by this means perfectly oxidized. The mixture of oxide, sulphate, and metallic copper is treated in a beaker with the above mixture, and entirely dissolved at a gentle heat; the sulphuric acid is precipitated by chloride of barium, and estimated as usual. As, along with the sulphurous acid, sulphuric acid always passes over into the bulb apparatus, it is advisable, in order to avoid all loss of sulphuric acid, which might arise from condensation of the latter on the cork of the combustion tube, to employ a tube which is drawn out at one extremity at a very obtuse angle into a fine tube, which fits into the strong arm of a bulb apparatus made for the purpose, and then connected with caoutchouc. The author examined *taurine* by this process, and found in three experiments, in the first, 25.68; in the second, 25.66; and in the third, 25.49 per cent. of sulphur. *Redtenbacher's* formula  $C_4H_7NO_6S_2$  requires 25.60 per cent. The combustion must not be carried on too quickly, otherwise a slight loss might readily occur from vapor passing through the solution of pot-

\* Poggendorff's *Annalen*, 72, p. 145.

ash without being absorbed thereby. In illustration of the importance of carefully examining organic substances for sulphur, and of the great mistakes which may be committed from neglecting to do so, it may be mentioned that the substance above alluded to, viz: *taurine*, which contains nearly 26 per cent. of sulphur, had originally assigned to it the formula  $C_4H_7NO_{10}$ , and was supposed to be altogether free from that element.

5. *By Acetate of Lead*.—A very convenient method of detecting minute quantities of sulphur in organic substances, which does not, however, enable us quantitatively to estimate it, is to boil the compound nearly to dryness with a concentrated solution of caustic potash. The residue is dissolved in water, and introduced into a flask provided with a tube funnel; a strip of paper, which has been thoroughly moistened with acetate of lead, and subsequently touched with a few drops of carbonate of ammonia, is suspended inside the flask between the cork and the neck; on pouring a little dilute hydrochloric acid slowly through the tube-funnel, sulphuretted hydrogen gas will be evolved should sulphur be present, and the lead-paper will turn brown.

*Testing for, and Estimation of, Phosphorus*.—The substance may be oxidized by the process of either *Rüling* or *Kemp*, or with fuming nitric acid, or with a mixture of nitric acid and chlorate of potash, and the solutions obtained may be examined for phosphoric acid by one of the methods described in the section on phosphoric acid.

1. *Analysis of non-volatile Solids, not containing Nitrogen*.—The first important point is to dry the substance thoroughly. This is done either in the water or air-bath, or in vacuo over sulphuric acid, or by any other of the methods described in the first chapter of this treatise, the means employed depending on the physical and chemical characters of the substance under examination. With the view of illustrating the details of the whole operation, we will take, as the simplest case that can be brought before the student, the analysis of the crystalizable sugar of manna, namely, *mannite*, giving the results as they occurred in an actual analysis.

The crystalline sugar, having been finely pulverized, is dried in a watch-glass in the water-bath until two weighings, made at the interval of half an hour from each other, furnish

Fig. 21.



a constant result. The fine powder is now introduced into a small stoppered bottle, the exact size and shape of Fig. 21. The weight of the bottle (which is kept in the water-bath along with the substance, to insure its being thoroughly dry) is, when empty, 76.66 grains, and, when filled with the mannite, 84.76 grains.


A Hessian crucible, of the capacity of about four ounces, is nearly filled with oxide of copper, carefully prepared in the following manner:—Some shreds of pure copper (clippings from electro-types) are dissolved in pure nitric acid; the solution is evaporated to dryness in a porcelain basin, and the residual basic salt heated to moderate redness in a Hessian crucible until fumes of nitrous vapor cease to be evolved. It is constantly stirred during the ignition with a copper rod, to promote the escape of the gas. The last traces of nitric acid adhere somewhat obstinately to the oxide of copper; the process should not, therefore, be hurried, but it is better to keep up a moderate heat for a considerable time than to attempt to quicken the operation by urging the fire, as in this case the lower portions of the oxide are apt to fuse, and, on cooling, the mass becomes so hard that it is difficult to remove it from the crucible, and, subsequently, to reduce it to powder. Before considering the process to be finished, a portion of the oxide should be tested; with which view a small quantity is introduced into a tube of combustion glass and strongly heated, the aperture of the tube being closed with the finger. On removing the latter, the smell will generally indicate the existence of nitrous vapors, and the tube itself should be carefully examined for the appearance of ruddy fumes. The decomposition being complete, the oxide is allowed to cool, then transferred to a mortar, in which it is reduced to a tolerably fine powder, after which it is fit for use, and may be preserved in a wide mouth stoppered bottle. The same oxide may be employed for several experiments: by merely pouring a little acid on it, the metal is oxidized afresh, and the oxide is restored to its former purity by calcination. The Hessian crucible above alluded to is nearly filled with oxide of copper thus prepared; its cover is put on, and it is placed among the coals of a coal or charcoal fire, taking the greatest care that



no organic matter from the fire comes accidentally into contact with it. It is heated to low redness; meanwhile, the other materials required for the analysis are being prepared.

1. *The Combustion Tube*.—This is drawn out from a tube of hard German glass, with the aid of the blowpipe lamp. A tube free from flaws, and which has been previously tested as to its capability of bearing the requisite heat without blowing out, is selected, from thirty inches to three feet long; it is heated, first gradually, and then with the full power of the lamp, in the middle, until it becomes sufficiently soft to rend asunder; the two ends are then drawn from each other, and by a dextrous turn of the wrist two tubes are prepared, shaped as shown in Fig. 22, each from fifteen to eighteen

Fig. 22.



inches long. The fine points of the tubes are then sealed, and the open ends are fused at the edges, so as to enable them to bear the pressure of the cork without splitting. The tube which is selected for the combustion, is thoroughly cleaned and dried; for this purpose a piece of clean filtering paper is twisted round the end of a long stout copper wire, and with this the tube is well wiped out; it may, perhaps, be necessary to wash it out with distilled water. In this case the greatest care must be taken to dry it thoroughly afterwards, which may be done either by folding loosely over the mouth a piece of filtering paper and burying it in the sand of the sand bath, or by heating it from end to end over a spirit-lamp, drawing a current of air through it the whole time by putting a long tube, open at both ends, to the bottom, and sucking with the mouth. If the tube has been washed out with water, a small drop of the liquid will often obstinately remain at the very point of the sealed end, which is expelled with a sort of explosion on putting the point into the flame of a spirit-lamp. The tube being thus cleaned and dried, is kept corked till about to be used, in order to prevent the entrance of any impurity.

2. *The Chloride of Calcium Tube.*—This is shown in Fig. 23. The chloride of calcium is prepared by dissolving chalk

Fig. 23.



in hydrochloric acid, filtering the solution, and evaporating it to dryness: the dry mass is then fused in a Hessian crucible: it must be kept in a well-stopped bottle. In filling the tube, a little cotton wool is first introduced at the large end, which is then closed with the finger; vigorous suction is now applied at the small end (seen in the figure with its cork attached), the finger is then suddenly removed, and the cotton is forced up to the end of the bulb, where it acts as a plug in preventing any of the small fragments of the chloride from getting into and choking up the narrow neck of the tube. The bulb is next filled with coarse pieces of chloride of calcium, and the remainder of the tube, to within half an inch of the end, is then filled up with finer fragments; a second plug of cotton-wool is introduced, and, finally, the tube is closed with a good sound cork, well secured with sealing-wax, nicely smoothed round the edges; through the centre of this cork there proceeds a piece of stout quill tube about three inches long, through which connection is established between the chloride of calcium tube and the potash apparatus. A small hook is seen in the figure attached to the tube. This is made of platinum wire, and is intended to offer a facility for hanging the apparatus to the scale of the balance, in which it is accurately weighed.

3. *The Potash Bulb Tube.*—The construction of this apparatus (the invention of which by *Liebig* may be considered as one of the leading causes of the rapid progress of organic chemistry within the last few years, from the remarkable manner in which it has facilitated the analysis of organic bodies) will be understood by reference to the annexed figure. It consists of a tube on which five bulbs are blown, three at the bottom, the middle of which is the largest, and one on each of the sides; the three bottom bulbs communicate with each other by pretty wide openings, but each outer bulb is separated from the other by about two inches of tube; one of the side bulbs, *d*, must be larger than either of the others. The

objects of this arrangement is to expose a large surface of caustic potash ley to the gases evolved during the combustion of the organic substance, so as to insure the complete absorption of the carbonic acid. The method of filling the bulbs with the alkaline ley is shown in Fig. 25. A porcelain basin

Fig. 24.




Fig. 25.



is filled with a solution of caustic potash, specific gravity about 1.27. This is prepared in the usual manner, or more conveniently by the following receipt, given by Dr. Gregory.\* Two parts of the subcarbonate of potash of the shops are dissolved in twenty or twenty-four of boiling water. One part of quick-lime is slaked by being covered with hot water in any convenient vessel. In this way the whole of the lime is converted into a uniform cream, without the formation of any hard sandy particles which occur in the ordinary method of slaking. The cream of lime is added in small portions to the boiling solution of carbonate of potash, which is boiled a few minutes after each addition, water being occasionally added to supply the loss by evaporation. When the whole of the lime has been added, the mixture is boiled for a short time longer, and is then allowed to cool, the cover of the vessel being carefully closed. After twelve hours the whole of the ley may be decanted perfectly clear and quite caustic, if the

\* Instructions for the Chemical Analysis of Organic Bodies, by Justus Liebig. Translated by Dr. W. Gregory.

vessel has been nearly full. The carbonate of lime is sandy, and occupies a very small bulk. The clear liquid is now to be boiled down rapidly in a clean iron vessel, till small crystals begin to separate. It is then allowed to cool in a stoppered bottle of green glass, when it deposits the whole of the sulphate of potash originally present in the subcarbonate, that salt being entirely insoluble in a strong solution of caustic potash. The specific gravity of this ley is from 1.25 to 1.27; it is nearly pure, containing no foreign matter except a little chloride of potassium, and it is perfectly adapted for organic analysis.

The basin being filled with the ley the end of the tube communicating with the largest of the side bulbs is dipped into the liquor, and to the extremity of the tube, communicating with the smaller bulb, a suction tube is attached by means of a perforated cork: suction is now applied with the lips, and the ley is thus drawn into the apparatus to the extent shown in the figure. The bulbs are then moved from their inclined position, the suction tube taken off, and the interior of the tube which had been immersed in the alkaline liquor is wiped dry with a twisted slip of filtering-paper; and, finally, the whole apparatus is wiped thoroughly dry with a clean cloth. It is now accurately weighed, being suspended from the pan of the balance.

3. *The Combustion Furnace.*—This is shown in Fig. 26. It is made of sheet iron, from twenty-two to twenty-four inches

Fig. 26.



long, and four inches high. The bottom is three inches wide, and is furnished with a series of small slips or apertures, which serve as a grate. The side walls are slightly inclined outwards, and are, at the top, about five inches apart. To support the combustion tube, a series of straight and upright pieces of strong sheet iron are riveted to the bottom of the furnace, between the apertures; they are of exactly equal heights, and



their upper edges are slightly curved, so as to coincide exactly with the aperture at the end of the furnace. To confine the fire to particular portions of the tube, two screens are employed of the form represented in Fig. 27, and seen also in their places in Fig. 26. The openings in these screens must be sufficiently large to receive the analyzing tube without difficulty; a screen is placed at the anterior part of the furnace during the combustion, to protect the cork of the tube from the heat of the coals. The furnace is placed, during the combustion, either on a large tile resting on a block of wood, a wedge being thrust between the tile and the wood to give the air free access to all the holes of the grating, or it may be placed upon a stand.

Fig. 27.



4. *Charging the Combustion Tube.*—A sheet of clean glazed paper being laid on the table, the cork is removed from the combustion tube, and warm oxide of copper introduced to about *a* (Fig. 22); this serves as a measure for the quantity required for the analysis; it is shaken from the tube into a clean warm porcelain mortar, which should have a rough or unglazed bottom, as rendering the mixture less liable to adhere to it: about an inch of oxide is left at the end of the tube. The substance to be analyzed is now shaken from the little stoppered bottle, in which it has been weighed, into the oxide in the mortar, and the whole gently but well mixed together with the pestle. The incorporation being complete, the mixture is transferred from the mortar to the tube, which is best done by depressing the open extremity into the mixture, and turning the tube round; the portions which cannot in this way be got into the tube are poured on a smooth glazed card, and thus introduced. The mortar is now rinsed out with a fresh quantity of warm oxide, which is also transferred to the tube, and which will occupy the space from *a* up to about *b*; lastly, the tube is filled to within an inch of the end with pure oxide from the crucible. The distribution of the mixture in the tube is, therefore, as follows:—From the extremity to *c*, pure oxide; from *c* to *a*, the mixture of oxide and the organic substance; from *a* to *b*, rinsings of the mortar; and from *b* to *d*, pure oxide. The process of filling the tube should be completed before the oxide of copper has got cold. The cork is now put in its place, and the tube, being grasped between the fore-finger and thumb of each hand, is tapped smartly a few


times on the table, so as to shake together the contents, to free the pointed extremity entirely from oxide, and to have a channel above the mixture from end to end to allow of the escape of the gaseous products of decomposition which would otherwise force the mixture from the tube. Fig. 28 shows the

Fig. 28.



tube as it should appear with the mixture shaken into its place; now, as during the process of mixing, the oxide of copper may have absorbed aqueous vapor from the air, and as this moisture would vitiate the results of the analysis, by giving too high a number for the hydrogen, the next step of the operation is to get rid of this moisture, which is done by placing the tube in a wooden trough and covering it with hot sand, the temperature of which should be above  $212^{\circ}$ , but not sufficiently high to char paper. To facilitate the removal of the aqueous vapor, the air is exhausted from the tube, while it is surrounded with the hot sand, by means of a small exhausting syringe, as shown in Fig. 29; after a few strokes of the piston the stopcock is opened, by which fresh air is admitted,

Fig. 29.




which becomes completely dried by passing through a chloride of calcium tube. This process of alternate exhaustion and readmission of air is repeated ten or a dozen times, and the absence of all hygroscopic moisture is thereby ensured.

5. *Arrangement of the Apparatus for the Combustion.*—This will be perfectly understood from an inspection of Fig. 30. The chloride of calcium tube is connected with the com-

bustion tube by means of a perforated cork, which has been thoroughly dried in the water bath; the operator must be careful in the selection of this cork, as, if a deficiency of tightness is detected when the apparatus comes to be examined previous to commencing the analysis, it is here that the fault will generally be found to lie. The cork should be thoroughly sound, and should be cut smooth and tapering; the hole through which the chloride of calcium tube enters should be round and smooth. The chloride of calcium tube

Fig. 30.



is connected with the potash apparatus by a double caoutchouc tube secured by strong silk cord; the caoutchouc should be soft so as to yield to the pressure of the cord, which should be tied in a bow and not in a knot, in order that it may be readily removed at the end of the analysis. It will be noticed that it is the extremity of the potash apparatus, in connection with the *large* bulb, which is attached to the chloride of calcium tube. The combustion tube should project a full inch from the end of the furnace, the screen being placed over it to protect the cork, as shown in the figure. The bulbs of the potash tube rest on a folded towel or silk handkerchief placed on blocks of wood raised to the requisite height, and the apparatus is inclined slightly by placing a cork underneath one of the side bottom bulbs, as seen in the sketch. The whole arrangement should have a slight inclination forwards, from the sealed end of the combustion tube to the junction of the chloride of calcium tube with the potash-bulb. The apparatus being thus far disposed, the next step is to see that the junctions are all perfectly air-tight; this is done in the following manner:—A red hot coal is held near the large side bulb of the potash tube, the inclosed air becomes hereby expanded, the ley sinks, and, as the heat increases, a portion of the expanded air escapes in bubbles through the several bulbs, out at the open end of the tube; when about a dozen bubbles

have in this way been expelled, the hot coal is removed, and the bulbs are set level on the cloth; as the bulb cools, the air remaining in it contracts, and the potash ley rushes back and fills it more or less. It is now left for a few minutes, during which time the operator may be employed in re-weighing the little bottle which contained the substance about to be analyzed; if at the end of five minutes or so the potash ley should show no disposition to recede from the large side bulb, and once more take up a horizontal position, it may be concluded that the apparatus is perfectly tight; on the other hand, should the liquid not preserve the level which it had acquired after the cooling of the large bulb, then the junctions are not tight, and the fault will most likely be found in the cork. Supposing, however, the apparatus to have been proved to be air-tight; the potash apparatus is once more inclined, and the combustion commenced.

6. *Management of the Combustion.*—A good supply of red-hot charcoal being provided close at hand, that part of the tube included between the anterior part of the furnace and the first screen is quickly surrounded with small pieces of hot coal, so as to bring it speedily to a red heat; the potash in the large bulb will almost immediately be seen to recede, owing to the expansion of the heated air; the screen is then gradually shifted backwards about an inch at a time, exposing a fresh portion of the tube, which, as before, is surrounded with red-hot charcoal; as soon as the heat reaches the mixture of the organic substance and the metallic oxide, the decomposition of the former commences, carbonic acid and aqueous vapor begin to be evolved—the latter is seen lining the interior of the front part of the chloride of calcium tube in the form of dew, while the former passes into the potash apparatus, driving forward all the air present in the bulbs. At first, the bubbles appear to pass through the ley without being absorbed; but as the combustion proceeds, the absorption is more and more complete, and, after a time, if the substance under analysis is free from nitrogen only a solitary bubble occasionally breaks through the liquid, nothing but pure carbonic acid passing through the chloride of calcium. The combustion should be so managed that the bubbles of gas shall follow each other in a uniform, uninterrupted, and tolerably rapid stream; and the screen should be gradually moved backwards until the whole length of the tube is surrounded



with red-hot charcoal. As soon as the evolution of gas in some degree slackens, the heat is raised by fanning the embers with a piece of paste-board; if the operation has been managed according to the above directions, and if the mixture of the organic substance with the oxide of copper has been thoroughly made, the gas generally ceases suddenly. On this taking place the cork is removed from underneath the small side bulb of the potash apparatus, and the latter laid level on the cloth. The alkaline ley soon begins to recede, slowly at first, but, when it reaches the large bulb which is left at the end of the combustion full of carbonic acid, it rushes rapidly into it; there is no danger, however, of any of the liquid being carried into the chloride of calcium tube if the proper proportion between the bulbs has been observed in the construction of the potash apparatus. As soon as the operator sees the potash rushing back into the large side bulb, he clips off the extremity of the tube with a pair of nippers; this allows air to enter, and the alkaline liquor immediately recedes. The hot coals are now removed from the posterior part of the tube, a long tube open at both ends is held over the broken extremity, either by an assistant, or supported by some convenient rest, and the operator, having inclined the potash bulbs, places a suction tube on the end, and draws a current of air through the whole apparatus; by this means all the carbonic acid and aqueous vapor which remained in the apparatus are swept into the chloride of calcium tube and potash bulbs.

The analysis is now finished, and it only remains to take the apparatus apart, and after the lapse of about half an hour, to weigh the potash bulbs and chloride of calcium tube, and calculate the results.

7. *Calculation of Results.*—The particulars of the analysis of mannite are as follows:

|                                                       | Grains.            |
|-------------------------------------------------------|--------------------|
| Weight of the bottle and substance . . . . .          | 83.76              |
| Ditto of the bottle and residue . . . . .             | 79.64              |
| Weight of substance analyzed . . . . .                | <hr/> 4.12         |
| Weight of the potash bulbs after combustion . . . . . | 586.64             |
| Ditto before combustion . . . . .                     | <hr/> 580.65 <hr/> |

|                                                                   |        |
|-------------------------------------------------------------------|--------|
| Weight of carbonic acid produced . . . .                          | 5.99   |
| Weight of the chloride of calcium tube after combustion . . . . . | 276.06 |
| Ditto before combustion . . . . .                                 | 273.20 |
| Weight of water produced . . . . .                                | 2.86   |

These numbers furnish the data for calculating the percentage composition of the substance. We have proved by the preliminary experiments that there is no nitrogen, sulphur, phosphorus, or inorganic matter present; it is evident, therefore, that, after deducting from the weight of the mannite submitted to analysis the amount of carbon and hydrogen obtained in the forms of carbonic acid and water, the remainder must be calculated as oxygen. Let us see what quantities of these several elements we obtain as the result of our experiment. In the chloride of calcium tube we obtain 2.86 grains of water; how much hydrogen, then, in 4.12 grains of mannite? Now, as every 9 grains of water contain 1 grain of hydrogen, we find the quantity contained in 1 grain by the proportion:—

As  $9 : 1 :: 1 : x$ , or

$$\frac{9}{1} = \frac{1}{x}, \text{ or } 9 = \frac{1}{x} \text{ or } x = \frac{1}{9}$$

that is, the amount of water obtained, divided by 9, gives the amount of hydrogen; consequently,  $\frac{2.86}{9} = .31777 =$  the hydrogen in 4.12 grains of mannite; but it is far more convenient to express the amount in per-centage parts, thus:—

$$\frac{2.86 \times 100}{9 \times 4.12} = 7.71 = \text{per-centage amount of hydrogen.}$$

Again, in the potash bulbs we have condensed 5.99 grains of carbonic acid; what is the per-centage amount of carbon? 22 grains of carbonic acid contain 6 grains of carbon.

As  $22 : 6 :: 11 : 3$

As  $11 : 3 :: 1 : x$

$x = \frac{3}{11}$ ; consequently, the quantity of carbonic acid found, multiplied by 3 and divided by 11, gives the amount of car-

bon; and we get it in per-centage parts by multiplying by 300 and dividing by 11 times the quantity of substance analyzed, thus:—

$$\frac{5.99 \times 300}{11 \times 4.12} = 39.61 = \text{per centage amount of carbon.}$$

The composition of the mannite, according to the above analysis, is therefore

|          |   |   |   |   |   |   |       |
|----------|---|---|---|---|---|---|-------|
| Carbon   | . | . | . | . | . | . | 39.61 |
| Hydrogen | : | : | : | : | : | : | 7.71  |
| Oxygen   | . | . | . | . | . | . | 52.68 |
|          |   |   |   |   |   |   | <hr/> |
|          |   |   |   |   |   |   | 100   |

*Construction of a Formula from the per-centage Composition of a Substance.*—Although we may not, as in the case of mannite, be able always to determine the atomic weight of a compound, it is an easy matter to ascertain the *relative* proportion of the equivalents of the elements of which it is composed, provided we have before us a correct statement of its per-centage composition; in other words, we can, from such data, deduce its *empirical* formula; for this purpose we have only to divide the per-centage number of each element by its atomic weight, and to reduce the figures obtained to the simplest expression possible: thus, in our experiment with mannite, we have

$$\frac{39.61}{6} = 6.601 = \text{equivalent of carbon.}$$

$$\frac{7.71}{1} = 7.710 = \text{equivalent of hydrogen.}$$

$$\frac{52.68}{8} = 6.585 = \text{equivalent of oxygen.}$$

Now here the numbers 6.601 and 6.585 are so nearly alike that it is at once evident that in mannite the number of atoms of carbon and of oxygen are the same; and, on considering the above figures, it is seen that the simple numbers with which they best correspond are 6, 7, and 6. Let us see, then, how nearly the numbers calculated in per-centage parts from the formula



agree with the experimental ones:—

|                      | Theory.  |             | Experiment. |
|----------------------|----------|-------------|-------------|
| C <sub>6</sub> . . . | 36 . . . | 39.57 . . . | 39.61       |
| H <sub>7</sub> . . . | 7 . . .  | 7.69 . . .  | 7.71        |
| O <sub>6</sub> . . . | 48 . . . | 52.74 . . . | 52.68       |
|                      | <hr/> 91 | <hr/> 100   | <hr/> 100   |

The coincidence is so close that there can be no doubt that the above formula is the correct one, though we have no way of confirming it by determining the atomic weight of this peculiar kind of sugar. We shall give presently a case in which the absolute as well as the relative proportion of the atoms of an organic substance can be determined, and a *rational* formula deduced for it.

*Combustion with Chromate of Lead.*—Some organic substances cannot be thoroughly oxidized by burning them with oxide of copper, partly, according to *Dumas*, in consequence of the formation of a small quantity of *carburet of copper*, together with the reduced metal, and partly owing to the deposition here and there of small particles of carbon. With such substances this source of error is sometimes obviated by introducing into the posterior end of the combustion tube some chlorate of potassa, mixed with oxide of copper: this salt, being heated at the end of the combustion, gives off pure oxygen, in which all the combustible matter must be thoroughly oxidized. The object is, however, more conveniently attained by employing *chromate of lead* instead of oxide of copper. This substance is admirably adapted for oxidizing purposes, from its yielding up a portion of its oxygen by heat alone; a property not possessed by oxide of copper. Chromate of lead is prepared by precipitating a clear solution of acetate of lead, containing slight excess of acetic acid, by bichromate of potassa, washing the precipitate thoroughly on a linen strainer, drying, and igniting to fusion in a Hessian crucible. The fused mass is pulverized, and kept in a stoppered bottle. By heat, either alone or in contact with an organic substance, it is decomposed into green oxide of chromium, and basic chromate of lead. The combustion of an organic body, with chromate of lead, is conducted precisely in the same manner as with oxide of copper. The chromate is finely pulverized, and mixed while warm with the substance; but, as it is not in the least degree hygroscopic, the process of exhausting the




analyzing tube while buried in hot sand may be omitted; a narrower tube than that employed with oxide of copper may be used, and the chromate which has served for one experiment may be used again after refusion.

II. *Analysis of Volatile Solids and Liquids not containing Nitrogen.*—The analysis of waxy substances, and of volatile organic solids, is performed in tubes which are somewhat longer and wider than those generally employed. The analyzing tube is filled also in a different manner, as it would obviously be inadmissible to triturate volatile substances with hot oxide of copper, and the nature of oily and waxy bodies renders their admixture in the usual manner impracticable. Solid fusible fats, oils, &c., are weighed in a little tube, the size and shape of Fig. 31. The chromate of lead or oxide of copper is introduced, while hot, into a wide thin glass tube, about twenty inches long, or into a tube which can be closed air-tight with a brass cap and lead washer, Fig. 32; in this it is allowed to cool; if chromate of lead is the oxidizing agent employed, a layer of about two inches is first introduced into the combustion tube; but, if oxide of copper is to be used, the same quantity of a mixture of chlorate of potash and oxide is shaken in; the little tube, with its charge of substance, is then dropped into the analyzing tube, and heat applied so as to melt it, and cause it to spread over the lower side; the tube is then filled with the oxidizing agent by introducing its open end within the copper or wide glass tube, containing the oxide of copper or chromate of lead, and turning it round. The tube being filled, the substance to be analyzed is diffused through the oxide or chromate by placing it for a few minutes in hot sand; keeping it well corked during the time, the combustion is then proceeded with in the usual manner. If the substance is not of a waxy or fatty nature, it is mixed with the oxide or chromate by means of a copper wire, the end of which is formed like a corkscrew; but the operation requires to be conducted with skill and rapidity.

Volatile liquids, such as alcohol, ether, &c., are weighed in two or three small glass bulbs, the size

Fig. 31.



copper

Fig. 32.



and shape shown in Fig. 33. These bulbs should be drawn out of a long piece of quill tubing, in order to prevent any moisture from getting into them while they are being expanded by the breath. They are filled by heating

Fig. 33.



them slightly over a spirit-lamp, and immersing their pointed extremities in the fluid to be analyzed; on cooling, the liquid enters the bulb from the contraction of the heated air, the bulb is again gently heated, on which more air is expelled, and then, on once more dipping the open end into the liquid, an additional quantity enters. In this manner the bulb is about three parts filled with the liquid; upon which its extremity is sealed, and it is weighed, and, the weight of the empty bulb having been previously taken, that of the included liquid is found. The analyzing tube employed should be longer and wider in proportion as the liquid is more volatile. The oxidizing agent is allowed to cool in the closed copper or glass tube, Fig. 32, and, a layer of two inches having been introduced into the combustion tube, the centre of the neck of one of the little bulbs is slightly scratched with a file, the point is quickly broken off, and both bulb and point are dropped into the tube and covered immediately with three or four inches of oxide of copper; another bulb is then introduced in a similar manner, covered with a layer of oxide, and so on with a third, should the substance to be analyzed be included in more than two bulbs. The tube is then tapped to open a channel for the escape of the gases.

The analysis of volatile liquids requires a great deal of care on the part of the operator. Thus, if a high heat were suddenly applied to one of the bulbs, a sudden gush of vapor would be produced, a portion of which might either be expelled from the tube without undergoing combustion, or if it were resolved into carbonic acid and water, these products would be evolved with such impetuosity as to eject the potash from the bulbs. The greatest care is therefore necessary in conducting the operation. About six inches of the anterior portion of the tube are first heated to redness, and a screen placed behind to prevent the communication of heat to the locality of the bulbs; the fluid in the first bulb is then gently distilled out by holding a red-hot charcoal near it, and the

vapor, thus gradually coming into contact with the oxidizing agent, is quietly burned. In this way, the contents of all the bulbs are brought into contact with the heated oxide, and it is advisable to keep a few pieces of hot charcoal against the closed end of the tube, to prevent any of the liquid from distilling back and condensing there.

### III. *Analysis of Organic Substances containing Nitrogen.*

—The determination of the nitrogen of an organic compound is always an operation distinct from that of the determination of the carbon and hydrogen. It is necessary, however, to modify in some degree the arrangements for the latter process, in the analysis of substances containing nitrogen, or the number for the carbon would always come out too high. The reason of this is, that, when an organic compound containing nitrogen is burnt with oxide of copper or chromate of lead, a portion of the nitrogen becomes converted into nitric oxide gas, which, on coming into contact with the potash in the bulb, is further oxidized into nitrous acid, and is retained by the alkali. It is necessary, therefore, to decompose these oxygen compounds of nitrogen before they can leave the combustion tube; which object is perfectly attained by introducing a layer of four or five inches of fine and pure copper turnings into the anterior part of the tube, and keeping them intensely ignited during the whole analysis. The nitric oxide and nitrous acid are completely decomposed by copper at a high temperature, nitrogen being evolved in a gaseous form, which passes unabsorbed through the chloride of calcium tube and potash bulbs.


The copper turnings employed for this purpose must be free from impurities, to insure which it is advisable to tarnish them by heating them in a crucible, with free access of air, and then to reduce the film of oxide which has formed on their surface by heating them to redness in a glass tube, through which a current of hydrogen is passing.

There are three different ways of estimating the nitrogen of an organic substance, namely, 1st, by collecting the gas in a free state and measuring its volume; 2d, by determining the relative proportion between the evolved carbonic acid and nitrogen gases; and, 3d, by converting the nitrogen into ammonia, and estimating it as such.

1. *Estimation of Nitrogen in a Gaseous State.*—This is the method of *Dumas*, and is applicable to the analysis of all


nitrogenous substances, in whatever form that element may exist in them. The substance is burned in the usual way with oxide of copper or chromate of lead, a layer of reduced copper turnings being placed in the anterior portion of the tube, which should be at least two feet long, and not drawn out at the closed extremity, but merely sealed; and from five to eight inches of dry bicarbonate of soda at the posterior end, the object of which is to enable the operator to expel all the atmospheric air from the analyzing tube at the commencement of the operation, and all the nitrogen from it at the end by a current of carbonic acid. The mixture of the substance with the oxidizing agent is made in the manner already described, and the tube filled as shown in Fig. 34; thus, from *a* to *b*, bicarbonate of soda: from *b* to *c*, pure oxide or chro-

Fig. 34.



mate: from *c* to *d*, the intimate mixture of the substance with the oxidizing agent: from *d* to *e*, rinsings of the mortar: from *e* to *f*, pure oxide or chromate: and from *f* to *g*, copper turnings. The tube is arranged in the furnace, as shown in Fig. 35, and, the first object being to expel the whole of the

Fig. 35.



atmospheric air, a screen is placed about three inches from the end, and hot coals are applied round the tube behind it so



as to heat intensely the bicarbonate of soda, and fill the whole tube with carbonic acid. The conducting tube *c d* fitted into the combustion tube *a b*, with a good sound cork, passes under the surface of mercury contained in a small pneumatic trough *v*. The bubbles of gas, as they break through, are received from time to time into a test-tube filled with caustic potash; and, when they are completely absorbed, it may be concluded that the atmospheric air has been thoroughly expelled from the apparatus. As the success of the experiment depends in a great measure on thus perfectly driving off the air, the operator must not hurry this preliminary process, but continue to apply heat to the bicarbonate of soda till a dozen or so bubbles following are completely absorbed by the caustic ley. A stout glass cylinder *c*, very accurately graduated into *cubic centimetres* or hundredths of a cubic inch, and of the capacity of about 200 c. c. or 13 c. i. is now filled two-thirds with mercury and one-third with potash ley and inverted in the pneumatic trough immediately over the conducting-tube *a*;<sup>\*</sup> the combustion is then proceeded with in the ordinary manner, the carbonic acid yielded by the decomposition of the substance is absorbed by the ley, while the nitrogen passes into the cylinder in its gaseous form. At the end of the operation, the remainder of the bicarbonate of soda is strongly ignited, and the carbonic acid evolved sweeps the whole of the nitrogen still contained in the tube into the graduated cylinder, while it is itself absorbed by the potash. The analysis being concluded, the cylinder containing the nitrogen is allowed to remain at rest for some time, to insure the complete absorption of the carbonic acid: it is then carefully transferred to a large deep glass vessel containing water, by placing underneath its edge the ground glass plate, on removing which under the water the mercury and the alkaline ley sink to the bottom of the vessel, their places being supplied by the water. The water within and without the cylinder is then brought to the same level, and the volume of gas read off, the state of

\* As caustic potash acts on the cuticle, making the skin slippery, the best way of filling the cylinder is first to pour in the mercury, then the requisite quantity of potash ley, and, lastly, pure water; the jar is then inverted by laying on its edge (which should be ground perfectly smooth) a ground glass plate. If the fingers are allowed to become soiled with the alkali, there will be a danger of the tube slipping through them when the operator is in the act of inverting it in the pneumatic trough.

the barometer and thermometer being at the same time noted. The analysis is now concluded, and it only remains to calculate the results. The method of doing this will be best understood by quoting the results of an actual experiment.

Weight of substance submitted to analysis .600 gramme = 9.264 grains.

Volume of nitrogen gas collected 41.5 cubic centimetres = 2.531 cubic inches; thermometer, 18.5° Cent. = 65.3 Fahr.; barom. 7573 millimetres = 29.9 inches.

*Correction of the Gas for Temperature.*—It is assumed that gases, when heated from the freezing to the boiling point of water, that is, from 0° to 100° of *Celsius*' thermometer, expand 0.3665, or, in other words, that they expand  $\frac{0.3665}{100} =$

0.00365 for every degree of the centigrade scale: to find, therefore, what volume the 41.5 cub. cent. of nitrogen observed at 18.5° would occupy at 0°, we must multiply the number of degrees above 0° by the expansion coefficient for one degree, add the product to 1, and divide the observed volume by this sum, thus:—

$$\frac{41.5}{1 + (18.5 \times 0.00365)} = 38.87 \text{ cub. cent., the volume the gas}$$

would occupy at 0° Cent. This volume has now to be corrected for pressure; but before doing so it is necessary to take into consideration *the tension of the aqueous vapor* at the observed temperature: for since the gas was measured in its moist state it must have contained a quantity of vapor of water diffused through it proportional to the temperature, which would counterbalance part of the column of air pressing on the gas; this portion must, therefore, be subtracted from the observed height of the barometer, in order to arrive at the true pressure. There is a table in *Faraday's Chemical Manipulation*, founded on the experiments of *Dalton* and *Ure*, showing the proportion, by *volume*, of aqueous vapor existing in any gas standing over or in contact with water at the corresponding temperatures, and at a mean barometric pressure of 30°, and in the appendix will be found a similar Table, extracted from *Fresenius'* "Quantitative Analysis," in which the force of the aqueous vapor at every degree of Celsius from 0° to 40° is expressed in *millimetres*. Referring to this latter table, it will be found

that at the temperature at which the experiment we are now considering was made, viz: 18.5 Cent., the tension of the aqueous vapor amounts to 15.85 millimetres: this, therefore, being deducted from 757.3 millimetres, the observed height of the barometer, gives .741.45 millimetres as the true pressure from which to correct the volume of gas.

*Correction of the Gas for Pressure.*—The normal pressure is assumed to be 760 millimetres (29.9 in.): therefore— $760 : 741.45 :: 38.87 : 37.92$  cub. cent. = the volume of nitrogen corrected for temperature, pressure, and aqueous vapor. The next question is—

What is the weight of 37.92 cub. cent. of dry nitrogen gas at 0° cent. and 760 millimetres barom.?

The specific gravity of nitrogen is 0.9706, atmospheric air being unity; and it has been ascertained by careful experiments, that 1 litre (1000 cubic centimetres, or 61.03 cubic inches), weighs at 0° cent. and 0.76 metre barom., 1.2609 grammes (19.46 grains): therefore—

As  $1000 : 1.2609 :: 37.92 : .0478$  grammes (.738 grs.) = the weight of the nitrogen yielded by .600 grammes of the substance at the standard temperature and pressure; and—

As  $.600 : .0478 :: 100. : 7.96$  = the per centage amount of nitrogen in the substance analyzed.

Having thus detailed the general principles of the method of deducing the per centage amount of nitrogen from the volume of gas obtained, we will give a formula founded on the above considerations, by which the calculation may be made in a few minutes, and a good deal of trouble saved.

Let  $v$  be the observed volume of gas.

$B$  the observed height of the barometer.

$p$  the tension of aqueous vapor.

$t$  the observed temperature.

$m$  the weight of the substance analyzed.

Then—

$$\frac{0.12609 v (B-p)}{m 0.76 (1+0.003665 t)} \text{ or } \frac{0.1659 v (B-p)}{m (1+0.003665 t)} =$$

the per centage amount of nitrogen. If the analysis quoted above as an illustration be calculated according to this for-

mula, the result will be found to be the same as that at which we arrived by the more circuitous method.

II. *Estimation of Nitrogen by determining the Relative Proportion between the Carbonic Acid and Nitrogen yielded by the Decomposition of the Substance. Liebig's Method.*—This method, which is applicable only to the analysis of substances rich in nitrogen, is performed by burning the substance in the usual way with oxide of copper in a long tube not drawn out at the closed end, and containing at least 5 inches of reduced copper turnings at its anterior end. After a considerable portion of the substance has been decomposed, and when it is concluded that all the atmospheric air has been expelled from the tube, the evolved gases are collected over mercury in a series of graduated tubes about a foot long and half an inch wide. These tubes are then transferred, one

Fig. 36.




Fig. 37.



at a time, to a tall cylinder, Fig. 36, containing mercury, where the united volumes of carbonic acid and nitrogen are accurately measured, the mercury within and without the tubes being brought to the same level: a small quantity of potash ley is then thrown up into the tubes from the siphon, Fig. 37, by gently blowing, the bent extremity being introduced at the open end of the tubes; and after the absorption of the carbonic acid is complete, the residual gas is again measured, the mean result of all the tubes is taken, and the relative proportion of the carbonic acid to the nitrogen gas expresses immediately without any further calculation, the proportion of the equivalents of carbon to those of nitrogen, since one equivalent of carbon is consumed by two equivalents of oxygen, without the volume of the latter undergoing any alteration, yielding, therefore, two volumes of carbonic acid; and one equivalent of nitrogen yields also two volumes of nitrogen gas.


The amount of carbon must have been ascertained by a



previous experiment: and, that being known, the weight of the nitrogen may be calculated from the atomic weights of carbonic acid and nitrogen: thus, suppose the proportion of carbonic acid to nitrogen to be as 10 to 4, then the compound analyzed contains  $10 \times 6 = 60$  carbon to  $4 \times 14 = 56$  nitrogen. This is the proportion in which these elements exist in uric acid, for the analysis of which this method answers very well; but in cases where the proportion of nitrogen is very small, or where it is evolved in a variable proportion at different stages of the analysis, it is inapplicable, and the method before described, or the one we shall next consider, must be adopted.

*Estimation of Nitrogen by converting it into Ammonia.*—This method, which was invented by *Drs. Will and Varrentrap*, and which is founded on the action of the hydrates of the alkalis on nitrogenous compounds at high temperatures, has already been described (page 249). This process, though exceedingly accurate, is very tedious, on account of the necessity of evaporating the platinum salt on the water bath; and it is expensive, on account of the alcohol and ether which are required. An important modification of the method has, in consequence of these objections, been devised by *Peligot*.\* The combustion is executed in the same manner as in *Will and Varrentrap's* method, and the ammonia condensed in a

Fig. 38.



similar bulb apparatus (see annexed cut), but which, instead of containing hydrochloric acid, is partly filled with a fixed

\* *Comptes Rendus*, March 29th, 1847; and *Chem. Gaz.*, May, 1847

weight or volume of sulphuric acid of known strength. Now, as the ammonia which combines with the acid lowers its strength, by determining after combustion the composition of this liquid, and comparing it with that it previously possessed, it is easy to ascertain the quantity of ammonia that has been condensed; and, consequently, the amount of nitrogen yielded by the substance submitted to analysis. This operation is executed with as much rapidity as precision, by means of an alkaline solution, likewise of known strength. *Peligot* prefers a solution of lime in syrup. By triturating slaked lime with a solution of sugar, it dissolves in far greater proportion than in pure water; and the compound formed possesses the same alkaline reaction as if the base which it contains were free. It is easily preserved, without alteration,\* in bottles protected from contact with the carbonic acid of the atmosphere, as with this acid it forms carbonate of lime: nevertheless, as this insoluble salt renders the liquid turbid, it need only be filtered to serve again to determine the strength of the sulphuric acid. The operation is conducted as follows:—

A certain quantity of sulphuric acid of known strength is accurately measured into the condensing apparatus. The acid employed by *Peligot* contains 61.250 grammes of  $\text{SO}_3$  HO to 1 litre of water; consequently, 100 cubic centimetres correspond to 2.12 grammes of ammonia, or 1.75 gramme of nitrogen.

When the combustion is finished, the acid which has served to condense the ammonia is poured into a cylindrical glass, the apparatus carefully washed, and to this liquid, diluted with much water, a few drops of litmus are added, to give it a red color. By means of the solution of lime in sugar, which is contained in a burette graduated in cubic centimetres and in tenths of a cubic centimetre, the acid liquid is accurately saturated, being guided by the blue color which the liquor suddenly acquires when the point of saturation is attained. The quantity of alkaline liquor required to produce this effect is read off on the burette; and as the amount of the lime compound which saturates 10 cubic centimetres of the normal solution of sulphuric acid has been determined by a previous

\* It has been objected that this solution does not keep of a uniform strength. I have found, however, in accordance with the statement in the text, that it may be kept for a great length of time perfectly clear, provided the bottle is carefully closed.—N.

experiment, by subtracting from this quantity that found for the acid which has absorbed the ammonia from the nitrogenous substance, we find the volume of the acid solution which has been saturated by the ammonia, and, consequently, the weight of the nitrogen which the body contained.

Shortly after the publication of this method, some experiments to test its accuracy were undertaken by the author of this Treatise; as they were perfectly satisfactory, it may be worth while to quote them.\*

The substance experimented upon was *Vitelline*, a nitrogenous principle extracted from the yolk of the egg. The standard sulphuric acid employed was of the specific gravity 1.0504; the quantity of dry acid which a small bottle of about one cubic inch capacity contained was very accurately determined by precipitation with chloride of barium to be 15.8 grains, which agrees exactly with the theoretical amount calculated from the specific gravity by *Ure's* Table. By a simple calculation it was ascertained that this quantity of dry acid is equivalent to 6.704 grains of ammonia, or 5.521 grains of nitrogen. The solution of lime in sugar was of such a strength that it required 54.25 divisions of the burette to neutralize exactly the bottle full of standard acid. The condensing apparatus employed is larger than it is usually made; it has three bulbs instead of two, and will hold about two-thirds of the contents of the bottle without being sufficiently full to excite any apprehension of the rushing back of the acid into the combustion tube at the close of the operation.

*Example 1.* 7.53 grains of vitelline were burned with soda, lime, and the ammonia condensed in the standard acid, which, after the combustion was finished, was transferred to a beaker, and the apparatus rinsed out repeatedly with distilled water; the remainder of the acid in the bottle was then added, and the whole diluted to about half a pint, and a few drops of litmus added; 45 burette measures of the sugar lime were required to saturate the acid, 9.25 measures (54.25—45) therefore represent the quantity of sugar lime equivalent to the ammonia given off by the substance; a simple calculation shows this to be equal to 0.941 grains of nitrogen, or 12.5 per cent.

In a second experiment, in which 10.17 grains were burned,

\* *Chemical Gazette*, Oct. 15th, 1847.

42 measures of the sugar lime were required to saturate the acid, which gives 12.25 as the representative of the sulphuric acid condensed by the ammonia, 1.246 grains as the amount of nitrogen = 12.35 per cent.

In a third experiment a different standard acid was employed, and a fresh preparation of vitelline analyzed. The acid was equivalent to 4.004 grains of ammonia, or 3.297 grains of nitrogen; and it required for neutralization 32 divisions of sugar lime, which was also a fresh preparation.

7.24 grains were burned; after the combustion 23.25 measures of sugar lime were required to saturate the acid;  $32 - 23.25 = 8.75$  represent, therefore, the sulphuric acid neutralized by the ammonia; this gives 0.9016 for the ammonia in the substance, or 12.45 per cent.

These three experiments agree, it will be observed, very closely with each other. Two experiments in which the nitrogen was estimated as double chloride of platinum and ammonium, gave 13.02 and 12.6 per cent. of nitrogen, numbers which are rather higher than those obtained by the new method; indeed, from the very principles of *Peligo*t's process, the results must always be a trifle below the truth, it being always necessary to add a slight excess of the alkaline solution, in order to see, by the change of the liquid from red to blue, when neutralization has taken place. It is true that, when we are experimenting with a perfectly colorless acid, the smallest addition of the lime solution above that required for the perfect neutralization of the acid immediately determines the blue color; but, after the acid has served to condense the ammonia given off by the combustion of an animal substance with soda-lime, it is always more or less colored; nor can a considerable tinge of yellow be prevented, although it may be much diminished by using a long combustion tube and a great excess of soda lime: this color renders it somewhat difficult to hit the precise moment when neutralization takes place; if the sugar lime be added till the liquor becomes distinctly blue, a deficiency of nitrogen amounting nearly to one per cent. may easily occur, and it is only practice that will enable the operator to stop exactly at the proper time. The best practical rule is, to use a long combustion tube; to keep its anterior portion very hot, and to dilute the acid considerably with water previous to adding the alkaline solution. One great advantage which this new method of *Peligo*t's pos-




sesses over all others is the great saving of time which it effects, as by it a nitrogen determination may be executed in less than half an hour, with as much accuracy as by the other methods which require at least three hours.

*Peligot* states that it is equally applicable to the analysis of substances containing but very little nitrogen, as wheat, vegetable soil, &c., provided a sufficient quantity of the substance be employed; and he expresses his belief that the process will prove very useful to chemists, especially to those engaged in investigations bearing upon animal and vegetable physiology, by enabling them to multiply, at a far less expense of time and money, determinations which are only of value in as far as they are comparative, and, consequently, very numerous.\*

\* Nöllner's process, which he claims to be less tedious and expensive, and more practicable than Will and Varrentrap's, "requires no evaporation, avoids any danger of the ascent of the acid liquid into the combustion-tube, loss of platinum, and especially of time. Ignite the nitrogenous substance in an ordinary combustion-tube with hydrate of lime or with soda-lime (the hydrate of lime preferable); but instead of passing the generated ammonia into muriatic acid, employ a solution of pure tartaric acid in absolute alcohol; so that the ammonia disengaged is instantly converted into bitartrate of ammonia, and deposited in the form of a crystalline powder, which is perfectly insoluble in absolute alcohol.

"As the bitartrate of ammonia contains 10.2 and the ammonio-chloride of platinum contains only 7.6 per cent. ammonia, it may be objected to this method that it is less accurate; but if, on the other hand, it be considered that a loss is more easily avoided by simplifying the method; that pure tartaric acid is more readily obtained than pure platinum or pure chloride of platinum; that, moreover, the bitartrate of ammonia has a far less specific gravity than the ammonio-chloride of platinum, so that with the same quantity of ammonia a far more bulky precipitate is obtained; the inventor thinks this method, which has constantly afforded him satisfactory results, may be recommended not only to those engaged in manufacturing processes, but to chemists occupied in the most accurate investigations. As it would be difficult to remove the precipitate from the absorption apparatus in general use, take two wide-mouthed bottles, each of which contains from half an ounce to three-quarters of an ounce of absolute alcohol, in which so much tartaric acid is dissolved, that at the end of the operation an excess of tartaric acid is present. The tube, curved at right angles,

Fig. 39.



passing from the combustion-tube into the first bottle, must not dip into the tartaric acid solution, as it would soon become stopped by the separation of the salt, and

Should the preliminary examination of the organic compound have indicated the presence of *chlorine*, it must be burned with chromate of lead, since, if oxide of copper were employed, a portion of sub-chloride of that metal would form, and condense in the chloride of calcium tube; and, should *sulphur* be present, a tube of perfectly dry *peroxide of lead* must be included between the chloride of calcium tube and the potash bulbs, in order to convert into sulphuric acid and retain as sulphate of lead all the sulphurous acid which may have formed from the oxidation of the sulphur.

The amount of chlorine in chlorinated compounds is determined by igniting them with soda lime, or by transmitting their vapor through soda lime, should they be of a volatile nature. The ignited mass is dissolved in dilute nitric acid, and the chlorine determined as chloride of silver. When the organic compound is of an acid nature, *Löwig* dissolves it in

the solution of the tartaric acid would ascend on the cooling of the combustion-tube. The pneumatic tube connecting the first bottle with the second need only dip a few lines into the liquid of the second glass, and to avoid any stoppage, should not be too narrow—about the diameter of an ordinary writing pen. Into the cork of the first bottle a safety-tube is inserted, which is immersed in the liquid; and to be sure that no ammonia is lost, the second bottle is connected with a third, in which, however, when the firing is well conducted, no precipitate is ever seen to form. Should the aperture of the pneumatic tube show signs of becoming stopped up, it is only requisite to blow gently into the safety-tube to remove instantly the film of tartrate of ammonia.

“As shown by Varrentrap and Will, towards the end of the operation, especially with substances containing much carbon, a quantity of free hydrogen gas is given off, owing to the decomposition of the hydrate water of the alkali. Now this evolution of hydrogen, and also of aqueous vapor from the excess of hydrated lime, so completely expels the whole of the ammonia, that it appeared to me quite superfluous to break off the pointed end of the combustion-tube, and to draw the air contained in it through the tartaric acid solution; at all events, in investigations for technical purposes, it suffices, by removing some of the incandescent coals, to allow cold air to pass in through the safety-tube, and then to drive it through the acid solution by the re-application of heat. When all evolution of gas has ceased, allow the apparatus to remain connected until it has acquired so low a temperature that it may easily be taken to pieces. The precipitate is then collected upon a weighed filter, an alcoholic solution of tartaric acid added to the liquid which passes through, to see whether any further precipitate is produced, and the precipitate then washed with *absolute* alcohol until what passes through no longer exhibits any acid reaction. As the precipitate is crystalline, it is very soon washed, and not less quickly dried in the water-bath at 212° F.

“The nitrogen is then easily calculated from the known composition of the bitartrate of ammonia with 1 equiv. water. According to Dulk, 100 parts contain—

10.2 ammonia = 8.4 nitrogen,  
79.0 tartaric acid, and  
10.7 water.”

dilute potash ley, evaporates the solution to dryness, and ignites the residue, by which the chlorine present is converted into a metallic chloride.

*Determination of the Rational Formula and Atomic Weight of an Organic Substance.*

1. *An Organic Acid.*—The most satisfactory method is to convert it into a silver salt, and to determine accurately the amount of metal which it contains.

*Example.*—From 0.320 gramme of a certain crystalline substance having acid properties, there are obtained 0.825 gramme of carbonic acid, and 0.1715 gramme of water. Another portion of the acid is exactly neutralized with ammonia, and the solution mixed with nitrate of silver. A white curdy precipitate falls, which is washed on a filter with cold water and purified by two or three crystalizations out of boiling water; 0.334 gramme of this new substance, being ignited, yields 0.1485 gramme of pure silver.

These numbers calculated in per cents. give the following as the composition of the acid, and salt:—

| <i>Acid.</i>    |   |   |   |   |       |
|-----------------|---|---|---|---|-------|
| Carbon          | . | . | . | . | 70.31 |
| Hydrogen        | . | . | . | . | 5.95  |
| Oxygen          | . | . | . | . | 23.74 |
| <hr/>           |   |   |   |   |       |
| Hydrated acid   | . | . | . | . | 100   |
| <i>Salt.</i>    |   |   |   |   |       |
| Oxide of silver | . | . | . | . | 47.73 |
| Anhydrous acid  | . | . | . | . | 52.27 |
| <hr/>           |   |   |   |   |       |
| Silver salt     | . | . | . | . | 100   |

Now, the atomic weight of oxide of silver is 116; therefore,

$$\text{As } 47.73 : 52.27 :: 116 : x$$

$x = 127.03$ , the atomic weight of the anhydrous acid, and  $127.03 + 9 = 136.03$ , the atomic weight of the hydrated acid; and, to deduce from this number the formula of the hydrated acid, we have, first, the proportions:—

$$\text{As } 100 : 70.31 :: 136.03 : x; x = 95.64$$

$$\text{As } 100 : 5.95 :: 136.03 : x; x = 8.09$$

$$\text{As } 100 : 23.74 :: 136.03 : x; x = 32.29$$

Then, by dividing each of these numbers respectively by the atomic weights of carbon, hydrogen, and oxygen, we have

$$\frac{95.64}{6} = 15.94 \text{ for the carbon,}$$

$$\frac{8.09}{1} = 8.09 \text{ for the hydrogen,}$$


$$\frac{32.29}{8} = 40.36 \text{ for the oxygen,}$$

numbers which evidently correspond closely with the formula  $C_{16}H_8O_4$ , which is, therefore, the rational formula of the acid in question; and which, when calculated in per-centage parts, agrees almost exactly with that determined by experiment. Thus,

| Calculation.      | Experiment. |
|-------------------|-------------|
| C 70.58 . . . . . | 70.31       |
| H 5.88 . . . . .  | 5.95        |
| O 23.54 . . . . . | 23.74       |
| <hr/> 100         | <hr/> 100   |

2. *An Organic Base*.—The atomic weight and formula of this interesting class of bodies are best determined by analyzing with great accuracy the insoluble double salts which they form with *bichloride of platinum*.

*Example*.—*Hofman* and *Muspratt* obtained, by acting on *nitrotoluide* with sulphuretted hydrogen, a crystalline body having basic properties, 0.1955 gramme of which, by combustion with oxide of copper, gave 0.5630 gramme of carbonic acid and 0.1515 gramme of water. A double salt of the hydrochlorate of this base and platinum was formed, 0.4337 gramme of which gave, by cautious ignition, 0.1372 gramme of platinum. Now there is every reason for supposing that this double salt is analogous in composition to the double chloride of platinum and ammonium



if so, its atomic weight is found from the proportion—

As  $0.1372 : 0.4337 :: 98.68$  (the atomic weight of platinum) :  $x$

$x = 311.93$ , and by deducting from this number the sum of the atomic weight of one equivalent of bichloride of platinum (169.68) and one equivalent of hydrochloric acid 36.5, we get the atomic weight of the new base,  $311.93 - 206.18 = 105.75$ .



The per-centage composition of the base, as found experimentally, is—

|          |   |   |   |   |   |       |
|----------|---|---|---|---|---|-------|
| Carbon   | . | . | . | . | . | 78.53 |
| Hydrogen | . | . | . | . | . | 8.61  |
| Nitrogen | . | . | . | . | . | 12.86 |
|          |   |   |   |   |   | <hr/> |
|          |   |   |   |   |   | 100   |

from which numbers its empirical formula may be deduced thus:

$$\text{As } 6 : 78.53 :: 1 : x; x = 13.09$$

$$\text{As } 1 : 8.61 :: 1 : x; x = 8.61$$

$$\text{As } 14 : 12.86 :: 1 : x; x = 0.918$$

or  $\text{C}_{14}\text{H}_9\text{N}$ , which agrees best with the experimental numbers. Thus:

|                 |   |   |   |    |   |       |       |
|-----------------|---|---|---|----|---|-------|-------|
| $\text{C}_{14}$ | . | . | . | 84 | . | .     | 78.50 |
| $\text{H}_9$    | . | . | . | 9  | . | .     | 8.41  |
| N               | . | . | . | 14 | . | .     | 13.09 |
|                 |   |   |   |    |   | <hr/> |       |
|                 |   |   |   |    |   | 107   |       |
|                 |   |   |   |    |   |       | <hr/> |
|                 |   |   |   |    |   |       | 100   |

The theoretical number 107 agrees so well with the experimental number 105.75, that there can be no doubt that  $\text{C}_{14}\text{H}_9\text{N}$  is the correct formula for the new substance.

## CHAPTER IV.

### ON THE QUANTITATIVE ANALYSIS OF MINERAL WATERS.

THE substances to be estimated may be, amongst bases, *potassa, soda, lithia, ammonia, lime, magnesia, strontia, alumina, protoxide of manganese and iron*, and, amongst electro-negative bodies, *sulphuric, phosphoric, silicic, nitric and carbonic acids; chlorine, bromine, iodine, fluorine and sulphuretted hydrogen; crenic and apocrenic acids*.

If the operator should have the opportunity of collecting the water himself at the source, he should pay attention to the following particulars:—1st, its temperature as compared with that of the air; 2d, the geological formation of the locality whence the spring originates; 3d, the yield of water;

4th, its physical appearance; 5th, whether or not it deposits any solid matter in the pipes or channels through which it makes its exit from the spring or well; 6th, its smell and taste: in short, he should make himself acquainted as accurately as possible with every particular he can obtain with respect to the general history of the water he is about to analyze.

The quantity of water required for a thorough examination is about twelve gallons; if, however, the analyst should have an opportunity of evaporating down a considerable quantity (say *ten gallons* to two or three pints) on the spot for the detection and estimation of those ingredients which only exist in minute quantities, such as *iodine, bromine, phosphoric acid, fluorine, manganese, alumina, strontia, lithia*, and the *organic acids*: or, if he should choose to dispense with a search for these bodies, then a few pints will suffice for a complete analysis of the water for the other ingredients. It is important, however, that a certain quantity of the water should be collected at the spring for the express determination of the total amount of carbonic acid; for this purpose, four or five stoppered bottles of about a pint capacity should be charged each with one ounce of a strong solution of chloride of calcium and an ounce and a half of ammonia, free from carbonic acid; they should then be filled with the water taken slowly from the spring, and poured quietly in, to prevent any loss of carbonic acid from splashing; all the carbonic acid contained in the water will thus be precipitated in the form of carbonate of lime. Thus



The precipitates in the different bottles, which should be nearly alike in quantity, are collected on a filter, dried at  $212^\circ$ , and weighed. They are then mixed together and analyzed by *Fresenius* and *Will's* method; the result shows the total amount of carbonic acid in the united volumes of the several bottles of water.

Should the water contain sulphuretted hydrogen, the bottles are charged with a small quantity of a solution of *arsenious acid* in hydrochloric acid; they are then filled carefully with the water as before, sulphuret of arsenic is precipitated. It is collected on a filter, washed with cold water, dried at  $212^\circ$  and weighed; for its composition, see page 345. From the weight obtained, the quantity of sulphuretted hydrogen in the volume of water from which it was precipitated is calculated.

*Determination of the Specific Gravity of the Water.*—This is effected in a very simple manner by the method described in page 117 *Morfit's Manipulations*. As the specific gravity bottle has been adjusted with distilled water at 60° F., it is of course necessary that the mineral water should be brought to the same temperature previous to weighing it. The bottle contains exactly 1000 grains of distilled water; the specific gravity, therefore, of the mineral water is exactly as its weight, water being 1000.

*Determination of the Total Amount of Solid Ingredients.*—One thousand grains of the water are carefully evaporated to dryness on the water-bath in a platinum crucible, the residue is dried at various temperatures, and the weight taken when no further diminution is perceptible. If the water contain any considerable amount of earthy chlorides, and especially if it contain ammoniacal salts, a very exact result cannot, in this manner, be obtained regarding the amount of the solid contents, for the earthy chlorides require for their existence a small proportion of water, which they do not lose at 212°, while, at a higher temperature, some hydrochloric acid may be set free; chloride of ammonium is also partly volatilized at temperatures higher than 212°. If the water does not contain *ammonia*, *oxide of iron*, or *alumina*, *Schweitzer*\* recommends, as an excellent control, to change the carbonates, chlorides, &c., into sulphates, the total amount of which must closely correspond with the amount of the various ingredients when computed as sulphates; this method is indeed applicable when ammonia is present, as that substance being dissipated by heat must be deducted from the total amount of ingredients obtained by analysis. Another method, in cases where great accuracy is desirable, is to evaporate the water with a proportionate quantity of chemically pure anhydrous carbonate of soda sufficient to decompose the earthy chlorides and sulphates. This method of evaporating with carbonate of soda is advantageous, moreover, in preventing the formation of sulphate of lime, which is a troublesome ingredient, inasmuch as it adheres closely to the evaporating vessel, is not soluble in dilute hydrochloric acid, and very sparingly soluble in water. As the solid matters obtained by the evaporation of a mineral water are frequently very deliquescent, the crucible should be

\* See his account of the analysis of the Bonnington water, *Mem. Chem. Soc.*, vol. ii. p. 201.

cooled underneath a receiver in close proximity to a vessel containing sulphuric acid, and weighed as quickly as possible.

The general character of the water having been ascertained by a qualitative examination, conducted in the manner directed in Part I. p. 191, the quantitative examination is proceeded with in the following manner.

*Estimation of the Sulphuric Acid.*—Ten thousand grains (more or less, according as the preliminary experiment has indicated a greater or less amount of sulphuric acid) are acidified with hydrochloric acid, and precipitated at a boiling temperature by chloride of barium; the precipitate is allowed to settle, then collected on a filter, washed, dried, ignited, weighed, and the amount of sulphuric acid calculated as directed, page 253.\*

*Estimation of the Chlorine, Iodine, and Bromine†* (should the water contain the two latter), *conjointly*.—Two thousand or three thousand grains of the water according to the quantity of chlorine, &c., supposed to be present, are acidified with nitric acid, the chlorine precipitated with nitrate of silver, and estimated as directed, page 305.

Should the water contain organic matter, it should be freed from it before estimating the chlorine, or it would be partly precipitated, together with the silver salt, increasing its weight; with this view it should be evaporated with carbonate of soda, the liquid filtered from the earthy carbonate thereby precipitated evaporated to dryness, the residue fused, redissolved in water, nitric acid added, and then precipitated with nitrate of silver. As an illustration of the interference of organic matter with a correct determination of the chlorine, *Schweitzer* obtained from the Bonnington water, as a mean of several experiments, 10.053 grains of chloride of silver from 4 ounces of the *fresh* water, and 9.694 grains after evaporating it with carbonate of soda, as above described.

*Estimation of the total Amount of Lime and Magnesia, Silicic Acid, and Oxide of Iron.*—About 1200 grains of the water are acidified with nitric acid, and evaporated to dryness at a heat below ebullition. The perfectly dry residue is

\* It is better to determine the various ingredients of a mineral water from *weighed* than from *measured* quantities of the water; if the operator has not the advantage of the large balance, he can employ a specific gravity bottle, the contents of which, when quite full and the stopper in its place, are known accurately.

† For Fehling's method of estimating the Bromine in Salt Springs, see *Ch. Gaz.* 7, 42.



digested with dilute hydrochloric acid, the silicic acid remains undissolved, having, by the evaporation, been reduced to its insoluble condition. It is separated by filtration, and estimated as directed, page 396. The filtrate which contains the oxide of iron, lime, and magnesia, in the form of chlorides, is supersaturated with ammonia, by which oxide of iron is precipitated, and is collected and determined as directed at page 289. The lime is precipitated from the filtrate from the oxide of iron with oxalate of ammonia, and estimated as carbonate, in the manner described at page 255, and the magnesia, from the filtrate from the oxalate of lime (concentrated, if necessary, by evaporation), with phosphate of soda, and estimated as pyrophosphate, as directed, page 257.

*Schweitzer* proceeds in a different manner. He commences with evaporating a large quantity of the water down to a few ounces, together with a proportionate quantity of anhydrous carbonate of soda; he throws the residue on a filter, and lixiviates the solid matter with boiling distilled water till the filtered liquor gives no indications of sulphates and chlorides; he then makes analysis of the soluble and insoluble ingredients separately. The soluble portion contains the alkalies and magnesia in the form of sulphates, chlorides, nitrates, bromides, or iodides; and the insoluble portion of the earths in the form of carbonates, silica, oxide of iron, oxide of manganese, &c.

*Estimation of the Lime, Magnesia, and Oxide of Iron dissolved in the water by free Carbonic Acid.*—Ten or twelve thousand grains of the water are boiled for some time in a flask, the free carbonic acid is hereby expelled, and the substances which it held in solution are precipitated. The operator must be careful not to allow the volume of the water to be much diminished by the ebullition, or a portion of *sulphate* of lime may be precipitated, together with the earthy carbonates; boiling distilled water should be added from time to time to the flask. The precipitate is collected on a filter, dissolved in hydrochloric acid, a few drops of nitric acid added, and the oxide of iron, lime, and magnesia separated from each other in the usual manner.

*Schweitzer* dissolves the insoluble matter obtained by his process in nitric acid, evaporates the solution to dryness, and leaves the residue for several hours in contact with nitric acid; he then boils with hydrochloric acid, and, having separated the silicic acid, he precipitates the iron by succinate of

ammonia. To the filtrate from the persuccinate of iron he adds hydrosulphuret of ammonia, which throws down the manganese; he boils the sulphuret of manganese with hydrochloric acid, precipitates it with carbonate of soda, washes and ignites the precipitate which he estimates as *red oxide of manganese*. Having removed the excess of hydrosulphuret of ammonia from the fluid filtered from the sulphuret of manganese, by boiling it with hydrochloric acid, *Schweitzer* mixes it in a vessel that can be closed with ammonia; the precipitate which hereupon forms he filters quickly, protecting it as much as possible from the air, and, having washed and ignited it, he redissolves it in hydrochloric acid. He mixes the solution with bicarbonate of potash, and, having dissolved the precipitate (should any form) in hydrochloric acid, he boils the solution with caustic soda; if a precipitate should hereby be produced, it is oxide of iron, and must be redissolved in hydrochloric acid and precipitated by ammonia: the caustic ley may contain alumina; to obtain which, it is supersaturated with hydrochloric acid, and precipitated by ammonia. All the magnesia present is retained in solution by the bicarbonate of potash; to obtain it, *Schweitzer* neutralizes the fluid with hydrochloric acid, evaporates it quickly with carbonate of potash, and, when nearly dry, mixes it with boiling water and filters; he then washes, ignites, and estimates the residue as magnesia. The ammoniacal solution from which the magnesia had been precipitated contains the *lime*, which is precipitated with oxalate of ammonia.

*Estimation of the Lime and Magnesia in the Filtrate from the Precipitate produced by Ebullition.*—They are determined in the usual manner, the lime being first precipitated by oxalate of ammonia, and the magnesia by phosphate of soda. The joint amount of the oxide of iron, lime, and magnesia obtained in the precipitate by boiling, and, in the filtrate, ought to correspond with the total quantity of those ingredients found by the previous experiment.

*Estimation of the Alkalies.*—About 10,000 grains of the water are evaporated to about one-half, then mixed with excess of baryta water, filtered, carbonate of ammonia added, again filtered, the filtrate evaporated to dryness, ignited, and the alkalies separated from each other, and determined as directed, page 238. If, however, the water contains a fixed alkaline carbonate, a different plan is adopted. The water is concentrated by evaporation, filtered, and divided into two

parts; in one, the amount of chlorine is at once determined by nitrate of silver; the other is evaporated to dryness with slight excess of hydrochloric acid, the residue ignited, redissolved in water, and precipitated in its turn by nitrate of silver. The amount of chlorine obtained from this second portion above that obtained from the first is the equivalent of the quantity of carbonated alkali originally present in the water. Having thus ascertained the amount of carbonated alkali, the total quantity of the alkalies present is found by boiling the water with chloride of barium for some time, and then adding baryta water and filtering; the filtrate is precipitated with carbonate of ammonia, again filtered and evaporated to dryness; the residue consists of the alkalies in the form of chlorides. *Fresenius* says, that a mineral water which contains an alkaline carbonate cannot contain *soluble* lime and magnesia salts, and that, therefore, all the lime and magnesia which is found must be considered as carbonates kept in solution by the agency of carbonic acid. It may be doubted whether this proposition is altogether correct; it is certain that a soluble double carbonate of soda and magnesia exists, and there are grounds for believing that a similar double salt of lime and soda may be formed under the same circumstances in a mineral water; it is better, at all events, to determine the lime and magnesia in the residue left by evaporation than in the precipitate formed by boiling.

*Estimation of the Iodine.*—The filtrate from the precipitate produced by evaporating ten or twelve gallons of the water down to two or three pints, is evaporated to dryness together with carbonate of soda, the residue is digested repeatedly with alcohol, the alcoholic extract evaporated to dryness, and the residue gently ignited in a platinum crucible to destroy the organic matter; it is then dissolved in water and filtered, the clear liquid is carefully neutralized with dilute hydrochloric acid, and then precipitated with protiodide of palladium; the protiodide of palladium, after standing at rest twelve hours, is collected on a filter, washed with warm water, dried at a temperature below  $212^{\circ}$ , and weighed. For its composition, see page 424.

*Estimation of the Bromine.*—The fluid filtered from the protiodide of palladium is saturated with sulphuretted hydrogen gas, in order to remove the excess of the palladium salt; it is then filtered, boiled with nitric acid, filtered again if

necessary, and then precipitated with nitrate of silver; the precipitate which contains all the bromine, together with the chlorine in the form of bromide and chloride of silver, is analyzed according to the directions given, page 422. *Schweitzer*, having separated the excess of the palladium salt, evaporates to dryness, re-dissolves in water, concentrates, and then adds to the solution a few drops of an ammoniacal solution of chloride of silver, prepared by mixing one part of a saturated solution of chloride of silver in ammonia, with one part of ammonia and one of water; this solution, though it produces no turbidity in a saturated solution of chloride of sodium, he finds to indicate a very minute quantity of bromine, which it precipitates as bromide of silver.\*

*Estimation of the Nitric Acid.*—About a gallon of the water, more or less, according to the amount of solid ingredients, is concentrated to a few ounces, filtered from the insoluble matter, and the filtrate macerated with a sufficient quantity of sulphate of silver to change the chlorides, iodides and bromides into sulphates. The fluid separated from the silver precipitate is made alkaline by carbonate of soda, concentrated in the water bath, and then mixed in a tubulated retort, with an adequate quantity of chemically pure sulphuric acid (previously boiled), more than sufficient to convert all the ingredients present into bisulphates. The mixture is heated on the sand bath, and the vapours conducted into a glass receiver containing a solution of hydrate of barytes, the distillation being stopped as soon as fumes of sulphuric acid begin to make their appearance. The fluid thus obtained in the receiver is evaporated in the water bath nearly to dryness, and the residue left for twelve hours exposed to the air, in order to change the excess of hydrate of baryta into a carbonate. It is advisable to evaporate the fluid twice nearly to dryness, and filter each time, and to use for lixiviation as little water as possible, so as to prevent any of the carbonate of baryta from being dissolved. The carbonate of baryta being separated, the fluid is precipitated with dilute sulphuric acid, and from the amount of sulphate of baryta obtained the quantity of nitrate is calculated, and from this the proportion of nitric acid. This method was adopted by *Schweitzer* in his analysis of the *Bonnington* water.

\* See his analysis of *Bonnington* water, also of the sea water in the English Channel, near Brighton. L. and E. Phil. Mag., vol. xv. p. 51.



*Estimation of the Ammonia.*—A considerable measured quantity of the water is concentrated by evaporation, having previously acidified it slightly with hydrochloric acid. The concentrated fluid is mixed in a tubulated glass retort with considerable excess of caustic soda, and boiled for a long time, the evolved vapors being condensed in a receiver containing dilute hydrochloric acid, and kept cool by being surrounded with ice or cold water. The boiling having been continued till only two or three ounces of fluid remain in the retort, the distilled fluid is mixed with bichloride of platinum, and evaporated in a porcelain vessel. The dry residue is lixiviated by a mixture of two volumes of alcohol and one of ether, in which the ammonio-chloride of platinum is perfectly insoluble; it is then dried at  $212^{\circ}$  and weighed: for its composition, see page 249. To control the correctness of the weight, the double salt may be ignited, and the weight of the platinum obtained compared with theory. *Schweitzer* states, that the addition of bichloride of platinum to the distillate, previous to evaporating it even at a temperature below  $212^{\circ}$ , is quite essential to obtaining correct results; inasmuch as the chloride of ammonium rises with the aqueous vapors—a fact easily ascertained by covering the vessel during evaporation with filtering paper, which, when lixiviated, will clearly evince the presence of chloride of ammonium, as has been noticed by *Berzelius*.

*Estimation of Lithia.*—Should there be reasons for suspecting the presence of this alkali, it must be looked for in the filtrate, produced by evaporating 10 or 12 gallons of the water, about a pound of which should be retained for the purpose. It is boiled to dryness with excess of carbonate of soda; the residue redissolved in water, filtered, and again evaporated to dryness with phosphate of soda; an insoluble double phosphate of soda and lithia is hereby formed: for the properties and composition of which see page 252.

*Estimation of the Protoxide of Manganese.*—This is to be looked for in the precipitate produced by boiling down a large quantity of the water; a portion of it is dissolved in hydrochloric acid, supersaturated with ammonia, and precipitated by hydrosulphuret of ammonia; the precipitate, which may contain *iron, alumina, manganese, and possibly strontia*, is redissolved in hydrochloric acid; and, nitric acid having been added to peroxidize the iron, the alumina is separated by caustic potassa, and the iron from the manganese by suc-

ciate or benzoate of ammonia; the *strontia*, should it be present, is precipitated from the filtrate with solution of sulphate of lime.

*Estimation of the Phosphoric Acid.*—This is also to be looked for in the precipitate by boiling down several gallons of the water, a portion of which is dissolved in hydrochloric acid, and the phosphoric acid tested for and precipitated by sesquichloride of iron and acetate of soda, in the manner directed, page 385; another portion of the precipitate may be tested for *fluorine* by dissolving it in hydrochloric acid, precipitating by ammonia, and heating the washed and dried precipitate in a platinum crucible with sulphuric acid, and observing whether the evolved fumes have any action on a clean glass plate held over the crucible.

*Estimation of the Organic Acids (Crenic and Apocrenic).*—According to the observations of *Mulder*, which will be referred to again in the section on the analysis of soils, there exist in the soil at least seven different organic substances, viz: *crenic acid*, *apocrenic acid*, *geic acid*, *humic acid*, *ulmic acid*, *humin*, and *ulmin*; he divides these substances into two groups—the *humic*, including *geic acid*, *humic acid*, *ulmic acid*, *humin* and *ulmin*, and the *crenic*, including *crenic* and *apocrenic* acids; of these bodies *humin* and *ulmin* are insoluble in water and in alkalies, the others are more or less soluble in both; the *humic* group are precipitated from their alkaline solution by an acid, while *apocrenic* and *crenic* acids are retained in solution; none of these acids contain nitrogen as a constituent element, though they all stand in the closest relation to ammonia, with which they form salts in the soil, and the same is probably the case when the two latter exist in mineral waters.

The *crenic* and *apocrenic* acids are not precipitated from their alkaline solutions by an acid as above stated. To detect and estimate them in water, therefore, a weighed portion of the precipitate, produced by boiling down some gallons, is boiled for some time with potassa ley, then passed through a filter, acidified with acetic acid, and acetate of copper added, the formation of a brownish precipitate indicates apocrenate of copper, in which, according to *Mulder*, about 50 per cent. of apocrenic acid is contained. The fluid filtered from this precipitate is mixed with excess of carbonate of ammonia, and then boiled; if *crenic* acid be present, a bluish green precipitate

is formed, which, when dried at  $284^{\circ}$  Fahrenheit, contains, according to *Mulder*, 74.12 per cent. of oxide of copper.

Besides these organic acids most mineral waters contain certain other organic matters,\* which may be determined in the filtrate from the precipitate produced by boiling down a considerable quantity of the water, by evaporating it to dryness with carbonate of soda: the residue is dried at about  $284^{\circ}$  Fahrenheit, weighed, ignited, and then again weighed: the loss indicates the amount of extracted matter.

*Arrangement of the Results of Analysis.*—The usual method, and the one which seems the most rational (though it must be observed that there is a diversity of opinion on the subject amongst chemists), is to arrange the electro-negative and electro-positive ingredients, as established by direct experiment, into binary combinations, in the ratio of their mutual affinities, the strongest acid being combined with the strongest base, paying attention, however, to the fact, long since pointed out by *Berthollet*, viz: that the force of affinity is considerably modified by the degree of solubility of the salts. It is impossible to lay down any but very general rules for the classification of the results of the analysis of a mineral water, so much depending on the nature of those results, and on various circumstances connected with the history of the water; but, however the results are arranged, the total amount of the fixed constituents must correspond to the joint amount of the several ingredients; the amounts of the chlorine and sulphuric acid obtained must agree with the joint amounts of the chlorides and sulphates, and the quantity of lime obtained from an evaporated quantity of the water should agree with that obtained jointly from the precipitate produced by boiling a corresponding weight of the water, and from the boiled water filtered from that precipitate.

\* Dupasquier's method of determining the presence of organic matter in water is as follows:—Take from 25 to 50 grms. of the water to be examined in a small flask; add to it a few drops of a solution of chloride of gold, so as to impart to it a faint yellowish tint, and then boil the liquid. If the water only contains the usual quantity of organic matter, it retains its yellowish tint; if, on the contrary, it contains an abnormal quantity, the water at first becomes brown, and then assumes a bluish tint, which indicates the decomposition of the gold salt; this tint becomes more and more marked by continuing the boiling, if the proportion of organic matter is considerable; but the least brownish tint of the liquid indicates with certainty that the organic matter exceeds the ordinary proportion.—*Comptes Rendus*, April 5, 1847.

Of the several analyses of waters which have lately been published, we select that of the *Thames* water, conducted by *Mr. G. F. Clark*,\* under the superintendence of *Dr. Hofmann*, as an illustration of the method of arranging the results of analysis according to the views of *Fresenius*.

The water was collected on the 16th of December, 1847, from the middle of the river, two hours after high tide, in the neighborhood of *Twickenham*, which is fourteen miles from London Bridge.

The temperature of the water was  $9^{\circ}.5$  Cent., or  $49^{\circ}.1$  Fahr., that of the air being  $13^{\circ}$  Cent., or  $55^{\circ}.4$  Fahr.

The specific gravity was 1.0003, distilled water being 1. A careful qualitative analysis pointed out the presence of *potassa*, *soda*, *lime*, *magnesia*, *iron*, *alumina*, *chlorine*, *sulphuric acid*, *silicic acid* and *organic matter*. A trace of *phosphoric acid* was also observed; neither *bromine* nor *iodine* could be detected in the water, even after considerable concentration. The quantitative analysis gave the following results:—

#### A. Determination of the Total Amount of Fixed Constituents.

| Amount of water employed.<br>Grammes. | Amount obtained.<br>Gramme. | Per centage. |
|---------------------------------------|-----------------------------|--------------|
| I. 1182.582                           | .378                        | .0319639     |
| II. 1000.208                          | .323                        | .0322932     |
| Mean . . .                            |                             | .03212855    |

#### B. Determination of Sulphuric Acid.

| Amount of water<br>employed.<br>Grammes. | Amount of sulphate<br>of baryta obtained.<br>Gramme. | Per centage of sulphuric<br>acid. |
|------------------------------------------|------------------------------------------------------|-----------------------------------|
| I. 610.293                               | .350                                                 | .0024265                          |
| II. 581.275                              | .330                                                 | .0024294                          |
| Mean. . . .                              |                                                      | .0024279                          |

\* Quarterly Journ. of the Chem. Soc., in which periodical several other analyses of mineral waters will be found, and may be profitably consulted by the student. *Schweitzer's* elaborate analysis of the *Bonnington* water, to which allusion has repeatedly been made in the text, will amply repay a careful perusal.



*C. Determination of Chlorine.*

| Amount of water<br>employed.<br>Grammes. | Amount of chloride<br>of silver obtained.<br>Gramme. | Per centage of<br>chlorine. |
|------------------------------------------|------------------------------------------------------|-----------------------------|
| I. 610.65                                | .039                                                 | .0015794                    |
| II. 580.35                               | .038                                                 | .0016192                    |
|                                          |                                                      | <hr/>                       |
|                                          |                                                      | .0015993                    |

*D. Determination of Silicic Acid.*

| Amount of water<br>employed.<br>Grammes. | Amount of silicic<br>acid obtained.<br>Gramme. | Per centage of<br>silicic acid. |
|------------------------------------------|------------------------------------------------|---------------------------------|
| I. 1182.582                              | .0045                                          | .0003805                        |
| II. 1000.208                             | .0040                                          | .0003999                        |
|                                          |                                                | <hr/>                           |
|                                          |                                                | .0003902                        |

*E. Determination of Lime and Magnesia.*

| Amount of water<br>employed.<br>Grammes. | Amount of carbonate<br>of lime obtained.<br>Gramme. | Per centage of<br>lime. |
|------------------------------------------|-----------------------------------------------------|-------------------------|
| I. 1000.598                              | .2096                                               | .0117305                |
| <sup>a</sup> II. 906.002                 | .1899                                               | .0117377                |
|                                          |                                                     | <hr/>                   |
|                                          | Mean . . .                                          | .0117341                |

*Determination of the Magnesia in the Filtrate from the Oxalate of Lime.*

| Amount of water<br>employed.<br>Grammes. | Amount of pyrophosphate<br>of magnesia obtained.<br>Gramme. | Per centage of<br>magnesia. |
|------------------------------------------|-------------------------------------------------------------|-----------------------------|
| I. 1000.598                              | .0195                                                       | .0007140                    |
| <sup>b</sup> II. 906.002                 | .0175                                                       | .0007077                    |
|                                          |                                                             | <hr/>                       |
|                                          |                                                             | .0007108                    |

*F. Determination of the Alkalies.*

| Amount of water<br>employed.<br>Grammes. | Amount of mixed<br>chlorides obtained.<br>Gramme. |
|------------------------------------------|---------------------------------------------------|
| I. 1000.000                              | .0305                                             |
| <sup>a</sup> II. 1184.304                | .0390                                             |

*Determination of Potassa.*

| Amount of water<br>employed.<br>Grammes. | Amount of chloride of<br>platinum and potassium<br>obtained.<br>Gramme. | Per centage of<br>potassa. |
|------------------------------------------|-------------------------------------------------------------------------|----------------------------|
| I. 1000.000                              | .0265                                                                   | .0005105                   |
| II. 1184.304                             | .0320                                                                   | .0005205                   |
| Mean . . .                               |                                                                         | .0005155                   |

*Determination of Soda.*

| Amount of water<br>employed.<br>Grammes. | Amount of chloride of<br>sodium obtained.<br>Gramme. | Per centage of<br>soda. |
|------------------------------------------|------------------------------------------------------|-------------------------|
| I. 1000.000                              | .0022407                                             | .0011867                |
| <sup>c</sup> II. 1184.304                | .0024679                                             | .0013071                |
| Mean . . .                               |                                                      | .0012469                |

3193.6 grammes of the water were evaporated down to 574.475 grammes. The precipitate, which was formed and separated, weighed 5.558 grammes.

*Determination of Organic Matter in the Filtrate.*

| Amount of filtrate<br>employed.<br>Grammes. | Amount of organic<br>matter burnt off.<br>Gramme. | Per centage upon the<br>whole amount of water. |
|---------------------------------------------|---------------------------------------------------|------------------------------------------------|
| I. 81.520                                   | .148                                              | .0032629                                       |
| II. 129.839                                 | .236                                              | .0032668                                       |
| Mean . . .                                  |                                                   | .00326485                                      |

*Determination of Organic Matter in the Precipitate.*

| Amount of precipitate<br>employed.<br>Gramme. | Amount of organic<br>matter burnt off.<br>Gramme. | Per centage upon the<br>whole amount of water. |
|-----------------------------------------------|---------------------------------------------------|------------------------------------------------|
| I. .0925                                      | .0090                                             | .0016918                                       |
| II. .1565                                     | .0155                                             | .0017221                                       |
| Mean . . .                                    |                                                   | .00170695                                      |

*Determination of Carbonic Acid.*—At the time of collecting the water, a siphon capable of containing 557 cubic centimetres (about 34 cubic inches) of distilled water was filled

three times, and discharged into a bottle containing chloride of calcium and ammonia; the precipitate which was formed weighed, when dry, 0.937 gramme.

| Amount of precipitate<br>employed.<br>Gramme. | Amount of carbonic<br>acid evolved.<br>Gramme. | Amount calculated on<br>the whole precipitate<br>Gramme. |
|-----------------------------------------------|------------------------------------------------|----------------------------------------------------------|
| I. .4175                                      | .156                                           | .3052263                                                 |
| II. .4585                                     | .155                                           | .3167611                                                 |

Mean . . . . ..3109937

per centage in the water .01860565.

Arrangement of the results according to the principles laid down by *Fresenius*.\*

The potassa and soda are assumed to be in combination with sulphuric acid: we have, therefore, .0005155 potassa combined with .0004387 sulphuric acid, forming .0009542 sulphate of potash, and .0012469 soda combined with .0016104 sulphuric acid, forming .0028573 sulphate of soda.

|                                              |           |          |
|----------------------------------------------|-----------|----------|
| Total per centage amount of sulphuric acid   | . . . . . | .0024279 |
| Of which there is combined with the alkalies | . . . . . | .0020491 |

|                   |           |          |
|-------------------|-----------|----------|
| Leaving . . . . . | . . . . . | .0003788 |
|-------------------|-----------|----------|

which is assumed to be in combination with .0002651 lime, forming .0006439 sulphate of lime.

|                                                |           |          |
|------------------------------------------------|-----------|----------|
| Total per centage amount of lime               | . . . . . | .0117341 |
| Of which there is combined with sulphuric acid | . . . . . | .0002651 |

|                   |           |          |
|-------------------|-----------|----------|
| Leaving . . . . . | . . . . . | .0114690 |
|-------------------|-----------|----------|

Total per centage amount of chlorine . . . . .0015993  
which is assumed to be combined with .0009010 calcium, forming .0025003 chloride of calcium, leaving .010276 lime, which must be in combination with .0080202 carbonic acid, forming .0182278 carbonate of lime.

|                                                                                             |           |          |
|---------------------------------------------------------------------------------------------|-----------|----------|
| Total per centage amount of magnesia                                                        | . . . . . | .0007108 |
| Which is assumed to be combined with carbonic acid, forming .0014673 carbonate of magnesia. | . . . . . | .0007565 |

The following are, therefore, the proportions in which the ingredients of the water exist.

\* Quantitative Analysis.

|                                                     | In 100 litres.<br>Grammes. | In a gall.<br>Grains. |
|-----------------------------------------------------|----------------------------|-----------------------|
| Sulphate of potassa . . .                           | .9542                      | .66794                |
| ———— of soda . . .                                  | 2.8573                     | 2.00011               |
| ———— of lime . . .                                  | .6439                      | .45073                |
| Chloride of calcium . . .                           | 2.5003                     | 1.75021               |
| Carbonate of lime . . .                             | 18.2278                    | 12.75946              |
| ———— of magnesia . .                                | 1.4673                     | 1.02711               |
| Silicic acid . . . . .                              | .3902                      | .27314                |
| Phosphoric acid . . . .                             | traces                     | traces                |
| Alumina . . . . .                                   | traces                     | traces                |
| Carbonate of oxide of iron .                        | traces                     | traces                |
| Soluble organic matter . .                          | 3.2648                     | 2.28536               |
| Insoluble do. . . . .                               | 1.7069                     | 1.19483               |
|                                                     | <hr/> 32.0127              | <hr/> 22.40889        |
| Direct determination of fixed constituent . . . . . | 32.1285                    | 22.48995              |

Having deducted from the per centage of carbonic acid that portion in combination with lime and magnesia, the per centage of free carbonic acid is found to be .0098289, corresponding to 513.44 cubic centimetres in 100 litres, or 1.4233 cubic inches in an imperial gallon.

The iron and alumina were not separated, but both determined in the state of sesquioxides; the mean of two experiments gave .00001335 per cent.

## CHAPTER V.

### ON THE ANALYSIS OF SOILS.

THE following directions are from a paper issued from the "*Museum of Economic Geology*."\*

In selecting specimens, care must be taken to obtain a fair average sample, and to insure the true subsoil or subjacent

\* Pharm. Journ., vol. iv.



hard rock, clay, sand, &c. Specimens of the latter should be obtained as near as possible beneath the spot whence the soil may have been selected, for it sometimes happens that the soil of a field varies in places from resting on different kinds of subsoil.

The quantity of soil taken as a specimen should weigh about a pound, which should be tied up in a canvas bag and labeled.

With respect to specimens of subsoils, if of marl, sand, or clay, portions weighing about a pound should be tied up in a canvas bag, labeled to correspond with the respective soils above them. If the subjacent rocks be hard, a piece also weighing about a pound, and fresh broken from the body of the rock, as nearly as possible beneath the surface whence any specimen of soil may have been selected should suffice, and should be wrapped in strong brown paper, labeled to correspond with the soil above it.

I. Dry the specimen at  $212^{\circ}$  Fahr., powder, sift through a lawn sieve, rub in a mortar, again dry at  $212^{\circ}$ , and put into a stoppered bottle.

II. Spread 500 grains on a sheet of writing paper, and expose to the air for twelve hours; note the increase of weight; from seven to ten grains is a favorable indication.

III. Determine the amount of carbonic acid in 100 grains, by treating it in a counterpoised bottle with hydrochloric acid with the usual precautions.

IV. Determine the amount of organic matter in 200 grains, by heating to redness in a platinum crucible, with occasional stirring; weigh the residue, and divide it into two equal parts: introduce one into a counterpoised bottle containing hydrochloric acid, and estimate the disengaged carbonic acid; if this be less than that obtained before calcination, the difference must be added to the weight of the calcined product under operation, and this deducted from the weight before calcination will indicate the amount of organic matter.

V. The other half of the residue left after calcination is now to be boiled in a flask with about an ounce of hydrochloric acid. By this means all the ingredients except the silica and part of the alumina will be dissolved, some of them being decomposed. The insoluble part is to be separated by filtration, washed until no longer acid, and dried. The solution, together with the washings of the insoluble powder, is to be

marked A, and put aside for further examination. The powder is to be finely pulverized and mixed with four times its weight of dried carbonate of soda; the mixture is then to be heated in a platinum crucible until it fuses into a glass. The crucible and its contents being placed, while warm, in a Wedgewood dish containing distilled water, about an ounce of hydrochloric acid is to be added and heat applied. More acid and water may be added if necessary, until nothing more is dissolved. This being done, the solution and insoluble part are to be evaporated to dryness, in order to aggregate the silica held in suspension; and care must be taken, during this operation, that no hard lumps are left in the solution, as the silica sometimes forms a coating over such particles through which the acid will not act. The residue, after the evaporation, is to be heated with water mixed with about half an ounce of hydrochloric acid, the solution is to be filtered, and the insoluble part washed. The latter is the silica, which must be carefully heated to redness, and weighed while warm.\* To the solution from which the silica has been separated ammonia is to be added; the *alumina* is hereby precipitated, which is washed, ignited, and weighed with the same precautions as the silica.

VI. The solution A is now to be examined. For this purpose add ammonia in excess, and afterwards strong acetic acid in considerable excess, and boil the mixture; *phosphate of peroxide of iron* and *phosphate of alumina* (if present) will be precipitated. Collect and wash the precipitate, and label the solution C. Treat the precipitate with solution of caustic potassa, which will redissolve the *phosphate of alumina*, and leave the *phosphate of iron*: separate, wash, dry, and weigh the latter; add ammonia to the potash solution to throw down the phosphate of alumina, which is, in like manner, to be collected and weighed.

It must not be inferred that the phosphates of iron and alumina obtained in this manner existed as such in the soil; the phosphoric acid may have been, at least in part, in combination with lime or magnesia, while the iron may have been in the state of peroxide, and the alumina uncombined; but, on dissolving these ingredients in the hydrochloric acid, the

\* Or rather the crucible should be allowed to cool underneath a receiver close to a vessel containing sulphuric acid, and weighed with the cover on.

phosphate of lime or magnesia would be decomposed, and phosphate of iron and alumina formed. As this decomposition would always take place under the circumstances indicated, it next becomes a question whether the equivalent proportions of peroxide of iron, or alumina, or of phosphoric acid existed in excess. To determine this point, divide the solution c into two parts; to one add a few drops of solution of perchloride of iron, which, if any earthy phosphates still remain undecomposed, will occasion a precipitate of phosphate of iron, in which case it may be concluded that the whole of the iron originally in the solution has been obtained in the state of phosphate of iron. Continue the addition of perchloride of iron as long as a precipitate is formed, and treat this precipitate the same as that first obtained from solution A. If, on the other hand, no precipitate be formed from the perchloride of iron, it will be necessary to try whether there be more iron or alumina in the solution. In this case, add to the other half of the solution c liquid ammonia, so as to render it slightly alkaline; then add hydrosulphuret of ammonia, which will throw down peroxide of iron, oxide of manganese and alumina, if present; collect and wash this precipitate, and label the solution D. Dissolve the precipitate in hydrochloric acid and boil the solution, add caustic potassa in excess, which will throw down peroxide of iron and oxide of manganese, but will retain alumina in solution; the two former being thus separated, add hydrochloric acid to the filtered solution in slight excess, and finally precipitate the alumina by ammonia.

VII. The quantity of manganese contained in soils is usually so small as to render its separation from the iron unnecessary. Its presence may be indicated by the black color which the iron precipitate assumes on being exposed to the air, or by the smell of chlorine, which is afforded on adding a few drops of hydrochloric acid to the precipitate. If thought desirable to separate the two oxides, dissolve them in hydrochloric acid and add *precipitated carbonate of lime*, which will throw down the oxide of iron. Separate the precipitate, and add to the filtrate ammonia and oxalate of ammonia, by which the lime is removed; then add *caustic soda*. Collect, dry, and weigh the precipitate, which may be estimated as oxide of manganese.

VIII. The solution D may still contain lime, magnesia, and

salts of potassa and soda. Boil, to drive off any sulphuretted hydrogen which it may contain, then add oxalate of ammonia as long as a precipitate of oxalate of lime is formed. Collect, dry, and weigh this precipitate, and label the solution E; if the precipitate be dried at  $212^{\circ}$ , it will contain one atom of water.

IX. Add hydrochloric acid to the solution E; evaporate to dryness, and heat to dull redness. Redissolve in water, and add *red oxide of mercury*; treat the residue with water, pure magnesia (if present) will remain, which is to be collected and weighed.

X. The *chlorides of potassium and sodium*, as well as the sulphate of lime, have yet to be determined. Boil 200 grains of the dried specimen in ten ounces of distilled water; filter the solution and wash the insoluble part; divide the solution into two equal parts; to one add nitric acid, and then *chloride of barium* as long as any precipitate occurs. Collect, wash, and dry this precipitate, which is sulphate of baryta, obtained from the decomposition of sulphate of lime. To the other half of the solution add nitric acid, and then *nitrate of silver* as long as any precipitate occurs, which treat as in the former case. This will be chloride of silver, obtained from the decomposition of the *chlorides of potassium and sodium*.

The above process, though it has no pretensions perhaps to great accuracy, is sufficiently exact for most practical purposes. When a complete analysis is to be made, *Dr. Ure* adopts the following method.\* A known weight (about 100 grains) of the soil is introduced into a large glass flask with a thin concave bottom, capable of holding at least a quart of water, and over it is poured a sufficient quantity of dilute hydrochloric acid. The flask is placed on the ring of a retort-stand and exposed to a gentle heat, while the beak of a large glass funnel, having its mouth covered with a porcelain basin filled with distilled water, is inserted into its neck. By this arrangement, a continuous ebullition may be maintained in the mixture of soil and acid, without loss of acid or nuisance from its fumes, because the vapors are condensed whenever they reach the cold basin above the funnel; and in this way a boiling heat may be kept up till every constituent of the soil, except the silica, becomes dissolved. The funnel and

\* Pharm. Journ., June, 1845.



porcelain basin should be properly supported on the rings of the retort-stand. *Dr. Ure* maintains the action for *six or eight hours*, at the end of which time he throws the contents of the matrass on a filter, and supersaturates the filtered liquor with ammonia. The silica which remains on the filter having been washed, is dried and weighed.

The *alumina*, *oxide of iron*, and *phosphate of lime* thrown down by the ammonia being washed on the filter, and dried to a cheesy consistence, are removed with a bone spatula into a silver basin, and digested with heat in a solution of pure potassa, whereby the alumina is dissolved; the alkaline solution is passed through a filter and saturated with hydrochloric acid; ammonia is then added, pure white *alumina* falls, which is collected on a filter, washed, ignited, and weighed.

The *iron* and *phosphate of lime* on the filter may be dried, gently ignited and weighed, or otherwise directly separated from each other without that step, by the action of dilute alcohol, acidulated with sulphuric acid at a gentle heat. Thus the oxide of iron will be dissolved, and its solution may be passed through a filter, while the *sulphate of lime* will remain undissolved, and may be dried, ignited, and weighed; *five* parts of it correspond with *four* of phosphate. The *iron* is obtained in the state of sesquioxide by precipitation with ammonia.

The first filtered liquor, with excess of ammonia, contains the *carbonate of lime* and the *magnesia*. The former is separated by solution of oxalate of ammonia, and digestion, at a gentle heat, for a few hours; it is then filtered, washed, dried, and gently ignited, by which it is converted into carbonate, in which form it is weighed. The *magnesia* in the filtrate is precipitated with phosphate of soda.

For some refractory soils in which the alumina exists as a double or triple silicate, it becomes necessary to fuse about fifty grains of the sample in fine powder, mixed with four times its weight of dry carbonate of soda, the mixture being put into a platinum crucible, and into a cavity in the centre fifty grains of hydrate of potassa being laid. The crucible is slowly raised to a red white heat, when its contents fuse into a homogeneous liquid, of a gray or brown color, according to the metals present in it. *Manganese* gives a purple tint: and *iron* a red brown. The fused matter should be poured out into a shallow platinum basin, and, as soon as it

is cold, it should be pulverized, dissolved in dilute hydrochloric acid, the solution evaporated to dryness, the dry mass again digested with hot water acidulated with hydrochloric acid, and the whole thrown down upon a filter. Pure *silica* remains, which is washed, dried, ignited, and weighed. The filtered liquor, which contains the remaining constituents of the soil, is treated as already described.

Besides these systematic investigations, *Dr. Ure* directs researches to be made for certain peculiar substances, and especially for the so-called *neutro-saline* constituents, in the following manner. One hundred grains of the soil are triturated with twenty times their weight of distilled water, placed in a beaker till the clayey matter subsides, and the clear liquor is then decanted into a filter. A little of the filtered solution should be tested with nitrate of baryta, and also with oxalate of ammonia. If precipitates are afforded, the presence of *sulphate of lime* is indicated, and the following steps must be taken to eliminate it entirely.—Two hundred grains of the soil are triturated with a quart of distilled water, holding in solution fifty grains of sal ammoniac. The mixture should be allowed to clarify itself by subsidence, when the supernatant clear liquor should be evaporated down to two ounce measures, and then mixed with an equal bulk of *strong whisky* (11 per cent. over proof). The whole of the sulphate of lime will then be separated from the fluid, and, after being drained on a filter, may be dried, ignited, and weighed.

For determining the *alkaline salts*, the water filtered from the one hundred grains of soil should be evaporated down to one-fifth of its bulk, and then treated, 1st, with nitrate of baryta for the *sulphates*; 2d, with nitrate of silver for the *chlorides*; 3d, with oxalate of ammonia for the *nitrate of lime*, or *chloride of calcium*, provided no sulphate of lime is indicated by the first test; 4th, with litmus paper for the *alkaline* or *acid* reaction; 5th, with soda chloride of platinum for *potassa*, salts which are very valuable for the vigorous growth of many plants. The portions of the soil tested for potassa salts should, before being digested in water, be gently calcined, to insure the expulsion of every particle of ammoniacal salt; otherwise the precipitate afforded by soda chloride of platinum would be fallacious.

Another peculiar research to which *Dr. Ure* directs especial attention, is that which determines the amount of ammo-

nia in a soil, which may exist either ready formed, or in its elements, capable of affording a portion of that azotic food so indispensable to vigorous vegetation. The actual ammonia is easily obtained, by distilling the soil along with *milk of lime*; the distillate will contain all the volatile alkali, which may be estimated by a standard solution of sulphuric acid, according to *Peligot's* method, described page 468. What *Dr. Ure* calls the *potential* ammonia, *slumbering*, so to speak, in its embryo elements, may be estimated by igniting 200 grains of the soil with its own weight of a mixture of hydrate of soda and quicklime.

*Dr. Ure* gives also the following simple method of testing for phosphoric acid in a soil:—Digest it for an hour or so, at a moderate heat, with dilute *nitric* acid (free from hydrochloric acid). Throw the mixture on a filter; to the filtered liquor add *potassa water* cautiously, till the instant that a precipitate begins to appear; then drop into it a weak solution of nitrate of silver. If any phosphoric salts be present, a yellowish precipitate will immediately fall, which is resolvable in an excess of nitric acid. Whatever is not thus dissolved is chloride of silver, and ought to be separated by filtration. On adding then weak potassa water cautiously to the filtered liquor, pure *phosphate of silver* will be obtained, without any alumina or iron, provided the liquor be still acidulous in a slight degree. The portion of soil should be fresh, not calcined, because the phosphates, when ignited, afford a white precipitate with nitrate of silver. The stronger the solution of the phosphoric compound is, the more characteristic is the yellow precipitate with silver; and then ammonia may be used to effect the partial separation of the excess of acid.

A solution of *sulphate of magnesia*, containing a little sal ammoniac, is probably the best test liquor for detecting phosphates in faintly acidulous, but still better in neutral, solutions.

The determination of phosphoric acid in soils is best effected by the following process, proposed originally by *Schulze*, and modified by *Liebig*. It is founded on the insolubility of phosphate of peroxide of iron and phosphate of alumina in *acetic* acid:—The hydrochloric solution of the soil is evaporated to dryness, nitric acid being added during the evaporation, the dry mass is treated with dilute hydrochloric acid, and the solution filtered off from the insoluble silica. To the

acid solution ammonia is added, and then acetic acid; the mixture is boiled, filtered while hot, and the precipitate, which contains the whole of the phosphoric acid, in combination with iron and alumina, is collected on a filter, washed, dried, weighed, and digested with caustic potassa, which dissolves the latter. This is the process as originally proposed by *Schulze*. According to *Liebig's* modification,\* ammonia is added to the hydrochloric solution of the soil, till a precipitate begins to form; acetic acid is then added, and, finally, acetate of soda in excess; the mixture is boiled and filtered. The precipitate, having been washed with hot water, is dissolved in hydrochloric acid, ammonia added to alkaline reaction, and then hydrosulphuret of ammonia. The fluid is filtered off from the precipitated sulphuret of iron, and the latter is washed with water mixed with hydrosulphuret of ammonia. The filtrate is concentrated by evaporation, *sulphate of magnesia* added, and the mixture stirred; the formation of a crystalline precipitate indicates phosphoric acid; this precipitate consists of basic phosphate of magnesia and ammonia. It is collected on a filter, washed with water containing a little ammonia, dried, and ignited; the phosphoric acid is estimated as pyrophosphate of magnesia.

According to *Mr. Nesbit*† this process is inapplicable where phosphate of alumina is contained in the solution, the phosphoric acid being kept back in the precipitate formed by ammonia and hydrosulphuret of ammonia, and cannot be obtained in the filtrate.

Although the quantity of soluble saline matter extracted from a moderate quantity of any of our soils is rarely so great as to admit of a rigorous quantitative examination, it is, nevertheless, very desirable that a qualitative analysis of the aqueous extract should be made, in order to furnish information as to the ingredients which are supplied directly to the plant with the water which they imbibe from the soil. In some soils, those, for instance, of Egypt and India, and of other warm countries, soluble saline matter in the form of chlorides, sulphates, and nitrates, to the amount of 14 per cent., has been found.‡ The qualitative examination will

\* *Fresenius*—Quantitative Analysis, p. 516.

† Quarterly Journ. of the Chemical Society, No. 1, p. 45.

‡ See Johnstone's Lectures on Agricultural Chemistry and Geology, p. 43, Appendix.



always inform the operator whether or not a quantitative analysis is required. The most convenient plan, therefore, is to digest a large quantity (from two to three pounds) of the soil with distilled water, and, having thrown it on a moist filter and thoroughly washed the insoluble matter, to divide the filtrate into two parts, using one part for the qualitative, and setting aside the other for the quantitative examination, should such be found necessary.

As the analysis of soils is a subject which is likely early to occupy the attention of the student in analytical chemistry, we have, with a view of assisting him in his labors, collected in a tabular form the different steps of the treatment of the hydrochloric solution. The substance of this Table is taken from the article on the analysis of soils, in *Johnstone's Agricultural Chemistry*, a work which we take the liberty of strongly recommending to the attention of the agricultural student.

| To the hydrochloric solution<br>Add ammonia in excess.                                                                                                                                                                                                                                                                                             |  | The precipitate is<br><i>Oxalate of lime.</i><br>Wash, heat to redness to convert into carbonate, and weigh.                                                                                                                                                                                                                                                                                                                          |  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| <p>The solution contains<br/><i>Lime, magnesia, oxide of manganese, potassa, and soda.</i><br/>Add oxalate of ammonia, and cover from the air.</p>                                                                                                                                                                                                 |  | <p>The precipitate is<br/><i>Oxalate of lime.</i><br/>Wash, heat to redness to convert into carbonate, and weigh.</p>                                                                                                                                                                                                                                                                                                                 |  |
| <p>The solution contains<br/><i>Oxide of manganese, magnesia, potassa, and soda.</i><br/>Add hydrosulphuret of ammonia.</p>                                                                                                                                                                                                                        |  | <p>The precipitate is<br/><i>Sulphuret of manganese.</i><br/>Dissolve in hydrochloric acid, precipitate by carbonate of soda.<br/>Wash, heat to redness in the air, and weigh.<br/>Every 100 grains may be considered to indicate the presence of 93.84 grains of protoxide of manganese.</p>                                                                                                                                         |  |
| <p>The solution contains<br/><i>Magnesia, potassa, and soda.</i><br/>Acidify with hydrochloric acid, boil, filter, evaporate to dryness, and heat to incipient redness, to drive off the ammoniacal salt. Redissolve in water, mix with a little pure red oxide of mercury: evaporate again to dryness, heat to redness, and treat with water.</p> |  | <p>The residue is<br/>caustic magnesia.<br/>Wash, ignite in water, and add bi-nite, and weigh.<br/>chloride of platinum.</p>                                                                                                                                                                                                                                                                                                          |  |
| <p>The solution contains<br/>The double chloride of platinum and potassium.<br/>Wash with dilute alcohol, dry at a gentle heat, and weigh.</p>                                                                                                                                                                                                     |  | <p>The precipitate is the<br/>double chloride of platinum and potassium.<br/>Wash with dilute alcohol, dry at a gentle heat, and weigh.</p>                                                                                                                                                                                                                                                                                           |  |
| <p>The solution contains<br/><i>Alumina and oxide of iron.</i><br/>Add ammonia, and digest the precipitate in a solution of caustic potassa.</p>                                                                                                                                                                                                   |  | <p>The precipitate is<br/><i>Oxide of iron,</i><br/>which wash, dry, ignite, and weigh.</p>                                                                                                                                                                                                                                                                                                                                           |  |
| <p>The solution contains<br/><i>Alumina.</i><br/>Add hydrochloric acid till the solution is sour, and then excess of ammonia; alumina is precipitated, which collect, wash, dry, ignite, and weigh.</p>                                                                                                                                            |  | <p>The precipitate is<br/><i>Oxide of iron,</i><br/>which wash, dry, ignite, and weigh.</p>                                                                                                                                                                                                                                                                                                                                           |  |
| <p>The precipitate contains<br/><i>alumina and oxide of iron.</i><br/>It may be treated according to Liebig's plan; or, where great accuracy is not particularly desired, it may be fused in a platinum crucible with three times its weight of carbonate of soda: the fused mass is extracted with water.</p>                                     |  | <p>The solution contains<br/><i>Alkaline phosphate.</i><br/>Neutralize with nitric acid, and add nitrate of silver, when phosphate of silver will fall; or with hydrochloric acid, and add chloride of calcium and ammonia, when bone earth will fall: every 100 grains of phosphate of silver are equal to 23.51 of phosphoric acid or 48.50 of bone earth, and every 100 grains of bone earth contain 48.45 of phosphoric acid.</p> |  |
| <p>The precipitate contains<br/><i>alumina and phosphates of iron and alumina.</i><br/>Digest in acetic acid.</p>                                                                                                                                                                                                                                  |  | <p>The precipitate contains<br/><i>alumina and oxide of iron.</i><br/>It may be treated according to Liebig's plan; or, where great accuracy is not particularly desired, it may be fused in a platinum crucible with three times its weight of carbonate of soda: the fused mass is extracted with water.</p>                                                                                                                        |  |
| <p>The solution contains<br/><i>Alumina and oxide of iron.</i><br/>Add ammonia, and digest the precipitate in a solution of caustic potassa.</p>                                                                                                                                                                                                   |  | <p>The solution contains<br/><i>Alkaline phosphate.</i><br/>Neutralize with nitric acid, and add nitrate of silver, when phosphate of silver will fall; or with hydrochloric acid, and add chloride of calcium and ammonia, when bone earth will fall: every 100 grains of phosphate of silver are equal to 23.51 of phosphoric acid or 48.50 of bone earth, and every 100 grains of bone earth contain 48.45 of phosphoric acid.</p> |  |

In reference to the detection of minute quantities of phosphoric acid in soils, rocks, &c., we may allude to the method adopted by *Mr. Fownes*, by which he succeeded in obtaining evidence of the existence of this important acid in several rocks of igneous origin, such as white porcelain clay from *Dartmoor*, green basalt from *Derbyshire*, and various *lavas*, &c. &c. The minerals were finely powdered in a porphyry mortar, and boiled with dilute hydrochloric acid: the solutions contained large quantities of alumina and oxide of iron. The liquids were separated from the insoluble part by decantation, evaporated nearly to dryness, water added, and then an excess of ammonia. The copious bulky precipitate obtained was washed and digested in dilute acetic acid. The undissolved residue was dried, ignited, and fused with *silica* and carbonate of soda; when cold, the melted mass was acted on with boiling water, and the soluble and highly alkaline portion was separated by filtration from the insoluble silicate of alumina. The solution was mixed with excess of nitric acid, evaporated to dryness, water added, and the product filtered. The liquid thus obtained was divided into two portions; one of these was carefully neutralized with a little ammonia, and then mixed with a few drops of nitrate of silver, a *distinct yellow precipitate* appeared, which was freely soluble in dilute nitric and acetic acids. The other portion was mixed with excess of ammonia, sal ammoniac added, and then a few drops of solution of sulphate of magnesia; after a short time a distinct crystalline precipitate appeared, which increased on agitation. It was found necessary to add *silica* to the undissolved residue previous to fusion with carbonate of soda, in order to retain the whole of the alumina in an insoluble condition.

*Determination of the Specific Gravity of a Soil.*—A portion is dried in the water bath until it ceases to lose weight; a small bottle is filled up to a mark made in its neck with distilled or rain water, and the weight accurately taken. Part of the water is then poured out of the bottle, and 1000 grains of the dry soil introduced in its stead, the bottle is well shaken to expel all the air from the pores of the soil, filled up to the mark in the neck with water, and again weighed. The weight of the soil divided by the difference between the weight of the bottle with soil and water, and the sum of the weights of the bottle of water and soil together gives the specific gravity.

*Example.*—Suppose the bottle with the water to weigh 2000 grains, and with water and soil 2600, then—

|                                                                                                                                                                                                         | Grains. |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|
| Weight of bottle with water alone                                                                                                                                                                       | 2000    |
| Do. with dry soil                                                                                                                                                                                       | 1000    |
| <hr/>                                                                                                                                                                                                   |         |
| Sum, being the weight which the bottle and the soil<br>would have had could the soil have been introduced<br>without displacing any of the water                                                        | 3000    |
| Actual weight of bottle and water                                                                                                                                                                       | 2600    |
| <hr/>                                                                                                                                                                                                   |         |
| Difference, being the weight of water taken out to ad-<br>mit 1000 grains of dry soil.                                                                                                                  | 400     |
| Therefore 1000 grains of soil must have the same bulk as<br>400 grains of water, or the soil must be $2\frac{1}{2}$ times heavier than<br>water, since $\frac{1000}{400} = 2.5 =$ its specific gravity. |         |

*Determination of the Relative Proportions of Gravel, Sand, and Clay.*—A certain quantity, (say four or five hundred grains) of the soil is well agitated with hot water in a large flask, the whole is then poured into a *Phillip's* precipitating jar, and allowed to stand for a couple of minutes; the water, together with the fine floating matter, is then poured off into another vessel, and the process is repeated several times, till nothing but sand and gravel remain; these are now dried and weighed, and then sifted through a gauze sieve more or less fine, when the gravel and coarse sand are separated and may be weighed, and their respective proportions estimated. These separated portions of gravel and sand should now be moistened with water and examined carefully with the aid of a microscope, with the view of ascertaining if they are wholly silicious, or if they contain also fragments of the different kinds of rock, *sand-stones, slates, granites, traps, lime-stones, or iron-stones*. A few drops of strong hydrochloric acid should also be added, when the presence of limestone is shown more distinctly by an effervescence, which can be readily perceived by the aid of a glass—of peroxide of iron, by the brown color which the acid speedily assumes; and of black oxide of manganese, by the distinct smell of chlorine, which is easily recognized.



*Determination of the absorbing Power of the Soil; its Power of holding Water; and the Rapidity with which it Dries.*—*Johnston* gives the following directions for determining these several points. A thousand grains of the perfectly dry soil are spread over a sheet of paper, and exposed to the air for twelve or twenty-four hours, and then weighed. The increase of weight shows its power of absorbing moisture from the air. If it amounts to 15 or 20 grains, it is so far an indication of great agricultural capabilities. This same portion of soil may now be put into a funnel on a double filter, and cold water poured upon it drop by drop, till the whole is wet, and the water begins to trickle down the neck of the filter. It may now be covered with a piece of glass, and allowed to stand for a few hours, occasionally adding a few drops of water, until there remains no doubt of the whole soil being perfectly soaked. The two filters and the soil are then to be removed from the funnel, the filters opened and spread for a few minutes upon a linen cloth, to remove the drops of water which adhere to the paper. The wet soil and inner filter being now put into one scale and the outer filter into the other, and the whole carefully balanced, the true weight of the wet soil is obtained. Suppose the original wet soil now to weigh 1400, then the soil is capable of holding 40 per cent. of water; for—

$$\text{As } 1000 : 400 :: 100 : 40$$

The wet soil, with its filter, may now be spread out upon a plate and exposed to the air, in what may be considered ordinary circumstances of temperature and moisture for 4, 12, or 24 hours, and the loss of weight then ascertained. This will indicate the comparative rapidity with which such a soil would dry, and the consequent urgent demand for draining, or the contrary. As great a proportion of the water is said to evaporate from a given weight of sand saturated with water, in 4 hours, as from an equal part of pure clay in 11, and of peat in 17 hours, when placed in the same circumstances.

*The Organic Constituents of the Soil.*—We have already in the last chapter alluded to the observations of *Mulder*\* on this subject, and have stated that he reduces the number of organic substances as at present known to exist in the soil to seven. The varieties would indeed be incalculable but for the

\* *Chemistry of Vegetables and Animal Physiology*. Translated, with Notes, by *Johnston*, pp. 143 *et seq.*

existence of a general cause which reduces them to a small number. This cause is the transformation and decomposition which vegetables undergo at their death, by which they are converted chiefly into a substance called *humus*. This change is remarkably uniform, since from the innumerable organic combinations which exist in plants and animals the same few constituents of the black layer of soil are derived; and if we exclude those substances which are mixed accidentally with the black soil, as well as those substances which have not yet undergone sufficient decomposition, its constituents are limited to a small number of organic substances—substances existing in it everywhere, and on the decomposition of which the growth of plants depends. These substances have the following properties:—Some of them are soluble in water, others in alkalis; others again are insoluble in both, while some dissolve more or less readily in alcohol and ether. The latter are of a resinous nature, and do not appear to have any share whatever in vegetation.

If a soil be exhausted by means of water, a great many salts may be extracted from it, among which may be mentioned the alkalies, lime, magnesia, and ammonia, in combination with *formic*, *acetic*, *carbonic*, *crenic*, *apocrenic*, and *humic* acids. From the soils thus treated with water, alkaline solutions extract substances which may be precipitated by acids. In different kinds of soils the substances thus extracted are sometimes different. They all consist, however, of one or more of the following:

Geïc acid  $C_{40}H_{12}O_{14}$

Humic acid  $C_{40}H_{12}O_{12}$

Ulmic acid  $C_{40}H_{14}O_{12}$

The latter is that which, in neutral vegetable substances undergoing decay, is formed first. From it, by absorption of oxygen from the air, *humic acid* is produced, and finally, by a further absorption, *geïc acid*. The substances which are insoluble in alkalies, *ulmin* and *humins*, can be rendered soluble, and so converted into *ulmic* and *humic* acids respectively, by the decomposition which is always going on in the constituents of the soil.

The base by which *Mulder* supposes these acids to be rendered soluble in water, is *ammonia*. He does not adopt the idea of *Liebig*, that this ammonia is carried down to the soil from the atmosphere, by means of rain water, but he accounts for its

presence in the following manner:—Nitrogen, in the state of pure gas, and also atmospheric air are possessed of one common property, namely, that when in contact within an enclosed space with putrefying substances, from which hydrogen is in consequence given off, *the nitrogen combines with the hydrogen, and forms ammonia*. This property of nitrogen is well known. It is the principle on which *saltpetre* is formed, the production of that substance being always preceded by that of ammonia. Now, air is contained in the soil, and is in continual contact with moist and decomposing substances. This air could produce saltpetre, if there were only a sufficient abundance of bases, and that even without the presence of putrefying organic substances.

There are in *Ceylon* 22 natural saltpetre grottos, where there are no organic substances from which nitrogen might be supplied. Nitrogen is derived from the air contained in these caverns, and in favorable circumstances even the water is decomposed, and ammonia at the same time produced, which afterwards is oxidized into nitric acid by the oxygen of the air, in places where it has more easy access; this acid then combines again with the bases from the walls of the grottos, and forms nitrates. All this would happen in the soil if organic substances were not present to absorb the oxygen, and thus to prevent the oxidation of the nitrogen in the ammonia, and the formation of saltpetre. In a porous soil in which moist air is contained, nitrogen is combined with the hydrogen of the organic bodies only into ammonia, the oxygen of the water, and from the air, being consumed in the higher oxidation of the organic substances themselves. In this way the first product of the decomposition of organic substances, namely, *ulmic acid* ( $C_{40}H_{14}O_{12}$ ), is converted into *humic acid* ( $C_{40}H_{12}O_{12}$ ), and this again into *geïc acid* ( $C_{40}H_{12}O_{14}$ ), which in its turn is further oxidized into *apoerenic acid* ( $C_{48}H_{24}O_{32}$ ), and, finally, into *erenic acid* ( $C_{24}H_{12}O_{16}$ ).

It is to this formation of ammonia from the constituents of atmospheric air and water that we must look, according to the Dutch chemist, for the cause of one of the most important peculiarities in the growth of plants. It is owing to this slow formation of ammonia, that the organic substances of the soil insoluble in water are rendered soluble, and can be offered to plants as organic food, even without a supply of ammoniacal manure to the soil. In other words, it is owing to this cause

that the five acids already mentioned can be converted into soluble ammoniacal salts. It is particularly worthy of remark, and a fact of great interest, that these humic substances, which can be extracted from the soil by alkalies, and precipitated by acids, have a great uniformity, from whatever kind of soil they may have been prepared; and they are remarkably similar to those substances which by the action of several chemical agents may be obtained from the materials which are generally diffused through the animal and vegetable kingdoms. The manner in which *sugar* is changed into ulmin, humin, and geïc acid, by a simple transposition of its elements, is thus suggested by *Mulder*:—

|                                                     |   |   | C. | H. | O. |
|-----------------------------------------------------|---|---|----|----|----|
| $\frac{1}{2}$ of 7 equiv. of sugar + O <sub>2</sub> | . | . | 42 | 35 | 37 |
| 2 equiv. of carbonic acid                           | . | . | 2  |    | 4  |
| 19 do. of water                                     | . | . |    | 19 | 19 |
| 1 do. of <i>ulmin</i>                               | . | . | 40 | 16 | 14 |
|                                                     |   |   | 42 | 35 | 37 |
| $\frac{1}{2}$ of 7 equiv. of sugar + O <sub>4</sub> | . | . | 42 | 35 | 39 |
| 2 equiv. of carbonic acid                           | . | . | 2  |    | 4  |
| 23 do. of water                                     | . | . |    | 23 | 23 |
| 1 do. of <i>humin</i>                               | . | . | 40 | 12 | 12 |
|                                                     |   |   | 42 | 35 | 39 |
| $\frac{1}{2}$ of 7 equiv. of sugar + O <sub>6</sub> | . | . | 42 | 35 | 41 |
| 2 equiv. of carbonic acid                           | . | . | 2  |    | 4  |
| 23 do. of water                                     | . | . |    | 23 | 23 |
| 1 do. of geïc acid                                  | . | . | 40 | 12 | 14 |
|                                                     |   |   | 42 | 35 | 41 |

In the same manner the conversion of *cellulose*, *starch*, *gum*, *pectin*, and other analogous substances, which are so very much diffused through plants into the humic substances, may be represented; and the way in which his *protein* even may be converted into humic acid, by the influence of hydrochloric acid and oxygen, is shown in a very ingenious manner by *Mulder*.\*

\* Chemistry of Vegetable and Animal Physiology, p. 159.



The *crenic* and *apocrenic* acids, like the humic acids, exist in the soil in the state of salts of ammonia, potassa, and soda, combined with lime, magnesia, and oxide of iron; they never exist in the soil uncombined. They unite intimately with ammonia, which, however, can be completely separated from them by caustic potassa. *Apocrenic* acid, when artificially prepared, is a *five-basic* acid. It is produced in the form of apocrenate of ammonia when humic acid in whatever way prepared, or wood charcoal, is exposed to the action of nitric acid. Its value in the soil is very highly estimated by *Mulder*, as in consequence of its *five-basic* character it may supply plants either with several bases at once, or these bases may be alternately exchanged according as the proportion of a more powerful base in the soil is less, and that of a more feeble one temporarily greater; in consequence of these properties he assigns to it a much higher rank than the humic class of acids.

The formation of *apocrenate* of ammonia, by the oxidation of humate of ammonia, is continually going on in the soil during the warmth of summer (except on the very surface which is directly exposed to the air). Each minute portion produced can be taken up by the roots of plants, in the form of double apocrenates of ammonia and various fixed bases, provided there be a sufficient supply of water at hand; and, while in this way the soil loses its apocrenates, a new portion of apocrenate of ammonia is formed from the *humic acid* or *humic*, which is present in large excess. We may thus call the production of apocrenic acid in one respect an organic nitrification.

The series of organic acids present in the soil is, according to the views of *Mulder*, concluded by a fifth important substance, a final product of the oxidation of organic substances before they are entirely changed into carbonic acid and water, namely, *crenic* acid, the composition of which is  $C_{24}H_{12}O_{16}$ . It also is combined with ammonia in the soil, and forms double salts, which are soluble in water. These exist, along with the apocrenates, in all kinds of water\* which have been in contact with organic substances in the soil. They were first found by *Berzelius* in spring water; they exist also in the waters of ditches, marshes, and bogs. *Crenic* acid is four-

\* See last Chapter.

basic. By the continual tendency to nitrification in the soil, apocrenic acid must always be converted into crenic acid, the series of *ulmic*, *humic*, *geïe*, and *apocrenic* acids thus terminating with *crenic* acid. In the upper layer of the soil, however, where the air is not inclosed, and consequently no tendency to nitrification exists, crenic acid must conversely be changed into apocrenic acid.

*Johnston*\* thinks that to the five acids, mentioned by *Mulder*, several others may be added, as occurring in certain circumstances in the soil. Thus, from a sample of compressed peat, he extracted by ammonia a substance, from which hydrochloric acid threw down a dark brown acid, having the composition  $C_{24}H_{12}O_{12}$ ; the same peat, when digested with solutions of caustic potassa, or of carbonate of potassa, or carbonate of soda, and precipitated by an acid, gave a substance, having the formula  $C_{24}H_{14}O_9$ ; agreeing, therefore, with the ulmic acids of *Mulder*, in containing an excess of hydrogen, but not reducible to his ulmic group, the excess of hydrogen being very much greater than in ulmic acid, and the equivalent containing only twenty-four instead of forty equivalents of carbon. These acids agree with those of *Mulder* in their tendency to unite with several bases at once, and to combine with oxygen and nitrogen from the air, producing ammonia and acids containing more oxygen than the humic and ulmic acids. Again, from a substance called *Pigotite*, found on certain parts of the rocky coasts of Cornwall, where caves occur, *Johnston* extracted an acid, represented by the formula  $C_{12}H_5O_8$ . This acid was obviously formed from the decaying vegetable matter of the soil, and was combined with alumina. It approaches very closely in composition to the *crenic* acid of *Mulder*, and is called by its discoverer *Mudescous* acid; on treating its compound with alumina, with nitric acid, *Johnston* obtained still another acid, the formula of which is  $C_{12}H_5O_{10}$ .

The above is a very brief and imperfect outline of the present state of our knowledge regarding the nature of the organic constituents of the soil. It will be seen that the subject is still quite in its infancy, and that no attempt can as yet be made to point out a method of analyzing a soil with a view of isolating any particular acid. The following mode of examination must, therefore, for the present suffice.

\* See his translation of *Mulder's* work, p. 184.

*Determination of the total Amount of Organic Matter.*—From 100 to 200 grains of the soil thoroughly dried, at a temperature not higher than between  $250^{\circ}$  and  $300^{\circ}$  Fahrenheit, are burned in a platinum crucible till all blackness disappears. The earth is then moistened with carbonate of ammonia, dried, and again gently ignited. The difference in weight furnishes a close approximation to the amount of organic matter present. It is not absolutely exact, because it is impossible thoroughly to expel the whole of the water from some soils, without partially decomposing the organic matter.

*Determination of the Acids of the Humic Group.*—About 500 grains of the soil are digested for several hours at about  $200^{\circ}$  Fahrenheit, with a solution of carbonate of soda; the fluid is then filtered off, an operation which, with soils containing much alumina, frequently takes a considerable time;\* the filtrate is mixed with slight excess of hydrochloric acid, whereupon the humic acid separates in the form of light brown flakes; these are collected on a tared filter, washed, dried, and weighed; the dry mass is then burned, and the weight of the ashes subtracted from that of the dry flakes; the remainder is the amount of humic acid.

*Determination of the Humus.*—About 500 grains of the soil are digested for some hours with caustic potassa in a porcelain basin; the alkaline ley is diluted with water, filtered, the undissolved matter washed, and the filtrate precipitated by hydrochloric acid. The whole of the *humus* is by this treatment converted into humic acid; and the difference in weight between the precipitate thus obtained and that of the former experiment, when carbonate of soda was employed as the solvent, represents the quantity of organic matter existing in the soil in the form of *humus*; and the two weights added together, and deducted from the amount which the soil lost by ignition, shows the quantity of the other organic ingredients not belonging to the humic group.

Should the operator wish to determine the amount of resinous and waxy matters in the soil, he may extract them by digesting about 2000 grains with strong alcohol, precipitating them from the alcoholic solution by water; and, should he desire to know the quantity of nitrogen which the soil contains, he

\* Should the first filtrate be still muddy, it should be concentrated by evaporation, and again passed through the filter, when it will, in most cases, be obtained quite clear.

may burn a known quantity with soda lime in the manner described in detail at page 250.

---

## CHAPTER VI.

ON THE ANALYSIS OF COMPOUNDS CONTAINING THE OXIDES OF IRON AND MANGANESE, ALUMINA AND ALKALINE EARTHS IN COMBINATION WITH PHOSPHORIC, ARSENIC AND SILICIC ACIDS.

BY. R. FRESENIUS.

Journ. für Prakt. Chem., 1848, and Chem. Gaz. 7-22.

### I. *Separation of the Peroxide of Iron from Phosphoric Acid in the presence of Alkaline Earths.*

a. MANY chemists have hitherto assumed, that by fusing the perphosphate of iron with carbonated alkali and exhausting the mass with boiling water, the perphosphate of iron may be completely separated from phosphoric acid (Berzelius, Rammelsberg); nay, that even when alkaline earths are present, the phosphoric acid passes entirely to the alkali, and is dissolved on treatment with water (Rose).

I had formerly convinced myself that phosphate of lime and phosphate of magnesia could not be perfectly decomposed with carbonate of soda; but now I have found that even the peroxide of iron cannot be wholly deprived of phosphoric acid by this treatment. In fact, if the residue, after being most carefully washed, is dissolved in muriatic acid, precipitated with ammonia and sulphuret of ammonium, filtered, and the solution mixed with chloride of ammonium and sulphate of magnesia, there is always obtained a very perceptible precipitate of ammonio-phosphate of magnesia; it consequently requires no further proof that all the methods based upon the above principle are inaccurate.

b. When a muriatic solution containing phosphoric acid, peroxide of iron and lime, is mixed with carbonate of soda until the free acid is nearly saturated, then mixed with an excess of acetate of soda and boiled, the whole of the phosphoric acid is precipitated with the peroxide of iron, whilst the lime remains



in solution. The peroxide of iron and phosphoric acid may then be separated by sulphuret of ammonium. This method is not inaccurate, but it is extremely inconvenient, especially when mere traces of phosphoric acid have to be estimated and the amount of peroxide of iron is very great, a case which very frequently occurs in the analysis of iron ores, soils, &c.

With respect to the other method, which is given in my Introduction to Quantitative Analysis, of separating phosphoric acid from peroxide of iron (it consists in adding tartaric acid, and then ammonia, to the solution, and lastly a mixed solution of chloride of ammonium and sulphate of magnesia), I must observe that it has now been found to lead to erroneous results; as a mixture of a solution of tartaric acid, sulphate of magnesia, chloride of ammonium and ammonia deposits after a short time, when of a certain degree of concentration, a crystalline precipitate, which has entirely the appearance of the ammonio-phosphate of magnesia. The employment of citric acid, sugar, &c., instead of the tartaric acid, has not yielded satisfactory results.

c. The method which I now employ is based upon an entirely new principle. The solution, which we will suppose to contain much peroxide of iron, lime and some phosphoric acid, is heated to boiling, removed from the lamp, and a solution of sulphite of soda added until the color has become pale green, and carbonate of soda produces a white precipitate; it is then boiled until the smell of sulphurous acid has disappeared, any excess of free acid neutralized with carbonate of soda, a few drops of chlorine water mixed with it, and lastly an excess of acetate of soda. The smallest quantity of phosphoric acid is immediately detected by the production of a white flocculent precipitate of perphosphate of iron.\* [This reaction is so sensitive because the perphosphate of iron is insoluble both in acetic acid and in the acetate of the protoxide of iron, whilst it dissolves abundantly in a solution of the peracetate of iron. It is owing to this circumstance that no precipitate is ever obtained when a nearly neutral solution of the peroxide of iron, containing only a small amount of phosphoric acid, is mixed with acetate of soda; the blood-red liquid remains clear in the

\* When the solution contains silicic or arsenic acid, a precipitate is formed in the absence of phosphoric acid. These two acids must therefore be first separated, before the phosphoric acid can be detected with certainty by the above reaction.

cold, and the whole of the iron, with the phosphoric acid, is only deposited on boiling.] Chlorine water is now added gradually until the liquid appears reddish; it is then always turbid. It is boiled until it has become clear, which soon results, filtered hot, and the precipitate washed with hot water. This precipitate contains the whole of the phosphoric acid as perphosphate of iron mixed with a minute quantity of basic peracetate of iron; the solution contains nearly the whole of the iron and the lime, which are easily separated by sulphuret of ammonium. The precipitate containing the phosphoric acid and iron may be readily and completely decomposed, after solution in muriatic acid, by the addition of ammonia and sulphuret of ammonium. But perfect decomposition may also be effected in the following manner, avoiding the use of sulphuret of ammonium. It is dissolved in muriatic acid, reduced with sulphite of soda as above, an excess of caustic potash or soda added, boiled until the precipitate has become black and granular, and then filtered through very close paper.\* This precipitate is protoperoxide of iron free from phosphoric acid: it is dissolved in muriatic acid, and united with the other solution of iron. The filtered solution contains the phosphoric acid, which is precipitated in the usual manner as ammonio-phosphate of magnesia.

## II. *Separation of Iron from Alumina.*

One of the most frequent operations of analytical chemistry is the separation of peroxide of iron from alumina by caustic potash; it is, however, very inaccurate. It had already been noticed by several persons, that the separation of these two oxides by caustic potash was not complete; and Knopp† has in consequence proposed precipitating the solution with sulphuret of ammonium, and then boiling with potash. This latter method is, however, extremely inconvenient, as the liquid, even though yellow and free from iron at the commencement, almost always passes through green and ferruginous in the washing, whether pure water or water containing sulphuret of ammonium is employed. The following experiment will show

\* When the filter is too porous, very often some of the fine precipitate passes through, especially when washed. Should this happen, the filtrate is suffered to stand, the clear liquid decanted, and the remainder filtered through a separate little filter.

† Chem. Gaz., vol. v. p. 14.

the inaccuracy of the usual method. A solution of chloride of aluminum, containing 1.000 grm. alumina, was mixed with a solution of perchloride of iron, an excess of caustic soda added to it, boiled, filtered hot, the filtrate acidified with muriatic acid, and carefully precipitated with ammonia. After standing several hours in a warm place, it was filtered. The alumina upon the filter was yellow, and led me to suspect the presence of iron, which was subsequently confirmed. The hydrated peroxide of iron also contained alumina, since although completely washed it gave a precipitate, although a very small one, on being again boiled with caustic soda and treating the filtrate as above. Instead of 1.000 grm. alumina, only 0.909 (which moreover contained iron) was obtained; there was consequently a loss of 10 per cent. After standing for eight days, the filtered solution deposited some alumina; consequently the whole of the lost alumina had not remained with the iron, but a portion had not been precipitated by the ammonia. After some experiments the cause of it was found out. It is owing to the circumstance, that, on filtering the liquid containing the caustic alkali through paper, organic matter is dissolved, which prevents the precipitation. This was proved by the following experiments:—

A solution of pure chloride of aluminum, containing 1.320 grms. alumina, was precipitated with potash, the precipitate redissolved in an excess of potash, the liquid heated to boiling filtered, acidified with muriatic acid, and precipitated with ammonia. The alumina obtained amounted only to 1.290, that is 97.72 per cent. In a second experiment, made in the same manner, instead of 2.640 grms. only 2.590 or 98.48 per cent. were obtained. This evil is avoided by filtering through asbestos instead of paper; but far more simply and better by heating the liquid acidified with muriatic acid, and boiling with a little chlorate of potash (upon the addition the flask is removed from the fire). By this means the organic substance, preventing the complete precipitation of the alumina, is destroyed, as the following experiments will show. A solution containing 0.3420 alumina was treated as above described; after being acidified with muriatic acid, boiled with chlorate of potash, it gave 0.3418 grm. alumina, that is 99.94 per cent. In a second experiment, instead of 0.150, 0.1495 or 99.67 per cent. was obtained.

The other source of inaccuracy, which in the first experi-

ment had raised the loss of alumina to 10 per cent., and which is owing to its not being possible to free the hydrated peroxide of iron completely from alumina by caustic potash, may be avoided without the application of Knop's inconvenient method. The acid solution, containing the alumina and peroxide of iron, is heated to ebullition in a flask, removed from the fire, and reduced with sulphite of soda. The liquid, after being kept boiling for some time, is neutralized with carbonate of soda, an excess of caustic soda added, and, after being well shaken, boiled until the liquid has become black and granular. [The succussion which precedes the boiling may be avoided by inserting a coil of platinum wire, and also by constant agitation. As soon as it really boils the thumping ceases.] It is now removed from the fire and allowed to subside, the clear liquid passes through a close filter, and the precipitate washed with hot water, at first by decantation, and then upon the filter. The filtered solution, treated in the above-mentioned manner with muriatic acid and chlorate of potash, furnishes, upon precipitation with ammonia and several hours' standing, *the whole* of the alumina in a perfectly pure state.

### III. *Separation of Alumina from Phosphoric Acid.*

To make an accurate analysis of a compound containing alumina, peroxide of iron, lime, magnesia and phosphoric acid, it is necessary, in the first place, to separate the alumina from the other bases. This is readily effected by precipitating the liquid, after the peroxide of iron has been reduced by sulphite of soda, with carbonate of soda, and then boiling with the addition of an excess of caustic soda. It must be borne in mind, in this case, that, on boiling, the carbonic acid which had been combined with the protoxide of iron passes to the soda, which it converts into carbonate; consequently, to retain the alumina in solution, it is requisite to add from time to time some caustic soda, and especially when the precipitate has become black and granular. In this way the alumina, together with *a portion* of the phosphoric acid, is obtained in solution (when alumina and peroxide of iron are the only bases present, *the whole* of the phosphoric acid is in the filtered solution), and we have now to seek for a simple method of separating the two.

The following furnishes perfectly satisfactory results:—The



alkaline solution is rendered acid, boiled with some chlorate of potash, precipitated with ammonia (avoiding a large excess), and chloride of barium added as long as a precipitate appears. After digesting for some time, it is filtered. The precipitate, which contains the whole of the alumina and phosphoric acid (the latter combined in part with alumina and in part with baryta), is collected upon a filter, washed with a little water, and dissolved in as little muriatic acid as possible. The solution is saturated with carbonate of baryta with the assistance of heat, an excess of caustic soda added, and heat applied. Any baryta contained in the solution is precipitated by carbonate of soda and filtered. The whole of the alumina is now in the solution, and the whole of the phosphoric acid in the precipitate. The solution is rendered acid with muriatic acid, boiled with chlorate of potash, precipitated with ammonia, allowed to stand for some hours in a warm spot; the alumina filtered, washed, dried, calcined and weighed. The precipitate is dissolved in muriatic acid, and the baryta precipitated with dilute sulphuric acid, separated by filtration, and the phosphoric acid determined as ammonio-phosphate of magnesia as usual.

#### IV. *Course of Analysis.*

The compound, the analysis of which we will describe, I will suppose to contain a large amount of peroxide of iron, protoxide of manganese, alumina, lime, magnesia, phosphoric acid, sulphuric acid, arsenic acid, silicic acid and sand, as is the case with iron ores.

A weighed quantity (which should not be too small) of the finely-pulverized mineral is digested with moderately-dilute muriatic acid in a flask, at a temperature near to boiling point, until all that is soluble has passed into solution. The liquid is diluted, passed through a filter of known weight of ash, and the residue washed. With brown iron ore the quantity is in general very small. It is dried with the filter, carefully separated from it, calcined and weighed; it is then transferred into a boiling solution of carbonate of soda, allowed to boil for some time, filtered through the filter first employed, washed, dried, calcined and weighed. The difference between this weight (sand, alumina, &c.) and the one first obtained gives the amount of insoluble residue, or silicic acid.

The ferruginous muriatic solution is filtered from the resi-

due, carefully evaporated to perfect dryness, and kept for some time at a temperature slightly above that of boiling water. After it has been moistened with muriatic acid, and kept for some time with it at a gentle heat, water is added, and any silica separated by filtration. Its weight, added to that above obtained, gives the total amount of silicic acid in combination.

The ferruginous solution is heated to boiling in a flask, and reduced with sulphite of soda as described under I. When the whole of the sulphurous acid has been expelled by boiling, sulphuretted hydrogen is passed into the liquid until it is saturated with it. The precipitate produced is the protosulphuret of arsenic. The amount of arsenic contained in it is ascertained, after deducting the sulphur in it, which has been previously determined as sulphate of baryta, from its weight determined at  $212^{\circ}$ . If the precipitate does not appear yellow, but brown or black, there is reason to suspect some other metallic oxides, and it must be further examined in the ordinary manner.

The liquid filtered from the protosulphuret of arsenic is boiled to expel the whole of the sulphuretted hydrogen, then precipitated with carbonate of soda, and boiled with an excess of caustic soda (as directed in II.) until the precipitate appears black and granular. It is allowed to subside, the clear liquid poured off, the precipitate washed by decantation with hot water, and finally brought upon a filter of close texture, and washed with hot water.

*a. Treatment of the Precipitate.*—The precipitate (which contains proto and peroxide of iron, protocarbonate of manganese, carbonate and phosphate of magnesia) is again transferred, together with the filter, into the flask, and digested with muriatic acid. After standing for some time in a warm place, it dissolves entirely, although not so readily as the hydrated peroxide of iron. When no more black particles are perceptible, it is filtered; the filter is left whole, a little hot water poured over it, the flask inclined so that it remains hanging to the side, and the liquid runs off, &c. In this manner it may be quickly and completely washed. The filtered solution is reduced with sulphite of soda, nearly neutralized with carbonate of soda, heated to boiling, mixed with a few drops of chlorine-water, then with an excess of acetate of soda; and when the liquid or the precipitate has not a red-

dish tint, chlorine water is added until this is the case. The whole is boiled until the precipitate has separated, filtered hot, and the precipitate, consisting of phosphate and some basic acetate of the peroxide of iron, washed.

a. The filtered solution is precipitated, after the addition of ammonia and while hot, with sulphuret of ammonium, filtered quickly, the precipitate consisting of protosulphuret of iron and manganese, washed uninterruptedly with hot water, and the lime in the solution determined by oxalate of ammonia; and, after removing the oxalate of lime, the magnesia thrown down by phosphate of soda. The precipitate of the sulphurets is dissolved in muriatic acid, oxidized with chlorate of potash or nitric acid, boiled until all the chlorine is expelled, allowed to cool to about  $140^{\circ}$ , nearly neutralized with carbonate of soda, the peroxide of iron precipitated with carbonate of baryta, and the other oxides estimated in the usual manner.

β. The precipitate, containing the perphosphate of iron, is dissolved in muriatic acid, reduced with sulphite of soda, boiled for some time with an excess of caustic soda, and filtered. The solution containing the phosphoric acid is supersaturated with muriatic acid, and placed aside. The precipitate of proto-peroxide of iron is also dissolved in muriatic acid, oxidized with nitric acid, the solution added to the principal solution of the iron, separated from the manganese and baryta, and the whole precipitated with ammonia.

b. *Treatment of the filtered Alkaline Solution.*—This liquid, which contains the alumina, is treated exactly as described under III. The alumina is consequently weighed in a pure state. The solution, freed from baryta and containing phosphoric acid, is united with the above-mentioned liquid containing the other portion of phosphoric acid, supersaturated with ammonia, and precipitated with sulphate of magnesia, with the addition of chloride of ammonium if necessary.

The sulphuric acid in the mineral is determined in a separate portion by dissolving it in muriatic acid, filtering the dilute solution, and precipitating with chloride of barium.

How far the course of analysis is simplified when one or the other of the substances in question is not present, I have not considered necessary to mention, nor the mode in which the qualitative examination should be conducted. I will only observe, with respect to the latter, that the course of analysis

proposed cannot be deviated from without disadvantage; and further, that it is of great importance, before commencing the qualitative analysis, to ascertain the presence or absence of alumina, manganese and alkaline earths; for when no alumina is present, the first precipitation with carbonate of soda and the boiling with caustic soda may be omitted; the whole of the phosphoric acid is contained in the alkaline liquid holding the alumina in solution when no alkaline earths are present; and the residue which had remained undissolved by the potash may be at once treated for the separation of the iron from manganese; or, when no manganese is present, precipitated at once with ammonia from the muriatic solution after previous oxidation, calcined, and calculated as peroxide of iron.

In proof of the accuracy of this method, the author prepared a liquid containing known quantities of peroxide of iron, alumina, lime, magnesia and phosphoric acid, and divided it into two equal portions, each of which was analyzed precisely according to the preceding directions. Each half of the liquid contained—

|                      | Grms. | Found. |        |
|----------------------|-------|--------|--------|
|                      |       | I.     | II.    |
| Phosphoric acid . .  | 0.100 | 0.0993 | 0.0995 |
| Lime . . . . .       | 0.133 | 0.1328 | 0.1327 |
| Magnesia . . . .     | 0.103 | 0.1020 | 0.1029 |
| Peroxide of iron . . | 1.443 | 1.4426 | 1.4424 |
| Alumina . . . . .    | 0.150 | 0.1495 | 0.1495 |
|                      | 1.929 | 1.9262 | 1.9270 |

Or in 100 parts—

|                      |        |       |       |
|----------------------|--------|-------|-------|
| Phosphoric acid . .  | 5.18   | 5.14  | 5.16  |
| Lime . . . . .       | 6.89   | 6.88  | 6.88  |
| Magnesia . . . .     | 5.34   | 5.29  | 5.33  |
| Peroxide of iron . . | 74.81  | 74.78 | 74.77 |
| Alumina . . . . .    | 7.78   | 7.75  | 7.75  |
|                      | 100.00 | 99.84 | 99.89 |



## CHAPTER VII.

## ON THE ANALYSIS OF ASHES OF PLANTS.

THE method recommended by *Drs. Will* and *Fresenius* is the following:—\*

*First Preparation.*—Plants in a normal and healthy condition should be selected, unless the design be to study diseases and their causes. All foreign matter, such as dirt, dust, &c., should be carefully removed; but the plants should not be washed, or certain soluble salts might be extracted. Plants which have been exposed to moist weather should, for the same reason, be rejected.

The design of analyzing the ashes of plants may be—1st, simply to ascertain the amount and nature of their inorganic constituents; or, 2dly, the operator may have in view the discovery of the presence or absence of certain substances in the soil, such as *alkalies*, *alkaline earths*, and *phosphates*: For the latter purpose an examination of the ashes of all the varieties of plants growing upon the soil must be undertaken; and when a knowledge is hereby obtained of the composition of the inorganic constituents of both weeds and of cultivated plants, and when to this is added an acquaintance with the nature of the soluble constituents of the soil itself, the analyst is in a position to determine for what crops the soil in question is best adapted. *Woods*, *herbs*, and *roots*, after being perfectly dried, may be burned upon a clean iron plate; *leaves*, *fruit*, and *seeds* will be best burned in a Hessian crucible, by means of charcoal or coke: the crucible should be placed somewhat obliquely in the fire, in order to favor the access of air. Sometimes the ashes are left perfectly white, but some seeds require a higher temperature than others to rid the ashes entirely of charcoal: care must, however, be taken not to allow the heat to rise sufficiently high to fuse the alkaline salts, or it will be found afterwards almost impossible thoroughly to burn away the charcoal. During the operation of burning, and especially towards the end of the process, the ashes should be allowed to lie as lightly in the crucible as possible, in order

\* *Memoirs of the Chemical Society*, vol. ii. p. 179, *et seq.*

that air might circulate freely through them; they should not, therefore, be stirred together: by attending to this, a much whiter ash is procured than would otherwise be the case. After the ashes have been well burnt in the crucible, it is advisable to transfer them to a platinum dish, and to heat them to low redness over a gas or spirit lamp, with constant stirring; they should then be rubbed to a fine powder, and transferred while warm to a well stoppered bottle. *Rose* objects to this mode of preparing the ash for analysis; his important observations on this subject will be referred to at length further on.

The ash being prepared, the first step is to determine, by means of a qualitative examination, to which class the ashes belong:—whether to the *silicious*, or to the *phosphoric*, or to the *carbonic* class. A small portion is treated with concentrated hydrochloric acid, which generally dissolves it completely, unless the ash abounds in silica; if a strong effervescence accompany the solution in hydrochloric acid, carbonates of the alkalis or alkaline earths predominate, and the whole of the phosphoric acid present is probably combined with peroxide of iron; if no (or only moderate) effervescence attend the solution, phosphates predominate; and, if complete solution in hydrochloric acid cannot be obtained, the ash belongs to the *silicious* class.

To the clear hydrochloric solution acetate of ammonia is either at once added, or it is first neutralized by means of caustic ammonia, and free acetic acid afterwards added. In most cases a yellowish white gelatinous precipitate is formed, consisting of *phosphate of peroxide of iron*. This precipitate is collected on a filter, and ammonia added in excess to the clear filtrate, by which means a fresh precipitate may be obtained: if it be red, it is peroxide of iron. The solution is well protected from the air, and allowed to stand for some time; if no further precipitation take place, then it is known that the ash contains no other phosphate than that previously precipitated; but, should a white deposit gradually form, it consists of *phosphates of lime and magnesia*, and shows that the ash under examination contains more phosphoric acid than is combined with the peroxide of iron. It is not necessary to proceed further with the qualitative examination, unless the operator should wish to test for *fluorine*, *oxide of manganese*, *iodine*, *bromine*, or any other peculiar substance, the presence of which may be suspected, and in such cases separate por-

tions of the ash must be used for each experiment, as also for determining quantitatively the amounts of carbonic acid in the ashes abounding in that principle, and of the alkalies in the ashes belonging to the *silicious* class.

I. *Determination of the Quantity of Ashes yielded by a given weight of the Plant.*—This is a problem, the solution of which is of considerable importance: a quantity of solid matter is annually removed from the soil in the crop taken from it, which loss should be repaired as nearly as possible by the judicious addition of manure. It is the nature of the manure to be furnished which the farmer seeks from the analytical chemist; but the farmer must take his share in the inquiry by informing the analyst as to the weight of the crop which a given surface of soil should yield, and this he can in most cases do with sufficient accuracy. The vegetable substance under examination should be dried in the water bath, or still better in a current of dry air produced by the efflux of water till it ceases to lose weight.\* The quantity of substance employed in this experiment depends on the proportion of its inorganic constituents. Of *herbs* and *seeds*, which are in general rich in these matters, from 30 to 50 grains will be sufficient, whilst of *woods* ten times that amount must be taken. The combustion succeeds best in a platinum crucible, which should at first be covered, and a gentle heat only applied, but a stronger heat must afterwards be employed, the lid of the crucible being removed to ensure the perfect combustion of the charcoal. Those ashes which do not effervesce with acids, as the ashes of seeds, may be treated with nitric acid, and again ignited, by which treatment they will speedily be rendered quite white. If a very strong heat has been employed, the carbonic acid in those ashes which effervesce with hydrochloric acid will be expelled, but it may be restored by moistening the ashes with solution of carbonate of ammonia, and afterwards again exposing them to gentle ignition: so also, at a high temperature in contact with charcoal, the sulphates (if any be present) may be converted into sulphurets, but the reconversion of those compounds into the original salts may be effected by heating the ashes intensely, and for a considerable time, together with pure peroxide of mercury. Although the above method of estimating the amount of ashes yielded by a plant

\* See Fig. 283 "*Morfil's Manipulations.*"

is not altogether free from objection, it is, nevertheless, a sufficiently close approximation to truth to answer every practical purpose; indeed, it is doubtful whether more accurate methods would really be more valuable, since it is found that the amount of ashes yielded by the same plant is not constant.

II. *Analysis of Ashes, rich in Carbonates and Sulphates.*—*Determination of the Silica, Charcoal, and Sand.*—About 60 grains of the ashes, which have been found to be soluble in hydrochloric acid, are treated with concentrated acid in a matrass, held obliquely so as to avoid any loss of the liquid during the evolution of the carbonic acid; a gentle heat is then applied, until it is evident that everything is dissolved excepting the carbonaceous and sandy particles. The whole is now carefully removed into a porcelain basin, evaporated to dryness over a water bath, and then heated somewhat more strongly, as is usual in separating silica (see page 395). The mass when cold is moistened with strong hydrochloric acid, digested for half an hour with a sufficient quantity of water, and boiled; after which the acid liquor is poured upon a stout filter, which has previously been dried at  $212^{\circ}$ , and weighed. The silica remains on the filter; and, if the ashes were not perfectly white and pure, some sand and charcoal also. The filter is washed and dried, and the substance carefully removed from it into a platinum or silver crucible without injury to the paper. This is effected without difficulty if the matters be perfectly dry, the paper in most cases only retaining so much as to be slightly colored by the charcoal. The powder is now boiled for half an hour with pure potash ley (free from silica), by which the whole of the silica, natural to the ash, will be gradually dissolved, leaving the sand and charcoal unacted upon. The insoluble matter is again collected on the same filter, and after being well washed it is dried at  $212^{\circ}$ , till it no longer loses weight. The increase upon the weight of the dried filter is to be estimated as charcoal and sand. The silica in the alkaline solution is determined by adding hydrochloric acid in excess, whereby it is precipitated; the whole is evaporated to dryness, and the further treatment conducted in the manner directed at page 395.

The acid solution originally filtered from the *silica, sand, and charcoal*, after being well mixed, is divided into *three*, or more conveniently into *four* equal portions, one portion being reserved in case of an accident happening with either of the



other quantities. The division is best effected by means of an accurately graduated tube or cylinder; the whole of the fluid is collected into the tube or cylinder, the measure of which thus represents the weight of ash experimented upon. The solution is now divided into three or four equal or known portions, the volume of each is noted, and they are labeled respectively with the letters *a*, *b*, *c*, and *d*.

In *a* the *peroxide of iron* (oxide of manganese) and the alkaline earths are estimated.

In *b* the alkalies.

In *c* the *phosphoric* and *sulphuric* acids.

*a. Estimation of the Peroxide of Iron, Oxide of Manganese, and Alkaline Earths.*—To the solution ammonia is added until the precipitate thereby produced no longer entirely redissolves; acetate of ammonia is next added, and sufficient acetic acid to render the solution strongly acid. From the form and appearance of the precipitate, it can easily be judged whether it still contains *phosphate of lime*; if this be the case, more acetic acid must be added. The yellowish white precipitate which remains consists of *phosphate of peroxide of iron*  $2\text{Fe}_2\text{O}_3 + 3\text{PO}_5$ ; its separation from the fluid is assisted by gently heating; it is then well washed on the filter with hot water, ignited, and weighed. To the filtered solution neutral oxalate of ammonia is added as long as a precipitate continues to be formed, and the amount of lime is determined in the usual manner (see page 256). When it has been shown by the qualitative analysis that, besides phosphate of iron, the ash contains peroxide of iron or oxide of manganese (in which case the presence of the earthy phosphates is very rarely detected), the solution, previous to the separation of the lime, should be supersaturated with ammonia, and precipitated by means of sulphuret of ammonium, the two oxides being afterwards separated according to one of the methods given at page 292. If the ashes under examination contained earthy phosphates, the solution filtered from the oxalate of lime will contain free acetic acid; if otherwise, there will be free ammonia; it is next somewhat concentrated, rendered ammoniacal, treated with a solution of phosphate of soda, and the precipitate formed collected and estimated as pyrophosphate of magnesia. (See page 257.)

*b. Estimation of the Alkalies.*—The solution is treated with baryta water until it gives an alkaline reaction; it is

then gently heated and filtered. By this means we get rid of all the *sulphuric* and *phosphoric acids*, the *peroxide of iron*, the *magnesia*, and part of the lime. The precipitate is washed on a filter as long as the washings render turbid a solution of nitrate of silver. It is next warmed, treated with caustic and carbonate of ammonia, and allowed to stand until the precipitate becomes heavy and granular. The whole is now filtered, and the solid matter washed, after which the solution is evaporated to dryness, and the residue heated to redness in a platina capsule to expel the ammoniacal salts. What remains consists of the chlorides of potassium or sodium, or more generally of a mixture of the two. The weight being noted, a little water is added, which generally leaves undissolved a trace of magnesia; this is collected on a filter, its quantity subtracted from that of the supposed alkaline chlorides, and added to that of the magnesia, as previously ascertained. The quantity of potash is determined by means of chloride of platinum in the usual way (see page 236), and that of the soda is calculated from that of the chloride of sodium indicated by deducting the weight of the chloride of potassium from that of the mixed alkaline chlorides; or the amount of the two alkalis may be determined by the *indirect* method as directed in page 240.

*c. Estimation of the Sulphuric and Phosphoric Acids.*—From the acidulous solution the sulphuric acid is first separated by chloride of barium; the filtered liquor is nearly neutralized by ammonia; acetate of ammonia is added, and then a solution of perchloride of iron until the liquor begins to turn red in consequence of the formation of acetate of iron. Care must here be taken that sufficient acetate of ammonia be added to convert the whole of the chlorine of the perchloride into sal-ammoniac. The solution is now boiled until it becomes colorless, all the iron being then precipitated. The precipitate, after being washed with hot water, consists of phosphate of iron and a quantity of basic acetate of iron. It is dried, ignited in a platinum crucible, treated with a few drops of nitric acid, re-ignited and weighed. It is next digested with concentrated hydrochloric acid, by which it is speedily dissolved. The solution is diluted with hot water mixed with tartaric acid, and ammonia added until the yellowish white precipitate, which is at first formed, disappears. A clear solution of a dingy green color is thus obtained, from which

the iron is precipitated by hydrosulphuret of ammonia. The precipitate and supernatant fluid are digested together in the water bath until the latter loses its green tinge, and is of a clear yellow color, resembling that of hydrosulphuret of ammonia with excess of sulphur. It is now rapidly filtered, access of air being prevented, and the precipitate is washed with hot water containing a little hydrosulphuret of ammonia, until a drop of the filtered liquid, dried upon a platinum spatula and ignited, no longer gives any acid reaction. The sulphuret of iron is dissolved from the filter by means of hot and dilute hydrochloric acid; the solution is boiled, treated with a few drops of nitric acid to peroxidize the iron, and ammonia is then added in excess. The precipitate is pure peroxide of iron, the weight of which, deducted from that of the basic phosphate, gives the quantity of phosphoric acid. (See page 385.) The perchloride of iron used in this experiment must be quite free from sulphuric acid.

*Estimation of the Chlorine.*—A fresh portion (about 15 grains) of the ashes is weighed out and exhausted with hot water, slightly acidulated with nitric acid; the solution is precipitated with nitrate of silver, following the directions given at page 306. If the ashes should contain appreciable quantities of *iodine* and *bromine* these bodies will be found in the precipitated silver salt; for their quantitative estimation, however, a larger quantity of the ashes must be employed.

*Estimation of the Carbonic Acid.*—The amount of this acid is determined with the apparatus of Drs. *Fresenius* and *Will*, described at page 245.

III. *Analysis of Ashes abounding in Silica.*—Ashes of this kind are in general only partially soluble in acids. Their alkalies must, therefore, be determined in a separate portion of the ash. The chlorine and carbonic acid are determined in the same manner as when the ash is entirely soluble in acids. The quantity of chlorine found in ashes of this class is, however, probably always somewhat less than it should be, since the alkaline chlorides, when ignited with silica and carbon, undergo a partial decomposition.

*Estimation of the Silica.*—Pure potassa or soda ley is poured upon about sixty grains of the ashes, and evaporated to dryness in a platinum or silver dish. The silicic acid compounds are, by this treatment, dissolved, leaving the sand unaffected. The heat should not be so great as to fuse the

mass, or some of the charcoal might be oxidated at the expense of the water of the hydrated alkali. Diluted hydrochloric acid is poured upon the mass, the whole evaporated, and the silica, charcoal, &c. determined in the manner already described. The acidulous solution filtered from the insoluble matter is divided into two parts; one is employed for the determination of the sulphuric and phosphoric acids, and the other for that of the peroxide of iron and the alkaline earths by the methods detailed above.

*Estimation of the Alkalies.*—A second portion of the ash (about fifty grains) is ignited in a platinum crucible with four times its weight of *hydrated baryta*. The acid solution which remains after separating the silica, &c. is precipitated successively with baryta water and carbonate of ammonia, the alkalies being then obtained in the state of chlorides. The further treatment has already been described.

*Arrangement of the Results.*—Since the analysis of the ashes of a plant can convey no precise information as to the manner in which the several acids and bases found are actually combined in the living vegetable, the method recommended by *Fresenius* and *Will*,\* namely, that of enumerating the per centage weights of the acids and bases found is probably the best which the present state of our knowledge admits of; but, whether this or any other method be adopted, it is highly desirable that there should be uniformity on the subject, for it is only thus that the results of different analyses can be compared together, and so applied to the solution of certain interesting questions in physiology and in agriculture. The chlorine found in the analysis is always calculated as chloride of sodium, and the manganese as *manganoso-manganic oxide* ( $Mn_3O_4$ ). As an illustration of this method, we may quote *Messrs. Rowney and How's* analysis of the ashes of the orange-tree.†

Amount of ash left by—

|                               |       |
|-------------------------------|-------|
| 100 parts of the root . . .   | 4.48  |
| 100 parts of the stem . . .   | 2.74  |
| 100 parts of the leaves . . . | 13.73 |
| 100 parts of the fruit . . .  | 3.94  |
| 100 parts of the seeds . . .  | 3.30  |

\* *Fresenius' Quantitative Analysis*, p. 507.

† *Mém. Chem. Soc.*, vol. iii. p. 370.



*Per Centage Composition of the Ashes of the Root.*

|                     |   |   |   |   |   |       |
|---------------------|---|---|---|---|---|-------|
| Potassa             | . | . | . | . | . | 15.43 |
| Soda                | . | . | . | . | . | 4.42  |
| Lime                | . | . | . | . | . | 49.89 |
| Magnesia            | . | . | . | . | . | 6.91  |
| Sesquioxide of iron | . | . | . | . | . | 1.02  |
| Chloride of sodium  | . | . | . | . | . | 1.18  |
| Phosphoric acid     | . | . | . | . | . | 13.47 |
| Sulphuric acid      | . | . | . | . | . | 5.78  |
| Silicic acid        | . | . | . | . | . | 1.75  |

---

*Per Centage Composition of the Ashes of the Stem.*

|                     |   |   |   |   |   |       |
|---------------------|---|---|---|---|---|-------|
| Potassa             | . | . | . | . | . | 11.69 |
| Soda                | . | . | . | . | . | 3.07  |
| Lime                | . | . | . | . | . | 55.13 |
| Magnesia            | . | . | . | . | . | 6.34  |
| Sesquioxide of iron | . | . | . | . | . | 0.57  |
| Chloride of Sodium  | . | . | . | . | . | 0.25  |
| Phosphoric acid     | . | . | . | . | . | 17.09 |
| Sulphuric acid      | . | . | . | . | . | 4.64  |
| Silicic acid        | . | . | . | . | . | 1.22  |

---

*Per Centage Composition of the Ashes of the Leaves.*

|                     |   |   |   |   |   |       |
|---------------------|---|---|---|---|---|-------|
| Potassa             | . | . | . | . | . | 16.51 |
| Soda                | . | . | . | . | . | 1.68  |
| Lime                | . | . | . | . | . | 56.38 |
| Magnesia            | . | . | . | . | . | 5.72  |
| Sesquioxide of iron | . | . | . | . | . | 0.52  |
| Chloride of sodium  | . | . | . | . | . | 6.66  |
| Phosphoric acid     | . | . | . | . | . | 3.27  |
| Sulphuric acid      | . | . | . | . | . | 4.43  |
| Silicic acid        | . | . | . | . | . | 4.83  |

---

*Per Centage Composition of the Ashes of the Fruit.*

|                     |   |   |   |   |   |       |
|---------------------|---|---|---|---|---|-------|
| Potassa             | . | . | . | . | . | 36.42 |
| Soda                | . | . | . | . | . | 11.42 |
| Lime                | . | . | . | . | . | 24.52 |
| Magnesia            | . | . | . | . | . | 8.06  |
| Sesquioxide of iron | . | . | . | . | . | 0.46  |
| Chloride of sodium  | . | . | . | . | . | 3.87  |
| Phosphoric acid     | . | . | . | . | . | 11.07 |
| Sulphuric acid      | . | . | . | . | . | 3.74  |
| Silicic acid        | . | . | . | . | . | 0.44  |
|                     |   |   |   |   |   | <hr/> |
|                     |   |   |   |   |   | 100   |

*Per Centage Composition of the Ashes of the Seed.*

|                     |   |   |   |   |   |       |
|---------------------|---|---|---|---|---|-------|
| Potassa             | . | . | . | . | . | 40.28 |
| Soda                | . | . | . | . | . | 0.92  |
| Lime                | . | . | . | . | . | 18.97 |
| Magnesia            | . | . | . | . | . | 8.74  |
| Sesquioxide of iron | . | . | . | . | . | 0.80  |
| Chloride of sodium  | . | . | . | . | . | 0.82  |
| Phosphoric acid     | . | . | . | . | . | 23.24 |
| Sulphuric acid      | . | . | . | . | . | 5.10  |
| Silicic acid        | . | . | . | . | . | 1.13  |
|                     |   |   |   |   |   | <hr/> |
|                     |   |   |   |   |   | 100   |

In the above calculations the unessential constituents, viz: *carbonic acid, sand and charcoal*, are deducted.\*

*Rose's Method of examining the Ashes of Organic Bodies.*—It has been mentioned above, that the method of preparing the ashes of plants for analysis, by igniting the vegetable in Hessian crucibles, and continuing the heat until all the organic matter is destroyed, has been objected to by *Rose*, who observes† that, if the fixed constituents of plants are

\* The reader is referred to a paper, by *Mr. Watts*, on the "Analysis of the Ash of the Hop," published in the third volume of the "Memoirs of the Chemical Society," p. 392, *et seq.* In this analysis an entirely different system from that above detailed was pursued; separate examinations of the aqueous and the hydrochloric solutions were made, and the acids and bases are arranged as they were supposed to exist in the plant. The analysis itself is remarkable as pointing out the unusual presence of *phosphate of alumina*.

† In a paper read before the Royal Academy of Berlin; *Chem. Gaz.*, vol. v., p. 158, *et seq.*

examined according to the process which he adopted in examining the ashes of *ox-blood*, results differing entirely from those yielded by the ash analyses hitherto published may be obtained.

The process adopted by the Berlin chemist in his analyses of the ashes of blood was this. The blood was exposed in a covered platinum crucible to a very faint red heat, then extracted with cold water, and the colorless liquid evaporated to dryness. It was found to consist of alkaline chlorides and carbonates, with very minute quantities of alkaline sulphates and phosphates. The charred mass, extracted with water, was now treated with hydrochloric acid: the filtered solution did not yield, with ammonia, a very considerable precipitate, which, though it looked almost like pure hydrated oxide of iron, contained some phosphoric acid as well as lime and magnesia. In the filtered solution a pretty considerable quantity of oxalate of lime was obtained with oxalate of ammonia, proving the presence of carbonate of lime in the charred blood; and in the liquid separated there was also a small quantity of magnesia. The cinder, after treatment with water and hydrochloric acid, yielded a very considerable quantity of a red-colored ash, on being burnt in an atmosphere of oxygen. It was in a semifused state, and contained peroxide of iron (which formed the chief part) and earthy and alkaline phosphates. These results differ considerably from those of *M. Enderlin*, whose method was\* to evaporate fresh blood to dryness, and then to powder and incinerate the residue. The ash thus obtained dissolved in hydrochloric acid *without* effervescence, whence he concluded that the alkalinity of blood cannot be caused by an alkaline carbonate, and that there cannot exist in the blood any alkaline salts with organic acids. The salts found by *M. Enderlin* in the ashes of blood he states to be *tribasic phosphate of soda* ( $3\text{NaO}, \text{PO}_5$ ), *chlorides of sodium and potassium*, *sulphate of soda*, *phosphate of lime*, *phosphate of magnesia* and *oxide*, with some *phosphate of iron*, the alkalinity of the blood being produced by phosphate of soda ( $3\text{NaO}, \text{PO}_5$ ). If the phosphate of soda in the blood were the ordinary phosphate ( $2\text{NaO}, \text{HO}, \text{PO}_5$ ), it would, according to *M. Enderlin*, be converted by a red heat into the *pyrophosphate* ( $2\text{NaO}, \text{PO}_5$ ), the third atom of base (HO)

\* See *Liebig's Annalen*, and *Chem. Gaz.*, vol. iii. p. 229.

escaping; but, according to *Rose*, the ordinary phosphate of soda ( $2\text{NaO}, \text{HO}, \text{PO}_5$ ) would, at a high temperature, decompose *carbonate of soda* and be converted into tribasic phosphate ( $3\text{NaO}, \text{PO}_5$ ); and that, in consequence, the conclusions of *M. Enderlin* are erroneous. It has been shown, also, by *Marchand*,\* that the circumstance of no carbonates being found in the ash does not in the least prove that they are not contained in the blood, and that we are as little justified in admitting unconditionally the presence of tribasic phosphate of soda ( $3\text{NaO}, \text{PO}_5$ ) because that salt is found in the ash. Indeed *Marchand* declares that the admission of the presence of  $3\text{NaO}, \text{PO}_5$  in the blood *absolutely requires* the admission of that of carbonate of soda, since it has been proved that  $3\text{NaO}, \text{PO}_5$  is converted, on exposure to a moist atmosphere containing carbonic acid, into  $2\text{NaO}, \text{HO}, \text{PO}_5$ , and  $\text{NaO}, \text{CO}_2$ .

The same objections which have been urged against the conclusions drawn by *Enderlin* with regard to the salts existing in the blood, from the analysis of the ashes prepared at high temperatures, have been also applied by *Rose* to the conclusions drawn from the results of the analysis of the ashes of plants prepared in the usual manner. It had previously been remarked by *Erdmann*† that the mode of preparation of the ashes for analysis has great influence on their apparent composition. His method was to burn the plant or seeds in a muffle furnace, in which, in the course of three or four hours, upwards of 200 grains of the most beautiful ash of corn may be obtained. The ashes so prepared, especially in those seeds that are difficult to reduce to ash, generally contain the phosphoric acid in a lower state of saturation than those prepared in a crucible. Thus the ash of rye, which usually contains an alkaline phosphate, yielding, with oxide of silver, a white precipitate, gives a yellow one when it has been prepared by long-continued ignition in a covered crucible; and biphosphate of potassa, when ignited for a long time with carbonized sugar, is converted into a bibasic, and finally even into a tribasic salt. It is evident, therefore, that a reduction of the phosphoric acid has taken place, and the same is the case with the sulphuric acid. These facts induced *Rose* to undertake

\* Journ. für Prakt. Chem., April 6th, 1846; and Chem. Gaz., vol. iv. p. 210.

† See *Liebig's Annalen*, liv. p. 341—356, 360—363; lvi. p. 122; lvii. pp. 67, 68; and Chem. Gaz., vol. iv. p. 230, *et seq.*



an examination of the fixed constituents of certain plants by the same method which he had adopted in the analysis of ox-blood, a method which, although it may be objected to in that it takes more time, furnishes (he says) far more correct results, and gives satisfactory answers to several questions as to how, or in what combinations, the constituents found in the ash were contained in the organic substance.

His method is as follows.\* The organic substance is charred at a very faint red heat, so that the water with which it is extracted is not colored yellowish or brownish. At this temperature, which, owing to the volatilization of so many substances, is much lower than would appear, no alkaline chlorides are volatilized, nor can chlorine be expelled from them, in the form of hydrochloric acid, by acid phosphates. The alkaline and earthy phosphates are not able to expel the carbonic acid from the alkaline carbonates, either contained in the organic substance or formed by charring; nor can phosphoric acid be eliminated, from its combinations, from silica, reduced by carbon, and volatilized in the form of phosphorus. The charring is effected either in a spacious covered platinum crucible, over a spirit lamp; or, with larger quantities of the organic substances, in a spacious covered Hessian crucible, especially if they do not fuse. When there is no longer much empyreumatic odor perceptible, the heating is discontinued, the cold mass left for some time in contact with water, and the solution of the salts furthered by heating. The edulcoration requires considerable time and much hot water; but, if the highest degree of accuracy is not desired, the edulcoration may be discontinued when several drops of the wash-water leave a scarcely perceptible residue on evaporation upon a slip of platinum foil: this point is very soon attained.

The aqueous extract contains the alkaline salts. The alkaline chlorides were contained as such in the organic substance previous to the charring, as well as at least a part of the alkaline sulphates and phosphates. If, as in most cases, carbonated alkali is found in the aqueous extract of the charred

\* For the report of *Prof. Rose's* important paper on the "Examination of the Ashes of Organic Bodies," given in the text, the author is indebted to the "*Chemical Gazette*;" he has preferred transcribing the paper almost in full to giving any abstract of it, to avoid the possibility of any misconception in any of the details of the operation.

mass, it either pre-existed in the organic substance, or the alkali in it was combined with an organic acid, or some other organic body which acted the part of an acid towards the alkali. If the organic substance contain sulphate of lime, this, when carbonated alkalies are present in sufficient quantity in the charred mass, is converted, on treating the latter with water, into carbonate of lime and alkaline sulphate. In the same way, when phosphate of lime is present, a certain quantity of alkaline phosphates is formed from it, in the aqueous extract, by the alkaline carbonates. Carbonated alkali and phosphate of lime are not perfectly decomposed even by fusion at very high temperatures.

The decomposition in presence of much water is likewise imperfect; and, the more alkaline phosphate is obtained in the aqueous extract, the more concentrated the solution, the more carbonated alkali it contains, and the longer the charred mass has been digested at an elevated temperature. Alkaline sulphates and phosphates will, however, be found in far smaller quantities in the aqueous extract of the charred mass than was to be expected from the ash analyses that have hitherto been published. Frequently the two, and especially the latter, are present only when too high a temperature has been employed in the charring. From this, however, it is evident that the nature of the salts in the aqueous extract may vary somewhat, according to the temperature employed and the longer or shorter digestion of the mass with water. When the charring is effected at too high a temperature, the greater portion of the carbonated alkalies are decomposed by the earthy phosphates.

The accurate examination of the salts in the aqueous extract is not accompanied with any great difficulties. One circumstance, however, renders it somewhat less easy. Carbonate and phosphate of lime and magnesia frequently dissolve to a considerable extent in neutral solutions of alkaline salts, particularly of alkaline carbonates and phosphates; in the course of time they are deposited from the solutions, especially after the application of heat. When, therefore, the aqueous extract is evaporated, it frequently becomes somewhat turbid, and deposits small quantities of earthy salts. It should consequently be evaporated nearly to dryness, diluted with water, and the solution set aside for some time; when the earthy salts have subsided, it is filtered, the filtered solution evapo-

rated to dryness, and its weight determined. When there is no alkaline sulphate or phosphate present, the examination is very easy. The quantity of carbonic acid is determined in a suitable apparatus, by decomposition with nitric acid; and, upon this, that of the chlorine by a solution of silver: upon which, after removing the excess of silver by hydrochloric acid and concentrating the liquid, the potash may be separated from the soda by chloride of platinum. With the presence of alkaline sulphate or phosphate, it is advisable to divide the quantity of the alkaline salts, and in the one-half to determine the quantity of the chlorine and the alkalies, and in the other that of the carbonic acid by decomposition with hydrochloric acid; that of the sulphuric acid by a salt of barytes; and, after removing the baryta by means of sulphuric acid, and supersaturating with ammonia, to ascertain the quantity of phosphoric acid by means of a solution of a salt of magnesia, to which chloride of ammonium has been added.

The charred mass, exhausted with water, is now digested with hot hydrochloric acid for some length of time, and then washed with water. This operation requires considerably more time and water than in the treatment of the charred mass with water; and, if the washing were to be continued until some drops of the filtered liquid no longer produced any opalescence in a solution of silver, an enormous length of time, several months, would be required, especially in operating upon large quantities. The edulcoration, therefore, is only continued until a considerable quantity of the wash-water does not exhibit a trace of a precipitate when treated with ammonia; it will then also be seen that a large quantity of the wash-water, when evaporated upon platinum, no longer leaves any perceptible residue; this does not require much time, especially when hot water is used.

The acid solution contains the earthy phosphates which existed as such in the organic substance, and the peroxide of iron. It is precipitated by ammonia, and, after having determined the weight of the precipitate, the bases are separated from the phosphoric acid. On separating the earthy phosphates by means of ammonia, a small quantity remains dissolved in the filtered liquid, owing to the presence of chloride of ammonium; consequently, upon adding oxalate of ammonia, a precipitate of oxalate of lime is obtained, but its quantity is usually larger than corresponds to the phosphate of lime

dissolved by the chloride of ammonium; consequently, a portion of the lime existed as carbonate of lime in the charred mass, or was formed by the decomposition of the sulphate or phosphate of lime by the alkaline carbonates. The liquid filtered from the oxalate of lime indicates, on the addition of a solution of phosphate of soda, the presence of some magnesia. The insoluble earthy salts, which separated from the aqueous extract, may be examined conjointly with those in the acid extract.

With respect to the charred mass which has been exhausted with water and hydrochloric acid, it might be imagined that it could contain only silica or silicates, undecomposable by dilute hydrochloric acid; but it yields a very large amount of ash on complete combustion, even when the organic substance contains no silica or mere traces. *Rose* effects the complete combustion of the charred mass in a thin porcelain crucible, provided with a platinum cover, which is perforated in the centre, and into which there passes a curved silver tube about eight inches long, through which dry oxygen gas is conveyed into the crucible. The crucible is half filled with the substance and heated over a spirit-lamp, and, with proper care, not a particle of the ash is carried away, and the combustion proceeds with great rapidity: a further quantity of the substance is conveyed from time to time into the crucible. The ash thus obtained may be weighed with great accuracy. Its weight added to that of the evaporated aqueous extract of the charred mass, and to that of the insoluble earthy salts dissolved by the hydrochloric acid, gives the correct quantity of fixed constituents in the organic substance employed.

The ash obtained, especially when derived from vegetable substances, consists of the same constituents as were found in the aqueous and acid extracts; if alkalies were present in them, we likewise find them in the ash of the exhausted charred substance; otherwise, it consists principally of earthy phosphates. When the subject of the analysis is *the blood*, nearly the whole of the *iron* is met with in this ash. Only about a tenth part of it is found in the acid extract of the charred mass, and indeed the less the more carefully the charring was effected with exclusion of the air. When the organic substance contains no silica, various views may be entertained respecting the origin of the ash from the charred mass which has been exhausted with water and acid. The



most probable is, perhaps, to derive it from an imperfect exhaustion of the two solvents. When an organic substance is destroyed by heat, the charcoal formed may contain such cavities that the inorganic salts surrounded by them are protected from the action of the solvents. The globules of the blood, those of yeast, and the cells of plants, form, perhaps, after charring, extremely minute vesicles, with such small apertures that no liquid can penetrate into them. That the vessels of wood are capable of forming extremely thin filaments with minute apertures by charring is known from the investigations of *Degen*. The charred mass of an organic substance (yeast), after it has been most carefully exhausted by water and hydrochloric acid, was ground to the finest powder upon a plate of agate; the two solvents now extracted only imperceptible traces of fixed constituents, and, after burning the exhausted charred mass, *Rose* obtained the same large amount of ash as from the non-pulverized charcoal. It may, nevertheless, be supposed that the extremely minute vesicles were not destroyed and torn by the friction upon the agate plate. The microscope threw no light upon the subject.

It is known that charcoal is capable, by a weak kind of affinity, of removing certain salts from their solutions. *Rose* found it almost impossible, also, to remove entirely by washing the whole of the hydrochloric acid from the charred mass which had been digested in hot acid; but the quantity of ash is too considerable for us to ascribe this origin to it, since it is known that the salts which the charcoal has combined with may be entirely separated by long treatment with water at different temperatures. If *sulphate of potash* and *phosphate of lime* are mixed with *sugar* and the whole charred, water, and after this hydrochloric acid, will extract the two salts completely, so that, on subsequently burning the charred mass in an atmosphere of oxygen, not a trace of ash is obtained. *Rose* then discusses the several views which might be advanced to account for the ashes obtained from the charred mass. The following is remarkable from the curious considerations it involves with respect to the combinations of the organic with the inorganic materials in the living vegetable. The salts found in the ashes may, perhaps, not have pre-existed as such in the organic substances, but were first formed by oxidation after the burning of the coal. It has long been known that the protein compounds, of both animal and vege-

table origin, contain *sulphur* and *phosphorus* in an unoxidized state; but the supposition has never been advanced, that the radicals of the earths and alkalies may likewise be contained in organic substances, in an unoxidized state, perhaps combined with those elements. These would certainly constitute a very peculiar class of combinations, such as at present we are not acquainted with. If they are really combined with organic substances in the living body, they cannot have been essentially altered on destroying the organic body by charring, or they have entered into combination with carbon and nitrogen, which are insoluble both in water and in hydrochloric acid.

The salts found in the ashes of the charred mass exhausted with water and acid, especially when derived from vegetable substances, are similar to those which occur in the aqueous and acid extract. If this be really true, then those salts found in the ash after the destruction of the living plants are probably contained in them only in part as such, and in part in a deoxidized state. The inorganic salts, therefore, which are taken up from the soil by the living plant are partially deoxidized by it, and in this state form combinations with organic substances contained in the plant.

This view (observes *Rose*) is far more probable with respect to several animal substances, especially the blood, than in reference to plants. It has long been suspected that the iron in the blood was contained in it in an unoxidized state: and, according to the recent investigations of *Mulder*, the iron is actually extracted by acids from *hæmatine* with evolution of hydrogen gas. On the other hand, it is very remarkable that iron cannot be extracted from the charred blood by hydrochloric acid. This subject deserves investigation. With respect to plants, the view above advanced can evidently only be confirmed or refuted by following the method of analysis above described, and thus it is that *Rose* has pronounced it by far the most rational mode of investigation.

It has been shown by *Rose* that frequently very considerable quantities of alkaline carbonates are extracted by water from several organic substances by charring, in the ashes of which no carbonic acid was found by former investigators. But all organic substances do not yield alkaline carbonates when treated in this manner, even though considerable quantities of alkali are contained in their ash. Highly remarkable

in this respect is *yeast*, the ashes of which, according to *Mitscherlich*, contain no carbonic acid and no metallic chlorides; and *Rose's* experiments show that they are likewise not to be found in the aqueous extract of the charred yeast. Yeast diffuses, on being charred, an odor similar to that of the protein compounds: the aqueous extract did not turn litmus paper blue—became turbid on evaporation, and deposited a large quantity of earthy phosphates. The mass evaporated to dryness yielded, on filtration, a clear solution which faintly reddened litmus-paper, and contained, therefore, not a trace of alkaline carbonates; the only substances that could be found in it were alkaline phosphates, with very minute traces of alkaline sulphates and chlorides. The charred mass gave, on treatment with hydrochloric acid, a solution from which ammonia threw down a considerable precipitate of earthy phosphates. The cinder, exhausted with water and acid, furnished on combustion a very large quantity of ash, which contained the same constituents which had been extracted from the charred mass.

---

## CHAPTER VIII.

### ON THE ANALYSIS OF URINE AND URINARY CALCULI.

FROM the following analysis of this important secretion by *Berzelius*, it will be seen that its composition is very complicated; indeed the Chemistry of Urine is as yet very imperfect, for in no complete analysis which has hitherto been published has any account been taken of the *hippuric acid*, or the *kreatine*, or *kreatinine*, which *Liebig* has announced to be constant constituents, while, according to the same chemist, normal urine contains no lactic acid; so that in the subjoined analysis the 17.14 parts which are set down to this acid and its salts are, in reality, something else, the nature of which has yet to be discovered.

*Analysis of Urine by Berzelius.*

|                                                     |   |   |   |   |   |        |
|-----------------------------------------------------|---|---|---|---|---|--------|
| Water                                               | . | . | . | . | . | 933.00 |
| Urea                                                | . | . | . | . | . | 30.10  |
| Uric acid                                           | . | . | . | . | . | 1.00   |
| Lactic acid, lactates, and animal matter            | . | . | . | . | . | 17.14  |
| Mucus of the bladder                                | . | . | . | . | . | 0.32   |
| Sulphate of potash                                  | . | . | . | . | . | 3.71   |
| Sulphate of soda                                    | . | . | . | . | . | 3.16   |
| Phosphate of soda                                   | . | . | . | . | . | 2.94   |
| Phosphate of ammonia                                | . | . | . | . | . | 1.65   |
| Chloride of sodium                                  | . | . | . | . | . | 4.45   |
| Hydrochlorate of ammonia                            | . | . | . | . | . | 1.50   |
| Earthy matters, with a trace of fluoride of calcium | . | . | . | . | . | 1.00   |
| Silicious earths                                    | . | . | . | . | . | 0.03   |

---

 1000

Urine may be acid, neutral, or alkaline, even in a healthy condition of the body, its reaction to test paper as well as the nature of the salts which it contains depending in a great measure on the nature of the food, so that the physician has the saline condition of this secretion greatly under his control, a fact of great value in the treatment of calculous diseases. When the food contains salts of potassa and soda with organic acids, the urine becomes alkaline; these acids becoming oxidized in the circulation yield carbonic acid, which combines with the alkalis, and the alkaline carbonates appear in the urine. When the food contains but very little of such salts of organic acids, the urine may be neutral, and when it contains none at all it becomes acid from the solution of uric or hippuric acid, or both, in phosphate of soda.\*

The specific gravity of healthy urine may vary from 1.012 to 1.030, and contain about 7 or 8 per cent. of solid matter, the remainder being water. In certain diseases, however, the density of the secretion may be considerably greater, as well as its proportion of solid ingredients. The following table, showing the quantity of solid matter in diabetic urine of different specific gravities between 1.020 and 1.050, was drawn up by *Dr. Henry*, and assuming its correctness, *Dr. Frampton*† has given the following simple method of deter-

\* Turner's Chemistry, by *Liebig* and *Gregory*. Eighth edition.

† Medical Gazette.



mining, without having recourse to actual experiment, the amount of solid matter voided in a given time in urine of any specific gravity. If *Dr. Henry's* table be examined, it will be found that there is an increase of solid matter in each wine pint of urine, corresponding to the increase of one degree of specific gravity of exactly 12.2 grains, or of 1.2 grains of solid matter in each ounce for every one degree of specific gravity. Hence, to determine the amount of solid contents in urine, say specific gravity 1.025, we have only to multiply the constant quantity 1:2 grains, by 25; making 30 grains, to give us the solid contents of one ounce, whose specific gravity is 1.025, and this again by the number of ounces voided in a given time, say 40 ounces (making 1200 grains), to give us the whole contents of solid matter dissolved in the urine passed in that time. This rule will be found, on trial, to give results so nearly coinciding with those of the table (the error is constantly just 1.6 grains in excess in the wine pint), it is so easy both to recollect and to apply, and so much more convenient than a table not always at hand, that it is well worthy of the notice of medical men.

In the experiments, which furnished the following table, the urine was evaporated at a steam heat till it ceased to lose weight, and till it left an extract which, on cooling, became quite solid. In reference to such tables, *Dr. Bence Jones*\* observes, that though they may be true for the total quantity of water passed in twenty-four hours, they are not so for the urine made at any one period of the day. The water made before and after dinner, for instance, may have the same specific gravity, but the total quantity of solid residue in each case may be entirely different.

*Dr. Henry's Table of Solid Matter in Urine of different Densities.*

| Specific gravity of the<br>urine, water being<br>1000. |     | Quantity of solid<br>extract in a wine<br>pint in grs. |     | Quantity of solid extract in a<br>wine pint in |     |      |      |
|--------------------------------------------------------|-----|--------------------------------------------------------|-----|------------------------------------------------|-----|------|------|
|                                                        |     |                                                        |     | oz.                                            | dr. | scr. | grs. |
| 1020                                                   | ... | 382.4                                                  | ... | 0                                              | 6   | 1    | 2    |
| 1021                                                   | ... | 401.6                                                  | ... | 0                                              | 6   | 2    | 1    |
| 1022                                                   | ... | 420.8                                                  | ... | 0                                              | 7   | 0    | 0    |
| 1023                                                   | ... | 440.0                                                  | ... | 0                                              | 7   | 1    | 0    |
| 1024                                                   | ... | 459.2                                                  | ... | 0                                              | 7   | 1    | 19   |

\* Phil. Trans., Part iv., for 1846.

| Specific gravity of the<br>urine, water being<br>1000. |     | Quantity of solid<br>extract in a wine<br>pint in grs. | Quantity of solid extract in a<br>wine pint in |     |      |      |
|--------------------------------------------------------|-----|--------------------------------------------------------|------------------------------------------------|-----|------|------|
|                                                        |     |                                                        | oz.                                            | dr. | scr. | grs. |
| 1025                                                   | ... | 478.4                                                  | 0                                              | 7   | 2    | 18   |
| 1026                                                   | ... | 497.6                                                  | 1                                              | 0   | 0    | 17   |
| 1027                                                   | ... | 516.8                                                  | 1                                              | 0   | 1    | 16   |
| 1028                                                   | ... | 536.0                                                  | 1                                              | 0   | 2    | 16   |
| 1029                                                   | ... | 555.2                                                  | 1                                              | 1   | 0    | 15   |
| 1030                                                   | ... | 574.4                                                  | 1                                              | 1   | 1    | 14   |
| 1031                                                   | ... | 593.6                                                  | 1                                              | 1   | 2    | 13   |
| 1032                                                   | ... | 612.8                                                  | 1                                              | 2   | 0    | 12   |
| 1033                                                   | ... | 632.0                                                  | 1                                              | 2   | 1    | 12   |
| 1034                                                   | ... | 651.2                                                  | 1                                              | 2   | 2    | 11   |
| 1035                                                   | ... | 670.4                                                  | 1                                              | 3   | 0    | 10   |
| 1036                                                   | ... | 689.6                                                  | 1                                              | 3   | 1    | 9    |
| 1037                                                   | ... | 708.8                                                  | 1                                              | 3   | 2    | 8    |
| 1038                                                   | ... | 728.0                                                  | 1                                              | 4   | 0    | 8    |
| 1039                                                   | ... | 747.2                                                  | 1                                              | 4   | 1    | 7    |
| 1040                                                   | ... | 766.4                                                  | 1                                              | 4   | 2    | 6    |
| 1041                                                   |     |                                                        |                                                |     |      |      |
| 1042                                                   | ... | 804.8                                                  | 1                                              | 5   | 1    | 4    |
| 1043                                                   |     |                                                        |                                                |     |      |      |
| 1044                                                   | ... | 843.2                                                  | 1                                              | 6   | 0    | 3    |
| 1045                                                   |     |                                                        |                                                |     |      |      |
| 1046                                                   | ... | 881.6                                                  | 1                                              | 6   | 2    | 1    |
| 1047                                                   |     |                                                        |                                                |     |      |      |
| 1048                                                   | ... | 920.0                                                  | 1                                              | 7   | 1    | 0    |
| 1049                                                   |     |                                                        |                                                |     |      |      |
| 1050                                                   | ... | 958.4                                                  | 1                                              | 7   | 2    | 15   |

It is no part of our plan, neither would it be at all suited to the design of the present work, to give any detailed account of the numerous and important investigations which have been made within the last few years on the urine, both in health and in disease. To the physiologist and pathologist it cannot be doubted that the subject must be one of the highest interest; but it is not to a general treatise on chemical analysis that the cultivator of medical science would refer for such information as he might require in this department of his studies. We have, nevertheless, thought that it might add to the usefulness of our work to bring together some of the later methods, which have been adopted by chemists for

the detection and quantitative estimation of certain of the ingredients of this complicated secretion.


*Quantitative Estimation of Urea.*—Two methods have long been in use, viz: separating it as *nitrate*, and calculating its proportion; or as *oxalate*, this being subsequently decomposed by carbonate of lime, and the urea weighed in its pure state. Both these methods are fallacious, on account of the solubility of both the salts; the following have, therefore, been proposed as substitutes.

1. *Rabsky's Method.*\*—Concentrated sulphuric acid, in the quantity of half that of the urine used, is added to the latter, and the mixture kept in a moderate state of ebullition; much water is thus vaporized, and the fluid becomes black. The temperature continues to rise, until at about  $392^{\circ}$  (it should not very much exceed this temperature) carbonic acid is evolved in small bubbles; the cessation of this disengagement of gas indicates that the urea is completely decomposed. The black residue is then thoroughly exhausted with water, and the solution filtered: the clear yellow filtrate is then evaporated in the water bath, and the generated sulphate of ammonia treated with alcohol and chloride of platinum. Since urine contains salts of potassa and ammonia, which will likewise be precipitated upon the addition of chloride of platinum, their exact proportion must be determined from a separate weighed portion by precipitation with chloride of platinum, and the corresponding amount must be subtracted from the first quantity. The author found this method to give accurate results, which were not interfered with by mixing the urea with sugar previous to analysis: in applying it, however, it is necessary to remove all those substances which might introduce error, such as *uric acid*, *hippuric acid*, *albumen*, &c. In many instances it may be advisable to separate the urea previously by oxalic acid, and to decompose the oxalate subsequently with sulphuric acid. In calculating the amount of urea, one part of ammonia-chloride of platinum corresponds to 0.134498 of urea.

The conversion of urea into carbonate of ammonia, which also takes place when the urine is left to itself, will be understood from the following equation, in which it is seen that by

\* *Lancet*, Dec. 6, 1845.

the addition of the elements of water all its carbon is converted into carbonic acid, and all its nitrogen into ammonia.



The carbonate of ammonia thus formed is of course instantly decomposed in the above experiment by the sulphuric acid, sulphate of ammonia being generated, and carbonic acid set free.

2. *Heintz's Method.*\*—*Estimation of the Potassa and Ammonia.*—A weighed quantity (from 100 to 120 grains) of the urine is treated with about 30 drops of hydrochloric acid, and set aside in a cool place for 24 hours; it is then filtered through a very small filter into a large platinum or porcelain crucible; the filter and glass are washed with a small quantity of water; the filtrate is treated with about 100 grains of sulphuric acid, and the liquid evaporated over a small spirit lamp, taking care that it does not boil, until the evolution of carbonic acid commences. The crucible is then covered with a watch glass, and heated until the evolution of carbonic acid ceases, the temperature not being allowed to exceed  $180^\circ$ . The contents of the crucible are then filtered into a porcelain dish, the crucible and the watch glass are well washed, and the filtrate is evaporated until almost all the water has passed off. About 20 drops of hydrochloric acid are then added to the residue, and afterwards a sufficient quantity of chloride of platinum and alcohol mixed with æther. If the liquid from which the precipitate has subsided is of a very pale color, more chloride of platinum must be added. After 8 or 10 hours the precipitate is separated by filtration, washed, dried, and heated to redness in a crucible, which is at first covered, but subsequently open. The residue is treated with boiling dilute hydrochloric acid, the solution filtered, and this is repeated until the liquid which drops from the filter leaves no residue when evaporated upon platinum foil; the crucible and filter are dried at a gentle heat: the latter is burnt in the former, and

\* *Poggendorff's Annalen*, No. 9, 1845: and *Chem. Gaz.*, vol. iv. p. 17.



weighed. Thus the amount of platinum, which corresponds to that of the *potassa*, *ammonia*, and *urea*, is obtained.

Another weighed quantity of the fresh urine is treated at once with chloride of platinum, 3 volumes of alcohol and 1 of ether: at the end of 10 or 12 hours the mixture is filtered, and the precipitate heated to redness in a well covered and weighed platinum crucible. The residue is treated as above with dilute hydrochloric acid, and the filter is burned and weighed. We thus obtain the weight of platinum which corresponds to the potash and ammonia contained in the urine; its per-centage is calculated, and then deducted from that obtained in the first experiment: the difference gives the amount of platinum which corresponds to the urea.

In estimating the urea, if perfect accuracy be not required, the separation of the lithic acid may be avoided, the error hereby introduced amounts to about 0.7 part per 1000, placing the average amount of lithic acid in the urine at 1.0 per 1000. The filtration of the residue after the action of the sulphuric acid may be avoided, and it may be mixed at once with the chloride of platinum, alcohol, and ether.

The estimation of the amount of *potash* and *ammonia* in the urine should not be neglected, as it is liable to considerable variation: the author found it 1.0 to 11.6 parts per 1000. These two alkalies are precipitated together by treating fresh urine with chloride of platinum, alcohol, and ether. To separate them, the yellow precipitate is heated to redness, and the residue repeatedly extracted with boiling dilute hydrochloric acid: the solution is filtered, and the filter burnt. The platinum remaining corresponds to the quantity of ammonia and potash in the urine. On evaporating the filtered liquid with chloride of platinum and alcohol, a precipitate of *platino-chloride of potassium* is obtained, which is treated as above to estimate the potash it contains.

*Separation of Albumen.*—To estimate the urea in *albuminous* urine, a carefully weighed portion is treated with *bichloride of mercury* and boiled in a capacious dish. The liquid is then filtered, the precipitate slightly broken up and washed with water. When this is perfectly effected, a slow current of sulphuretted hydrogen is passed through the filtrate, and the liquid is filtered from the sulphuret of mercury formed.

The separation of the mercury may also be omitted, if care be taken to guard against the vapors of mercury which escape

on heating it with sulphuric acid. The filtrate is evaporated with the addition of sulphuric acid until the urea is completely decomposed. The fluid thus obtained is treated as above described. Another weighed portion of the urine is also precipitated with bichloride of mercury, the precipitate washed with alcohol, and the filtrate treated with bichloride of platinum and ether. The platinum obtained enables us to calculate the amount of potash and ammonia present.

The author found that *albumen* is not perfectly precipitated by boiling even from acid urine, neither indeed is it admissible to use nitric acid when the urine is subsequently to be treated for the estimation of urea, since, by the action of sulphuric acid, nitrous acid would be formed, which decomposes the urea so as to liberate part of the nitrogen in the gaseous state. He also found that with *alcohol* a considerable amount of albumen may, in many cases, remain unprecipitated; and that, moreover, the albumen precipitated by alcohol is very difficult to wash. The above process has been shown by *Heintz* to be applicable to the estimation of the urea in urine containing *blood*, *milk*, and *bile*. In the latter case, should the urea amount to *one-ninth* of that of the urine (which could hardly occur), the error would not exceed 0.16 per 1000.

*Bunsen's method of estimating Urea*\*.—It is founded on the fact, that aqueous solutions of urea are readily decomposed into carbonate of ammonia when heated above  $212^{\circ}$  in hermetically closed vessels. The metamorphosis begins even below  $248^{\circ}$ , but proceeds so slowly at this temperature that it is not completed in three or four hours; while, if the temperature is kept between  $428^{\circ}$  and  $464^{\circ}$ , three or four hours suffice for perfect decomposition. To apply this reaction to the determination of the amount of urea in liquids, it suffices to heat them, in strong glass tubes, with an ammoniacal solution of chloride of barium up to  $428^{\circ}$ — $464^{\circ}$ , a precipitate of carbonate of baryta equivalent to the amount of urea is obtained.

The author found that none of the different nitrogenous substances present in the urine interfered with the accuracy of this method, and he proved, by direct experiment, that it possesses sufficient accuracy even in the presence of substances the most widely diffused in the animal body. In order

\* *Leibig's Annalen*, March, 1848; and *Chem. Gaz.*, vol. vi. p. 222.

to avoid the influence which the so-called extractive substances of the urine may exert, *Bunsen* determines the urea from two separate portions of the urine, one of which has been previously deprived of its extractive substances by basic acetate of lead, and he gives a formula for facilitating the calculation from the results of the analysis.\*

*Estimation of the Uric Acid.*—A weighed quantity of the fresh urine is precipitated by strong acetic acid; the precipitate is collected on a weighed filter, and washed with water acidified with acetic acid. According to *Liebig*, the uric acid in the urine is held in solution by phosphate of soda; it has been proved, however, by *Heintz*, that this in nowise interferes with the accuracy of the method. The uric acid, during its precipitation, carries with it a certain quantity of the coloring substances of the urine; but, according to *Heintz*, the increase of weight from this cause is about compensated for by the loss which the uric acid sustains by washing. Lastly, the same chemist has proved, by direct experiment, that neither *sugar*, *albumen*, nor *blood*, have any essential influence upon the quantitative estimation of uric acid, provided acetic acid be employed as the precipitant.

*Estimation of the Hippuric Acid.*†—A weighed or measured quantity of fresh urine is evaporated over the water-bath to the consistence of a thin syrup, and, on cooling, one-twentieth part of strong hydrochloric acid added to it, then shaken with ether, this dissolves the hippuric acid which has separated. It frequently happens that the ethers, as in an emulsion, separate with difficulty from the resin; but this is instantly effected by the addition of a few drops of alcohol. In this case the ethereal solution of the hippuric acid should be shaken, previous to evaporation, with some water, in order to remove the urea taken up by the ethereal solution through the intermediation of the alcohol. When this is done, crystals of pure hippuric acid are obtained on evaporation of the ethereal solution. In stale urine the hippuric acid gives place to benzoic acid, and, when concentrated and distilled, a large quantity of acetic acid is also obtained. Another method of separating the hippuric acid from normal urine, is to evaporate

\* For this formula, and for the reasoning on which, it is founded, the reader is referred to the original paper, which is too lengthy for our limited space.

† *Liebig*, in *Archiv. der Pharm.* for March, 1844.

until the salts are deposited, and then to add strong alcohol and apply heat; uric acid remains undissolved. The clear solution is evaporated nearly to dryness, the residue redissolved in hot water, and the urea decomposed by passing a current of *chlorine* through the solution; a small quantity of a mineral acid is then added, and the solution concentrated, when the hippuric acid is obtained in a crystalline state.

*Detection of Bile in Urine.*—A spirituous extract of the secretion is evaporated nearly to dryness on the water-bath; the residue, when cold, is transferred to a test tube. When quite cold, *sulphuric acid* and a very small quantity of a solution of one part of *cane-sugar* to four or five of water is added, the temperature of the solution being kept as low as possible. In the course of a few minutes, if the most minute trace of bile be present, a *violet red color*, of more or less distinctness, is produced. Concentrated hydrochloric acid, heated with bile and sugar, likewise produces a red color, but it is much lighter and less beautiful than that with sulphuric acid. The following precautions, in the application of this test, are prescribed by its author\* (*M. Pettenkofer*).

1st. The temperature must not exceed 144° Fahr., otherwise the color may be destroyed; 2d, the quantity of sugar must not be too large, or sulphurous acid may be formed, whereby the color may be concealed; 3d, the sulphuric acid must be free from sulphurous acid; 4th, if the fluid should contain albumen, it should be previously coagulated; 5th, great excess of chlorides convert the color to a brownish red; they should, therefore, be separated. To detect the constituents of the bile in urine, *M. Schwertfeger*† recommends precipitating with basic acetate of lead. When bile is present, a yellow precipitate is formed, from which a green solution is obtained with alcohol containing some sulphuric acid, and from which pure alcohol extracts, with the assistance of heat, bilate of lead. It is impossible to conclude from the color of the urine as to the presence of bile, since similar colors may likewise originate from other causes.

*Detection and Separation of Kreatine.*—*Pettenkofer* and *Heintz* give the following as the most advantageous method.‡ To the alcoholic extract of the urine an alcoholic solution of

\* Ann. der Chem. und Pharm., Oct. 1844.

† Jahrb. für Prakt. Pharm., ix. p. 375.

‡ Comptes Rendus, March 22, 1847.



chloride of zinc is added; in a short time a deposit is formed, which contains the  *kreatine*  in combination with chloride of zinc, together with a small quantity of phosphate of zinc. These two substances are separated by boiling water, which dissolves the first, but which is without action upon the latter. The pure  *kreatine*  is obtained from the aqueous solution of its combination with chloride of zinc, by precipitating the zinc with hydrosulphuret of ammonia; after having evaporated the filtered liquor as far as possible without a precipitate being formed from the boiling solution, absolute alcohol is added to it, when the  *kreatine*  is immediately deposited in the form of small crystals resembling those obtained in operating upon the alcoholic solution of the aqueous extract of  *meat* . The composition of these crystals, according to  *Heintz* , leads to the formula  $C_3H_9N_3O_4 + 2HO$ , which is the same as that advanced by  *Liebig* .

*Detection of Oxalate of Lime.* —The following process is recommended by  *Dr. Golding Bird* .<sup>\*</sup> Allow a portion of the urine passed a few hours after a meal to repose in a glass vessel; if this be done in winter, or during the prevalence of frequent and rapid alterations of temperature, a more or less dense deposit of  *urate of ammonia*  will generally make its appearance, arising either from the sudden cooling of the urine, or from interference with the functions of the skin prior to excretion. In warm weather, however, or when the functions of the skin are tolerably perfect, the urine, albeit it may be loaded with oxalate of lime, may still appear limpid, or, at furthest, its lower layers only be rendered opaque by the deposition of a cloud of vesical mucus. Decant the upper  $\frac{2}{3}$ ths of the urine; pour a portion of the remainder into a watch glass, and gently warm it over a lamp; in a few seconds the heat will have rendered the fluid specifically lighter, and induced the deposition of crystals of  *oxalate* , if any were present; this may be hastened by gently moving the glass to and fro, so as to give the fluid a rotatory motion, which will collect the oxalate to the bottom of the capsule. The application of warmth serves also to remove the obscurity arising from the presence of  *urate of ammonia* , which, as is well known, is readily dissolved by exposing the urine containing it to a gentle heat.

<sup>\*</sup> Lond. Med. Gaz., 1841-2, p. 638.

Having allowed the urine to repose for a minute or two, remove the greater portion of the fluid with a pipette, and replace it by distilled water. A white powder, often of a glittering appearance, will now become visible, and this, under a low magnifying power, as by placing the capsule under a microscope furnished with a half-inch object-glass, will be found to consist of splendid crystals of oxalate of lime, in beautifully formed *octohedra*, with sharply defined edges and angles. It sometimes occurs that the oxalate is present in the form of exceedingly minute crystals: it then resembles a series of minute cubes, often adhering together like blood-discs; these, however, are readily and rapidly resolved into octohedra under a high magnifying power.

*Determination of the Alkaline and Earthy Phosphates.*—*Dr. Bence Jones*,\* in his investigations relative to the amount of phosphates in the urine of a healthy man, adopted the following method:—The specific gravity of the urine was first taken, and if ever it was not strongly acid, a drop or two of hydrochloric acid was added. Then, from a weighed quantity, usually about 1000 grains, the earthy phosphates were precipitated by means of pure ammonia, filtered, washed with ammoniacal water, and then heated to redness; a drop or two of nitric acid being added at last. The alkaline phosphates were estimated by taking usually about 500 grains of the urine, adding an excess of chloride of calcium and then pure ammonia; by this means all the phosphoric acid was precipitated as phosphate of lime; this was filtered, well washed, and heated to redness with nitric acid; by deducting the previously determined earthy phosphates, the difference was considered as alkaline phosphates. The results, though they answered well for purposes of comparison, are somewhat too high, in consequence of the formation of a small quantity of carbonate of ammonia and the precipitation of some sulphate of lime, which even long washing cannot entirely remove.

#### *Detection of Sugar in Urine.*

1. *Hünefeld's Test*.†—Place four ounces of the suspected urine in a glass exposed to the sun's rays, and add about six drops of a tolerably strong solution of chromic acid. In a

\* Contributions to the Chemistry of the Urine, Phil. Trans., Part 2, 1845.

† Journ. für Practische Chemie, vii. 42.

few minutes the mixture, previously orange red, becomes brownish, and soon after assumes a bistre-brown color, if sugar be present. These changes take place much more quickly if the mixture of urine and chromic acid be gently warmed before exposure to light. This test depends for its action upon the deoxidizing power of the sugar, by which the chromic acid is reduced to oxide of chromium; for, after warming the mixture, the addition of a few drops of *liquor potassæ* produces a copious deposit of green oxide. There is an important objection to this test, which renders all its indications liable to serious fallacy, depending upon the fact, that all urine containing a normal proportion of coloring matter deoxidizes chromic acid; and consequently urine, whether saccharine or not, will partially convert this acid into oxide. This change certainly does not occur so readily in non-saccharine urine as in a diabetic state of that fluid, but still it is sufficiently marked to prevent *Hünefeld's* test being regarded in any other light than a fallacious one.

2. *Runge's Test*.<sup>\*</sup>—Allow a thin layer of the suspected urine to evaporate on a white surface, as the bottom of a white plate; and, whilst warm, drop upon the surface a few drops of sulphuric acid, previously diluted with six parts of water. With healthy urine the part touched with the acid becomes merely of a pale yellow color, from the action of the latter on the coloring matter of the urine; whilst if sugar be present the spot becomes deep brown, and soon black from the decomposition of sugar by the acid, and consequent evolution of carbon. This test is stated to be so delicate that 1 part of sugar dissolved in 1000 of urine can be readily detected; and even when mixed with 2000 parts the indications are tolerably distinct. According to *Dr. Golding Bird*,<sup>†</sup> the presence of *albumen* introduces a fallacy into the application of this test, the acid assuming a tint nearly resembling that produced by sugar.

3. *Trommer's Test*.<sup>‡</sup>—This is a very trustworthy test, and much superior to either of the preceding. Add to the suspected urine contained in a large test-tube a few drops of a solution of sulphate of copper. A very inconsiderable troubling generally results, probably from the deposition of a lit-

<sup>\*</sup> *Poggendorff's Annalen*, Band 33, s. 431.

<sup>†</sup> *London Medical Gazette*.

<sup>‡</sup> *Phil. Mag.*, March, 1842.

the phosphate of copper. Sufficient *liquor potassæ* should then be added to render the whole strongly alkaline; a grayish green precipitate of hydrated oxide of copper falls, which, if sugar be present, wholly or partly redissolves in an excess of the solution of potassa, forming a blue liquid not very unlike the blue ammoniuret of copper. On gently heating the mixture nearly to ebullition, the copper falls in the state of sub-oxide, forming a red and copious precipitate. If sugar be not present, the copper is deposited in the form of black oxide. This test is founded on a fact long known, but not previously applied to the detection of sugar, of the power possessed by some organic matter of reducing oxide of copper, as well as some other oxides, to a lower state of oxidation. It is important that no more of the solution of sulphate of copper be used than is sufficient to afford a decided precipitate on the addition of the *liquor potassæ*. If this precaution be not attended to, a part only of the black oxide will be reduced to red oxide, unless a very large quantity of sugar be present, and thus the indications of the test will be rendered indistinct.

4. *Test of Fermentation.*—The development of the vinous fermentation, on the addition of a little ferment or yeast to a fluid, has long been applied to the detection of sugar. When a little yeast is added to healthy urine, and exposed to a temperature of about  $80^{\circ}$ , no other change occurs for some time, except the development of a portion of carbonic acid mechanically entangled in the yeast. When sugar is present in the urine thus treated, it soon becomes troubled, a tolerably free disengagement of bubbles of carbonic acid takes place, and a frothy scum forms on the surface of the fluid, which evolves a vinous odor. These changes take place with great rapidity, even when the quantity of sugar present is very small. If the evolved carbonic acid be collected, the quantity of sugar in the urine may be determined by measuring it, as a cubic inch of the gas very nearly corresponds to a grain of sugar.

In the great majority of specimens of diabetic urine it is not necessary to add yeast to excite fermentation, provided a sufficient temperature be employed.

5. *Test afforded by the Growth of Torulæ.*—If the smallest proportion of sugar exists in urine, exposed for a few hours to a temperature above  $70^{\circ}$ , and a drop of the fluid (taken from the surface) be examined under the microscope, numerous very minute ovoid particles will be discovered. In the



course of a few hours more these become enlarged, and appear as distinct oval or egg-shaped vesicles, which soon become developed into a confervoid or fungoid vegetation, identical with that which appears in ordinary saccharine fluids when undergoing the vinous fermentation. The advantages of this test are the facility with which its indications are observed by the microscope with an object-glass of one-seventh or one-eighth inch focus, and the certainty of any possible fallacy being corrected by the subsequent development of fermentation. It is, however, less convenient than *Trommer's*, in consequence of the time required before its indications can be observed.

6. *Löwig's Method*.—Evaporate the urine to the consistence of a syrup, then exhaust the residue with alcohol. The alcoholic urinary solution is then mixed with an alcoholic solution of potash, when, if sugar be present, a white precipitate, a compound of sugar and potash, is formed, which, when washed with alcohol, and then dissolved in water, yields a saccharine solution, which is fit for any further examination, and from which the amount of sugar may be ascertained quantitatively, if necessary.

#### *Urinary Calculi.*

*Uric Acid*.—These, which are the most abundant, are known by their solubility in caustic potassa, and their precipitation from the alkaline solution by acid. In nitric acid, with the aid of heat, they are soluble, and the solution, when evaporated to dryness, leaves a residue, which, on the addition of ammonia, assumes a purple red color (murexide). Before the blowpipe the uric acid calculus is consumed, leaving a small quantity of a white ash, which has an alkaline reaction.

*Urate of Ammonia*.—This calculus is distinguished from the last by its solubility in *carbonate of potassa*, and by its evolving ammonia when digested with caustic potassa.

*Bone Earth*.—This also is a common calculus. It is insoluble in caustic alkalies, and does not burn when heated. In a strong heat it fuses. It is insoluble in *acetic acid*, but is soluble in the mineral acids even when diluted.

*Ammonia-Magnesian Phosphate*.—This calculus is soluble in *acetic acid*, and again precipitated by ammonia. It evolves ammonia when digested with caustic potassa, and also when heated alone. It has frequently a crystalline appearance.

*Fusible Calculus.*—This is a mixture of the two preceding. It is partly soluble in acetic, and wholly in hydrochloric acid. It melts easily before the blowpipe into a pearly bead.

*Oxalate of Lime.*—Insoluble in acetic acid: converted by heat into carbonate of lime, which dissolves in acids with effervescence. It is also decomposed by boiling with carbonate of potassa. It is very hard, and has a dark-colored rough surface.

*Xanthic Oxide.*—This calculus is rare. It is soluble in potash, but is reprecipitated by carbonic acid. It dissolves in nitric acid without effervescence. It is distinguished from uric acid in not furnishing *murexide* when ammonia is added to the residue on evaporating the nitric solution.

The above are the most frequently occurring calculi. It is not uncommon, however, to meet with calculi in which layers of uric acid alternate with layers of phosphate of lime, ammonia-magnesian phosphate, and fusible calculus.

TABLE I.

*For the Conversion of Degrees on the Centigrade Thermometer into Degrees of Fahrenheit's Scale.*

| Cent. | Fahr. | Cent. | Fahr. | Cent. | Fahr. | Cent. | Fahr. | Cent. | Fahr. |
|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| —50   | —58.0 | 4     | 39.2  | 58    | 136.4 | 112   | 233.6 | 166   | 330.8 |
| —49   | —56.2 | 5     | 41.0  | 59    | 138.2 | 113   | 235.4 | 167   | 332.6 |
| —48   | —54.4 | 6     | 42.8  | 60    | 140.0 | 114   | 237.2 | 168   | 334.4 |
| —47   | —52.6 | 7     | 44.6  | 61    | 141.8 | 115   | 239.0 | 169   | 336.2 |
| —46   | —50.8 | 8     | 46.4  | 62    | 143.6 | 116   | 240.8 | 170   | 338.0 |
| —45   | —49.0 | 9     | 48.2  | 63    | 145.4 | 117   | 242.6 | 171   | 339.8 |
| —44   | —47.2 | 10    | 50.0  | 64    | 147.2 | 118   | 244.4 | 172   | 341.6 |
| —43   | —45.4 | 11    | 51.8  | 65    | 149.0 | 119   | 246.2 | 173   | 343.4 |
| —42   | —43.6 | 12    | 53.6  | 66    | 150.8 | 120   | 248.0 | 174   | 345.2 |
| —41   | —41.8 | 13    | 55.4  | 67    | 152.6 | 121   | 249.8 | 175   | 347.0 |
| —40   | —40.0 | 14    | 57.2  | 68    | 154.4 | 122   | 251.6 | 176   | 348.8 |
| —39   | —38.2 | 15    | 59.0  | 69    | 156.2 | 123   | 253.4 | 177   | 350.6 |
| —38   | —36.4 | 16    | 60.8  | 70    | 158.0 | 124   | 255.2 | 178   | 352.4 |
| —37   | —34.6 | 17    | 62.6  | 71    | 159.8 | 125   | 257.0 | 179   | 354.2 |
| —36   | —32.8 | 18    | 64.4  | 72    | 161.6 | 126   | 258.8 | 180   | 356.0 |
| —35   | —30.0 | 19    | 66.2  | 73    | 163.4 | 127   | 260.6 | 181   | 357.8 |
| —34   | —29.2 | 20    | 68.0  | 74    | 165.2 | 128   | 262.4 | 182   | 359.6 |
| —33   | —27.4 | 21    | 69.8  | 75    | 167.0 | 129   | 264.2 | 183   | 361.4 |
| —32   | —25.6 | 22    | 71.6  | 76    | 168.8 | 130   | 266.0 | 184   | 363.2 |
| —31   | —23.8 | 23    | 73.4  | 77    | 170.6 | 131   | 267.8 | 185   | 365.0 |
| —30   | —22.0 | 24    | 75.2  | 78    | 172.4 | 132   | 269.6 | 186   | 366.8 |
| —29   | —20.2 | 25    | 77.0  | 79    | 174.2 | 133   | 271.4 | 187   | 368.6 |
| —28   | —18.4 | 26    | 78.8  | 80    | 176.0 | 134   | 273.2 | 188   | 370.4 |
| —27   | —16.6 | 27    | 80.6  | 81    | 177.8 | 135   | 275.0 | 189   | 372.2 |
| —26   | —14.8 | 28    | 82.4  | 82    | 179.6 | 136   | 276.8 | 190   | 374.0 |
| —25   | —13.0 | 29    | 84.2  | 83    | 181.4 | 137   | 278.6 | 191   | 375.8 |
| —24   | —11.2 | 30    | 86.0  | 84    | 183.2 | 138   | 280.4 | 192   | 377.6 |
| —23   | —9.4  | 31    | 87.8  | 85    | 185.0 | 139   | 282.2 | 193   | 379.4 |
| —22   | —7.6  | 32    | 89.6  | 86    | 186.8 | 140   | 284.0 | 194   | 381.2 |
| —21   | —5.8  | 33    | 91.4  | 87    | 188.6 | 141   | 285.8 | 195   | 383.0 |
| —20   | —4.0  | 34    | 93.2  | 88    | 190.4 | 142   | 287.6 | 196   | 384.8 |
| —19   | —2.2  | 35    | 95.0  | 89    | 192.2 | 143   | 289.4 | 197   | 386.6 |
| —18   | —0.4  | 36    | 95.8  | 90    | 194.0 | 144   | 291.2 | 198   | 388.4 |
| —17   | + 1.4 | 37    | 98.6  | 91    | 195.8 | 145   | 293.0 | 199   | 390.2 |
| —16   | 3.2   | 38    | 100.4 | 92    | 197.6 | 146   | 294.8 | 200   | 392.0 |
| —15   | 5.0   | 39    | 102.2 | 93    | 199.4 | 147   | 296.6 | 201   | 393.8 |
| —14   | 6.8   | 40    | 104.0 | 94    | 201.2 | 148   | 298.4 | 202   | 395.6 |
| —13   | 8.6   | 41    | 105.8 | 95    | 203.0 | 149   | 300.2 | 203   | 397.4 |
| —12   | 10.4  | 42    | 107.6 | 96    | 204.8 | 150   | 302.0 | 204   | 399.2 |
| —11   | 12.2  | 43    | 109.4 | 97    | 206.6 | 151   | 303.8 | 205   | 401.0 |
| —10   | 14.0  | 44    | 111.2 | 98    | 208.4 | 152   | 305.6 | 206   | 402.8 |
| —9    | 15.8  | 45    | 113.0 | 99    | 210.2 | 153   | 307.4 | 207   | 404.6 |
| —8    | 17.6  | 46    | 114.8 | 100   | 212.0 | 154   | 309.2 | 208   | 406.4 |
| —7    | 19.4  | 47    | 116.6 | 101   | 213.8 | 155   | 311.0 | 209   | 408.2 |
| —6    | 21.2  | 48    | 118.4 | 102   | 215.6 | 156   | 312.8 | 210   | 410.0 |
| —5    | 23.0  | 49    | 120.2 | 103   | 217.4 | 157   | 314.6 | 211   | 411.8 |
| —4    | 24.8  | 50    | 122.0 | 104   | 219.2 | 158   | 316.4 | 212   | 413.6 |
| —3    | 26.6  | 51    | 123.8 | 105   | 221.0 | 159   | 318.2 | 213   | 415.4 |
| —2    | 28.4  | 52    | 125.6 | 106   | 222.8 | 160   | 320.0 | 214   | 417.2 |
| —1    | 30.2  | 53    | 127.4 | 107   | 224.6 | 161   | 321.8 | 215   | 419.0 |
| 0     | 32.0  | 54    | 129.2 | 108   | 226.4 | 162   | 323.6 | 216   | 420.8 |
| + 1   | 33.8  | 55    | 131.0 | 109   | 228.2 | 163   | 325.4 | 217   | 422.6 |
| 2     | 35.6  | 56    | 132.8 | 110   | 230.0 | 164   | 327.2 | 218   | 424.4 |
| 3     | 37.4  | 57    | 134.6 | 111   | 231.8 | 165   | 329.0 | 219   | 426.2 |

TABLE I.—CONTINUED.

| Cent. | Fahr. | Cent. | Fahr. | Cent. | Fahr. | Cent. | Fahr. | Cent. | Fahr. |
|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 220   | 428.0 | 241   | 465.8 | 262   | 503.6 | 283   | 541.4 | 304   | 579.2 |
| 221   | 429.8 | 242   | 467.6 | 263   | 505.4 | 284   | 543.2 | 305   | 581.0 |
| 222   | 431.6 | 243   | 469.4 | 264   | 507.2 | 285   | 545.0 | 306   | 582.8 |
| 223   | 433.4 | 244   | 471.2 | 265   | 509.0 | 286   | 546.8 | 307   | 584.6 |
| 224   | 435.2 | 245   | 473.0 | 266   | 510.8 | 287   | 548.6 | 308   | 586.4 |
| 225   | 437.0 | 246   | 474.8 | 267   | 512.6 | 288   | 550.4 | 309   | 588.2 |
| 226   | 438.8 | 247   | 476.6 | 268   | 514.4 | 289   | 552.2 | 310   | 590.0 |
| 227   | 440.6 | 248   | 478.4 | 269   | 516.2 | 290   | 554.0 | 311   | 591.8 |
| 228   | 442.4 | 249   | 480.2 | 270   | 518.0 | 291   | 555.8 | 312   | 593.6 |
| 229   | 444.2 | 250   | 482.0 | 271   | 519.8 | 292   | 557.6 | 313   | 595.4 |
| 230   | 446.0 | 251   | 483.8 | 272   | 521.6 | 293   | 559.4 | 314   | 597.2 |
| 231   | 447.8 | 252   | 485.6 | 273   | 523.4 | 294   | 561.2 | 315   | 599.0 |
| 232   | 449.6 | 253   | 487.4 | 274   | 525.2 | 295   | 563.0 | 316   | 600.8 |
| 233   | 451.4 | 254   | 489.2 | 275   | 527.0 | 296   | 564.8 | 317   | 602.6 |
| 234   | 453.2 | 255   | 491.0 | 276   | 528.8 | 297   | 566.6 | 318   | 604.4 |
| 235   | 455.0 | 256   | 492.8 | 277   | 530.6 | 298   | 568.4 | 319   | 606.2 |
| 236   | 456.8 | 257   | 494.6 | 278   | 532.4 | 299   | 570.2 | 320   | 608.0 |
| 237   | 458.6 | 258   | 496.4 | 279   | 534.2 | 300   | 572.0 |       |       |
| 238   | 460.4 | 259   | 498.2 | 280   | 536.0 | 301   | 573.8 |       |       |
| 239   | 462.2 | 260   | 500.0 | 281   | 537.8 | 302   | 575.6 |       |       |
| 240   | 464.0 | 261   | 501.8 | 282   | 539.6 | 303   | 577.4 |       |       |

TABLE II.

*Showing the respective Degrees of Tension of Aqueous Vapor for different Temperatures.*

(FROM FRESSENIUS' "INSTRUCTION IN CHEMICAL ANALYSIS.")

| Temperature<br>in degrees<br>(Celsius). | Force of the Aqueous<br>Vapor expressed in<br>Millimetres. | Temperature<br>in degrees<br>(Celsius). | Force of the Aqueous<br>Vapor expressed in<br>Millimetres. |
|-----------------------------------------|------------------------------------------------------------|-----------------------------------------|------------------------------------------------------------|
| 0                                       | 4.525                                                      | 21                                      | 18.505                                                     |
| 1                                       | 4.867                                                      | 22                                      | 19.675                                                     |
| 2                                       | 5.231                                                      | 23                                      | 20.909                                                     |
| 3                                       | 5.619                                                      | 24                                      | 22.211                                                     |
| 4                                       | 6.032                                                      | 25                                      | 23.582                                                     |
| 5                                       | 6.471                                                      | 26                                      | 25.026                                                     |
| 6                                       | 6.939                                                      | 27                                      | 26.547                                                     |
| 7                                       | 7.436                                                      | 28                                      | 28.148                                                     |
| 8                                       | 7.964                                                      | 29                                      | 29.832                                                     |
| 9                                       | 8.525                                                      | 30                                      | 31.602                                                     |
| 10                                      | 9.126                                                      | 31                                      | 33.464                                                     |
| 11                                      | 9.751                                                      | 32                                      | 35.419                                                     |
| 12                                      | 10.421                                                     | 33                                      | 37.473                                                     |
| 13                                      | 11.130                                                     | 34                                      | 39.630                                                     |
| 14                                      | 11.882                                                     | 35                                      | 41.893                                                     |
| 15                                      | 12.677                                                     | 36                                      | 44.268                                                     |
| 16                                      | 13.519                                                     | 37                                      | 46.758                                                     |
| 17                                      | 14.409                                                     | 38                                      | 49.368                                                     |
| 18                                      | 15.351                                                     | 39                                      | 52.103                                                     |
| 19                                      | 16.345                                                     | 40                                      | 54.969                                                     |
| 20                                      | 17.396                                                     |                                         |                                                            |



TABLE III.

*Showing the Quantity of Oil of Vitriol of Specific Gravity 1.8485, and of Anhydrous Acid in 100 Parts of dilute Sulphuric Acid, of different Densities, according to Dr. Ure.*

| Liquid. | Specific Gravity. | Dry.  | Liquid. | Specific Gravity | Dry.   |
|---------|-------------------|-------|---------|------------------|--------|
| 100     | 1.8485            | 81.54 | 50      | 1.3884           | 40.77  |
| 99      | 1.8475            | 80.72 | 49      | 1.3788           | 39.95  |
| 98      | 1.8460            | 79.90 | 48      | 1.3697           | 39.14  |
| 97      | 1.8439            | 79.09 | 47      | 1.3612           | 38.32  |
| 96      | 1.8410            | 78.28 | 46      | 1.3530           | 37.51  |
| 95      | 1.8376            | 77.46 | 45      | 1.3440           | 36.69  |
| 94      | 1.8336            | 76.65 | 44      | 1.3345           | 35.88  |
| 93      | 1.8290            | 75.83 | 43      | 1.3255           | 35.06  |
| 92      | 1.8233            | 75.02 | 42      | 1.3165           | 34.25  |
| 91      | 1.8179            | 74.20 | 41      | 1.3080           | 33.43  |
| 90      | 1.8115            | 73.39 | 40      | 1.2999           | 32.61  |
| 89      | 1.8043            | 72.57 | 39      | 1.2913           | 31.80  |
| 88      | 1.7962            | 71.75 | 38      | 1.2826           | 30.98  |
| 87      | 1.7870            | 70.94 | 37      | 1.2740           | 30.17  |
| 86      | 1.7774            | 70.12 | 36      | 1.2654           | 29.35  |
| 85      | 1.7673            | 69.31 | 35      | 1.2572           | 28.54  |
| 84      | 1.7570            | 68.49 | 34      | 1.2490           | 27.72  |
| 83      | 1.7465            | 67.68 | 33      | 1.2409           | 26.91  |
| 82      | 1.7360            | 66.86 | 32      | 1.2334           | 26.09  |
| 81      | 1.7245            | 66.05 | 31      | 1.2260           | 25.28  |
| 80      | 1.7120            | 65.23 | 30      | 1.2184           | 24.46  |
| 79      | 1.6993            | 64.42 | 29      | 1.2108           | 23.65  |
| 78      | 1.6870            | 63.60 | 28      | 1.2032           | 22.83  |
| 77      | 1.6750            | 62.78 | 27      | 1.1956           | 22.01  |
| 76      | 1.6630            | 61.97 | 26      | 1.1876           | 21.20  |
| 75      | 1.6520            | 61.15 | 25      | 1.1792           | 20.38  |
| 74      | 1.6415            | 60.34 | 24      | 1.1706           | 19.57  |
| 73      | 1.6321            | 59.52 | 23      | 1.1626           | 18.75  |
| 72      | 1.6204            | 58.71 | 22      | 1.1549           | 17.94  |
| 71      | 1.6090            | 57.89 | 21      | 1.1480           | 17.12  |
| 70      | 1.5975            | 57.08 | 20      | 1.1410           | 16.31  |
| 69      | 1.5868            | 56.26 | 19      | 1.1330           | 15.49  |
| 68      | 1.5760            | 55.45 | 18      | 1.1246           | 14.68  |
| 67      | 1.5648            | 54.63 | 17      | 1.1165           | 13.86  |
| 66      | 1.5503            | 53.82 | 16      | 1.1090           | 13.05  |
| 65      | 1.5390            | 53.00 | 15      | 1.1019           | 12.23  |
| 64      | 1.5280            | 52.18 | 14      | 1.0953           | 11.41  |
| 63      | 1.5170            | 51.37 | 13      | 1.0887           | 10.60  |
| 62      | 1.5066            | 50.55 | 12      | 1.0809           | 9.78   |
| 61      | 1.4960            | 49.74 | 11      | 1.0743           | 8.97   |
| 60      | 1.4860            | 48.92 | 10      | 1.0682           | 8.15   |
| 59      | 1.4760            | 48.11 | 9       | 1.0614           | 7.34   |
| 58      | 1.4660            | 47.29 | 8       | 1.0544           | 6.52   |
| 57      | 1.4560            | 46.48 | 7       | 1.0477           | 5.71   |
| 56      | 1.4460            | 45.66 | 6       | 1.0405           | 4.89   |
| 55      | 1.4360            | 44.85 | 5       | 1.0336           | 4.08   |
| 54      | 1.4265            | 44.03 | 4       | 1.0268           | 3.26   |
| 53      | 1.4170            | 43.22 | 3       | 1.0206           | 2.446  |
| 52      | 1.4073            | 42.40 | 2       | 1.0140           | 1.63   |
| 51      | 1.3977            | 41.58 | 1       | 1.0074           | 0.8154 |

TABLE IV.

*Showing the Quantity of Real or Anhydrous Nitric Acid in 100 Parts of Liquid Acid, at different Densities, according to Dr. Ure.*

| Specific Gravity. | Real Acid in 100 parts<br>of the Liquid. | Specific Gravity. | Real Acid in 100 parts<br>of the Liquid. |
|-------------------|------------------------------------------|-------------------|------------------------------------------|
| 1.5000            | 79.700                                   | 1.2947            | 39.850                                   |
| 1.4980            | 78.903                                   | 1.2887            | 39.053                                   |
| 1.4960            | 78.106                                   | 1.2826            | 38.256                                   |
| 1.4940            | 77.309                                   | 1.2765            | 37.459                                   |
| 1.4910            | 76.512                                   | 1.2705            | 36.662                                   |
| 1.4880            | 75.715                                   | 1.2644            | 35.865                                   |
| 1.4850            | 74.918                                   | 1.2583            | 35.068                                   |
| 1.4820            | 74.121                                   | 1.2523            | 34.271                                   |
| 1.4790            | 73.324                                   | 1.2462            | 33.474                                   |
| 1.4760            | 72.527                                   | 1.2402            | 32.677                                   |
| 1.4730            | 71.730                                   | 1.2341            | 31.880                                   |
| 1.4700            | 70.933                                   | 1.2277            | 31.083                                   |
| 1.4670            | 70.136                                   | 1.2212            | 30.286                                   |
| 1.4640            | 69.339                                   | 1.2148            | 29.489                                   |
| 1.4600            | 68.542                                   | 1.2084            | 28.692                                   |
| 1.4570            | 67.745                                   | 1.2019            | 27.895                                   |
| 1.4530            | 66.948                                   | 1.1958            | 27.098                                   |
| 1.4500            | 66.155                                   | 1.1895            | 26.301                                   |
| 1.4460            | 65.354                                   | 1.1833            | 25.504                                   |
| 1.4424            | 64.557                                   | 1.1770            | 24.707                                   |
| 1.4385            | 63.760                                   | 1.1709            | 23.910                                   |
| 1.4346            | 62.963                                   | 1.1648            | 23.113                                   |
| 1.4306            | 62.166                                   | 1.1587            | 22.316                                   |
| 1.4269            | 61.369                                   | 1.1526            | 21.519                                   |
| 1.4228            | 60.572                                   | 1.1465            | 20.722                                   |
| 1.4189            | 59.775                                   | 1.1403            | 19.925                                   |
| 1.4147            | 58.978                                   | 1.1345            | 19.128                                   |
| 1.4107            | 58.181                                   | 1.1286            | 18.331                                   |
| 1.4065            | 57.384                                   | 1.1227            | 17.534                                   |
| 1.4023            | 56.587                                   | 1.1168            | 16.737                                   |
| 1.3978            | 55.790                                   | 1.1109            | 15.940                                   |
| 1.3945            | 54.993                                   | 1.1051            | 15.143                                   |
| 1.3882            | 54.196                                   | 1.0993            | 14.346                                   |
| 1.3833            | 53.399                                   | 1.0935            | 13.549                                   |
| 1.3783            | 52.602                                   | 1.0878            | 12.752                                   |
| 1.3732            | 51.805                                   | 1.0821            | 11.955                                   |
| 1.3681            | 51.068                                   | 1.0764            | 11.158                                   |
| 1.3630            | 50.211                                   | 1.0708            | 10.361                                   |
| 1.3579            | 49.414                                   | 1.0651            | 9.564                                    |
| 1.3529            | 48.617                                   | 1.0595            | 8.767                                    |
| 1.3477            | 47.820                                   | 1.0540            | 7.970                                    |
| 1.3427            | 47.023                                   | 1.0485            | 7.173                                    |
| 1.3376            | 46.226                                   | 1.0430            | 6.376                                    |
| 1.3323            | 45.429                                   | 1.0375            | 5.579                                    |
| 1.3270            | 44.632                                   | 1.0320            | 4.782                                    |
| 1.3216            | 43.835                                   | 1.0267            | 3.985                                    |
| 1.3113            | 43.038                                   | 1.0212            | 3.188                                    |
| 1.3110            | 42.241                                   | 1.0159            | 2.391                                    |
| 1.3056            | 41.444                                   | 1.0106            | 1.594                                    |
| 1.3001            | 40.647                                   | 1.0053            | 0.797                                    |

TABLE V.

*Showing the Quantity of Absolute Alcohol in Spirits of different Specific Gravities, according to Lowitz.*

| 100 Parts. |        | Specific Gravity. |         | 100 Parts. |        | Specific Gravity. |         |
|------------|--------|-------------------|---------|------------|--------|-------------------|---------|
| Alcohol.   | Water. | At 65°.           | At 60°. | Alcohol.   | Water. | At 65°.           | At 60°. |
| 100        | 0      | 0.791             | 0.796   | 49         | 51     | 0.917             | 0.920   |
| 99         | 1      | 0.794             | 0.798   | 48         | 52     | 0.919             | 0.922   |
| 98         | 2      | 0.797             | 0.801   | 47         | 53     | 0.921             | 0.924   |
| 97         | 3      | 0.800             | 0.804   | 46         | 54     | 0.923             | 0.926   |
| 96         | 4      | 0.803             | 0.807   | 45         | 55     | 0.925             | 0.928   |
| 95         | 5      | 0.805             | 0.809   | 44         | 56     | 0.927             | 0.930   |
| 94         | 6      | 0.808             | 0.812   | 43         | 57     | 0.930             | 0.933   |
| 93         | 7      | 0.811             | 0.815   | 42         | 58     | 0.932             | 0.935   |
| 92         | 8      | 0.813             | 0.817   | 41         | 59     | 0.934             | 0.937   |
| 91         | 9      | 0.816             | 0.820   | 40         | 60     | 0.936             | 0.939   |
| 90         | 10     | 0.818             | 0.822   | 39         | 61     | 0.938             | 0.941   |
| 89         | 11     | 0.821             | 0.825   | 38         | 62     | 0.940             | 0.943   |
| 88         | 12     | 0.823             | 0.827   | 37         | 63     | 0.942             | 0.945   |
| 87         | 13     | 0.826             | 0.830   | 36         | 64     | 0.944             | 0.947   |
| 86         | 14     | 0.828             | 0.832   | 35         | 65     | 0.946             | 0.949   |
| 85         | 15     | 0.831             | 0.835   | 34         | 66     | 0.948             | 0.951   |
| 84         | 16     | 0.834             | 0.838   | 33         | 67     | 0.950             | 0.953   |
| 83         | 17     | 0.836             | 0.840   | 32         | 68     | 0.952             | 0.955   |
| 82         | 18     | 0.839             | 0.843   | 31         | 69     | 0.954             | 0.957   |
| 81         | 19     | 0.842             | 0.846   | 30         | 70     | 0.956             | 0.958   |
| 80         | 20     | 0.844             | 0.848   | 29         | 71     | 0.957             | 0.960   |
| 79         | 21     | 0.847             | 0.851   | 28         | 72     | 0.959             | 0.962   |
| 78         | 22     | 0.849             | 0.853   | 27         | 73     | 0.961             | 0.963   |
| 77         | 23     | 0.851             | 0.855   | 26         | 74     | 0.963             | 0.965   |
| 76         | 24     | 0.853             | 0.857   | 25         | 75     | 0.965             | 0.967   |
| 75         | 25     | 0.856             | 0.860   | 24         | 76     | 0.966             | 0.968   |
| 74         | 26     | 0.859             | 0.863   | 23         | 77     | 0.968             | 0.970   |
| 73         | 27     | 0.861             | 0.865   | 22         | 78     | 0.970             | 0.972   |
| 72         | 28     | 0.863             | 0.867   | 21         | 79     | 0.971             | 0.973   |
| 71         | 29     | 0.866             | 0.870   | 20         | 80     | 0.973             | 0.974   |
| 70         | 30     | 0.868             | 0.872   | 19         | 81     | 0.974             | 0.975   |
| 69         | 31     | 0.870             | 0.874   | 18         | 82     | 0.976             | 0.977   |
| 68         | 32     | 0.872             | 0.875   | 17         | 83     | 0.977             | 0.978   |
| 67         | 33     | 0.875             | 0.879   | 16         | 84     | 0.978             | 0.979   |
| 66         | 34     | 0.877             | 0.881   | 15         | 85     | 0.980             | 0.981   |
| 65         | 35     | 0.880             | 0.883   | 14         | 86     | 0.981             | 0.982   |
| 64         | 36     | 0.882             | 0.886   | 13         | 87     | 0.983             | 0.984   |
| 63         | 37     | 0.885             | 0.889   | 12         | 88     | 0.985             | 0.986   |
| 62         | 38     | 0.887             | 0.891   | 11         | 89     | 0.986             | 0.987   |
| 61         | 39     | 0.889             | 0.893   | 10         | 90     | 0.987             | 0.988   |
| 60         | 40     | 0.892             | 0.896   | 9          | 91     | 0.988             | 0.989   |
| 59         | 41     | 0.894             | 0.898   | 8          | 92     | 0.989             | 0.990   |
| 58         | 42     | 0.896             | 0.900   | 7          | 93     | 0.991             | 0.991   |
| 57         | 43     | 0.899             | 0.902   | 6          | 94     | 0.992             | 0.992   |
| 56         | 44     | 0.901             | 0.904   | 5          | 95     | 0.994             |         |
| 55         | 45     | 0.903             | 0.906   | 4          | 96     | 0.995             |         |
| 54         | 46     | 0.905             | 0.908   | 3          | 97     | 0.997             |         |
| 53         | 47     | 0.907             | 0.910   | 2          | 98     | 0.998             |         |
| 52         | 48     | 0.909             | 0.912   | 1          | 99     | 0.999             |         |
| 51         | 49     | 0.912             | 0.915   | 0          | 100    | 1.000             |         |
| 50         | 50     | 0.914             | 0.917   |            |        |                   |         |

TABLE VI.

*Showing the Quantity of Absolute Alcohol by Weight in Mixtures of Alcohol and Water of different Specific Gravities, according to Mr. Drinkwater.\**

| Sp. Gr.<br>at<br>60° Fahr. | Alcohol<br>per cent.<br>by weight. | Sp. Gr.<br>at<br>60° Fahr. | Alcohol<br>per cent.<br>by weight. | Sp. Gr.<br>at<br>60° Fahr. | Alcohol<br>per cent.<br>by weight. | Sp. Gr.<br>at<br>60° Fahr. | Alcohol<br>per cent.<br>by weight. |
|----------------------------|------------------------------------|----------------------------|------------------------------------|----------------------------|------------------------------------|----------------------------|------------------------------------|
| 1.0000                     | 0.00                               | .9959                      | 2.22                               | .9918                      | 4.64                               | .9877                      | 7.30                               |
| .9999                      | 0.05                               | .9958                      | 2.28                               | .9917                      | 4.70                               | .9876                      | 7.37                               |
| .9998                      | 0.11                               | .9957                      | 2.34                               | .9916                      | 4.76                               | .9875                      | 7.43                               |
| .9997                      | 0.16                               | .9956                      | 2.37                               | .9915                      | 4.82                               | .9874                      | 7.50                               |
| .9996                      | 0.21                               | .9955                      | 2.45                               | .9914                      | 4.88                               | .9873                      | 7.57                               |
| .9995                      | 0.26                               | .9954                      | 2.51                               | .9913                      | 4.94                               | .9872                      | 7.64                               |
| .9994                      | 0.32                               | .9953                      | 2.57                               | .9912                      | 5.01                               | .9871                      | 7.71                               |
| .9993                      | 0.37                               | .9952                      | 2.62                               | .9911                      | 5.07                               | .9870                      | 7.78                               |
| .9992                      | 0.42                               | .9951                      | 2.68                               | .9910                      | 5.13                               | .9869                      | 7.85                               |
| .9991                      | 0.47                               | .9950                      | 2.74                               | .9909                      | 5.20                               | .9868                      | 7.92                               |
| .9990                      | 0.53                               | .9949                      | 2.79                               | .9908                      | 5.26                               | .9867                      | 7.99                               |
| .9989                      | 0.58                               | .9948                      | 2.85                               | .9907                      | 5.32                               | .9866                      | 8.06                               |
| .9988                      | 0.64                               | .9947                      | 2.91                               | .9906                      | 5.39                               | .9865                      | 8.13                               |
| .9987                      | 0.69                               | .9946                      | 2.97                               | .9905                      | 5.45                               | .9864                      | 8.20                               |
| .9986                      | 0.74                               | .9945                      | 3.02                               | .9904                      | 5.51                               | .9863                      | 8.27                               |
| .9985                      | 0.80                               | .9944                      | 3.08                               | .9903                      | 5.58                               | .9862                      | 8.34                               |
| .9984                      | 0.85                               | .9943                      | 3.14                               | .9902                      | 5.64                               | .9861                      | 8.41                               |
| .9983                      | 0.91                               | .9942                      | 3.20                               | .9901                      | 5.70                               | .9860                      | 8.48                               |
| .9982                      | 0.96                               | .9941                      | 3.26                               | .9900                      | 5.77                               | .9859                      | 8.55                               |
| .9981                      | 1.02                               | .9940                      | 3.32                               | .9899                      | 5.83                               | .9858                      | 8.62                               |
| .9980                      | 1.07                               | .9939                      | 3.37                               | .9898                      | 5.89                               | .9857                      | 8.70                               |
| .9979                      | 1.12                               | .9938                      | 3.43                               | .9897                      | 5.96                               | .9856                      | 8.77                               |
| .9978                      | 1.18                               | .9937                      | 3.49                               | .9896                      | 6.02                               | .9855                      | 8.84                               |
| .9977                      | 1.23                               | .9936                      | 3.55                               | .9895                      | 6.09                               | .9854                      | 8.91                               |
| .9976                      | 1.29                               | .9935                      | 3.61                               | .9894                      | 6.15                               | .9853                      | 8.98                               |
| .9975                      | 1.34                               | .9934                      | 3.67                               | .9893                      | 6.22                               | .9852                      | 9.05                               |
| .9974                      | 1.40                               | .9933                      | 3.73                               | .9892                      | 6.29                               | .9851                      | 9.12                               |
| .9973                      | 1.45                               | .9932                      | 3.78                               | .9891                      | 6.35                               | .9850                      | 9.20                               |
| .9972                      | 1.51                               | .9931                      | 3.84                               | .9890                      | 6.42                               | .9849                      | 9.27                               |
| .9971                      | 1.56                               | .9930                      | 3.90                               | .9889                      | 6.49                               | .9848                      | 9.34                               |
| .9970                      | 1.61                               | .9929                      | 3.96                               | .9888                      | 6.55                               | .9847                      | 9.41                               |
| .9969                      | 1.67                               | .9928                      | 4.02                               | .9887                      | 6.62                               | .9846                      | 9.49                               |
| .9968                      | 1.73                               | .9927                      | 4.08                               | .9886                      | 6.69                               | .9845                      | 9.56                               |
| .9967                      | 1.78                               | .9926                      | 4.14                               | .9885                      | 6.75                               | .9844                      | 9.63                               |
| .9966                      | 1.83                               | .9925                      | 4.20                               | .9884                      | 6.82                               | .9843                      | 9.70                               |
| .9965                      | 1.89                               | .9924                      | 4.27                               | .9883                      | 6.89                               | .9842                      | 9.78                               |
| .9964                      | 1.94                               | .9923                      | 4.33                               | .9882                      | 6.95                               | .9841                      | 9.85                               |
| .9963                      | 1.99                               | .9922                      | 4.39                               | .9881                      | 7.02                               | .9840                      | 9.92                               |
| .9962                      | 2.05                               | .9921                      | 4.45                               | .9880                      | 7.09                               | .9839                      | 9.99                               |
| .9961                      | 2.11                               | .9920                      | 4.51                               | .9879                      | 7.16                               | .9838                      | 10.07                              |
| .9960                      | 2.17                               | .9919                      | 4.57                               | .9878                      | 7.23                               |                            |                                    |

The absolute alcohol, with which the experiments which furnished the data for the above Table were made, was prepared as follows:—Carbonate of potassa was exposed to a red heat to deprive it of water; and, when sufficiently cool, was

\* Memoirs of the Chemical Society, vol. iii. page 454.



pulverized and added to ordinary alcohol of specific gravity .850 at 60° Fahr. till it ceased to dissolve any more: the whole was then allowed to digest 24 hours, being frequently agitated, when the alcohol was carefully poured off. As much fresh-burned quicklime as was considered sufficient, when powdered, to absorb the whole of the alcohol, was introduced into a retort, and the alcohol added to it; after digesting 48 hours, it was slowly distilled in a water-bath, at a temperature of about 180° Fahr. The alcohol thus obtained was carefully redistilled, and its specific gravity at 60° Fahr. was found in two experiments to be .7946 and .7947. It was subsequently digested a second and a third time for several days with recently ignited quicklime, and redistilled at 172° Fahr. The mean of several determinations gave the number .79381, which the author thinks may be regarded as expressing the true specific gravity of absolute alcohol at 60° Fahr.

---

## TABLE VII.

IN the following table the figures are all calculated on the equivalent numbers assigned to the elementary substances in the table inserted at page 233, and which is from the latest authorities; few of the numbers differ very considerably from those given in similar tables in other works on Chemical Analysis; but, with the accuracy which is now introduced into the science, it was thought that the advantages of having a series of numbers in accordance with the atomic weights, as at present received, were sufficiently great to justify the time consumed in the recalculation.

The application of these tables, and their great convenience in quantitative analysis, may be illustrated by the following example:

1. Suppose, as the result of an experiment to determine the amount of sulphuric acid in a certain substance, 37.45 grains of sulphate of baryta are obtained: on turning to the table we find under the head of "required" *sulphuric acid*, "found" *sulphate of baryta*, a series of figures arranged in nine columns, those in the first column representing the quantity of sulphuric acid in a *unit* of sulphate of baryta, and

those in the other columns the multiples of that number by 2, 3, 4, 5, 6, 7, 8, and 9. In the case we are considering we require to learn the amount of sulphuric acid in 37.45 grains of sulphate of baryta; we turn to column 3, where we find the number 1.02872; we put down this number, therefore, shifting the decimal point one figure further to the right; we next turn to column 7, where we find the number 2.40058; we place this number under the former, preserving the decimal point unaltered; we have thus filled up the *tens'* and the *units'* place; the next number is 4, under which column we find the number 1.37176; but as this in our experiment is the first place of decimals, in writing down the number we shift the decimal point one figure further to the left; in like manner, the last number being 5, and in the second place of decimals, we shift the decimal point of the number found under column 5, viz: 1.71470 two places further to the left; the whole will consequently stand thus:—

$$\begin{array}{r}
 10.2872000 \\
 2.4005800 \\
 .1371760 \\
 .0171470 \\
 \hline
 12.8421030 \\
 \hline
 \end{array}$$

37.49 grains of sulphate of baryta contain, therefore, 12.842 grains of sulphuric acid.

TABLE VII.

| Required.                           | Found.                                            | 1       | 2       | 3       | 4       | 5       | 6       | 7       | 8       | 9        |
|-------------------------------------|---------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|----------|
| Aluminum<br>$Al_2O_3$               | Alumina<br>$Al_2O_3$                              | 0.53289 | 1.06578 | 1.59867 | 2.13156 | 2.66445 | 3.19734 | 3.73023 | 4.26312 | 4.79601  |
| Ammonia<br>$NH_3$                   | Chloride of Am-<br>monium<br>$NH_4Cl$             | 0.31776 | 0.63552 | 0.95328 | 1.27104 | 1.58880 | 1.90656 | 2.22432 | 2.54208 | 2.85984  |
| Ammonia<br>$NH_3$                   | Ammonio-chloride<br>of Platinum<br>$NH_4ClPtCl_3$ | 0.07611 | 0.15222 | 0.22833 | 0.30444 | 0.38055 | 0.45666 | 0.53277 | 0.60888 | 0.68499  |
| Antimony<br>Sb                      | Oxide of Antimony<br>$Sb_2O_3$                    | 0.84317 | 1.68634 | 2.52951 | 3.37268 | 4.21585 | 5.05902 | 5.90219 | 6.74536 | 7.58853  |
| Oxide of Anti-<br>mony<br>$Sb_2O_3$ | Antimony<br>Sb                                    | 1.18600 | 2.37200 | 3.55800 | 4.74400 | 5.93000 | 7.11600 | 8.30200 | 9.48800 | 10.67400 |
| Oxide of Anti-<br>mony<br>$Sb_2O_3$ | Sulphuret of Anti-<br>mony<br>$Sb_2S_3$           | 0.86443 | 1.72886 | 2.59329 | 3.45772 | 4.32215 | 5.18659 | 6.05101 | 6.91545 | 7.77988  |
| Oxide of Anti-<br>mony<br>$Sb_2O_3$ | Antimonious Acid<br>$SbO_4$                       | 0.95032 | 1.90064 | 2.85096 | 3.80128 | 4.75160 | 5.70192 | 6.65224 | 7.60256 | 8.55288  |
| Arsenic<br>As                       | Arsenious Acid<br>$AsO_3$                         | 0.75757 | 1.51514 | 2.27271 | 3.03028 | 3.78785 | 4.54542 | 5.30299 | 6.06056 | 6.81813  |
| Arsenic<br>As                       | Arsenic Acid<br>$AsO_5$                           | 0.65217 | 1.30434 | 1.95651 | 2.60868 | 3.26085 | 3.91302 | 4.56519 | 5.21736 | 5.86953  |
| Arsenious Acid<br>$AsO_3$           | Arsenic Acid<br>$AsO_5$                           | 0.86087 | 1.72174 | 2.58261 | 3.44348 | 4.30435 | 5.16522 | 6.02609 | 6.88696 | 7.74783  |
| Arsenious Acid<br>$AsO_3$           | Sulpharsenious<br>Acid<br>$AsS_3$                 | 0.80488 | 1.60976 | 2.41464 | 3.21952 | 4.02440 | 4.82928 | 5.63416 | 6.43904 | 7.24392  |

TABLE VII.—CONTINUED.

| Required.                        | Found.                                                         | 1       | 2       | 3       | 4       | 5       | 6       | 7       | 8       | 9       |
|----------------------------------|----------------------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| Baryta<br>BaO                    | Sulphate of Baryta<br>BaOSO <sub>3</sub>                       | 0.65706 | 1.31412 | 1.97118 | 2.62834 | 3.28530 | 3.94236 | 4.59942 | 5.28648 | 5.91354 |
| Baryta<br>BaO                    | Carbonate of Baryta<br>BaCO <sub>3</sub>                       | 0.77696 | 1.55392 | 2.33088 | 3.10784 | 3.88480 | 4.66176 | 5.43872 | 6.21568 | 6.99264 |
| Baryta<br>BaO                    | Silico-fluoride of Barium<br>BaF <sub>2</sub> SiF <sub>6</sub> | 0.52460 | 1.04720 | 1.57380 | 2.09440 | 2.64300 | 3.14760 | 3.67220 | 4.18880 | 4.72140 |
| Bismuth<br>Bi                    | Oxide of Bismuth<br>Bi <sub>2</sub> O                          | 0.89867 | 1.79734 | 2.69601 | 3.59468 | 4.49335 | 5.39202 | 6.29069 | 7.18936 | 8.08803 |
| Boron<br>B                       | Boric Acid<br>BO <sub>3</sub>                                  | 0.31241 | 0.62483 | 0.93724 | 1.24966 | 1.56207 | 1.87449 | 2.18690 | 2.49932 | 2.81173 |
| Bromine<br>Br                    | Bromide of Silver<br>AgBr                                      | 0.42016 | 0.84032 | 1.26043 | 1.68064 | 2.10080 | 2.52096 | 2.94112 | 3.36128 | 3.78144 |
| Cadmium<br>Cd                    | Oxide of Cadmium<br>CdO                                        | 0.87449 | 1.74899 | 2.62348 | 3.49797 | 4.37246 | 5.24696 | 6.12145 | 6.99594 | 7.87044 |
| Calcium<br>Ca                    | Lime<br>CaO                                                    | 0.71429 | 1.42857 | 2.14286 | 2.85714 | 3.57143 | 4.28571 | 5.00000 | 5.71429 | 6.42857 |
| Lime<br>CaO                      | Sulphate of Lime<br>CaOSO <sub>3</sub>                         | 0.41176 | 0.82353 | 1.23529 | 1.64706 | 2.05882 | 2.47059 | 2.88235 | 3.29412 | 3.70588 |
| Lime<br>CaO                      | Carbonate of Lime<br>CaOCO <sub>2</sub>                        | 0.56000 | 1.12000 | 1.68000 | 2.24000 | 2.80000 | 3.36000 | 3.92000 | 4.48000 | 5.04000 |
| Carbon<br>C                      | Carbonic Acid<br>CO <sub>2</sub>                               | 0.27273 | 0.54545 | 0.81818 | 1.09091 | 1.36364 | 1.63636 | 1.90909 | 2.18181 | 2.45455 |
| Carbonic Acid<br>CO <sub>2</sub> | Carbonate of Lime<br>CaOCO <sub>2</sub>                        | 0.44000 | 0.88000 | 1.32000 | 1.76000 | 2.20000 | 2.64000 | 3.08000 | 3.52000 | 3.96000 |
| Chlorine<br>Cl                   | Chloride of Silver<br>AgCl                                     | 0.24729 | 0.49458 | 0.74188 | 0.98917 | 1.23646 | 1.48375 | 1.73104 | 1.97834 | 2.22563 |



|                                    |                                                   |         |         |         |         |         |         |         |          |          |
|------------------------------------|---------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|----------|----------|
| Hydrochloric<br>Acid<br>HCl        | Chloride of Silver<br>AgCl                        | 0.25427 | 0.50853 | 0.76280 | 1.01707 | 1.27133 | 1.52560 | 1.77987 | 2.03414  | 2.28840  |
| Chromium<br>Cr                     | Oxide of Chro-<br>mium<br>$\text{Cr}_2\text{O}_3$ | 0.70112 | 1.40224 | 2.10336 | 2.80448 | 3.50560 | 4.20672 | 4.90784 | 5.60896  | 6.31008  |
| Chromic Acid<br>$2\text{CrO}_3$    | Oxide of Chro-<br>mium<br>$\text{Cr}_2\text{O}_3$ | 1.29888 | 2.59776 | 3.89664 | 5.19552 | 6.49440 | 7.79328 | 9.07216 | 10.39104 | 11.68992 |
| Chromic Acid<br>$\text{CrO}_3$     | Chromate of Lead<br>$\text{PbOCrO}_3$             | 0.31855 | 0.63710 | 0.95565 | 1.27420 | 1.59275 | 1.91130 | 2.22985 | 2.54840  | 2.86695  |
| Protoxide of Co-<br>balt           | Cobalt<br>Co                                      | 1.27141 | 2.54283 | 3.81424 | 5.08566 | 6.3570  | 7.62849 | 8.89990 | 10.17130 | 11.44273 |
| Copper<br>Cu                       | Oxide of Copper<br>$\text{CuO}$                   | 0.79839 | 1.59677 | 2.39516 | 3.19355 | 3.99193 | 4.77032 | 5.58871 | 6.38710  | 7.18548  |
| Fluorine<br>Fl                     | Fluoride of Cal-<br>cium<br>CaFl                  | 0.48320 | 0.96640 | 1.44960 | 1.93280 | 2.41600 | 2.89920 | 3.38240 | 3.86560  | 4.34880  |
| Fluorine<br>$3\text{Fl}$           | Fluoride of Silicon<br>$\text{SiFl}_3$            | 0.72434 | 1.44868 | 2.17302 | 2.89736 | 3.62170 | 4.34604 | 5.07038 | 5.79472  | 6.51906  |
| Hydrogen<br>H                      | Water<br>HO                                       | 0.11111 | 0.22222 | 0.33333 | 0.44444 | 0.55555 | 0.66667 | 0.77778 | 0.88889  | 1.00000  |
| Iodine<br>I                        | Iodide of Silver<br>AgI                           | 0.53917 | 1.07834 | 1.61751 | 2.15668 | 2.69585 | 3.23502 | 3.77419 | 4.31336  | 4.85253  |
| Iron<br>$\text{Fe}_2$              | Oxide of Iron<br>$\text{Fe}_2\text{O}_3$          | 0.70000 | 1.40000 | 2.10000 | 2.80000 | 3.50000 | 4.20000 | 4.90000 | 5.60000  | 6.30000  |
| Protoxide of Iron<br>$2\text{FeO}$ | Oxide of Iron<br>$\text{Fe}_2\text{O}_3$          | 0.90000 | 1.80000 | 2.70000 | 3.60000 | 4.50000 | 5.40000 | 6.30000 | 7.20000  | 8.10000  |
| Lead<br>Pb                         | Oxide of Lead<br>PbO                              | 0.92829 | 1.85658 | 2.78487 | 3.71316 | 4.64145 | 5.56974 | 6.49803 | 7.42932  | 8.35464  |

TABLE VII.—CONTINUED.

| Required.                                     | Found.                                                            | 1       | 2       | 3       | 4       | 5       | 6       | 7       | 8       | 9       |
|-----------------------------------------------|-------------------------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| Oxide of Lead<br>PbO                          | Sulphate of Lead<br>PbOSO <sub>3</sub>                            | 0.73608 | 1.47216 | 2.20823 | 2.94431 | 3.68039 | 4.41647 | 5.15255 | 5.88862 | 6.62470 |
| Oxide of Lead<br>PbO                          | Chloride of Lead<br>PbCl                                          | 0.80250 | 1.60500 | 2.40749 | 3.20999 | 4.01249 | 4.81499 | 5.61749 | 6.41998 | 7.22248 |
| Lead<br>Pb                                    | Chloride of Lead<br>PbCl                                          | 0.74495 | 1.48990 | 2.23485 | 2.97980 | 3.72475 | 4.46970 | 5.21465 | 5.95960 | 6.70455 |
| Oxide of Lead<br>PbO                          | Sulphuret of Lead<br>PbS                                          | 0.93309 | 1.86618 | 2.79926 | 3.73235 | 4.66544 | 5.59853 | 6.53162 | 7.46470 | 8.39779 |
| Magnesium<br>Mg                               | Magnesia<br>MgO                                                   | 0.61204 | 1.22407 | 1.83611 | 2.44815 | 3.06018 | 3.67222 | 4.28426 | 4.89630 | 5.50833 |
| Magnesia<br>MgO                               | Sulphate of Mag-<br>nesia<br>MgOSO <sub>3</sub>                   | 0.34015 | 0.68030 | 1.02046 | 1.36061 | 1.70076 | 2.04091 | 2.38106 | 2.72122 | 3.06137 |
| Magnesia<br>2MgO                              | Pyrophosphate of<br>Magnesia<br>2MgO.PO <sub>5</sub>              | 0.36468 | 0.72936 | 1.9404  | 1.45872 | 1.82340 | 2.18808 | 2.55276 | 2.91744 | 3.28212 |
| Manganese<br>Mn                               | Protioxide of Man-<br>ganese<br>MnO                               | 0.77571 | 1.55142 | 2.32713 | 3.10284 | 3.89855 | 4.65426 | 5.42997 | 6.20568 | 6.98139 |
| Manganese<br>Mn <sub>3</sub>                  | Mangano-man-<br>ganic Oxide<br>MnO+Mn <sub>2</sub> O <sub>3</sub> | 0.72176 | 1.44352 | 2.16528 | 2.88704 | 3.60880 | 4.33056 | 5.05232 | 5.77408 | 6.49584 |
| Protioxide of<br>Manganese<br>MnO             | Protosulphate of<br>Manganese<br>MnO <sub>2</sub> SO <sub>3</sub> | 0.47138 | 0.94276 | 1.41414 | 1.88552 | 2.35690 | 2.82828 | 3.29966 | 3.77104 | 4.24242 |
| Protioxide of<br>Mercury<br>Hg <sub>2</sub> O | Mercury<br>Hg <sub>2</sub>                                        | 1.03997 | 2.07994 | 3.11991 | 4.15988 | 5.19985 | 6.23983 | 7.27980 | 8.31977 | 9.35974 |

|                                           |                                                                       |         |         |         |         |         |         |         |         |          |
|-------------------------------------------|-----------------------------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|----------|
| Binoxide of Mercury<br>$\text{HgO}$       | Mercury<br>Hg                                                         | 1.07994 | 2.15988 | 3.23983 | 4.31977 | 5.39971 | 6.47965 | 7.55959 | 8.63954 | 9.71948  |
| Mercury<br>$\text{Hg}_2$                  | Protochloride of Mercury<br>$\text{Hg}_2\text{Cl}$                    | 0.84951 | 1.69902 | 2.54852 | 3.39803 | 4.24754 | 5.09705 | 5.94656 | 6.79606 | 7.64557  |
| Mercury<br>Hg                             | Sulphide of Mercury<br>HgS                                            | 0.86215 | 1.72431 | 2.58646 | 3.44862 | 4.31077 | 5.17293 | 6.03508 | 6.89724 | 7.75939  |
| Nickel<br>Ni                              | Protoxide of Nickel<br>NiO                                            | 0.78684 | 1.57369 | 2.36053 | 3.14738 | 3.93422 | 4.72106 | 5.50791 | 6.29475 | 7.08160  |
| Nitrogen<br>N                             | Ammonio-chloride of Platinum<br>$\text{NH}_4\text{Cl}, \text{PtCl}_2$ | 0.06285 | 0.12570 | 0.18855 | 0.25140 | 0.31425 | 0.37711 | 0.43996 | 0.50281 | 0.56566  |
| Nitrogen<br>N                             | Platinum<br>Pt                                                        | 0.14207 | 0.28415 | 0.42622 | 0.56830 | 0.71037 | 0.85245 | 0.99452 | 1.13660 | 1.27867  |
| Nitric Acid<br>$\text{NO}_5$              | Sulphate of Baryta<br>$\text{BaO}, \text{SO}_3$                       | 0.46295 | 0.92590 | 1.33335 | 1.75180 | 2.1475  | 2.77770 | 3.24065 | 3.70360 | 4.16655  |
| Nitric Acid<br>$\text{NO}_5$              | Carbonic Acid<br>$2\text{CO}_3$                                       | 1.22773 | 2.45545 | 3.68318 | 4.91091 | 6.13863 | 7.36636 | 8.59409 | 9.82182 | 11.04954 |
| Cyanogen<br>$\text{C}_2\text{N}$          | Cyanide of Silver<br>$\text{AgC}_2\text{N}$                           | 0.19403 | 0.38806 | 0.58209 | 0.77612 | 0.97015 | 0.16418 | 1.35821 | 1.55224 | 1.74627  |
| Hydrocyanic Acid<br>$\text{C}_2\text{NH}$ | Cyanide of Silver<br>$\text{AgC}_2\text{N}$                           | 0.19436 | 0.38873 | 0.58309 | 0.77756 | 0.97192 | 1.16619 | 1.36055 | 1.55492 | 1.74928  |
| Phosphorus<br>P                           | Phosphoric Acid<br>$\text{PO}_5$                                      | 0.44459 | 0.88918 | 1.33377 | 1.77836 | 2.22295 | 2.66754 | 3.11213 | 3.55672 | 4.00131  |
| Phosphoric Acid<br>$\text{PO}_5$          | Pyrophosphate of Magnesia<br>$2\text{MgO}, \text{PO}_5$               | 0.63532 | 1.27064 | 1.90596 | 2.54128 | 3.17660 | 3.81192 | 4.43724 | 5.08256 | 5.71788  |
| Phosphoric Acid<br>$3\text{PO}_5$         | Phosphate of Iron<br>$2\text{Fe}_2\text{O}_3, 3\text{PO}_5$           | 0.57417 | 1.14834 | 1.72251 | 2.29668 | 2.87085 | 3.44502 | 4.01919 | 4.59366 | 5.16753  |

TABLE VII.—CONTINUED.

| Required.                        | Found.                                                         | 1       | 2       | 3       | 4       | 5       | 6       | 7       | 8       | 9       |
|----------------------------------|----------------------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| Phosphoric Acid<br>$\text{PO}_5$ | Phosphate of Silver<br>$3\text{Ag}_2\text{O}, \text{PO}_5$     | 0.17146 | 0.34292 | 0.51438 | 0.68584 | 0.85730 | 1.02876 | 1.20022 | 1.37168 | 1.54314 |
| Phosphoric Acid<br>$\text{PO}_5$ | Pyrophosphate of Silver<br>$2\text{Ag}_2\text{O}, \text{PO}_5$ | 0.23689 | 0.47378 | 0.71067 | 0.94756 | 1.18445 | 1.42134 | 1.65823 | 1.89512 | 2.13201 |
| Potassium<br>K                   | Potash<br>K <sub>2</sub> O                                     | 0.83020 | 1.66041 | 2.49061 | 3.32081 | 4.15101 | 4.98122 | 5.81142 | 6.64162 | 7.47183 |
| Potash<br>K <sub>2</sub> O       | Sulphate of Potash<br>$\text{K}_2\text{O}, \text{SO}_3$        | 0.54084 | 1.08168 | 1.62251 | 2.16335 | 2.70419 | 3.24503 | 3.78587 | 4.32670 | 4.86754 |
| Potash<br>K <sub>2</sub> O       | Nitrate of Potash<br>$\text{K}_2\text{O}, \text{NO}_5$         | 0.46586 | 0.93173 | 1.39759 | 1.86346 | 2.32232 | 2.79518 | 3.26105 | 3.72691 | 4.19278 |
| Potassium<br>K                   | Chloride of Potassium<br>KCl                                   | 0.52454 | 1.04908 | 1.57362 | 2.09816 | 2.62270 | 3.14724 | 3.67178 | 4.19632 | 4.72086 |
| Potash<br>K <sub>2</sub> O       | Chloride of Potassium<br>KCl                                   | 0.63182 | 1.26364 | 1.89546 | 2.52728 | 3.15909 | 3.79091 | 4.42273 | 5.05455 | 5.68637 |
| Potash<br>K <sub>2</sub> O       | Potassio-chloride of Platinum<br>$\text{KClPtCl}_2$            | 0.19297 | 0.38593 | 0.57890 | 0.77186 | 0.96483 | 1.15780 | 1.35076 | 1.54373 | 1.73669 |
| Chloride of Potassium<br>KCl     | Potassio-chloride of Platinum<br>$\text{KClPtCl}_2$            | 0.30541 | 0.61083 | 0.91624 | 1.22166 | 1.52707 | 1.83429 | 2.13790 | 2.44332 | 2.74873 |
| Silicon<br>Si                    | Silicic Acid<br>$\text{SiO}_2$                                 | 0.47078 | 0.94156 | 1.41234 | 1.88312 | 2.35390 | 2.82468 | 3.29546 | 3.76624 | 4.23702 |
| Silver<br>Ag                     | Chloride of Silver<br>AgCl                                     | 0.75271 | 1.50542 | 2.25812 | 3.01083 | 3.76354 | 4.51625 | 5.26896 | 6.02166 | 6.77437 |



|                                   |                                                        |         |         |         |         |         |         |         |         |         |
|-----------------------------------|--------------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| Oxide of Silver<br>AgO            | Chloride of Silver<br>AgCl                             | 0.80850 | 1.61701 | 2.42551 | 3.23402 | 4.04252 | 4.85103 | 5.65983 | 6.46804 | 7.27654 |
| Sodium<br>Na                      | Soda<br>NaO                                            | 0.74172 | 1.48343 | 2.22515 | 2.96686 | 3.70858 | 4.45030 | 5.19201 | 5.93373 | 6.67544 |
| Soda<br>NaO                       | Sulphate of Soda<br>Na <sub>2</sub> SO <sub>3</sub>    | 0.43641 | 0.87282 | 1.30923 | 1.74564 | 2.18205 | 2.61846 | 3.05487 | 3.49128 | 3.92769 |
| Soda<br>NaO                       | Nitrate of Soda<br>NaO.NO <sub>5</sub>                 | 0.36442 | 0.72805 | 1.09327 | 1.45769 | 1.82211 | 2.18654 | 2.55096 | 2.91538 | 3.27981 |
| Soda<br>NaO                       | Chloride of Sodium<br>NaCl                             | 0.53010 | 1.06020 | 1.59030 | 2.12040 | 2.65050 | 3.18061 | 3.71071 | 4.24081 | 4.77091 |
| Sodium<br>Na                      | Chloride of Sodium<br>NaCl                             | 0.39318 | 0.78637 | 1.17955 | 1.57274 | 1.96592 | 2.35910 | 2.75229 | 3.14547 | 3.53866 |
| Soda<br>NaO                       | Carbonate of Soda<br>Na <sub>2</sub> O.CO <sub>2</sub> | 0.58470 | 1.16940 | 1.75410 | 2.33880 | 2.92349 | 3.50819 | 4.09289 | 4.67759 | 5.26229 |
| Strontium<br>Sr                   | Strontia<br>SrO                                        | 0.84567 | 1.69134 | 2.53701 | 3.38288 | 4.22835 | 5.07402 | 5.91969 | 6.76536 | 7.61103 |
| Strontia<br>SrO                   | Sulphate of Stron-<br>tia<br>SrO.SO <sub>3</sub>       | 0.56446 | 1.12892 | 1.79338 | 2.25784 | 2.82230 | 3.58676 | 3.95122 | 4.51568 | 5.38014 |
| Strontia<br>SrO                   | Carbonate of Stron-<br>tia<br>SrO.CO <sub>2</sub>      | 0.70205 | 1.40410 | 2.10615 | 2.80420 | 3.51025 | 4.21230 | 4.91435 | 5.60840 | 6.31845 |
| Sulphur<br>S                      | Sulphate of Baryta<br>BaO.SO <sub>3</sub>              | 0.13717 | 0.27434 | 0.41151 | 0.54868 | 0.68585 | 0.82302 | 0.96019 | 1.09736 | 1.23353 |
| Sulphur<br>S <sub>3</sub>         | Sulphuret of Ar-<br>senic<br>AsO <sub>3</sub>          | 0.39024 | 0.78048 | 1.17072 | 1.56096 | 1.95130 | 2.34144 | 2.73168 | 3.12192 | 3.51216 |
| Sulphuric Acid<br>SO <sub>3</sub> | Sulphate of Baryta<br>BaO.SO <sub>3</sub>              | 0.34294 | 0.68588 | 1.02872 | 1.37176 | 1.71470 | 2.05764 | 2.40058 | 2.74352 | 3.08646 |
| Tin<br>Sn                         | Oxide of Tin<br>SnO <sub>2</sub>                       | 0.78616 | 1.57233 | 2.35849 | 3.14466 | 3.93082 | 4.71698 | 5.50315 | 6.28931 | 7.07547 |
| Protoxide of Tin<br>SnO           | Oxide of Tin<br>SnO <sub>2</sub>                       | 0.89308 | 1.78616 | 2.67924 | 3.57232 | 4.46543 | 5.35848 | 6.25156 | 7.14464 | 8.03772 |
| Zinc<br>Zn                        | Oxide of Zinc<br>ZnO                                   | 0.80260 | 1.60520 | 2.40781 | 3.21041 | 4.01301 | 4.81561 | 5.61821 | 6.42082 | 7.22342 |



## APPENDIX.

### ON SOME NEW APPLICATIONS OF SULPHURETTED HYDROGEN IN CHEMICAL ANALYSIS.

BY M. EBELMEN.

**HITHERTO** sulphuretted hydrogen has rarely been employed in analysis, except to precipitate certain metals from their solution in acids. In many cases this substance is one of the most accurate and handy reagents known. The facts contained in the present paper will show that it may likewise be used with considerable advantage for separating certain substances one from the other by converting them in the dry way into sulphurets. It may then happen that one of the sulphurets formed is not acted upon by acids, while the other is; it may also happen that one of the sulphurets is volatile, and is separated from the other by the employment of a somewhat elevated temperature. I have employed this method in solving several problems of chemical analysis, the solution of which by our present means was not quite satisfactory. I shall now proceed to give the results obtained.

1. *Separation of Manganese from Cobalt.*—A considerable number of methods have been proposed for the separation of these two metals. The most accurate, according to Rose, would consist in converting the two oxides into protochlorides, by heating them in a current of hydrochloric acid gas, and treating the protochlorides at an elevated temperature with hydrogen. The protochloride of cobalt is alone reduced to the metallic state, so that water merely dissolves the protochloride of manganese. This method is complicated and not quite accurate; a little oxide of manganese always remains with the cobalt. It has recently been proposed to treat the solution of the two oxides in hydrochloric acid with an excess of carbonate of baryta, and then to pass into the neutralized liquid a current of sulphuretted hydrogen, which was said to precipitate only the cobalt in the state of sulphuret. I found that the cobalt was precipitated, it is true, before the manganese, but that the latter metal was entirely thrown down in the presence of carbonate of baryta by the sulphuretted hydrogen; it is consequently impossible to separate these two metals by this process.

The method which I have employed to solve the question is simple and very expeditious; it is founded on the fact, that the sulphuret of cobalt prepared in the dry way is not in the least acted upon by cold dilute hydrochloric acid, which does not apply to the sulphuret of manganese. I proceed as follows:—After having weighed the mixture of the two oxides to be separated, it is placed in a platinum or porcelain tray, and heated in a current of sulphuretted hydrogen. The action begins at the ordinary temperature. The mixture of the two oxides gives off considerable heat in the gas. The tube containing the two oxides is then raised to a dark red heat; the sulphuret is allowed to cool in a current of the gas, the tray drawn out of the tube, and digested in cold water containing a little hydrochloric acid. The sulphuret of manganese alone is dissolved. After some hours' digestion, it is filtered, the liquid boiled, precipitated with potash, and the oxide of manganese determined. The black residue of sulphuret of cobalt is redissolved in nitric acid, and this solution also precipitated by potash. The following experiments will serve to show the accuracy of the process:—

*First Experiment.*—A mixture of

|                        |           |            |
|------------------------|-----------|------------|
| Red oxide of manganese | . . . . . | 0.300 grm. |
| Protoxide of cobalt    | . . . . . | 0.300 ...  |

was dissolved in hydrochloric acid, the whole precipitated with potash, and the precipitate washed carefully and calcined; it weighed with the ash of the filter 0.611. It was then heated on a porcelain tray in sulphuretted hydrogen, the sulphurets digested for twelve hours in cold very dilute hydrochloric acid, and then filtered; the filtered liquid was perfectly colorless, and on treatment with potash gave 0.302 red oxide of manganese. The residue of sulphuret of cobalt was decomposed with nitric acid, and the filtered solution precipitated with potash; it gave 0.303 protoxide of cobalt. The red oxide of manganese, on examination before the blowpipe, gave with borax a perfectly colorless bead in the reducing flame, which proved that it contained no cobalt. The oxide of cobalt, treated with nitre and potash in a silver crucible, did not exhibit the least sign of the presence of manganese.

*Second Experiment.*—A mixture of

|                        |           |            |
|------------------------|-----------|------------|
| Red oxide of manganese | . . . . . | 0.481 grm. |
| Protoxide of cobalt    | . . . . . | 0.090 ...  |

treated as in the preceding experiment, gave

|                        |           |            |
|------------------------|-----------|------------|
| Red oxide of manganese | . . . . . | 0.486 grm. |
| Protoxide of cobalt    | . . . . . | 0.092 ...  |

Both the oxides were ascertained to be free from each other.

*Third Experiment.*—A mixture of 0.023 grm. red oxide of manganese and 0.980 protoxide of cobalt gave, on similar treatment, 0.028 oxide of manganese; the cobalt was not estimated. The oxide of manganese gave a perfectly colorless bead with borax in the reducing flame of the blowpipe. Dissolved in a small quantity of hydrochloric acid, it furnished a perfectly colorless liquid which gave with hydrosulphuret of ammonia an orange colored precipitate. The least trace of cobalt would have blackened it.

The slight excess found in the estimation of the manganese, and which is apparent in all the experiments, appears to be attributable to a small quantity of foreign substances in the alkaline solution used to precipitate the cobalt and manganese. The difficulty of obtaining alkalies absolutely free from silica or alumina is well known. It was also found that the cobalt and manganese from the preceding experiments always left a slight insoluble residue when treated with hydrochloric acid after having been calcined and weighed.

*Fourth Experiment.*—A mixture of 0.963 grm. red oxide of manganese and 0.012 protoxide of cobalt afforded on similar treatment 0.012 oxide of cobalt; the manganese was not determined. The oxide of cobalt did not contain a trace of manganese.

The two last experiments show that the process may be employed for the accurate separation of cobalt and manganese, even in the case where one of the metals greatly preponderates over the other. It may be applied directly in examining ores of manganese for oxide of cobalt. It would suffice to heat them in a current of sulphuretted hydrogen and then act upon them with very dilute hydrochloric acid. The whole of the cobalt will be contained in the insoluble residue.

*Separation of Manganese and Nickel.*—This is effected by the same method as that for manganese and cobalt. A mixture of

|                        |           |            |
|------------------------|-----------|------------|
| Protoxide of nickel    | . . . . . | 0.179 grm. |
| Red oxide of manganese | . . . . . | 0.321 ...  |

was dissolved in hydrochloric acid, precipitated with potash, the precipitate calcined, heated in sulphuretted hydrogen, and treated with cold very dilute hydrochloric acid. There was found—



|                        |             |
|------------------------|-------------|
| Oxide of nickel        | 0.178 grm.  |
| Red oxide of manganese | 0.320 . . . |

The results are consequently as precise in this case as in the separation of cobalt from manganese.

*Separation of Manganese and Zinc.*—I have attempted to apply the above process to the separation of zinc and manganese. As the sulphuret of zinc dissolves with time in dilute hydrochloric acid, I treated the mixture of the two sulphurets prepared in the dry way with acetic acid, the action of which was assisted by heat. In this way only the manganese is dissolved, but the sulphuret of zinc retains a small quantity of manganese which cannot be separated by this method. When operating with weighed quantities of zinc and manganese, I have always obtained too large an amount of oxide of zinc, and have found it to contain a certain quantity of oxide of manganese.

*Separation of Iron and Cobalt.*—When a mixture of peroxide of iron and cobalt is heated in sulphuretted hydrogen, and then acted upon even with concentrated hydrochloric acid, scarcely any iron is removed; the sulphuret of cobalt retains nearly the whole of the sulphuret of iron.

As the sulphuret of iron, which is obtained by heating peroxide of iron to a nascent red in sulphuretted hydrogen, is not acted upon by dilute cold hydrochloric acid, I imagined that this property might be turned to account for separating iron from manganese; but experiment has shown that the sulphuret of iron always contains a considerable proportion of sulphuret of manganese.

The volatility of certain sulphurets furnishes a means of separation which may be turned to account in some cases. I will mention two examples, the one relative to the separation of iron and arsenic, the other to the separation of arsenic and tin.

*Separation of Iron and Arsenic.*—When arseniate of iron is heated in a current of sulphuretted hydrogen, both the iron and arsenic are completely sulphurized; but the latter body is entirely volatilized. The separation is very accurate. A mixture was made of

|                |                                            |             |
|----------------|--------------------------------------------|-------------|
| Metallic iron  | 1.330 grm., corresponding to peroxide,     | 1.900       |
| Arsenious acid | 1.380 grm., corresponding to arsenic acid, | 1.711       |
|                |                                            | <hr/> 3.611 |

The two bodies were dissolved in *aqua regia*, the solution precipitated with ammonia in excess; the precipitate, dried and carefully removed from the filter, weighed after calcination 3.315; the filter and adherent matter were calcined separately in a porcelain crucible, and gave 0.055=3.370, which number is considerably lower than that which ought to have been obtained if the whole of the arsenic had been precipitated with the peroxide of iron. I found that a very considerable quantity of arsenic remained in the ammoniacal solution, but not a trace of iron. It amounted to 0.241 grm. or 14 per cent. of the total quantity. 3.370 arseniate of iron must therefore contain—

|                  |             |                   |
|------------------|-------------|-------------------|
| Peroxide of iron | 1.900 grm.  | 56.4 in 100 parts |
| Arsenic acid     | 1.470 . . . | 43.6 . . .        |
|                  | <hr/> 3.370 | <hr/> 100.0       |

which composition corresponds very nearly to the formula  $\text{AsO}_5 \cdot 2\text{Fe}^2\text{O}_3$ .

0.788 grm. of this arseniate was heated to a faint red heat in sulphuretted hydrogen. A large quantity of sulphuret of arsenic was volatilized. The sulphuret of iron which remained was of a greenish-yellow color, and possessed a certain metallic lustre; it weighed 0.6065. On dissolving it in nitromuriatic acid, precipitating with ammonia, it gave 0.444 peroxide of iron, which proves that the arseniate contained—

|                              |         |            |                |
|------------------------------|---------|------------|----------------|
| Peroxide of iron             | • • • • | 0.444 grm. | 56.3 per cent. |
| Arsenic acid (from the loss) | • • • • | 0.344      | 43.7           |
|                              |         | <hr/>      |                |
|                              |         | 0.788      |                |

The peroxide of iron was dissolved in hydrochloric acid; the solution, boiled with sulphurous acid and treated with sulphuretted hydrogen, gave not a trace of sulphuret of arsenic.

*Second Experiment.*—1.050 grm. of the same arseniate of iron, treated as above, gave—

|                  |         |            |                |
|------------------|---------|------------|----------------|
| Peroxide of iron | • • • • | 0.594 grm. | 56.5 per cent. |
| Arsenic acid     | • • • • | 0.456      | 43.5           |
|                  |         | <hr/>      |                |
|                  |         | 1.050      |                |

The peroxide of iron, examined as in the preceding experiment, did not give a trace of arsenic.

It is seen that the results of these two experiments agree very well with each other, and with those deduced synthetically; they perfectly establish the accuracy of the method. The native arseniates of iron may be directly analyzed by this method. It may also probably be applied without modification to the direct analysis of the arseniates of cobalt, nickel, zinc, copper and lead.

When a current of sulphuretted hydrogen is passed over heated perphosphate of iron, it is merely changed into the protophosphate, which dissolves without residue in hydrochloric acid, and without exhibiting any disengagement of sulphuretted hydrogen.

*Separation of Arsenic and Tin.*—The separation of arsenic and tin is considered to be one of the most difficult problems of analytical chemistry. Professor Rose states in his work on Analytical Chemistry, that he is not acquainted with any good method of separating these two substances. The plan recently proposed by M. Levot\* is very complicated. I have applied the method above given for the separation of iron from arsenic to the separation of arsenic from tin; and the following experiments will show that the process is susceptible of very great accuracy. I weighed off 0.495 grm. of fine tin, corresponding to 0.629 stannic acid, and 0.233 arsenious acid. The two substances were treated with hot nitric acid, evaporated nearly to dryness, then mixed with water. The oxide of tin weighed after calcination 0.746; it consequently contained 0.117, or 15.7 per cent. of its weight of arsenic acid; the rest of the arsenic had remained in solution. Of this 0.746 grm. arseniate of the oxide of tin I took 0.347, and heated it upon a porcelain tray in a current of sulphuretted hydrogen. A considerable quantity of sulphuret of arsenic sublimed; the residue appeared to be a mixture of bisulphuret of tin and of a lower sulphuret. Roasted and then strongly calcined in a platinum crucible, this residue of sulphuret left 0.286 stannic acid, or 82.4 per cent. According to synthesis 84.3 should have been found; but this slight difference is readily explained from the difficulty of obtaining absolutely pure tin. I assured myself, by reducing the 0.286 stannic acid and treating the tin obtained with hydrochloric acid, that the sulphuret of tin had not retained a trace of arsenic. The arsenic was not determined, but it would have been easy to have done so, as the whole of the sulphuret of arsenic was contained either in the tube or in the water into which the tube dipped. This method therefore appears applicable to the analysis of the arseniates of tin, and it may probably also be applied to the direct analysis of the arseniuret of tin. This substance, when exposed to the action of sulphuretted hydrogen, parts with the arsenic in the state of sulphuret; and the sulphuret of tin which remains is readily converted into stannic acid by roasting.—*Ann. de Chim. et de Phys.*, Jan. 1849, p. 92, and *Chem. Gaz.* vii. 82.

\* *Chem. Gaz.*, vol. iv. p. 159.

## ERRATA.

---

PAGE 117, 2d line from bottom, *for*  $\text{MO}_2$ , *read*  $\text{MoO}_2$ .

" 118, 21st " top, *for*  $\text{Mo}_3$ , *read*  $\text{MoO}_3$ .

" 159, 8th " bottom, *for* soluble, *read* insoluble.

" 370, 6th " top, *for*  $\text{MO}_3$ , *read*  $\text{MoO}_3$ .

" 371, 6th " "  $\text{MO}$ , *read*  $\text{Mo}$ .

" " 8th " "  $\text{MO}, \text{S}_2$ , *read*  $\text{MoS}_2$ .

" 168, 17th " " baryta, *read* lime.

" " " " barium, *read* calcium.







